



भारतीय विमानपत्तन प्राधिकरण,
Airports Authority of India
सिविल एयरपोर्ट पंतनगर,
Civil Airport, Pantnagar.

संख्या:-भाविप्रा/अभि.वि)/पी एन टी/ए0जी0एम (इ-इ)/का0 आ0-51/कार पार्किंग /2022-23/
Ref:- AAI/ Engg(E)/PNT/AGM(E-E)/W.O.-51 /carparking/ 2022-23/

दिनांक :-12.05.2022

Date :- 12.05.2022

सेवा में /To,

मेसर्स अवस्थी इलेक्ट्रिक वर्क्स
107 /265 ,ब्रह्मनगर
कानपुर-208011

M/s. Awasthi Electric Works,
107/265, Brahma Nagar
Kanpur-208011

कार्य का नाम :- डेवलपमेंट ऑफ पंतनगर एयरपोर्ट फॉर आर सी एस ऑपरेशन्स.सब हेड :- प्रोविज़न ऑफ लाइट्स
फॉर न्यू कार पार्किंग एट सिविल एयरपोर्ट पंतनगर

Name of Work: - Development of Pantnagar Airport for RCS operations SH: Provision of lights
for new Car Parking at Civil Airport Pantnagar

संदर्भ :- 1) आपकी टेंडर आई0डी0 (2022_AAI_110061_1) खोला गया दिनांक - 27.04.2022

Ref. :- 1) Your tender ID (2022_AAI_110061_1) opened on dated- 27.04.2022

महोदय /Sir,

- उपरोक्त कार्य हेतु आपका आफर अध्यक्ष ,भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताये गये मद मूल्यों पर आपका आफर कुल रुपये 8,08,100/- (रुपये आठ लाख आठ हजार एक सौ केवल) (जी0एस0टी0 अतिरिक्त)। जोकि टेंडर की अनुमानित/न्यायसंगत राशि रू0 8,26,036/- से 2.17 प्रतिशत कम है।

Your offer for the work mentioned above work is hereby accepted on behalf of the Chairman, Airport Authority of India at the item rates quoted by you totaling to Rs. 8,08,100/- (Eight Lakh Eight Thousand One Hundred only) (GST Extra). Which is 2.17 % below the estimated/justified cost put to tender of Rs 8,26,036/-.

- सहा0 महा0 प्रबन्धक (इंजी-विद्युत) भाविप्रा, सिविल एयरपोर्ट, बरेली कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप अपनी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामों पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 25.05.2022 तक प्रबन्धक (इंजी-विद्युत) भाविप्रा, पंतनगर के कार्यालय में उपस्थित हो तथा करारनामों को पूरा करें। ठेके का करारनामा 100/-रुपये के नोनज्यूडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा, तथा स्टाम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Asstt. General Manager Engg. (Elect.), AAI, Civil Airport, Bareilly shall be the Engineer in charge of the work. You are requested to attend the office of Manager Engg (Elect.), AAI, Civil Airport, Pantnagar by 26.05.2022 to sign and complete the contract agreement.


The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees Hundred only) and the cost of the stamp paper shall be borne by you.

जारी /Contd...

(Signature)
12/05/2022

3. आपके इ-टेंडर के साथ प्राप्त धरोहर राशि रुपये 16,521/- ठेके के सामान्य शर्तों पर दी गयी शर्त 1(A) के अनुसार जमानत राशि में परिवर्तित कार दी जाएगी। कृपया इस पत्र के जारी होने के 15 दिनों के भीतर सिविल एयरपोर्ट डिपोजिट के लिए रुपये 64,289/- (रु. चौसठ हजार दो सौ नवासी केवल) जमा कर दे, अन्यथा ठेके के करारनामे में दी शर्त के अनुसार इतनी राशि आपके रनिंग बिलों से काट ली जाएगी।
The earnest money amount of Rs. 16,521/- received along with your e-tender will be treated and converted as part of Security Deposit as per GCC Clause 1(A) of the contract document. Please deposit Rs 64,289/- (Rupees Sixty Four Thousand Two Hundred Eighty Nine Only) towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted from your running bills as per condition of the contract document.
4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केन्द्रीय नियम (रेगुलेशन एवं अबोलिशन) एवं न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।
You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments.
5. आपको निर्देश दिया जाता है कि आप तुरंत प्रबन्धक (इंजी-विद्युत), भाविप्रा, सिविल एयरपोर्ट, पन्तनगर से मिलें वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का समय 3 (तीन) माह है जोकि दसवें दिन या साइट सौंपने दोनो में से जो भी पहले से गिना जाएगा।
You are also directed to contact Manager Engg. (E), AAI, Civil Airport, Pantnagar immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work shall be 3 (Three) Months which shall be reckoned from tenth day or takeover of site whichever is earlier.
6. इस ठेके के संबंध में आगे का कोई भी पत्राचार सहायक महाप्रबन्धक (इंजी-विद्युत), भाविप्रा, सिविल एयरपोर्ट, बरेली, उत्तर प्रदेश के पते पर किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the Asstt. Gen. Manager Engg. (E), AAI, Civil Airport, Bareilly.
7. उपरोक्त सम्बन्धित सभी पत्र इस करारनामे के भाग होंगे। कार्य का निष्पादन स्वीकृत शर्तों के अनुसार किया जाएगा।
All the letters referred above shall form part of contract agreement. The work shall be executed as per terms & condition of contract accepted by you.
8. उक्त कार्य का त्रुटि दायित्व अवधि 12 (बारह) महीने होगी जो कि कार्य पूरा होने की तिथि से गिना जाएगा।
The defects liability period is 12 (Twelve) months from the certified date of completion of work.
9. कृपया पावती भेजे।
Please acknowledge the receipts

धन्यवाद / Thanking you,


भवदीय / Yours Faithfully,
सहायक महाप्रबन्धक (अभि.-विद्युत),
Asstt. General Manager Engg. (Elect.),
कृते तथा ओर से अध्यक्ष,
For and on behalf of Chairman,
भारतीय विमानपत्तन प्राधिकरण
Airports Authority Of India.

संलग्न/Enclosed :- शिडयूल ऑफ क्वान्टटी (3 पृष्ठ) / SOQ (3 Pages).

जारी / Contd...

प्रतिलिपि/ Copy To :-

1. महाप्रबन्धक (इंजी.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, उ.क्षे., आपरेशनल आफिस, रंगपुरी, गुडगाँव रोड, नई दिल्ली-37 / GM(Engg.-Elect.), AAI, NR, Operational Office, Rangpuri, Gurgaon road, New Delhi-37.
2. संयुक्त महाप्रबन्धक (इंजी.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, जौलीग्रंट एयरपोर्ट, देहरादून- 248140, / Jt. GM(Engg.-Elect.), AAI, Jolly Grant Airport, Dehradun -248140
3. विमानपत्तन निदेशक, भारतीय विमानपत्तन प्राधिकरण, सिविल एयरपोर्ट पंतनगर / Airport Director, Civil Airport, Pantnagar.
4. सहाय महाप्रबन्धक (वित्त), भारतीय विमानपत्तन प्राधिकरण, जौलीग्रंट एयरपोर्ट, देहरादून- 248140 / Asstt. General Manager (Finance), AAI, Jolly Grant Airport, Dehradun-248140
5. प्रबन्धक (इंजी.-विद्युत), भा.विप्रा., सिविल एयरपोर्ट पंतनगर / Manager (E-E), AAI, Civil Airport, Pantnagar.
6. करारनामा प्रतिलिपि / Agreement copy.
7. कार्य आदेश फाईल / Work Order File.

Government eProcurement System

Created By: md ansari

Created Date/Time: 27-Apr-2022 05:09 PM

Tender Title: Development of Pantnagar Airport for RCS operations SH Provision of lights for new Car Parking at Civil Airport Pantnagar

Tender ID: 2022_AAI_110061_1

Tender Inviting Authority: Airports Authority of India, Civil Airport, Pantnagar

Name of Work: -Development of Pantnagar Airport for RCS operations SH:Provision of Lights for new car parking at Civil airport Pantnagar .

Contract No: AAI/PNT/ELECT/CARPARKING

SCHEDULE OF WORK / ITEM(S)

SI.No	Description of Work / Item(s)	No.of Qty	Units	Awasthi Electric Works(GSTN-09ABAPA1866D125)	
				Rate	Amount (Rs.)
1.00	SH:1 Car Parking Lighting Pole and Fixture.				
1.10	Supply of 45 W/54W LED road lighting luminaire consisting of single piece, integral, grey powder coated high pressure die-cast aluminium housing, connecting strip, including power driver should having surge protection upto 8KV complete as required suitable for operation on 230 V, 50 Hz AC supply. (Bajaj ENXT P 54L WH CR PC SD (OR) EQUIVALENT as per list of Approved make).(05 years guarantee shall be provided for complete fitting including controller by manufacturer in favour of AAI)	32.00	each	1790.00	57280.00
1.20	Supply of hot dip galvanized octagonal poles with 130 mm Bottom dia , 70 mm top dia , 3 mm thick , base plate of size 200x200x 12 mm,having openable mechanism with L key set,with Double arm standard bracket not less than 500mm length Each and made of 40 mm dia pipe having suitable nipple of size 32mm dia GI pipe to hold the fittings with tilt angle not more than 20 degree including in built arrangement for incoming cable termination with 63A 4P connector and 6A (B curve) SP MCB etc. complete as required as per EIC for the following Heights. a) 6 Mtr	16.00	each	14500.00	232000.00
1.30	Installation of the following GI street light poles with 04 nos foundation bolts of M20X600mm long J type EN 8 grade with 1:2:4 Cement concrete(0.55x 0.55x 1.05 mtr) to the required depth as per special conditions(1:cement :2coarse sand:4graded stone aggregate 20mm nominal size)and necessary base concrete of 1:5:10 for 100mm thickness below the pole (1cement :5 fine sand : 10graded stone aggregate 40mm nominal size) suitable finishing on surface above the ground level etc complete as required. a) 6 Mtr	16.00	Job	3000.00	48000.00
1.40	Supplying and embedding following dia (ISI Marked) HDPE pipe in pole collar/ foundation (during casting) for cable entry including bending the pipe to the required shape complete as required a)63 mm dia	50.00	Mtr	125.00	6250.00

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Awasthi Electric Works(GSTN-09ABAPA1866D1Z5)	
1.50	Installation, testing and commissioning of 45 W/54W LED fitting on existing street light pole with 2 x 1.5 sqmm FRLS PVC insulated copper conductor round cable from cable looping box to fitting Complete as required as per EIC. A) ITC of 45 W LED fittings	32.00	Job	200.00	6400.00
2.00	SH : 2 Supply and LAYING of Cable and End TERMINATION				
2.10	Supply of XLPE/PVC insulated, PVC sheathed aluminium conductor armoured power cable of 1.1KV grade conforming to IS 7098 (Part I) 1978 with upto date amendments etc as required for the following sizes.(Make : As per approved list.) a) 4 x 6 sqmm	1000.00	Mtr	145.00	145000.00
2.20	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. a) 4 x 6 sqmm	33.00	set	250.00	8250.00
2.30	Supplying and laying of following size HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. (a)63 mm dia	900.00	Mtr	145.00	130500.00
2.40	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size in the existing RCC/HUME/Metal/HDPE pipe as required. (a)Upto 35 sq. mm.	950.00	Mtr	35.00	33250.00
3.00	SH : 3 EARTHING				
3.10	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having licking arrangement and watering pipe etc. (with charcoal/coke and salt) as required.	4.00	Job	7000.00	28000.00
3.20	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required	50.00	Mtr	260.00	13000.00
3.30	Providing and fixing 6 SWG dia G.I. Wire on surface or in recess for loop earthing as required	950.00	Mtr	25.00	23750.00
4.00	SH:4 Wiring of Toilet Block				
4.10	Supply, installation, testing and commissioning of pre-wired, fluorescent fitting/compact fluorescent fitting of all types, complete with all accessories and tube etc. directly on ceiling/wall, including connection with 1.5 sq.mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	12.00	each	450.00	5400.00

Signature
12/05/2022

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Awasthi Electric Works(GSTN-09ABAPA1866D1Z5)	
4.20	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in existing surface / recessed PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. (a)Group B	20.00	each	820.00	16400.00
4.30	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed PVC conduit as required (a)2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	20.00	Mtr	175.00	3500.00
4.40	Wiring for light/ power plug with 2X2.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed PVC conduit alongwith 1 No 2.5 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	20.00	Mtr	190.00	3800.00
5.00	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
5.10	5/6 Amps Switch	2.00	each	35.00	70.00
5.20	15/16 Amps Switch	2.00	each	125.00	250.00
5.30	3 pin 5/6 Amps Socket outlet	2.00	each	130.00	260.00
5.40	3 pin 15/16 Amps Socket outlet	2.00	each	65.00	130.00
6.00	Supply & Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	6.00	each	6500.00	39000.00
7.00	Supplying and fixing 3 pin,5 amp ceiling rose on the existing junction box/wooden block including connection etc as required.	18.00	each	125.00	2250.00
8.00	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) (a)8 way(2+6), Double Door	1.00	each	3500.00	3500.00
9.00	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, 10kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
9.10	Single Pole	6.00	each	195.00	1170.00
9.20	Single Pole and neutral	1.00	each	690.00	690.00

Total in Figures

Rs.

808100.00

(Rupees Eight lakh Eight Thousand One Hundred Only)

(R.S.Kanoj)

A.G.M.(Engg-E)