



भारतीय विमानपत्तन प्राधिकरण  
AIRPORTS AUTHORITY OF INDIA

No. AAI/BG/Engg(E)/CW-04/2022-23/514

Dated: 09.05.2022

To

M/s. Kalki Electricals /कल्कि इलेक्ट्रिकल्स,  
#94, 2<sup>nd</sup> Cross, S.T. Bed Layout,  
दूसरा क्रॉस, एस.टी. बिस्तर लेआउट,  
Koramangala कोरमंगला,  
Bangalore-बैंगलोर-560034

कार्य का नाम/Name of work: एएआई आवासीय कॉलोनी, कैम्ब्रिज लेआउट, उल्सूर, बैंगलोर में  
विट्रिफाइड टाइल फर्श और संबद्ध कार्य प्रदान करना: उप: विद्युत कार्य/- Providing Vitrified tiles  
flooring and allied works at AAI Residential Colony, Cambridge Layout, Ulsoor,  
Bangalore: SH: Electrical works

Ref: 1) Your Tender opened on 21.04.2022

Dear Sir,

1. अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से उपरोक्त कार्य के लिए आपके द्वारा दी गई दरों पर रु 1337030/- प्लस जीएसटी की राशि के लिए आपकी निविदा स्वीकृत की गई है स्वीकृत राशि निविदा की समर्थित लागत राशि 1627786.00/- से 17.86% प्रतिशत कम है Your Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, after negotiation the item rates quoted by you totaling to 1337030/- (Rupees Thirteen lakhs thirty seven thousand and thirty only only) which is 17.86% below the justified cost put to tender of Rs. 1627786.00/-
2. सहायक महाप्रबंधक (इंजीनियर- विद्युत) इस कार्य के प्रभारी इंजीनियर होंगे। अनुरोध है कि आप दिनांक 25.05.2022 तक संविदा करार को पूरा करने एवं हस्ताक्षर करने के लिए सहायक महाप्रबंधक (इंजीनियर- विद्युत), भाविप्रा, बैंगलूर के कार्यालय में आएँ। संविदा करार सौ रुपये के गैर न्यायिक स्टैप पेपर पर निष्पादित किया जाएगा जिसकी लागत आपको वहन करनी होगी। AGM Engg-E, AAI, Bangalore-Airport, Bangalore-, shall be the Engineer-in-charge of the work. You are requested to attend the office of AGM Engg-E, AAI, Bangalore within 25.05.2022 to sign and complete the contract agreement. The Contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees- hundred only) and the cost of stamp paper shall be borne by you.



Tel: 25229861


Office of AGM(Engg-E)

3. कृपया इस पत्र की प्राप्ति के दस दिनों के अंदर प्रतिभूति के लिए रु 133703/- जमा करें अन्यथा ये राशि संविदा दस्तावेज की शर्तों के अनुसार काट ली जाएगी। /Please deposit Rs.133703/---(Rupees one lakh thirty three thousand seven hundred and three only) towards security deposit on or before 10 days from the date of issue of this letter, failing which, the same will be deducted as per conditions of tender.
4. अनुरोध है कि आप संविदा श्रमिक (विनियम एवं उन्मूलन) अधिनियम 1970 एवं संविदा श्रमिक (विनियम एवं उन्मूलन) अधिनियम 1971 एवं केंद्रीय एवं राज्य सरकारों के न्यूनतम मजदूरी अधिनियम एवं उनके अंतर्गत बनाए गए नियमों का अनुपालन करें। You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Act 1971 and minimum wages act and rules thereof central and state governments.
5. आप प्रबंधक (इंजीनियर- विद्युत), भाविप्रा, बेंगलूर से तुरंत संपर्क करें जो आपको कार्यस्थल सौंपेंगे। कृपया ध्यान दें, इस कार्य को पूरा करने की अवधि छह महीने की होगी जिसकी गणना यह पत्र जारी करने के दस दिन की जायेगी। /You are also directed to contact Manager (E-E) AAI, Bangalore, immediately who will hand over the site to you. Please note that the time allowed for carrying out the work shall be **06 Months** and same shall be reckoned from 10th days of issue of this letter.
6. अनुबंध के संबंध में किसी भी प्रकार के अग्रिम पत्राचार के लिए इंजीनियर प्रभारी (इंजी -वि ) को संबोधित किया जायेगा। / Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge ie Asst Gen Manager (Engg-E), AAI, Old HAL Airport & KIA.
7. कृपया पावती और स्वीकृति की निशानी के रूप में अधोहस्ताक्षरी को यह प्राप्त करने के बाद इसके साथ संलग्न इस पत्र की दूसरी प्रति, हस्ताक्षर कर अधोहस्ताक्षरी को वापस भेजें। Please acknowledge receipt and return the duplicate copy of this letter enclosed herewith after signing it to the under signed as a token of acceptance.

Thanking you

Encls: Schedule of Quantities

भवदीय/Yours faithfully,

  
 सहायक महाप्रबंधक, इंजीनियरी (इलेक्ट्रिकल),  
 Asst. General Manager (Engg-E)  
 अध्यक्ष, भाविप्रा के लिए एवं उनकी ओर से  
 For and on behalf of the Chairman  
 Airports Authority of India.



Tel: 25229861

Office of AGM(Engg-E)

Government eProcurement System  
 Created By: NARENDRA P  
 Created Date/Time: 21-Apr-2022 04:23 PM  
 Tender Title: Providing vitrified tiles Flooring and allied works at AAI Residential Colony, Cambridge Layout Ulsoor, Bangalore SH Electrical Works  
 Tender ID: 2022\_AAI\_110490\_1

**Tender Inviting Authority: Asst.General Manager (Engg. – Electrical), AAI, Bangalore**

**Name of Work: Providing Vitrified tiles flooring and allied works at AAI Residential Colony, Cambridge Layout, Ulsoor, Bangalore. SH: Electrical Works**

Contract No: 2022\_AAI\_110490\_1

### SCHEDULE OF WORK / ITEM(S)

| Sl.No | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                 | No.of Qty | Units | Rate    | Amount    |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------|---------|-----------|
| 1.00  | Supply, Installation, testing and commissioning of 20W LED type batten fitting as per technical specifications attached, complete directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required. Model Equivalent to HAvels LUMLINE+BS20WLED865SPCSS | 200.00    | Each  | 500.00  | 100000.00 |
| 2.00  | Supply, Installation, testing and commissioning of 1200mm sweep ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, including providing and fixing phenolic laminated sheet cover on the fan box etc. as required                            | 180.00    | Each  | 1600.00 | 288000.00 |
| 3.00  | Supplying and fixing angle holder including connection etc. as required.                                                                                                                                                                                                                                                                      | 430.00    | Each  | 80.00   | 34400.00  |
| 4.00  | Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required.                                                                                                                                                                                                     |           |       |         |           |
| 4.10  | 2 Module Box                                                                                                                                                                                                                                                                                                                                  | 240.00    | Each  | 160.00  | 38400.00  |
| 4.20  | 3 Module Box                                                                                                                                                                                                                                                                                                                                  | 190.00    | Each  | 200.00  | 38000.00  |
| 4.30  | 4 Module Box                                                                                                                                                                                                                                                                                                                                  | 50.00     | Each  | 250.00  | 12500.00  |
| 4.40  | 6 Module Box                                                                                                                                                                                                                                                                                                                                  | 50.00     | Each  | 300.00  | 15000.00  |
| 4.50  | 8 Module Box                                                                                                                                                                                                                                                                                                                                  | 140.00    | Each  | 330.00  | 46200.00  |
| 4.60  | 12 Module Box                                                                                                                                                                                                                                                                                                                                 | 100.00    | Each  | 380.00  | 38000.00  |

|       |                                                                                                                                                                                                                                                                                                           |         |      |         |           |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|---------|-----------|
| 5.00  | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.                                                                                                                                      | 1370.00 | Each | 60.00   | 82200.00  |
| 5.10  | S.P. 5/6 amps, one way modular switch                                                                                                                                                                                                                                                                     | 60.00   | Each | 100.00  | 6000.00   |
| 5.20  | S.P. 5/6 amps, two way modular switch,                                                                                                                                                                                                                                                                    | 240.00  | Each | 120.00  | 28800.00  |
| 5.30  | S.P. 15/16 amps, one way modular switch                                                                                                                                                                                                                                                                   | 470.00  | Each | 110.00  | 51700.00  |
| 5.40  | 3 pin 5/6 amps modular socket outlet                                                                                                                                                                                                                                                                      | 240.00  | Each | 166.00  | 39840.00  |
| 5.50  | 6 pin 15/16 amps modular socket outlet                                                                                                                                                                                                                                                                    | 180.00  | Each | 220.00  | 39600.00  |
| 5.60  | Supplying and fixing of electronic step type regulator                                                                                                                                                                                                                                                    | 50.00   | Each | 110.00  | 5500.00   |
| 5.70  | Supplying and fixing of Call bell Switch                                                                                                                                                                                                                                                                  | 230.00  | Each | 8.00    | 1840.00   |
| 5.80  | Modular Blanking Plate                                                                                                                                                                                                                                                                                    | 50.00   | Each | 1000.00 | 50000.00  |
| 6.00  | Supplying and fixing 10 way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) | 50.00   | Each | 166.00  | 8300.00   |
| 7.00  | Supplying and fixing 20amps rating, 240/415 volts, 10 kA, "C" curve,miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.                                                                | 450.00  | Each | 40.00   | 18000.00  |
| 8.00  | Fixing of 5 to 32amps rating, 240/415 volts, 10 kA, "C" curve,miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.                                                                      | 50.00   | Each | 125.00  | 6250.00   |
| 9.00  | Supplying and fixing call bell/ buzzer suitable for single phase, 230 volts, complete as required.                                                                                                                                                                                                        | 95.00   | Each | 1200.00 | 114000.00 |
| 10.00 | Supply and Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.                                                                                                                                                    |         |      |         |           |

|                                  |                                                                                                                                                                                                      |        |      |        |            |
|----------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--------|------------|
| 11.00                            | Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required |        |      |        |            |
|                                  |                                                                                                                                                                                                      | 380.00 | Mtr  | 200.00 | 76000.00   |
| 11.10                            | 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire                                                                                                                                                           | 900.00 | Mtr  | 220.00 | 198000.00  |
| 11.20                            | 2 X 4 sq. mm + 1 X 4 sq. mm earth wire                                                                                                                                                               | 50.00  | Each | 10.00  | 500.00     |
| 12.00                            | Supply of 20mm PVC Junction Box                                                                                                                                                                      |        |      |        |            |
| Total in Figures (Excluding GST) |                                                                                                                                                                                                      |        |      |        | 1337030.00 |

(Rupees in words: Thirteen lakhs thirty seven thosuand and thirty only)

  
 (P. Narendra)  
 Asst. General Manager (E-E)  
 AAI, Bangalore Airport