



भारतीय विमानपत्तन
प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

संदर्भ संख्या:

Ref. No.: AAI/ENGG/NER/DGM(E-C)/Misc-Civil/W. O.-2/22-23

दिनांक:

Date: 27-6-22

सेवा मे, / To,

मैसर्स बिनोद कुमार प्रसाद / M/s BINOD KUMAR PRASAD
बजार पट्टी वार्ड न. 9, / Bazar Patty, Ward No.-9,
नार्थ लखिमपुर / North Lakhimpur
जिला - जोरहाट असम / District - LAKHIMPUR, ASSAM
पिन नंबर / Pin No.-787001 e-mail:- prasadbino002@gmail.com

Sub: - Misc. Civil work regarding improvement of ASTI & B-Block Colony i/c. provision of new car parking shed at Guwahati.

निविदा आई.दि./ Tender ID: 2022_AAI_114117_1

महोदय /Sir (s),

सीपीपी पोर्टल के माध्यम से 20/05/2022 को खोली गई अपनी तकनीकी बोली और 31/05/2022 को खोली गई वित्तीय बोली का संदर्भ लें।

Reference your technical bid opened on 20/05/2022 and financial bid opened on 31/05/2022 through CPP Portal.

- उपरोक्त कार्य के लिए आपकी मदद दर ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत मद दरों पर कुल रु.19,00,694/- (उन्नीस लाख छह सौ चौरानवे रुपये मात्र) (जीएसटी को छोड़कर) स्वीकार की जाती है। जो कि अनुमानित लागत निविदा के लिए रखी गई राशि रु.27,53,000/- (जीएसटी को छोड़कर) रुपये से 30.96% कम है।

Your Item Rate e-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totalling of Rs.19,00,694/-/- (Rupees Nineteen Lakh Six Hundred and Ninety-four Only) (Excluding GST) which is 30.96 % below the estimated cost put to tender of Rs. 27,53,000/- excluding GST.

- उप महाप्रबंधक (अभि-सि), भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उ.पू. क्षेत्र, इस कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु उप महाप्रबंधक (अभि-सि), भारतीय विमानपत्तन प्राधिकरण, क्षेत्रीय मुख्यालय, उ.पू.क्षेत्र के कार्यालय में इस पत्र के जारी होने की तारीख से 15 दिनों के भीतर उपस्थित हों। संविदा करार रु.100/- (सौ रुपये मात्र) के न्यायिकेतर (नॉन ज्युडिशियल) स्टाम्प पेपर पर बनाया जाएगा और स्टाम्प पेपर की लागत आपको वहन करनी होगी।

Deputy General Manager (E-C), AAI, RHQ, NER, shall be the Engineer-in-Charge of the work. You are requested to attend office of the Engineer-in-charge i.e. Deputy General Manager (E-C), AAI, RHQ, NER, to sign and complete the contract agreement within 15 days from the date of issue of this letter. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

- कृपया इस पत्र के जारी होने के 10 दिन के भीतर शेष प्रतिभूति जमा के रूप में रु 1,35,009/- (एक लाख पैंतीस हजार और नौ रुपये मात्र) जमा करें, अन्यथा सुरक्षा जमा राशि (SD) को RA बिल से काट लिया जाएगा, वही इस राशि की कटौती संविदा दस्तावेज (पृष्ठ 18), एन आई टी पर जी सी सी पर दी गई शर्त 1 (A) के अनुसार आपके चालु बिलों से काट ली जाएगी।

AC



भारतीय विमानपत्तन
प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

Please deposit **Rs.1,35,009/- (Rupees One Lakh Thirty-five Thousand and Nine only)** towards security deposit within 10 (Ten) days from the date of issue of this work order, on failing which the same will be deducted from the RA bill, as per condition of Clause No. 1 (A) of GCC (page no.18) of contract document.

4. आपसे अनुरोध है कि संविदा श्रमिक (विनियमन एवं समापन) अधिनियम 1970 और संविदा श्रमिक (विनियमन एवं समापन) केन्द्रीय नियमावली 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण मजदूर कल्याण उपकर अधिनियम 1996 और केंद्र और राज्य सरकार के नियमों के प्रावधान का अनुपालन करें, जो निविदा के GCC के धारा 19, 19A, 54/55 पृष्ठ पर निर्दिष्ट है।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction workers Welfare Cess Act 1996 as specified in Clause 19, 19A on Page 54/55 of GCC of tender and rules of Central and State Government.

5. आपको निर्देश दिए जाते हैं कि आप सहायक महाप्रबंधक (ई-सी), आरएचक्यू, एनईआर एएआई, गुवाहाटी से तत्काल सम्पर्क करें जो कि आपको कार्यस्थल सुपद करने की व्यवस्था करेंगे।

You are also directed to contact Assistant General Manager (E-C), RHQ, NER AAI, Guwahati immediately who will arrange to hand over the site to you.

6. कृपया यह नोट कर लें कि काम करने का समय 05 (पांच) महीने, जिसकी गणना कार्यादेश पत्र जारी होने की तिथि के 10वें दिन या साइट को सौंपने की तिथि, जो भी पहले हो, से की जाएगी।

Please note that the time allowed for carrying out the work shall be 05 (Five) Months which shall be reckoned from the 10th day of the date of issue of the letter of work order or date of hand-over of the site, whichever is earlier.

7. संविदा के संबंध में आगे किया जाने वाला पत्राचार सामान्यतः इंजीनियर प्रभारी से किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.

8. कृपया पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप विधिवत हस्ताक्षर करके हमें वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

9. यदि कोई विसंगति पाई जाती है, तो अंग्रेजी संस्करण को सही माना जाएगा।


In case any discrepancy is found, then English version will be taken as correct.

धन्यवाद/ Thanking you.

Encl:

1. मात्रा की अनुसूची / Schedule of Quantities

भवदीय / Yours faithfully,


21/6/22

(शिवु जोश) / (Shibu Jose)

उप महाप्रबंधक (अभि-सि) / Dy. Gen. Mgr. (E-C)

भा. वि. प्रा., क्षे.मु. उ.पु.क्षे. / AAI, RHQ, NER,

गुवाहाटी / Guwahati. 781015

For and on behalf of the Chairman, AAI

प्रतिलिपि/ Copy To:-
Agreement.

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AGM(E-C), AAI, RHQ, NER, Ghy

Name of Work: Misc. Civil work regarding improvement of ASTI & B-Block Colony i/c. provision of new car parking shed at Guwahati.

Tender ID:2022_AAI_114117_1

Contract No: AAI/RHQ/NER/Misc./COL/NER/22-23

Name of
the Bidder/
Bidding
Firm /
Company :

Binod Kumar Prasad

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender.
Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE EXCLUDING GST In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT without GST Rs. P	TOTAL AMOUNT InWords
1	2	4	5	13	53	55
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	29.00	Cum	70.00	200.00	INR Two Thousand & Thirty Only
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	25.00	Cum	50.00	120.00	INR One Thousand Two Hundred & Fifty Only
3	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift upto 1.5 m. All kinds of soil.	80.00	Sqm	60.00	480.00	INR Four Thousand Eight Hundred Only

4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	22.00	Cum	1000.00	22000.00	INR Twenty Two Thousand Only
5	a) Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand(zone-III) : 8 graded stone aggregate 40 mm nominal size).	8.00	Cum	5000.00	40000.00	INR Forty Thousand Only
6	b) Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	29.00	Cum	6000.00	174000.00	INR One Lakh Seventy Four Thousand Only
7	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	1.00	Cum	6200.00	6200.00	INR Six Thousand Two Hundred Only
8	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work above plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	2.00	Cum	6000.00	12000.00	INR Twelve Thousand Only
9	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	71.00	Sqm	220.00	15620.00	INR Fifteen Thousand Six Hundred & Twenty Only
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	100.00	Kg	83.00	8300.00	INR Eight Thousand Three Hundred Only
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.	200.00	Kg	83.00	16600.00	INR Sixteen Thousand Six Hundred Only
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	5.00	Cum	6500.00	32500.00	INR Thirty Two Thousand Five Hundred Only
13	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	2.00	Cum	6500.00	13000.00	INR Thirteen thousand Only

14	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	65.00	Sqm	300.00	19500.00	INR Nineteen Thousand Hundred Only
15	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes.	1020.00	Kg	140.00	142800.00	INR One Lakh Forty Two Thousand Eight Hundred
16	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	37.00	Sqm	612.00	22644.00	INR Twenty Two Thousand Hundred & Forty Four O
17	Providing and fixing factory made Fiberglass Reinforced plastics (F.R.P.) chajja 4mm thick of required colour, size and design made by Resin Transfer Moulding (RTM) Machine Technology, resulting in void free compact laminate in single piece, having smooth gradual slope curvature for easy drainage of water and duly reinforced by 2nos. vertically and 1nos. horizontally 50x2mm thick M.S. flat with 12mm in built hole for grouting on the existing wall along with the 50mm flanges duly inserted and sealed in the wall complete in one single piece casted monolithically, including all necessary fittings. The FRP Chajja should be manufactured using unsaturated Polyester resin as per IS:6746 duly reinforced with fibre glass chopped strand mat (CSM) as per IS:11551 complete with protective Gel coat U/V coating on Top for complete resistance from the extreme of temperature, weather & sunlight. Note - Only plan area of chajjas shall be measured for making payment	50.00	Sqm	4000.00	200000.00	INR Two Lakh Only
18	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	20.00	Sqm	250.00	5000.00	INR Five Thousand Or
19	15 mm cement plaster on rough side of single or half brick wall of mix : 1:6 (1 cement: 6 coarse sand)	50.00	Sqm	250.00	12500.00	INR Twelve Thousand F Hundred Only

20	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	50.00	Sqm	110.00	5500.00	INR Five Thousand Five Hundred Only
21	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement :2 coarse sand : 4 stone aggregate 10 mm and down gauge) including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design In 75x75 mm deep chase	125.00	Mtr	120.00	15000.00	INR Fifteen Thousand On
22	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, 75 mm diameter	50.00	Mtr	175.00	8750.00	INR Eight Thousand Seven Hundred & Fifty Only
23	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, 110 mm diameter	100.00	Mtr	300.00	30000.00	INR Thirty Thousand Only
24	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS :5382 leaving 10 mm gap for thermal expansion. 75x75x75 mm	30.00	Nos	130.00	3900.00	INR Three Thousand Nine Hundred Only
25	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS :5382 leaving 10 mm gap for thermal expansion. 110x110x110 mm	60.00	Nos	200.00	12000.00	INR Twelve Thousand On
26	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS :5382 leaving 10 mm gap for thermal expansion. Bend 87.5° - 75 mm bend	30.00	Nos	80.00	2400.00	INR Two Thousand Four Hundred Only
27	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS :5382 leaving 10 mm gap for thermal expansion. Bend 87.5°- 110 mm bend	60.00	Nos	40.00	2400.00	INR Two Thousand Four Hundred Only

28	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge : Above 40 mm nominal bore	180.00	Mtr	120.00	21600.00	INR TwentyOne Thousand Six Hundred Only
29	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	24.00	Cum	300.00	7200.00	INR Seven Thousand Two Hundred Only
30	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall 20 mm nominal outer dia. Pipes.	10.00	Mtr	150.00	1500.00	INR One Thousand Five Hundred Only
31	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall 25 mm nominal outer dia. Pipes.	180.00	Mtr	170.00	30600.00	INR Thirty Thousand Six Hundred Only
32	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall 50 mm nominal outer dia. Pipes.	225.00	Mtr	500.00	112500.00	INR One Lakh Twelve Thousand Five Hundred Only
33	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge : External work 75 mm nominal inner dia. Pipes.	185.00	Mtr	1600.00	296000.00	INR Two Lakh Ninety Six Thousand Only



34	Providing and laying factory made chamfered edge Cement Concrete paver blocks In foot path, park & lawns driveway or light & traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of course sand, compacting and proper embedding/ laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, all complete as per manufacturer's specifications & direction of Engineer in-Charge. 60mm thick Cement concrete paver block of M-35 grade with approved colour, design & pattern	55.00	Sqm	900.00	49500.00	INR Forty Nine Thousand Five Hundred Only
35	Providing & fixing in position Phenol bonded Bamboowood flooring with planks of sizes 14mm thick, 1800mm length (minimum) and 100 mm wide(minimum), in approved colour, texture and finish, having Performance Appraisal Certificate (PAC) issued by Building Materials & Technology Promotion Council (BMTPC). The flooring shall be fixed with tongue and groove interlocking system, with underlayment of 4mm thick expanded polyethylene foam sheets having density 40kg/cum, over prepared surface with necessary quarter round planks of size 1900mm x 18mm and door reducer of size 1900mm x 44mm, wherever required. The bamboowood planks shall have minimum density of 1000 Kg/cum & minimum Hardness 1000 Kgf. with Eco friendly UV coating, all complete as per direction of the Engineer in-charge.	20.00	Sqm	4750.00	95000.00	INR Ninety Five Thousand Only
36	Providing & fixing in position Phenol bonded Bamboowood wall cladding at all height with planks of sizes 10mm thick, 1800mm length (minimum) and 130 mm wide (minimum), in approved colour, texture and finish, having Performance Appraisal Certificate (PAC) issued by Building Materials & Technology Promotion Council (BMTPC), with necesasary profiled edges fixed with 40mm SS screws 5 nos in each tile to frame work made of second class teak wood of size 20x15 mm in centre of each tile and bottom and top of work height, 40x15mm placed at ends of each tile. The cladding shall be laid over backlayment of 1.00 mm thick expanded polyethylene foam of density 40kg/cum in two layers, first layer on wall surface before fixing wooden frame and second layer on frame under cladding. The bamboowood planks shall have minimum density of 1000 Kg/cum & minimum Hardness 1000 Kgf. with Eco friendly UV coating, all complete as per direction of the Engineer in-charge.	41.00	Sqm	5100.00	209100.00	INR Two Lakh Nine Thousand One Hundred Only

37	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m) having 50 no rounds per 6 metre length, upto 3m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) /Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	260.00	Mtr	260.00	67600.00	INR Sixty Seven Thousand Only
38	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	700.00	Kg	110.00	77000.00	INR Seventy Seven Thousand Only
39	Supplying and fixing Vista vertical venetian blinds/equivalent with head rail made out of white powder coated aluminium extruded section and louver width of 80 mm.Dust guard range of fabric (89 mm wide) with fabric holder is fixed to the runners for smooth operation including all fittings etc required.	42.00	Sqm	1300.00	54600.00	INR Fifty Four Thousand Only
40	Providing & fixing of 80 mm CPVC Ball Valve of approved make and quality as per direction and satisfaction of EIC.	3.00	Nos	10000.00	30000.00	INR Thirty Thousand
41	Providing & fixing of 50 mm CPVC Ball Valve of approved make and quality as per direction and satisfaction of EIC.	20.00	Nos	890.00	17800.00	INR Seventeen Thousand Only
Total in Figures					1900694.00	INR Nineteen Lakh Six & Ninety Four Only
Quoted Rate in Words					INR Nineteen Lakh Six Hundred & Ninety Four Only	


 ADM 21
 21/6/22