



No: AAM/ENGG/ELEC/AMED-II/Cable Laying/ 2022-23/A-20

Date: 15.07.2022

To

M/s. VK Sam Engineering
No. 5, Rajiv Gandhi Nagar,
Ekkaduthangal,
Chennai – 600 032.

Name of Work: "Miscellaneous Electrical Works at Chennai Airport. SH: Providing Standby LT Power Supply at T1 & T4 Carpark area external installations at Chennai Airport, Chennai – Balance Work".

1. Ref: - Tender ID. 2021_AAI_114371_1.
Your E-Tender Opened on 04.05.2022.

Dear Sirs,

1. Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs.20,86,522.00 (Rupees Twenty Lakhs Eighty-Six Thousand Five Hundred and Twenty-Two Only) Excluding GST** Which is 10.33% Below the Estimated Cost put to tender Rs.23,27,012.00 (Rupees Twenty-Three Lakhs Twenty-Seven Thousand Twelve Only) Excluding GST.
2. Joint General Manager Engineering (Elec)-III EMD, Operational Office, Airports Authority of India, Chennai Airport, Chennai – 600016 shall be the Engineer-in charge of the work. You are requested to attend the office of Joint General Manager Engineering (Elec)-III, AAI, Chennai Airport on or before 25.07.2022 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs.100/- (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.
3. You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules there of Central and State Governments.
4. You are also directed to contact Asst. Manager Engineering (Electrical) Airport Maintenance Electrical Division II, Operational Office, Airports Authority of India, Chennai Airport immediately who will arrange to hand over the site to you.
5. Please note that the time allowed for carrying out the work shall be **02 (Two) Months** and same shall be reckoned from 7th day of issue of work order.

(Page 1 of 2)

चेन्नई एयरपोर्ट चेन्नई 600 016

दूरभाष:- 91-(044)-22564583

ईमेल:natarajan@aai.aero

Chennai Airport, Chennai-600 016

Tel: -91-(044)-22564583


e-Mailsnatarajan@aai.aero



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

6. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in charge.
7. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Yours faithfully,


S.NATARAJAN.

Jt. General Manager (Engg.-Elect.)-III
AAI Chennai.
AAI Chennai.

Encl: Schedule of Quantities (02 Pages)

(Page 2 of 2)

चेन्नै एयरपोर्ट चेन्नै 600 016

ईमेल: snatarajan@aai.aero

Chennai Airport, Chennai-600 016

दूरभाष:- 91-(044)-22564583

Tel: -91-(044)-22564583

e-Mailsnatarajan@aai.aero



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
चन्न एयरपोर्ट:: चेन्नै 600 016
CHENNAI AIRPORT:: CHENNAI 600 016


SCHEDULE OF QUANTITY

NAME OF WORK : Miscellaneous Electrical Works at Chennai Airport. SH: Providing Standby LT Power Supply at T1 & T4 Carpark area external installations at Chennai Airport, Chennai - Balance Work.

Sl. No.	Description of Items	Qty	Rate	Unit	Amount
SITC of feeder pillar, SITC of Change over Switch, cable laying, End Termination and Earthing etc.					
1	Fabrication, Supply, Installation, Testing & Commissioning of Outdoor MV Feeder Pillar Panel with double door arrangement, outer shell made up of 3mm and inner front, top covers and partitions made up of 2mm CRCA sheet steel, door dust tight, vermin proof, totally enclosed, cubicle type, floor mounting, free standing, including providing and fixing 400A Aluminium Bus bar with all accessories welding and earthing suitable for operation at 433 V, 3 phase, 4 wire, 50 Hz, A.C. Power Supply System complete with all accessories, interconnection, connection, earthing, painting, grouting, providing pedestal, Cable Entry provision etc. as required i/c dismantling the old panel and handed over to AAI store and providing required brick pedestal etc. complete and comprising of following:- a. 200Amps Change over Switch and 200A, 35 KA, 4P MCCB with Thermal magnetic releases as incomer with R,Y,B,ON, OFF, TRIP indication lamps, resin cast CT's with multifunction meter - 1 set as incomer. b. 63A, 25KA, 4P MCCB with thermal magnetic releases as incomer with ON, OFF, TRIP indication lamps, resin cast CT's with digital meter as outgoing - 6 Sets. As outgoing. c. TP contact MNX80, L&T or equivalent contractor with 24 hrs. digital timer along with 2A, SP MCB and control wiring for Street light/Hi-mast lighting control - 1 set. with all necessary accessories etc. complete as required. (a to c above)	1 Job	3,76,350.00	Job	3,76,350.00
2	Supply and fixing of 100amps Four pole ON Load Change over switch including Extendable handle in the existing feeder pillar including connection etc., as required L&T make Cat No.CO110000000 or equivalent etc., as required.	4 Nos	8,075.00	Each	32,300.00
3	Supply and fixing of 200amps Four pole ON Load Change over switch including Extendable handle, in the existing feeder pillar including connection etc., as required. L&T make Cat No. CO220000000A or equivalent etc., as required.	2 Nos	15,675.00	Each	31,350.00
4	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc., direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. a) OD - 63mm (Nominal) & ID-51mm (Nominal) b) OD - 120mm (Nominal) & ID-103mm (Nominal)	500 Mtrs 300 Mtrs	167.00 271.00	Metre	83,500.00 81,300.00
5	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required. a) Upto 35 sq. mm b) Above 35 sq. mm and upto 95 sq. mm	400 Mtrs 450 Mtrs	34.00 48.00	Metre	13,600.00 21,600.00
6	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. a) up to 35 sq. mm (clamped with 1mm thick saddle) b) Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	300 Mtrs 120 Mtrs	57.00 67.00	Metre	17,100.00 8,040.00
7	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required.				

Sl. No.	Description of Items	Qty	Rate	Unit	Amount
	a) Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	200 Mtrs	57.00	Metre	11,400.00
8	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE armoured aluminium conductor cable of 1.1 KV grade as required.				
	a) 3.5 x 35 Sq.mm.	16 Sets	238.00	Set	3,808.00
	b) 3.5 x 50 Sq. mm.	4 Sets	333.00	Set	1,332.00
	c) 3.5 x 70 Sq.mm.	4 Sets	428.00	Set	1,712.00
	d) 3.5 x 95 Sq.mm.	10 Sets	475.00	Set	4,750.00
9	Supply and making straight through cable joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated PVC sheathed/XLPE Aluminium conductor power cable of 1.1KV grade as required.				
	a) 3.5 x 35 Sq.mm.	4 Jobs	2,517.00	Job	10,068.00
	b) 3.5 x 50 sq.mm	2 Jobs	2,571.00	Job	5,142.00
	c) 3.5 x 70 sq.mm	2 Jobs	2,945.00	Job	5,890.00
	d) 3.5 x 95 sq.mm	4 Jobs	2,945.00	Job	11,780.00
10	Providing & Laying of 100mm dia 'B' class G.I pipe with GI fittings i/c Concrete road cutting, excavation, laying the G. I Pipe in depth of 30cm, re-filling with cement concrete 1:2:4 and making good the same etc., as required.				
	a) 100 mm dia.	125 Mtrs	1,686.00	Metre	2,10,750.00
11	Providing & Laying of 100mm dia 'B' class G.I pipe with GI fittings i/c cutting Bituminous surface, (30cm deep) re-filling with cement concrete and making good surface the same as required.				
	a) 100 mm dia.	125 Mtrs	1,505.00	Metre	1,88,125.00
12	Earthing with Copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement, 20mm GI watering pipe of 2.7 metre long and 40mm GI Pipe of 2.7metre long for supply and laying of 25 X 5mm thick copper strip with charcoal/ coke and salt etc., as required.	25 Jobs	21,850.00	Job	5,46,250.00
13	Constructing masonry Chamber 60x60x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) , i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mmnominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design etc., as required.	20 Jobs	5,225.00	Job	1,04,500.00
14	Supplying and laying 25 mm X 3 mm thick copper strip inside of 40mm G.I. Pipe ground/surface as strip earth electrode, including connection/ terminating with nut, bolt, spring, washer etc. as required. (Jointing shall be done by bolt & spring washer spaced at 50mm) overlapping and with 2 sets of brass nut etc., as required.	120 Mtr	1425.00	Metre	1,71,000.00
15	Providing and fixing 25 mm X 3 mm copper strip on surface or in recess for connections etc. as required	150 Mtr	760.00	Metre	1,14,000.00
16	Replacement of existing broken and damaged RCC/CI earth pit enclosure with new 10mm thick MS chequered cover plate with opening arrangement size of 300mm x 300mm including civil repair works and making good surface the same etc., as required.	25 Job	1,235.00	job	30,875.00
Total Rs.					20,86,522.00

(Rupees Twenty Lakh Eighty Six Thousand Five Hundred and Twenty Two Only)
(Excluding GST)


 (S. NATARAJAN)
 Jt. Gen. Manager (E-E) - III

Signature Not Verified

Digitally signed by KANAPARTY RAMESH BABU
 Date: 2024.07.23 17:11:57 IST
 Location: eProcurement System for Central PSUs