



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

संदर्भ संख्या : AAI/RHQ/NER/AGM (E-E)/TEZ-WO- BHS /2022-23/
Ref. No. :

दिनांक : 22.07.2022
Date. :

सेवा में /To,

M/s Gannon Dunkerley & Co. Ltd.,
New Excelsior building, 3rd Floor,
A K Nayak Marg, Fort, Mumbai-400001
email id: gannon.dunkerley@yahoo.com
Ph. No.: 09339902016 / 08777291050

विषय: “बैगेज हैंडलिंग कन्वेयर का प्रतिस्थापन और संशोधन (एसएच: तेजपुर हवाई अड्डे पर 05 साल के एआईसीएमसी के साथ बैगेज हैंडलिंग सिस्टम की डिजाइन और आपूर्ति, स्थापना, परीक्षण और कमीशनिंग)।”

Sub: Work Order for “Replacement and Modification of Baggage Handling Conveyors (SH: Design & Supply, Installation, Testing and Commissioning of Baggage Handling System with 05 years AICMC at Tezpur Airport).”

रेफरी: ई-Bid. 2022_AAI_116076_1 आपकी कीमत बोली 07.07.2022 को खोली गई।

Ref: E-Bid no. 2022_AAI_116076_1, your price bid opened on 07.07.2022.

महाशय/Dear Sir(s),

1. ऊपर उपरोक्त कार्य के लिए आपकी निविदा एतद्वारा अध्यक्ष, एएआई की ओर से आपके द्वारा उद्धृत मद दरों पर रु. 34,02,900.00 (रुपए चौतीस लाख दो हजार नौ सौ केवल) राशि के लिए स्वीकार की जाती है, जो कि एसआईटीसी की ओर उचित लागत रु. 50,16,000.00 से 32.16% कम है और 5 साल एआईसीएमसी के लिए रु. 6,69,409.00 एएआई की पूर्व-निर्धारित दर पर कुल रु. 40,72,309.00 (जीएसटी को छोड़कर)।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, AAI at the item rates quoted by you, for an amount of Rs. 34,02,900.00 (Rupees Thirty Four Lakhs Two Thousand Nine Hundred Only) towards SITC which is 32.16% below the Justified cost of Rs. 50,16,000.00 and Rs. 6,69,409.00 is for 5 years AICMC at AAI's pre-decided rate, totaling Rs. 40,72,309.00 (Excluding GST).

2. संयुक्त. महाप्रबंधक (अभि-विद्युत), भारतीय विमानपत्तन प्राधिकरण, आरएचक्यू, एनईआर, गुवाहाटी - 781015 कार्य के इंजीनियर-इन-चार्ज हैं, और सहा. महाप्रबंधक (अभि-विद्युत), भा.वि.प्र., क्षेत्रीय मुख्यालय, उ.पू.क्षे गुवाहाटी-15, उनके अधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि आप संयुक्त. महाप्रबंधक (अभि-विद्युत), भारतीय विमानपत्तन प्राधिकरण, आर एच क्यू-उत्तर पूर्वी क्षेत्र, गुवाहाटी - 781015 के कार्यालय में अपनी ओर से हस्ताक्षर करने के लिए अधिकार प्राप्त प्रतिनिधि को अनुबंधित समझौते पुर्न करने के लिए 01.08.2022 तक तैनात करें। करार अनुबंध को रु 100/- के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा। और स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी।

10/07/2022

Contd...2/-

The Jt. General Manager (E-E), Airports Authority of India, RHQ, NER, Guwahati - 781015 is the Engineer-In-Charge of the work and Asstt. General Manager (E-E), AAI, RHQ, NER, Ghy-15 will be his authorized representative. You are requested to depute your accredited representative empowered to sign the contract agreement on your behalf to attend the office of the Jt. General Manager (E-E), Airports Authority of India, RHQ, NER, Guwahati - 781015 by 01.08.2022 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Hundred Only) and the cost of the stamp paper shall be borne by you.

3. आपके टेंडर से साथ प्राप्त बयाना राशि रु. **1,00,320.00 (रुपया एक लाख तीन सौ बीस मात्र)** को संविदा दस्तावेज के पृष्ठा 16 पर दी गई शर्त 1(A) के अनुसार सुरक्षा जमा के हिस्से के रुप में परिवर्तित कर दिया गया है। कृपया इस पत्र के जारी होने के 10 दिन में सुरक्षा जमा के लिए रु. **3,06,911.00 (रुपये तीन लाख छह हजार नौ सौ ग्यारह केवल)** जमा करा दें, ऐसा नहीं करने पर संविदा दस्तावेज के पृष्ठा 16 पर दी गई खण्ड 1 (A) के अनुसार आपके रनिंग बिल से काट दी जाएगी।

The earnest money amount of **Rs. 1,00,320/- (Rupees One Lakhs Three Hundred Twenty Only)**, received along with your tender has been converted as part of security deposit as per **condition clause no. 1 (A)** of the contract document. Please deposit **Rs. 3,06,911.00 (Rupees Three Lakhs Six Thousand Nine Hundred and Eleven only)** towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per **Tender Clause-1 (A) on page 16** of the contract document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) केंद्रीय नियम, 1971 और न्यूनतम मजदूरी अधिनियम और नियम केंद्र / राज्य सरकारों के प्रावधानों का पालन करें।

You are requested to comply with the provisions of contract labour (Regulation & Abolition) Act of 1970 and contract labour (Regulation & Abolition) Central Rules, 1971 & Minimum Wages Act and Rules thereof Central/ State Governments.

5. आपको प्रबंधक (अभि-विद्युत), भा.वि.प्र., तेज़पुर हवाई अड्डा, तेज़पुर, से तुरंत संपर्क करने के लिए निर्देशित दिया जाता है जो आपको साइट सौंपने की व्यवस्था करेगा। कृपया ध्यान दें कि कार्य पूरा होने के लिए अनुमत समय 04 (चार) महीना है जिसे **31.07.2022** से गीणना जायेगा।


You are also directed to contact the Manager (E-E), AAI, Tezpur Airport, Tezpur, immediately who will arrange to handover the site to you. Please note that the time allowed for completion of the work is **04 (four) Months** which shall be reckoned from **31.07.2022**.

6. इस काम के लिए आपकी निविदा इस पुरस्कार पत्र के साथ समझौते का हिस्सा बन जाएगी। अन्य सभी नियम एवं शर्तें एनआईटी के अनुसार होंगी।

Your tender for this work shall form part of the agreement along with this award letter. All other terms & conditions shall be as per NIT.

7. अनुबंध के संबंध में आगे कोई पत्राचार आम तौर पर संयुक्त. महाप्रबंधक (अभि-विद्युत), भारतीय विमानपत्तन प्राधिकरण, आरएचक्यू, एनईआर, गुवाहाटी - 781015 को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Jt. General Manager (E-E), AAI, RHQ, NER, Guwahati Airport - 781015.


ए.जी.एम(ई-ई) / AGM(E-E)
ए.ए.आई / AAI, आर.एच.क्यू / RHQ
एन.ई.आर / NER
गुवाहाटी / GUWAHATI

Contd... 3/-

8. कृपया पीओ की प्राप्ति की पावती दें। और इस पीओ की डुप्लीकेट कॉपी को आपकी स्वीकृति के टोकन के रूप में आपके द्वारा विधिवत हस्ताक्षरित और मुहर लगा कर लौटा दें।/ Please acknowledge the receipt and return the duplicate copy of this order duly signed & stamped by you as a token of your acceptance.
9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी ।
In case any discrepancy is found, then English version will be taken as correct.
धन्यवाद/Thanking you,

Yours faithfully

(कैशिंग होनपम)

सहायक महाप्रबंधक (अभि-विद्युत)
Asst. General Manager (E-E)

कृते अध्यक्ष की ओर से,

For and on behalf of CHAIRMAN
भा.वि.प्र., क्षेत्रीय मुख्यालय, उ.पू.क्षे गुवाहाटी-15
AAI, RHQ, NER, Guwahati-15

ए.जी.एम(ई-ई) / AGM(E-E)
ए.ए.आई / AAI, आर.एच.क्यू / RHQ
एन.ई.आर / NER
गुवाहाटी / GUWAHATI


अनुलग्नक: मात्रा का बिल / Encl: Bill of Quantities.

Bill of Quantities

Name of Work: Replacement and Modification of Baggage Handling Conveyors (SH: Design & Supply, Installation, Testing and Commissioning of Baggage Handling System with 05 years AICMC at Tezpur Airport).

Tender Id : 2022_AAI_116076_1

Sl.No	Item No.	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
1.00	1	ENDLESS SLAT CONVEYOR (ARRIVAL) Design, supply, installation, testing & commissioning of heavy duty Endless Slat Type Flat Arrival Baggage Conveyor System (Approx. 42.6 Mtr.) having nominal useful width of 950mm, having rubber slats black in colour with smooth top of PVC / PU / Rubber, antistatic, flame retardant, height 450mm from finished floor level and speed of 24- 30 mtrs / min. The carousel shall have die-cast aluminium chain block friction type suitable capacity drive unit complete with overlapping slats finished chain track unit frame work tension adjustment device stainless steel side covering (inner & outer side panels of 1.6 mm thick stainless steel for PAX area and 2 mm thick MS for non PAX area) in the passenger area as well as in the non passenger area, toe-kick plate at inner & outer sides, infill, rubber slat of suitable dimensions with MS slat support having live loading capacity of 35 kgs per linear meter and all other accessories including cutting and drilling of holes, equipment grouting, earthing, necessary wiring, connection / interconnection etc. as required for successful commissioning of baggage conveyor system complete as per the direction of Engineer-in-charge. (with friction drive as per Technical Specification).	42.60	Meter	44000.00	1874400.00
2.00	2	CONTROL PANEL: ARRIVAL SITC of sheet steel clad (14 SWG) dust and vermin proof, wall / floor mounted PLC based Control Panel with locking arrangement suitable for operation (for 1 No. arrival conveyor belts) on 415 volts, 3 phase, 50Hz AC supply, digital voltmeter & ammeter with selector switches, LED phase indication lamps, ON / OFF Timer (0-180 sec) and buzzer, suitable rating 4P MCCB incomer, Busbar, TP MPCB, control MCB, ELCB, power contactors, emergency stop switch, control and power wiring, soft starter mechanism, earthing etc. complete as required as per the direction of Engineer-in-charge.	1.00	Job	125000.00	125000.00
3.00	3	DEPARTURE CONVEYOR SYSTEM Design, supply, installation, testing and commissioning of heavy duty Slider Bed Departure Conveyor of 16.6 mtr. Long connector conveyor + 12.6 mtr. Long Transport + 3 Mtr. long Take-away conveyor measured across the center line having frame 1050mm (useful width not less than 1000 mm) and 400 mm height from finished floor level for easy handling of passenger baggage weighing 35 kg. per linear mtr at speed of 21 to 25 mtr/min. complete with PVC belt on bed construction as specified i/c drive unit, end pulleys, take up pulley, side panels (1.6 mm thick of stainless steel for PAX area and 2 mm thick MS for non PAX area) and all other accessories for successful commissioning of the conveyor as per above length, specifications & drawings.	32.20	Meter	27500.00	885500.00
4.00	4	CONTROL PANEL: Departure SITC of sheet steel clad (14 SWG) dust and vermin proof, wall / floor mounted PLC based Control Panel with locking arrangement suitable for operation on 415 volts, 3 phase, 50Hz AC supply, digital voltmeter & ammeter with selector switches, LED phase indication lamps, ON/OFF Timer (0-180 sec) and buzzer, suitable rating 4P MCCB incomer, Busbar, TP MPCB, control MCB, ELCB, power contactors, emergency stop switch, control and power wiring, earthing etc. complete as required as per the direction of Engineer-in-charge.	1.00	Job	200000.00	200000.00
5.00	5	GRAVITY ROLLER CONVEYOR Design, supply, installation, testing and commissioning of Gravity Roller structure of 2mtr. in length measured along the centre line complete in all respects i/c frame section, rollers, supports as per specifications / drawings as approved by Engg.-in-charge.	1.00	Job	40000.00	40000.00


 E. J. E. M. (E. J. E. M.) / AGM(E-E)
 ए. जे. ई. एम. / आई. आर. एच. क्यू. / RHQ
 एन. ई. आर. / NER
 भारतीय विमानपत्तन प्राधिकरण

मुख्यालय, ३.५.२०२२

महाप्रबंधक (अभि-विद्युत), भारतीय विमानपत्तन प्राधिकरण, आर एच क्यू-३०२२

Sl.No	Item No	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
6 00	6	DRAUGHT CURTAIN Supply & Installation of Draught Curtain cover for the opening of conveyer belt, of suitable size fabricated with 3mm thick Nylon Rubber flaps, to be fixed by SS flat strip as per size of shutter opening etc. the opening size shall be as per dimensions /drawings approved by engg. -in-charge, complete as required (Arrival and Departure)	3 00	Nos.	8000 00	24000 00
7 00	7	ROLLING SHUTTER SITC of electrically operated Rolling Shutter with arrangement for auto and manual operation to suit to the opening in wall fabricated extruded Aluminium provided with suitable rated tubular geared single phase motor directly coupled to the shaft of the shutter, limit switch or sensor interlock with conveyer starter, complete with guide channels, wiring, earthing, painting etc. as required for the successful operation of the shutter for minimum opening size 1.5mtr (L) x 1.35mtr (W) (Arrival and Departure)	3 00	Nos.	80000 00	240000 00
8 00	8	Dismantling and shifting of existing Departure System and 1 No. Arrival Carousel including its Control Panel, Rolling Shutters etc. to Nearest AAI's Stores	1 00	Job	7000 00	7000 00
9 00	i)	For Departure System	1 00	Job	7000 00	7000 00
10 00	ii)	For 1 No. Arrival System				3402900 00
		Total of Rs.				3388900 00
		Total of item no. 1 to 7 excluding item no.8 for finalizing AICMC Rate as per pre-decided.				
11 00	9	All inclusive Comprehensive Maintenance of departure and arrival conveyer system by providing quarterly inspection, repair, maintenance, tracking, alignment, replacement of unserviceable components, greasing, poling, topping up of gear oil in gear reducer, rolling shutter, cleaning and all other other associated maintenance job as per maintenance schedule and recommendation of OEM on following slat/slider belt/feeder/gravity roller conveyer and control panels to keep the conveyer system under serviceable condition including attending any numbers of breakdown as and when required. Note -The agency shall also required to pay quterly visit during the 12 month DLP period for Preventive maintenance. (i) Endless arrival slat conveyor (42.6 mtr loop length) along with their power cum control panels - 1No. (ii) Departure slider bed conveyor (16.6 mtr + 12.6 mtr + 3 mtr)- 1 No. along with their power cum control panels. (iii) Departure Gravity roller conveyor -1 No.				120137 00
12 00	a)	1st year after DLP of 1 year (3.545% of SITC cost, i.e item no -1 to 7) For 1 Job / Annum				127016 00
13 00	b)	2nd year (3.748% of SITC cost, i.e item no -1 to 7) For 1 Job / Annum				133895 00
14 00	c)	3rd year (3.951% of SITC cost, i.e item no -1 to 7) For 1 Job / Annum				140741 00
15 00	d)	4th year (4.153% of SITC cost, i.e item no -1 to 7) For 1 Job / Annum				147620 00
16 00	e)	5th year (4.356% of SITC cost, i.e item no -1 to 7) For 1 Job / Annum				154500 00
		Total of item no. 8 to 16				669409 00
		Total of Rs. Including AICMC				4072309 00

Signature Not Verified

Digitally signed by KEISHING HONPAM
Date: 2022.07.25 17:14:48 IST
Location: eProcurement System for Central PSUs
ए.जी.एम.ए.आई. / AAI
ए.ए.आई. / AAI
एन.ई.ओ.आर. / NER
गवाहाटी / GUWAHATI