



रजिस्टर्ड ए.डी. द्वारा/By Regd. A.D.

सं.सं. भाविप्रा/भोपाल/उप.म.प्र.(अभि.-वि.)/का.आ.-06/2022-23 1642(1-12)
Ref. No: AAI/BPL/DGM(E-E)/WO-06/2022-23

दिनांक: 04.07.2022
Date: 04.07.2022

सेवा में,

मेसर्स मनीष इलेक्ट्रिकल्स,
कल्पना नगर, 7 नं. चौराहा के पास,
मोरार, ग्वालियर - 474006
ई-मेल: manishelectricals21@gmail.com

M/s Manish Electricals,
Kalpana Nagar, Near 7 No. Chouraha,
Morar, Gwalior - 474006
E-mail: manishelectricals21@gmail.com

विषय : "राजा भोज विमानतल, भोपाल में नए एटीसी टॉवर सह तकनीकी ब्लॉक का निर्माण ।
उपशीर्ष: शिफ्टिंग ऑफ़ सी.सी.आर्स, जी.एल.एफ. यूपीएस एवं जी.एल.एफ. फीडर केबल्स की रीरूटिंग ।"
Subject: "Construction of ATC Tower cum Technical Block at Raja Bhoj Airport Bhopal. SH:
Shifting of CCRs, GLF UPS and rerouting of GLF feeder cables."

संदर्भ : 1) दिनांक 29.06.2022 को खोली गई आपकी निविदा
Ref.: 1) Your tender opened on dated 29.06.2022

महोदय/Dear Sir,

- 1- उल्लेखित कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत कुल ₹. 1,11,22,960/- (₹. एक करोड़ ग्यारह लाख बाईस हजार नौ सौ साठ मात्र) जी.एस.टी. रहित की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि ई-निविदा की अनुमानित लागत ₹. 1,64,29,398/- (₹. एक करोड़ चौसठ लाख उन्तीस हजार तीन सौ अठानवे मात्र) जी.एस.टी. रहित से 32.30 % कम है ।
Your E-Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 1,11,22,960.00 (Rupees One Crore Eleven Lakh Twenty Two Thousand Nine Hundred Sixty only) Excl. GST which is 32.30% below the estimated cost put to E-Tender of Rs. 1,64,29,398.00 (Rupees One Crore Sixty Four Lakh Twenty Nine Thousand Three Hundred Ninety Eight Only) Excl. GST.
- 2- उप. महाप्रबंधक (अभि.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, राजा भोज विमानतल, भोपाल इस कार्य के इंजीनियरिंग प्रभारी होंगे। आपसे निवेदन है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु 28.07.2022 तक उप. महाप्रबंधक (अभि.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, भोपाल विमानपत्तन के कार्यालय में उपस्थित हो। संविदा करार ₹ 500/- (पाँच सौ रुपये) के न्यायिकेतर (नॉन - ज्युडिशियल) स्टॉप पेपर पर बनाया जायगा तथा स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी ।
Dy. Gen. Manager (Engg.-Elect.), Airports Authority of India, Raja Bhoj Airport, Bhopal shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Dy. Gen. Manager (Engg.-Elect.), Airports Authority of India, Raja Bhoj Airport, Bhopal by 28.07.2022 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 500/- (Rupees Five Hundred only) and the cost of the stamp paper shall be borne by you.

3

Contd...2

- 3- कृपया इस पत्र के जारी होने के 10 दिनों के अंदर प्रतिभूति जमा के रूप में रु. 11,12,296/- (रु. ग्यारह लाख बारह हजार दो सौ छियानबे मात्र) की राशि इस कार्यालय में जमा करा दें अन्यथा करारनामों की संविदा की सामान्य शर्त के पृष्ठ संख्या - 15 पर दी गई शर्त 1ए के अनुसार उक्त राशि आपके बिल से काट ली जाएगी ।

Please deposit **Rs. 11,12,296/- (Rupees Eleven Lakh Twelve Thousand Two Hundred Ninety Six Only)** towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of Clause 1A on page 15 of the contract document.

- 4- आपसे अनुरोध है कि आप ठेका श्रमिक (विनियम एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करें । साथ ही ठेका श्रमिक (विनियम एवं उन्मूलन) केन्द्रीय नियमावली 1971 एवं केन्द्रीय एवं राज्य सरकारों के न्यूनतम वेतन तथा उससे संबंधित अन्य नियमों का पालन करें ।

You are requested to comply with the provisions of contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages Act and rules thereof Central and State Governments.

- 5- आपको वरिष्ठ प्रबंधक (अभि.-वि.), भारतीय विमानपत्तन प्राधिकरण, राजा भोज विमानतल, भोपाल से तत्काल संपर्क करने का भी निर्देश दिया जाता है । आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा किया जाएगा ।

You are also directed to contact Sr. Manager (Engg.-Elect.), AAI, Bhopal Airport immediately who will arrange to hand over the site to you.

- 6- कृपया नोट करे की कार्य पूरा करने के लिए आपको **06 (छह) माह** का समय प्रदान किया जाता है । यह समय इस पत्र के जारी करने की तिथि के 10वें दिन से माना जाएगा ।

Please note that the time allowed for carrying out the work shall be **06 (Six) Months** to complete the work. The same shall be reckoned from 10th day from date of issue of this letter.

- 7- इस ठेके से संबंधित किसी भी प्रकार के पत्र व्यवहार के लिए उप महाप्रबंधक (अभि.-विद्युत), भा.वि.प्रा., राजा भोज विमानतल भोपाल - 462036 को संबोधित करें ।

Any further correspondence in connection with the contract should normally be addressed to the Dy. Gen. Manager (Engg.-Elect.), Airports Authority of India, R. B. Airport, Bhopal - 462036.


- 8- कृपया इस पत्र की प्राप्ति की सूचना दें तथा इसके साथ अनुलग्न अनुप्रति पर हस्ताक्षर करके टोकन के प्रतिग्रहण के रूप में अधोहस्ताक्षरी को वापस भेज दें ।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

- 9- यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी ।

In case any discrepancy is found, then English version will be taken as correct.

भवदीय / Yours Faithfully


(रामजी अवस्थी / Ramjee Awasthi)

उप महाप्रबंधक (अभि.-विद्युत)

Dy. Gen. Manager (Engg.-Elect.)

भा.वि.प्रा., राजा भोज विमानतल, भोपाल - 462036

AAI, Raja Bhoj Airport, Bhopal - 462036.

कृते तथा ओर से, अध्यक्ष,

For and on behalf of Chairman,

भारतीय विमानपत्तन प्राधिकरण,

Airports Authority of India.


N.O.O. / मूल प्रतिलिपि पर नहीं

Copy to/ प्रतिलिपि प्रेषित :-

1. संयुक्त महाप्रबंधक (सतर्कता), भा.वि.प्रा.
पश्चिमी क्षेत्र, सी.एस.आई. एयरपोर्ट, मुंबई-99. (निविदा प्रपत्र के शेड्यूल 'A' की कॉपी सहित)
Jt. General Manager (Vigilance) AAI.
Western Region, C.S.I. Airport, Mumbai-99 (Along with copy of Schedule 'A' of tender document)
2. आयकर आयुक्त
आयकर कार्यालय, होशंगाबाद रोड,
मैदा मिल के सामने, भोपाल।
Commissioner of Income Tax,
Income Tax office, Hoshangabad Road, Opposite Maida Mill, Bhopal.

आंतरिक/ INTERNAL

1. कार्यपालक निदेशक, पश्चिमी क्षेत्र, भा.वि.प्रा., राजीव गांधी भवन, सफ़दरजंग एयरपोर्ट, नई दिल्ली - 110003
..... जानकारी हेतु।
Executive Director, Western Region, AAI, Rajiv Gandhi Bhawan, Safdarjung Airport, New Delhi - 110003
..... for information please
2. महाप्रबंधक (अभि), भा.वि.प्रा, दुमना विमानतल, जबलपुर - 482005
General Manager (Engg.-Elect.), AAI, Dumna Airport, Jabalpur - 482005
..... जानकारी हेतु।
..... for information please
3. विमानपत्तन निदेशक, भा.वि.प्रा, राजा भोज विमानतल, भोपाल-462036
Airport Director, AAI, R.B. Airport, Bhopal - 462036
..... जानकारी हेतु।
..... for information please
4. संयुक्त महाप्रबंधक (अभि.-सि), भा.वि.प्रा, राजा भोज विमानतल, भोपाल-462036
Jt. Gen. Manager (Engg.-Civil), AAI, R.B. Airport, Bhopal - 462036
..... जानकारी हेतु।
..... for information please
5. सहायक महाप्रबंधक (वित्त), भा.वि.प्रा, राजा भोज विमानतल, भोपाल-462036
Asstt. Gen. Manager (Finance), AAI, R.B. Airport, Bhopal - 462036
..... जानकारी हेतु।
..... for information please
6. वरिष्ठ प्रबंधक (अभि- विद्युत), भा.वि.प्रा, राजा भोज विमानतल, भोपाल-462036
Sr. Manager (Engg.-Elect.), AAI, R.B. Airport, Bhopal - 462036
..... कार्यस्थल सौंपने एवं
उचित कार्यवाही हेतु।
..... To handover the site and
necessary action.
7. सहायक प्रबंधक (अभि- विद्युत), भा.वि.प्रा, राजा भोज विमानतल, भोपाल-462036
Asstt. Manager (Engg.-Elect.), AAI, R.B. Airport, Bhopal - 462036
..... ठेका करारानुसार कार्य
निष्पादन हेतु।
..... To Supervise the work as per
contract agreement.
8. करार प्रति/Agreement Copy.
9. कार्य फाईल/Works File.


 उप महाप्रबंधक (अभि.-विद्युत)
 Dy. Gen. Manager (Engg.-Elect.)

Tender Inviting Authority: AGM(E-E), AAI, R.B. Airport, Bhopal

Name of Work: Construction of ATC Tower cum Technical Block at RAJA BHOJ AIRPORT BHOPAL. SH: Shifting of CCRs, GLF UPS and rerouting of GLF feeder cables.

Contract No: AAI/BPL/ENGG(E)/NIT-06/2022-23

Name of the Bidder/ Bidding Firm / Company :	Manish Electricals
--	--------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1.00	Dismantling/Disconnecting, Shifting, Reinstallation, Testing and Commissioning of following capacity, Indoor type air cooled constant current regulator (CCR) complete etc. as required from Old Power House to New CCR Room at New ATC Tower near NITB of R. B. Airport Bhopal. 30 kW	3.00	Job	12000.00	36000.00	INR Thirty Six Thousand Only
2.00	Dismantling/Disconnecting, Shifting, Reinstallation, Testing and Commissioning of following capacity, Indoor type air cooled constant current regulator (CCR) complete etc. as required from Old Power House to New CCR Room at New ATC Tower near NITB of R. B. Airport Bhopal. 20 kW	3.00	Job	10000.00	30000.00	INR Thirty Thousand Only
3.00	Dismantling/Disconnecting, Shifting, Reinstallation, Testing and Commissioning of following capacity, Indoor type air cooled constant current regulator (CCR) complete etc. as required from Old Power House to New CCR Room at New ATC Tower near NITB of R. B. Airport Bhopal. 10 kW	2.00	Job	8000.00	16000.00	INR Sixteen Thousand Only
4.00	Dismantling/Disconnecting, Shifting, Reinstallation, Testing and Commissioning of following capacity, Indoor type air cooled constant current regulator (CCR) complete etc. as required from Old Power House to New CCR Room at New ATC Tower near NITB of R. B. Airport Bhopal. 7.5 kW	6.00	Job	7000.00	42000.00	INR Forty Two Thousand Only

3

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
5.00	Dismantling/Disconnecting, Shifting, Reinstallation, Testing and Commissioning of following capacity, Indoor type air cooled constant current regulator (CCR) complete etc. as required from Old Power House to New CCR Room at New ATC Tower near NITB of R. B. Airport Bhopal. 4 kW	8.00	Job	5500.00	44000.00	INR Forty Four Thousand Only
6.00	Dismantling/Disconnecting, Shifting, Reinstallation, Testing and Commissioning of 2x160 kVA UPS (Make: Vertiv) complete etc. as required from Old Power House to New CCR Room at New ATC Tower near NITB of R. B. Airport Bhopal.	1.00	Job	40000.00	40000.00	INR Forty Thousand Only
7.00	Dismantling/Disconnecting, Shifting, Reinstallation, Testing and Commissioning of Electrical Panel complete etc. as required from Old Power House to New CCR Room at New ATC Tower near NITB of R. B. Airport Bhopal.	1.00	Job	25000.00	25000.00	INR Twenty Five Thousand Only
8.00	Supply of 6.0 sqmm, 5 KV grade copper conductor XLPE insulated, polyethylene sheathed, single core, copper tape unscreened runway cable as required.	30400.00	Mtr	90.00	2736000.00	INR Twenty Seven Lakh Thirty Six Thousand Only
9.00	Supply of 16.0 sqmm, 5 KV grade copper conductor XLPE insulated, polyethylene sheathed, single core, copper tape unscreened runway cable as required.	2400.00	Mtr	190.00	456000.00	INR Four Lakh Fifty Six Thousand Only
10.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (80 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	14230.00	Mtr	148.00	2106040.00	INR Twenty One Lakh Six Thousand &Forty Only
11.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (80 cm below ground level) in the same trench including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	20000.00	Mtr	80.00	1600000.00	INR Sixteen Lakh Only
12.00	Providing and Fixing of 50 mm dia (medium class) G. I. pipes i/c digging work of 2 feet depth & 1 feet width for the road crossing & filling the surface with 1:3:6 PCC complete as required.	264.00	Mtr	790.00	208560.00	INR Two Lakh Eight Thousand Five Hundred & Sixty Only
13.00	Laying of one number PVC insulated and PVC sheathed runway cable of 5 KV grade upto 16 sqmm size in the existing RCC/ HUME/ METAL pipe as required.	34476.00	Mtr	15.00	517140.00	INR Five Lakh Seventeen Thousand One Hundred & Forty Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
14.00	Laying of one number PVC insulated and PVC sheathed runway cable of 5 KV grade upto 16 sqmm size in the existing masonry open duct as required.	500.00	Mtr	20.00	10000.00	INR Ten Thousand Only
15.00	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required.	32800.00	Mtr	22.00	721600.00	INR Seven Lakh Twenty One Thousand Six Hundred Only
16.00	Supply of 6.0 sqmm, 5 KV grade plug and receptacle having suitable field attachment with 5 KV grade XLPE insulated, PE sheathed, single core copper conductor unscreened cable as required.	80.00	Each	650.00	52000.00	INR Fifty Two Thousand Only
17.00	Supply of 16.0 sqmm, 5 KV grade plug and receptacle having suitable field attachment with 5 KV grade XLPE insulated, PE sheathed, single core copper conductor unscreened cable as required.	15.00	Each	900.00	13500.00	INR Thirteen Thousand Five Hundred Only
18.00	Supply of heat shrinkable jointing kit of 6.0 sq. mm size, single core copper conductor, 5 KV grade for Airfield lighting cable complete etc. as required.	10.00	Each	1000.00	10000.00	INR Ten Thousand Only
19.00	Supply of heat shrinkable jointing kit of 16.0 sq. mm size, single core copper conductor, 5 KV grade for Airfield lighting cable complete etc. as required.	5.00	Each	1200.00	6000.00	INR Six Thousand Only
20.00	Earthing with G. I. pipe 4.5 m long x 40 mm dia. (Drilling of 300 mm dia, 4.5 Mtr deep by using Borewell machine) including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. including charcoal or coke and salt complete as required.	24.00	Set	7500.00	180000.00	INR One Lakh Eighty Thousand Only
21.00	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	60.00	Mtr	680.00	40800.00	INR Forty Thousand Eight Hundred Only
22.00	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	60.00	Mtr	250.00	15000.00	INR Fifteen Thousand Only
23.00	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	2.00	Set	17000.00	34000.00	INR Thirty Four Thousand Only
24.00	Providing and fixing 25 mm X 5 mm copper strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required.	5.00	Mtr	1200.00	6000.00	INR Six Thousand Only

B

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
25.00	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.	5.00	Mtr	900.00	4500.00	INR Four Thousand Five Hundred Only
26.00	Supply of Following Size. XLPE insulated, PVC sheathed Al. conductor armoured power cable of 1.1 KV grade conforming to IS:7098 Part-I with upto date amendment etc. complete as required. 3.5 Core x 95 Sqmm.	2650.00	Mtr	465.00	1232250.00	INR Twelve Lakh Thirty Two Thousand Two Hundred & Fifty Only
27.00	Supply of Following Size. XLPE insulated, PVC sheathed Al. conductor armoured power cable of 1.1 KV grade conforming to IS:7098 Part-I with upto date amendment etc. complete as required. 3.5 Core x 50 Sqmm.	180.00	Mtr	305.00	54900.00	INR Fifty Four Thousand Nine Hundred Only
28.00	Supply of Following Size. XLPE insulated, PVC sheathed Al. conductor armoured power cable of 1.1 KV grade conforming to IS:7098 Part-I with upto date amendment etc. complete as required. 3.5 Core x 35 Sqmm.	440.00	Mtr	229.00	100760.00	INR One Lakh Seven Hundred & Sixty Only
29.00	Supply of Following Size. XLPE insulated, PVC sheathed Al. conductor armoured power cable of 1.1 KV grade conforming to IS:7098 Part-I with upto date amendment etc. complete as required. 3.5 Core x 25 Sqmm.	2370.00	Mtr	165.00	391050.00	INR Three Lakh Ninety One Thousand & Fifty Only
30.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	1340.00	Mtr	170.00	227800.00	INR Two Lakh Twenty Seven Thousand Eight Hundred Only
31.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) in the same trench including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	900.00	Mtr	90.00	81000.00	INR Eighty One Thousand Only
32.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. Above 35 sq. mm and upto 95 sq. mm	170.00	Mtr	30.00	5100.00	INR Five Thousand One Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
33.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/PVC pipe as required Upto 35 sq. mm	2268.00	Mtr	20.00	45360.00	INR Forty Five Thousand Three Hundred & Sixty Only
34.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required. Upto 35 sq. mm	530.00	Mtr	20.00	10600.00	INR Ten Thousand Six Hundred Only
35.00	Supplying and making end termination with brass compression gland and aluminum lugs for following size of XLPE insulated and PVC sheathed aluminum conductor cable of 1.1 KV grade as required 3.5 core x 50 Sq.mm (35mm)	12.00	Set	500.00	6000.00	INR Six Thousand Only
36.00	Supplying and making end termination with brass compression gland and aluminum lugs for following size of XLPE insulated and PVC sheathed aluminum conductor cable of 1.1 KV grade as required 3.5 core x 35 Sq.mm (32mm)	32.00	Set	500.00	16000.00	INR Sixteen Thousand Only
37.00	Supplying and making end termination with brass compression gland and aluminum lugs for following size of XLPE insulated and PVC sheathed aluminum conductor cable of 1.1 KV grade as required 3.5 core x 25 Sq.mm (28mm)	4.00	Set	500.00	2000.00	INR Two Thousand Only
Total in Figures					11122960.00	INR One Crore Eleven Lakh Twenty Two Thousand Nine Hundred & Sixty Only
Quoted Rate in Words		INR One Crore Eleven Lakh Twenty Two Thousand Nine Hundred & Sixty Only				


 Dy. Gen. Manager (Engg-E)
 AAI, R. B. Airport, Bhopal