



भारतीय विमानपत्तन प्राधिकरण  
AIRPORTS AUTHORITY OF INDIA

जबलपुर हवाईअड्डा, जबलपुर  
JABALPUR AIRPORT, JABALPUR-482005

संदर्भ सं. : W-29/Engg.(C)/PERI.EMER/2385-2397

दिनांक : 26-07-2022

सेवा में / To,

मेसर्स एम के एस इंजीनियरिंग कंपनी M/s. M K S ENGINEERING CO PVT LTD  
प्राइवेट लिमिटेड, 1 नमक कोठी, उत्तर 1 NAMAK KOTHI, NORTH CIVIL LINES,  
सिविल लाइन्स, जबलपुर JABALPUR  
मोबाइल : 91-9301550333 Mo. No. : 91-9301550333  
ई मेल : mkspvtltd.77@gmail.com E-mail : mkspvtltd.77@gmail.com

**Name of work** - "Up-gradation of Jabalpur Airport to make it suitable for operation of AB-320 type of Aircraft. SH. : Construction of Perimeter & Emergency Road at Jabalpur Airport"

**संदर्भ** - आपकी टेंडर दिनांक : 19/07/2022.

**Ref.** - Your Tender Dated : 19/07/2022.

महोदय / Sir,

- 1) ऊपर उल्लेखित कार्य हेतु आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गये मद मूल्यों पर आपकी टेंडर राशि कुल रु. 2,94,58,420.00 (रुपए दो करोड़ चौगानवे लाख अठावन हजार चार सौ बीस मात्र) (जीएसटी रहित) है, जो कि टेन्डर की अनुमानित लागत राशि रु. 2,99,45,244.00 (रुपए दो करोड़ नित्यानवे लाख पैतालिस हजार दो सौ चवालीस मात्र) (जीएसटी रहित) से (-)1.63% (एक दसमलाव छः तीन प्रतिशत) नीचे एवं टेन्डर की जस्टीफाइड राशि रु. 3,25,34,496.00 (रुपए तीन करोड़ पच्चीस लाख चौतीस हजार चार सौ छियानवे मात्र) (जीएसटी रहित) से (-)9.45% (नौ दसमलाव चार पांच प्रतिशत) नीचे हैं।

➤ Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the rates quoted by you totaling to Rs. 2,94,58,420.00 (Rupees Two Cr. Ninety Four Lacs Fifty Eight Thousand Four Hundred & Twenty Only) (Excluding GST) which is (-)1.63% (One Point Six Three Percent) below the estimated cost put to tender of Rs. 2,99,45,244.00 (Rupees Two Cr. Ninety Nine Lacs Forty Five Thousand Two Hundred & Forty Four Only) (Excluding GST) & (-)9.45% (Nine Point Four Five Percent) below the Justified cost of tender of Rs. 3,25,34,496.00 (Rupees Three Cr. Twenty Five Lacs Thirty Four Thousand Four Hundred & Ninety Six Only) (Excluding GST).

- 2) संयुक्त महाप्रबंधक (अभि.-सि.), भाविप्रा, जबलपुर एयरपोर्ट, जबलपुर कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 05.08.2022 तक संयुक्त महाप्रबंधक (अभि.-सि.), जबलपुर एयरपोर्ट, जबलपुर के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु.100/- के नोनज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा उठाया जाएगा।



भारतीय विमानपत्तन प्राधिकरण  
AIRPORTS AUTHORITY OF INDIA

जबलपुर हवाईअड्डा, जबलपुर  
JABALPUR AIRPORT, JABALPUR-482005

- **Jt. General Manager (Engg.-Civil)**, AAI, Jabalpur Airport, Jabalpur shall be Engineer-in-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the **Jt. General Manager (Engg.-Civil)**, AAI, Jabalpur Airport, Jabalpur by **05.08.2022** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred, only) and the cost of the stamp paper shall be borne by you.
- 3) कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर जमानत राशि रु. 29,45,842.00 (रु. उन्तीस लाख पैतालिस हजार आठ सौ बयालीस मात्र) जमा करवायें, अन्यथा निविदा के दस्तावेज की शर्त संख्या GCC Clause&1(A) के पृष्ठ-17 के अनुसार इसे आपके रनिंग बिलों में से वसूल किया जायेगा।
- Please deposit amount of **Rs. 29,45,842.00 (Rupees Twenty Nine Lacs Forty Five Thousand Eight Hundred and Forty Two Only)** towards security deposit within 10 days from the date of issue of this letter, failing which, the same shall be deducted from your running bill as per Clause-1(A) of GCC page-17 of the tender document.
- 4) आपसे निवेदन हैं कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केन्द्रीय नियम अनुबंध श्रम नियम (नियमन तथा उन्मूलन) एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।
- You are requested to comply with the provision of Contract Labour (regulation and Abolition) Act of 1970 and Contract Labour (regulation and Abolition) Central Rules 1971 and minimum wages act and rules thereof of Central and State Governments.
- 5) आपको निर्देश दिया जाता है कि आप तुरंत **वरि. प्रबंधक (अभि.-सि.)**, भाविप्रा, जबलपुर एयरपोर्ट, जबलपुर से मिलें वही आपको साइट सौंपने की व्यवस्था करेंगे।
- You are also directed to contact **Sr. Manager (Engg.-Civil)**, AAI, Jabalpur Airport, Jabalpur immediately who will arrange to hand over the site to you.
- 6) कृपया नोट कर लें कि काम करने का अनुमत समय **06 (छः) महीने** हैं जोकि इस पत्र के जारी करने के दसवे दिन से गिना जाएगा।
- Please note that the time allowed for carrying out the work shall be **06 (Six) months** and same shall be reckoned from the tenth day after the date of issue of this letter.
- 7) उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।
- The letters under reference shall form part of Agreement.
- 8) इस ठेके के संबंध में आगे कोई भी पत्राचार प्रभारी अभियंता **संयुक्त महाप्रबंधक (अभि.-सि.)**, भाविप्रा, जबलपुर जबलपुर एयरपोर्ट, जबलपुर के पते पर किया जाएगा।
- Any further correspondence in connection with this contract should normally be addressed to the **Jt. General Manager (Engg.-Civil)**, AAI, Jabalpur Airport, Jabalpur.

10  
9  
8  
7  
6  
5  
4  
3  
2  
1



भारतीय विमानपत्तन प्राधिकरण  
AIRPORTS AUTHORITY OF INDIA

जबलपुर हवाईअड्डा, जबलपुर  
JABALPUR AIRPORT, JABALPUR-482005

- 9) यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा।  
➤ In case any discrepancy is found then English version will be taken as correct.
- 10) कृपया पावती भेजे।  
➤ Kindly acknowledge the receipt.

धन्यवाद / Thanking you.

Encl. : BOQ

भवदीय / Yours Faithfully,

संयुक्त महाप्रबंधक (अभि.-सि.),  
26/3/22

Jt. General Manager (Engg.-Civil),

जबलपुर एयरपोर्ट, जबलपुर

Jabalpur Airport, Jabalpur

## SCHEDULE OF WORK / ITEM(S)

**Name of Work :** Up-gradation of Jabalpur Airport to make it suitable for operation of AB-320 type of aircraft. **SH. :** Construction of Perimeter & Emergency Road at Jabalpur Airport.

**Tender ID :** 2022\_AAI\_118157\_1

**Name of Agency :** M/s. M K S ENGINEERING CO PVT LTD, 1 Namak Kothi, North Civil Lines, Jabalpur

| S. No. | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                       | No. of Qty | Units | Rate    | Amount   |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------|---------|----------|
| 1.00   | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.<br>All kinds of soil                                   | 90.00      | Cum   | 125.00  | 11250.00 |
| 2.00   | Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.                                                                                                           | 30.00      | Cum   | 80.00   | 2400.00  |
| 3.00   | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)                                              | 6.00       | Cum   | 4000.00 | 24000.00 |
| 4.00   | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :<br>1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) | 2.00       | Cum   | 5700.00 | 11400.00 |

| S. No. | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                          | No. of Qty | Units | Rate    | Amount    |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------|---------|-----------|
| 5.00   | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :<br>1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)                                                                                                                                        | 18.00      | Cum   | 6000.00 | 108000.00 |
| 6.00   | Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :<br>1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)          | 4.00       | cum   | 5800.00 | 23200.00  |
| 7.00   | Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources). | 6.00       | cum   | 5800.00 | 34800.00  |
| 8.00   | Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete                                                                                                                                                                                                                                                                                                                                    | 16.00      | Sqm   | 220.00  | 3520.00   |
| 9.00   | Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform                                                                                                                                                                                                                                                                                                                                   | 22.00      | sqm   | 250.00  | 5500.00   |
| 10.00  | Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers                                                                                                                                                                                                                                                                                                                                  | 74.00      | sqm   | 250.00  | 18500.00  |
| 11.00  | Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts                                                                                                                                                                                                                                                                                                                                               | 5.00       | sqm   | 300.00  | 1500.00   |

| S. No. | Description of Work / Item(s)                                                                                                                                                                                                                                                                                              | No. of Qty | Units | Rate   | Amount    |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------|--------|-----------|
| 12.00  | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.<br>Thermo-Mechanically Treated bars of grade Fe-500D or more.                                                                                                               | 4500.00    | kg    | 88.00  | 396000.00 |
| 13.00  | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.                                                                                                          | 600.00     | Kg    | 95.00  | 57000.00  |
| 14.00  | Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.<br>In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete | 460.00     | Kg    | 105.00 | 48300.00  |
| 15.00  | Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer.<br>M.S. tube                                                                                                      | 110.00     | Kg    | 130.00 | 14300.00  |
| 16.00  | Dry brick on edge flooring in required pattern with bricks of class designation 3.5 on a bed of 12 mm mud mortar, including filling joints with Jamuna sand, with common burnt clay non modular bricks.                                                                                                                    | 9.00       | Sqm   | 550.00 | 4950.00   |
| 17.00  | 12 mm cement plaster: 1:6 (1 cement : 6 fine sand)                                                                                                                                                                                                                                                                         | 35.00      | sqm   | 190.00 | 6650.00   |
| 18.00  | 15 mm cement plaster: 1:6 (1 cement : 6 fine sand)                                                                                                                                                                                                                                                                         | 15.00      | sqm   | 220.00 | 3300.00   |
| 19.00  | 6 mm cement plaster: 1:3 (1 cement : 3 fine sand)                                                                                                                                                                                                                                                                          | 20.00      | Sqm   | 170.00 | 3400.00   |
| 20.00  | Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate                                                   | 12.00      | Sqm   | 270.00 | 3240.00   |
| 21.00  | Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work                                                                                                                                                                                          | 60.00      | Sqm   | 85.00  | 5100.00   |


| S. No. | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | No. of Qty | Units | Rate    | Amount    |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------|---------|-----------|
| 22.00  | Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. | 30.00      | Sqm   | 1690.00 | 50700.00  |
| 23.00  | Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :Ridges plain (500 - 600mm)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 14.00      | Sqm   | 1850.00 | 25900.00  |
| 24.00  | Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.                                                                                                                                                                                                                                                                                                                                                                                                                                            | 36.00      | Sqm   | 675.00  | 24300.00  |
| 25.00  | Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom.<br>With rapid setting bitumen emulsion On W.B.M / W.M.M. @ 0.4kg/sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 26750.00   | Sqm   | 25.00   | 668750.00 |

Sh. N. B. G.  
Sh. Prash.  
Sh. Ra.  
Sh. H.  
Sh. H.  
Sh. H.

| S. No. | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | No. of Qty | Units | Rate    | Amount    |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------|---------|-----------|
| 26.00  | Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom.<br>With rapid setting bitumen emulsion<br>On bituminous surface @ 0.25kg/sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 26750.00   | Sqm   | 18.00   | 481500.00 |
| 27.00  | Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. Complete<br>900 mm dia RCC pipes.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 30.00      | Mtr   | 5150.00 | 154500.00 |
| 28.00  | Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :<br>For fixed portion, Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15) | 70.00      | Kg    | 525.00  | 36750.00  |
| 29.00  | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 9.00       | Sqm   | 3290.00 | 29610.00  |

| S. No. | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | No. of Qty | Units | Rate    | Amount      |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------|---------|-------------|
| 30.00  | Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm ) having CBR Value-25                                                                                                                                  | 110.00     | Cum   | 1500.00 | 165000.00   |
| 31.00  | Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm ) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.                                                                                                                                                                                     | 90.00      | Cum   | 1500.00 | 135000.00   |
| 32.00  | Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equiped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge.<br>50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity. | 2006.00    | Cum   | 6800.00 | 13640800.00 |

| S. No. | Description of Work / Item(s)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | No. of Qty | Units | Rate         | Amount             |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------|--------------|--------------------|
| 33.00  | Providing and laying Bituminous concrete using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equiped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete and as per directions of Engineer-in-Charge.<br>40/50 mm compacted thickness with bitumen of grade VG-30 @ 5.5% (percentage by weight of total mix) and lime filler @ 3% (percentage by weight of Aggregate) prepared in drum Type Hot Mix Plant of 60-90 TPH capacity. | 1340.00    | Cum   | 9895.00      | 13259300.00        |
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |            |       | <b>Total</b> | <b>29458420.00</b> |

  
 Jt. General Manager (Engg.-Civil),  
 Jabalpur Airport, Jabalpur