

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AGM (E-C)

Name of Work: Replacement of Existing tile flooring with minimum 15 mm thickness vitrified tile flooring in Terminal Building (Phase-1) at SGRDJ International Airport Amritsar.

Contract No: 2022_AAI_118238_1

Name of the Bidder/ Bidding	SARPAL CONSTRUCTION CO						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBE R #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	QUOTED RATE In Figures To be entered by the Bidder inclusive of all taxes but excluding GST Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	10
1	Dismantling tile and cement mortar work in floor , dado wall and roofs including stacking of material within 50 meters lead. a) For thickness of tiles and mortar above 25 mm and up to 40 mm	item 1	3200.00	sqm	50.00	160000.00	INR One Lakh Sixty Thousand Only
2	Carriage of Lime, moorum, building rubbish By Mechanical Transport including loading,unloading and stacking for lead upto 2 km for all lifts, complete as per directions of Engineer-in-charge.	item 2	105.00	cum	1000.00	105000.00	INR One Lakh Five Thousand Only
3	Providing and laying full body homogenous Vitrified tiles of premium quality in floor with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing in 3 mm gap, keeping the finish level same as existing etc. all complete as specified and as directed by the Engineer-in-Charge. a) with minimum 15 mm thick full body vitrified tile of size 600x600 mm as per approved colour/ pattern.	item 3	3200.00	sqm	1350.00	4320000.00	INR Forty Three Lakh Twenty Thousand Only
4	Providing and laying full body homogenous Vitrified tiles of premium quality with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, risers of steps etc., in required design and pattern wherever required, stones of different finished surface texture, laid on 12 mm (average) thick cement mortar 1:3 (1 cement : 3 coarse sand) laid and jointed with white cement slurry @ 3.3 kg/sqm including pointing with white cement slurry admixed with pigment of matching shade, including rubbing, curing, polishing etc. all complete as per Architectural drawings, and as directed by the Engineer-in-Charge. a) with minimum 15 mm thick full body vitrified tile of size 600x600 mm as per approved colour/ pattern.	item 4	160.00	sqm	1400.00	224000.00	INR Two Lakh Twenty Four Thousand Only

5	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	item 5	600.00	kg	101.67	60999.99	INR Sixty Thousand Nine Hundred & Ninety Nine and Paise Ninety Nine Only
Total in Figures						4869999.99	INR Forty Eight Lakh Sixty Nine Thousand Nine Hundred & Ninety
Quoted Rate in Words		INR Forty Eight Lakh Sixty Nine Thousand Nine Hundred & Ninety Nine and Paise Ninety Nine Only					