

संदर्भ संख्या :- भाविप्रा/पुणे/अभि-सि/रोड कार्पेटिंग/2022-23/ 24

दिनांक:- 01.11.2022

सेवा में,
मेसर्स क्लिन्सी कंस्ट्रक्शन प्रा लि
ब्लॉक नं. ए/13, पहिली मंजिल,
हाइवे टावर, चिंचवड,
पुणे - 411 019

To,
M/s Clincy Construction Pvt Ltd,
Block No A/13, 1st Floor,
Highway Towers, Chinchwad,
Pune - 411019

कार्य का नाम :- पुणे हवाई अड्डे पर एयरसाइड पर एप्रन और टर्मिनल बिल्डिंग के बीच सड़क का सुदृढीकरण और पुनर्रचना।

Name of Work: Strengthening & recarpeting of road between Apron & Terminal Building on airside at Pune Airport, Pune.

संदर्भ / Ref.: 1) ई-टेंडर आई डी नं. 2022_AAI_120357_1 दिनांक 16.08.2022 को खोला गया
E-tender ID No. 2022_AAI_120357_1 Opened on 16.08.2022

2) उद्धृत राशि पर 8% की छूट के साथ बातचीत दिनांक 26.09.2022
Negotiation with rebate of 8% on quoted amount on 26.09.2022

महोदय/ Dear Sir,

1. उपर उल्लेखित कार्य हेतु आपका टेंडर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गये मद मूल्यों पर आपकी टेंडर राशी कुल रु. 23,90,840.80 (रूपये तेईस लाख नब्बे हजार आठ सौ चालीस और अस्सी पैसा मात्र) excluding GST 18% है, जो की टेंडर की अनुमानित लागत राशी रु. 23,64,000/- से 1.13% ऊपर है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 23,90,840.80 (Rupees Twenty Three Lakhs Ninety Thousand Eight Hundred Forty and Eighty Paise Only) excluding GST 18% which is 1.13% above the Estimated cost put to tender of Rs. 23,64,000/-.

2. संयुक्त महाप्रबंधक, अभि (सिविल) भा वि प्रा, पुणे विमान क्षेत्र कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप आपकी ओर से एक विश्वसनीय प्रतिनिधि नियुक्ति करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 11.11.2022 तक संयुक्त महाप्रबंधक, अभि (सिविल), पुणे एयरपोर्ट के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु. 100/- नानज्यूडिसियल स्टम्प पेपर पर निष्पादित किया जाएगा तथा पेपर का खर्च आपके द्वारा उठाया जायगा।

Contd....P/2

P-2

Jt. Gen. Manager (Engg-C), AAI, Pune Airport shall be the Engineer-In-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Jt. Gen. Manager (Engg-C), AAI, Pune Airport by 11.11.2022 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

3. आपके टेंडर के साथ प्राप्त धरोदर राशि रु. 47,280/-, ठेके के दस्तावेज़ के पृष्ठ 16 (GCC-clause 1A) पर दी गई शर्त 1(ए) के अनुसार जमानत राशि में परिवर्तित कर दी गई है। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर जमानत राशि की बकाया रु. 1,91,805/- अदा की जाए अन्यथा निविदा दस्तावेज़ के कंडीशन 1(ए) पेज संख्या 16 के अनुसार उक्त राशि रनिंग बिल से काटी जाएगी।

The earnest money amount of Rs. 47,280/-, received along with your tender will be treated and converted as part of security deposit as per clause 1(A) on page GCC-16 of tender document. Please deposit Rs. 1,91,805/- towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your running bills as per clause 1(A) on page 16 of the contract document.

4. आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केंद्रीय नियम (नियमन तथा उन्मूलन) एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधान का अनुपालन करें।

You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation & abolition) Central rules 1971 and minimum wages Act & rules thereof central and state Governments.

5. आपको निर्देश दिया जाता है कि आप तुरंत सहायक महाप्रबन्धक (अभि-सिविल)-I, भाविप्रा, पुणे विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Asst. General Manager (Engg-Civil)-I, AAI, Pune Airport, immediately who will arrange to hand over the site to you.

Contd...P/3

P-3

6. कृपया नोट कर लें कि काम पूर्ण करने का अवधि तीन (03) माह है जोकि इस पत्र के निर्गत दिनांक से दसवे दिन से गिना जायगा।

Please note that the time allowed for carrying out the work is Three (03) months, and same shall be reckoned from the 10th day after issue of this letter.

7. इस ठेके के संबंध में आगे का कोई भी पत्राचार संयुक्त महाप्रबंधक, अभि (सिविल), भाविप्रा, पुणे विमानक्षेत्र के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Jt. Gen. Manager (Engg-C), AAI, Pune Airport.

8. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All the letters referred above shall form part of contract.

9. कृपया पावती भेजें।


Please acknowledge the receipt.

यदि अंग्रेजी और हिन्दी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जाएगा।

If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

धन्यवाद / Thanking You,

भवदीय / Yours faithfully,



01/11/2022

संयुक्त महाप्रबंधक (अभि-सि) / JGM (Engg-C),
कृते तथा ओर से अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,
पुणे हवाई अड्डा, पुणे
For and on behalf of Chairman, Airports
Authority of India
Pune Airport, Pune

संलग्न/Encl: 1. Schedule –“A” (03 pages)

Schedule - A (Work Order)

कार्य का नाम : पुणे हवाई अड्डे पर एयरसाइड पर एप्रन और टर्मिनल बिल्डिंग के बीच सड़क का सुदृढ़ीकरण और पुनर्रचना।

Name of work: Strengthening & recarpeting of road between Apron & Terminal Building on airside at Pune Airport, Pune.

Name of agency : M/s CLINCY CONSTRUCTION PVT. LTD.

Sr. No.	Item description	UNIT	QTY	RATE	AMOUNT
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm	sqm	2180.00	180.00	3,92,400.00
2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications : On W.B.M. @ 0.75 Kg / sqm	sqm	2634.00	90.00	2,37,060.00
3	4 cm thick bitumastic sheet with hot bitumen of approved quality, using stone chippings (60% with 12.5 mm nominal size and 40% with 10 mm nominal size) @ 2.60 cum per 100 sqm and coarse sand @ 2.60 cum per 100 sqm of road surface and with bitumen @ 56 kg/cum of stone chippings and @ 128 kg/cum of sand over a tack coat with hot straight run bitumen, including consolidation with road roller of 8 to 10 tonne etc. complete. (tack coat to be paid separately) : With paving asphalt grade VG - 30 with no solvent	sqm	2554.00	600.00	15,32,400.00
4	Raising manhole cover and frame slab to required level including dismantling existing slab and making good the damage as required (Raising depth of manhole to be paid separately) : Rectangular manhole 90x80 cm with rectangular cover 600 x 450 mm of grade LD - 2.5	each	15.00	3800.00	57,000.00


Sr. No.	Item description	UNIT	QTY	RATE	AMOUNT
5	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity.	cum	2.00	8800.00	17,600.00
6	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge. Note - item to be applicable in urban areas having directions for restricted hours for movement/plying of load carrying motor vehicle of 3.5 cum or more	cum	254.00	360.00	91,440.00
7	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	Cum	4.00	13800.00	55,200.00
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	14.00	5800.00	81,200.00
9	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	138.00	880.00	1,21,440.00

5/6

Sr. No.	Item description	UNIT	QTY	RATE	AMOUNT
10	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	100.00	130.00	13,000.00
Total Rs. (A)					25,98,740.00
Rebate of 8% on quoted amount (A) Rs.					-2,07,899.20
Total Rs. (B)					23,90,840.80

Amount in words : (Rupees Twenty Three Lakhs Ninety Thousand Eight Hundred Forty and Eighty Paise only)

Note : GST shall be payable extra as per prevailing rate for AAI @ 18% on gross work done i.e. 9% CGST & 9% SGST OR 18% IGST.


 Jt. General Manager (Engg-Civil)
 AAI, Pune Airport
 Pune - 411 032

(6/6)