



भारतीयविमानपत्तनप्राधिकरण, कडपाहवाईअड्डा.
AIRPORTS AUTHORITY OF INDIA
KADAPA AIRPORT- 516003.

Ref.No.: AAI/KDP/Engg-C/CHAIN LINK FENCING/2022-23/

Date: 31.10.2022

To,

M/s. SP ENTERPRISES

H.NO.1084, DATLA SP HOUSE,

BESIDE GRAMA SACHIVALAYAM,

PEDDAGUMULURU(V), S RAYAVARAM(M),

VISAKHAPATNAM, AP-531083.

Name of Work: Providing chain link fencing around dense bushes near to Project Office and clearing of jungle inside operational area at Kadapa Airport.

Ref: Your tender for the subject work opened on 31.08.2022 in CPP portal
(Tender ID: 2022_AAI_124171_1).


Dear Sir (s),

1. Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs.53,28,500/- (Rupees Fifty Eight Lakhs Twenty Eight Thousand Five Hundred only) (Excluding GST)** which is 19.51% below the estimated cost put to tender of Rs.66.20 Lakhs (Excluding GST).
2. **Jt. General Manager (Engg-Civil), AAI, Vijayawada Airport** shall be the Engineer-in-charge of the work. You are requested to attend the office of the **Manager (Engg-Civil), AAI, Kadapa Airport** by **11.11.2022** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100.00 (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.
3. The Earnest money amount of Rs.1,32,400/- (Rupees One Lakh Thirty Two Thousand Four Hundred only) received online through payment gateway along with your e-tender will be treated and converted as part of security Deposit as per conditions of clause 1A at page 16 of the General Conditions of Contract of Contract of tender document. Please deposit **Rs.4,00,450/- (Rupees Four Lakhs Four Hundred and Fifty only)** as **Security Deposit** within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per conditions of clause 1A at page 16 of the General Conditions of Contract of tender document.
4. You are directed to apply for Security Clearance through BCAS portal, followed with Security Programme for obtaining entry permit into Terminal Building & Operational area for labours, and vehicles for carrying out the contract work.
5. You are requested to comply with the provision of contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central Rules 1971 and minimum wages act and rules there of central and state Governments.

6. You are also directed to contact Manager(Engg-Civil), Airports Authority of India immediately who will arrange to handover the site to you.
7. Please note that the time allowed for carrying out the work shall be **03(Three) Months**, which shall be reckoned from the 10th day after issue of this letter.
8. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
9. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl: Schedule 'A'.

Yours Faithfully,



Jt. Genl. Manager (Engg-Civil),
AAI, Vijayawada Airport.
For and on behalf of Chairman,
Airports Authority of India.

N.O.O:-

Copy to:

Internal:

1. General Manager (E-C) AAI, Chennai Project, Chennai. ✓
2. General Manager (F&A) AAI, Operational Offices, RHQ, Chennai. ✓
3. Airport Director, AAI, Kadapa Airport. ✓
4. Manager(E-C), AAI, Kadapa Airport. ✓


External:

1. Regional Provident Fund Commissioner, Provident Fund(PF) Office, near substation Vijay Takies, Opp. Big C Road, Kasturipeta, Vijayawada, AP.
2. Asst. Labour Commissioner (Central), Government of India, Ministry of Labour and Employment, CPWD building, Opp. To Hindu Office, Auto Nagar, Vijayawada, AP.

Schedule 'A'

Name of work: Providing chain link fencing around dense bushes near to Project Office and clearing of jungle inside operational area at Kadapa Airport.

Sln.	Description	Unit	Qty	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All Kinds of soil	Cum	350.00	200.00	70000.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size)	Cum	60.00	3500.00	210000.00
3	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footing bases of columns, etc. For mass concrete	Sqm	1210.00	200.00	242000.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size)	Cum	145.00	5000.00	725000.00
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. (a) In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg	13520.00	100.00	1352000.00
6	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : (a) Two or more coats on new work	Sqm	500.00	100.00	50000.00
7	Brick work with clay flyash bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	160.00	5500.00	880000.00
8	12 mm cement plaster of mix : (a) 1:6 (1 cement: 6 coarse sand)	Sqm	505.00	300.00	151500.00
9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	190.00	80.00	15200.00
10	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	Sqm	2640.00	500.00	1320000.00
11	Supply and Fixing of Galvanised steel barbed wire of 9.8 kg /100 M in horizontal lines, for existing Y angles of operational compound wall and angle posts of chain link fencing, fixed with G.I. staples or G.I. binding wire as per directions of Engineer in charge.	Metre	15200.00	13.00	197600.00
12	Hiring and operating of JCB for the purpose of uprooting the bushes all around outside perimeter boundary wall and operational area at Basic strip as per the direction of Engineer in charge(Rate includes cost of fuel, driver charges and contractor profit) (considering 8hrs/Day)	Hours	96.00	1200.00	115200.00
TOTAL Rs.					5328500.00


Jt. Genl. Manager (Engg-Civil),
AAI, Vijayawada Airport.