



सं.स. : भाविप्रा/वारा/अभि./कालोनी रोड/डब्लू-74/926-35/8630-39
Ref No.: AAI/VNS/ENGG/Colony Road/W-74/

दिनांक: 28.09.2022

Date: 28.09.2022

सेवा में,

मेसर्स अनिल इण्टरप्राइजेज
सी-19/15-ए-2-1-बी-ए
बादशाह बाग कालोनी, सिगरा,
वाराणसी-221001

M/s Anil Enterprises
C 19/15-A-2-1-B-A,
Badshah Bagh Colony, Siga,
Varanasi-221001

विषय : एल.बी.एस.आई. हवाईअड्डे, वाराणसी पर एयरपोर्ट के वीवीआईपी गेट से कार्गो बिल्डिंग गेट तक एप्रोच रोड के दोनों साइड शोल्डर और री-कार्पेटिंग का प्रावधान, रिहायशी कॉलोनी में क्षतिग्रस्त रोड की री-कार्पेटिंग, बाबतपुर पुलिस चौकी से सीआईएसएफ बैरक मेन गेट तक एनएच-56 साइड पर चारदीवारी का निर्माण और कचरा बिन के लिए पथ के साथ व्यू कटर का प्रावधान।

Provision of both side shoulder and re-carpeting of approach road from VVIP gate of Airport to Cargo building gate, re-carpeting of damaged road in residential colony, construction of boundary wall along NH-56 side from Babatpur Police Chowki to CISF Barrack main gate and provision of view cutter with pathway for garbage bin at LBSI Airport, Varanasi (Tender ID : 2022_AAI_125067_1)

संदर्भ : ई-निविदा खुलने की तिथि : 15.09.2022

प्रिय महोदय/Dear Sir,

- 1) उपरोक्त कार्य की, कुल निविदा रकम रुपये 1,80,35,501.40 (रुपया एक करोड़ अस्सी लाख पैंतीस हजार पाँच सौ एक एवं चालीस पैसे मात्र) (जी.एस.टी. रहित) की मद दर निविदा, जो कि कार्य की अनुमानित लागत रुपये 226.21 लाख से 20.27% (बीस दशमलव दो सात प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the net tender amount Rs 1,80,35,501.40 (Rupees One Crore Eighty Lakhs Thirty Five Thousand Five Hundred One and Forty Paise only) (Excluding GST) which is 20.27% (Twenty point Two Seven Percent) below to the estimated cost put to tender of Rs. 226.21 lakhs.

- 2) सहायक महाप्रबन्धक (अभि०-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे तथा सहायक प्रबन्धक (अभि०-सि०), भा. वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी उनके प्राधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि दिनांक 07.10.2022 तक सहायक महाप्रबन्धक (अभि०-सिविल) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपये के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

The AGM(Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work and Asstt. Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be our authorised representative. You are requested to attend the office of the AGM(Engg-Civil) by 07.10.2022 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.

- 3) धरोहर राशि रुपये 4,52,420.00 (चार लाख बावन हजार चार सौ बीस मात्र) संविदा प्रपत्र के अनुच्छेद 1ए पेज 16 के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपये 13,51,130.00 (रुपया तेरह लाख एककावन हजार एक सौ तीस मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

शेष पृष्ठ 2 पर....

-2-

The earnest money amount of Rs. 4,52,420.00 (Rupees Four Lakhs Fifty Two Thousand Four Hundred Twenty only) received along with your tender will be treated and converted as a part of security deposit. Please deposit Rs.13,51,130.00 (Rupees Thirteen Lakhs Fifty One Thousand One Hundred Thirty only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition GCC 1A on page 16 of the contract document.

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से सहा0 प्रबन्धक (अभि0-सि0), भा. वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।
You are also directed to contact the Asstt. Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi, immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 08(आठ) महीने हैं जो कि दिनांक 07.10.2022 से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be 08 (Eight) months and the same shall be reckoned from 07.10.2022
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः सहा0 महाप्रबन्धक (अभि-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी-221006, को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the AGM (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006
- 8) कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल प्रष्ठ 05 (सिविल कार्य रु. 1,80,35,501.40) संलग्न है।
Schedule 'A' (total page 05) (Civil works Rs. 1,80,35,501.40) of the work is enclosed.

उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।
In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

भवदीय

संलग्नक- यथोपरि
Encl:- As above

विनोद कुमार पांडे
स.म.प्र.(अभि.-सिविल), 28.10.
A GM (Engg-Civil)

अध्यक्ष, भा0वि0प्रा0 के लिए व उनकी तरफ से
For and on behalf of the Chairman, AAI

प्रतिलिपि:

मूल प्रति पर नहीं (NOO)

अ. बाहरी-

1. संयुक्त महाप्रबन्धक (अभि)-उ0क्षे0, भाविप्रा, नई दिल्ली-110037 : सूचनार्थ
2. सहायक श्रम आयुक्त (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ.
3. श्रम प्रवर्तन अधिकारी (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ

ब. आंतरिक-

- | | | |
|--|---|------------------------|
| 1. निदेशक विमानपत्तन | : | सूचनार्थ |
| 2. प्रभारी (वित्त) | : | -तदैव- |
| 3. सं.म.प्र. (अभि-विद्युत) | : | -तदैव- |
| 4. श्री आशीष कुमार गुप्ता, सहा0 प्रबन्धक (अभि-सिविल) | : | आवश्यक कार्यवाही हेतु। |
| 5. कार्यादेश फाईल | : | |
| 6. अनुबन्ध | : | |

मिनोद कुमार
28-09-10
स.म.प्र.(अभि.-सिविल),

Item Rate BoQ

Validate

Print

Help

Tender Inviting Authority: Airports Authority of India

Name of Work: Provision of both side shoulder & re-carpeting of approach road from VVIP gate of Airport to Cargo building gate, re-carpeting of damaged road in residential colony, construction of boundary wall along NH-56 side from Babatpur Police Chowki to CISF Barrak main gate and provision of view cutter with pathway for garbage bin at LBSI Airport, Varanasi

Contract No: 2022_AAI_125067_1

Name of the Bidder/ Bidding Firm / Company : M/s Anil Enterprises							
PRICE SCHEDULE							
Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	10
0.1	Civil Works						
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	Item1	1715.00	cum	120.00	205800.00	INR Two Lakh Five Thousand Eight Hundred Only
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Item2	308.00	cum	130.00	40040.00	INR Forty Thousand &Forty Only
3	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres.	Item3	3120.00	sqm	100.00	312000.00	INR Three Lakh Twelve Thousand Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	Item4	46.00	cum	5000.00	230000.00	INR Two Lakh Thirty Thousand Only
5	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Item5	18653.00	kg	72.00	1343016.00	INR Thirteen Lakh Forty Three Thousand &Sixteen Only
6	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more. Kg	Item6	5314.00	kg	72.00	382608.00	INR Three Lakh Eighty Two Thousand Six Hundred & Eight Only

सहायक महाप्रबंधक (अभि.-सिविल)
Asstt. General Manager (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
7	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	Item7	310.00	sqm	250.00	77500.00	INR Seventy Seven Thousand Five Hundred Only
8	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts	Item8	934.00	sqm	470.00	438980.00	INR Four Lakh Thirty Eight Thousand Nine Hundred & Eighty Only
9	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers	Item9	663.00	Sqm	415.00	275145.00	INR Two Lakh Seventy Five Thousand One Hundred & Forty Five Only
10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Item10	153.00	cum	5400.00	826200.00	INR Eight Lakh Twenty Six Thousand Two Hundred Only
11	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:4 (1 cement : 4 coarse sand)	Item11	84.00	cum	6100.00	512400.00	INR Five Lakh Twelve Thousand Four Hundred Only
12	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level: Concrete of M25 grade with minimum cement content of 330 kg /cum	Item12	145.00	cum	6300.00	913500.00	INR Nine Lakh Thirteen Thousand Five Hundred Only


सहायक महाप्रबन्धक (अभि.-सिविल)
Asstt. General Manager (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
13	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works above plinth level upto floor V level: Concrete of M25 grade with minimum cement content of 330 kg /cum	Item13	39.00	cum	7000.00	273000.00	INR Two Lakh Seventy Three Thousand Only
14	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Item14	46.00	quintal	450.00	20700.00	INR Twenty Thousand Seven Hundred Only
15	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	Item15	975.00	sqm	200.00	195000.00	INR One Lakh Ninety Five Thousand Only
16	15 mm cement plaster on rough side of single or half brick wall of mix:1:6 (1 cement: 6 coarse sand)	Item16	1068.00	sqm	240.00	256320.00	INR Two Lakh Fifty Six Thousand Three Hundred & Twenty Only
17	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Item17	2042.00	sqm	110.00	224620.00	INR Two Lakh Twenty Four Thousand Six Hundred & Twenty Only
18	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge : With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	Item18	624.00	cum	2250.00	1404000.00	INR Fourteen Lakh Four Thousand Only
19	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC infor all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	Item19	624.00	cum	2300.00	1435200.00	INR Fourteen Lakh Thirty Five Thousand Two Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
20	Providing and laying 80mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	Item20	2790.00	sqm	700.00	1953000.00	INR Nineteen Lakh Fifty Three Thousand Only
21	4 cm thick bitumastic sheet with hot bitumen of approved quality, using stone chippings (60% with 12.5 mm nominal size and 40% with 10 mm nominal size) @ 2.60 cum per 100 sqm and coarse sand @ 2.60 cum per 100 sqm of road surface and with bitumen @56 kg/cum of stone chippings and @ 128 kg/cum of sand over a tack coat with hot straight run bitumen, including consolidation with road roller of 8 to 10 tonne etc. complete. (tack coat to be paid separately) : With paving asphalt grade VG - 30 with no solvent	Item21	11430.00	sqm	390.00	4457700.00	INR Forty Four Lakh Fifty Seven Thousand Seven Hundred Only
22	Providing and applying tack coat using hot straight run bitumen of grade VG - 30, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications : On bituminous surface @ 0.50 Kg / sqm	Item22	9840.00	sqm	30.00	295200.00	INR Two Lakh Ninety Five Thousand Two Hundred Only
23	Providing and applying 2.5 mm thick road marking strips (retroreflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications.	Item23	420.00	sqm	415.00	174300.00	INR One Lakh Seventy Four Thousand Three Hundred Only
24	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Item24	41.00	cum	6100.00	250100.00	INR Two Lakh Fifty Thousand One Hundred Only
25	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Item25	5268.00	kg	90.00	474120.00	INR Four Lakh Seventy Four Thousand One Hundred & Twenty Only


 सहायक महाप्रबन्धक (अभि.-सिविल)
 Asstt. General Manager (Engg -Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
26	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Item26	1056.00	sqm	510.00	538560.00	INR Five Lakh Thirty Eight Thousand Five Hundred & Sixty Only
27	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	Item27	390.00	Meter	290.00	113100.00	INR One Lakh Thirteen Thousand One Hundred Only
28	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	Item28	174.00	cum	1028.00	178872.00	INR One Lakh Seventy Eight Thousand Eight Hundred & Seventy Two Only
29	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand) (Old bricks from BOQ item no. 28 will be used)	Item29	122.00	cum	1900.00	231800.00	INR Two Lakh Thirty One Thousand Eight Hundred Only
30	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in: Channels, angles, tees and flats	Item30	2267.00	kg	1.20	2720.40	INR Two Thousand Seven Hundred & Twenty and Paise Forty Only
Total in Figures						18035501.40	INR One Crore Eighty Lakh Thirty Five Thousand Five Hundred & One and Paise Forty Only
Quoted Rate in Words		INR One Crore Eighty Lakh Thirty Five Thousand Five Hundred & One and Paise Forty Only					


 सहायक महाप्रबन्धक (अभि.-सिविल)
 Asstt. General Manager (Engg.-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Civil Aviation Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi