



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

स्पीड पोस्ट/ ई-मेल

संदर्भ संख्या: भा0वि0प्रा0/पीएनटी/अभि0सिविल/हार्ड स्टैन्ड/2022-23/550
Ref. No. AAI/BLY/PNT/Engg (C)/Hard Stand/2022-23/550

दिनांक/ Dated: 16.11.2022

सेवा में,

मैसर्स श्री पारसनाथ कंस्ट्रक्शन,
सी-6/9 यमुना विहार,
नई दिल्ली-110053

M/s Shri Parasnath Construction,
C-6/9, Yamuna Vihar,
New Delhi-110053

विषय- प्रोजेक्ट ऑफ हार्ड स्टैन्ड एण्ड एसोसिएटेड वर्क्स एट ईस्ट एण्ड वेस्ट साईड ऑफ एप्रन एट पन्तनगर एयरपोर्ट (सिविल एवं इलैक्ट्रिकल वर्क्स)।

Subject: Provision of Hard Stand and Associated works at EAST and West side of Apron at Pantnagar Airport (Civil & Electrical Works)

संदर्भ- दिनांक 20.09.2022 को खोली गयी आपकी निविदा (निविदा आईडी- 2022_AAI_125624_1)

Ref: Your tender opened on 20-09-2022 (Bid 2022_AAI_125624_1)

महोदय/ Sir,

1. आपके द्वारा उपरोक्त कार्य की रू. **44,84,460.00** (जीएसटी रहित) (रू चवालीस लाख चौरासी हजार चार सौ साठ रुपये मात्र) की मदद से ई-निविदा जो कि उक्त कार्य की अनुमानित लागत रू **59,43,036/-** (जीएसटी रहित) से **24.54** प्रतिशत कम है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है ।

Your e- tender for work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totalling to **Rs. 44,84,460.00 (excluding GST)** (Rupees Forty four lakh Eighty four thousand and Four hundred sixty only) which is 24.54% below the estimated cost put up to tender of **Rs. 59,43,036/- (Excluding GST)**.

2. सहायक महाप्रबन्धक (अभियांत्रिकी-सिविल), भारतीय विमानपत्तन प्राधिकरण, सिविल इनक्लेव, बरेली इस कार्य के कार्य प्रभारी अभियंता होंगे। आपसे अनुरोध है कि इस पत्र के जारी होने की तारीख से 15 दिनों के भीतर सहायक महाप्रबन्धक (अभियांत्रिकी-सिविल), भारतीय विमानपत्तन प्राधिकरण, सिविल इनक्लेव, बरेली के कार्यालय में उपस्थित होकर ठेका संविदा को हस्ताक्षरित कर पूर्ण करें। ठेका रू0 100/- (मात्र सौ रुपये) के

[Handwritten Signature]
16/11/22



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

न्यायिकोत्तर मुद्रांक (नॉन ज्यूडीसियल) पत्र पर सम्पादित किया जायेगा एवं मुद्रांक पत्र की कीमत आपके द्वारा वहन की जाएगी।

Assistant General Manager (Engg-Civil), AAI, Civil Enclave, Bareilly shall be the Engineer-in-charge for the work. You are requested to attend the Office of **Asst. General Manager (Engg-Civil), AAI, Civil Enclave, Bareilly** within 15 days from the date of issue of this letter to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. आपसे अनुरोध है कि किसी भी अनुसूचित बैंक (लेकिन सहकारी या ग्रामीण बैंक नहीं) की बैंक गारंटी के रूप में अनुबंध मूल्य का 10 प्रतिशत (रु० 4,84,460.00) सुरक्षा जमा राशि के रूप में जमा करें अन्यथा सुरक्षा जमा राशि की कटौती प्रत्येक चल लेखा बिल से संविदा की धारा 1A के अनुसार की जाएगी।

You are requested to submit an amount equivalent to 10% of contract value (Rs. 4,84,460.00) as Security Deposit in the form of Bank Guarantee of any scheduled bank but not Cooperative or Gramin Bank Otherwise Security Deposit shall be recovered from each running bill as per clause 1A of conditions of contract.

4. आप से अनुरोध है कि ठेका श्रम (विनियमन और उत्सादन) अधिनियम 1970 एवं ठेका श्रम (विनियमन और उत्सादन) केन्द्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, भवन और अन्य निर्माण श्रमिक (सेवा कि शर्तों के रोजगार का विनियमन) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996, संविदा श्रमिक प्रावधान (विनियम एवं उन्मूलन) 1970 श्रमिक प्रावधान, विनियम एवं उन्मूलन केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम 1948, ई०पी०एफ० अधिनियम 1952, तथा ई०एस०आई० अधिनियम-1948, तथा इस संबंध में केन्द्र और राज्य सरकार के नियमों के प्रावधान का पालन करें।

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition and Regulation) Act 1986, Building and other Construction Workers (Regulation of Employment of Conditions of Service) Act 1996, Building and other Construction Workers Welfare Cess Act 1996, Minimum Wages Act 1948, EPF Act 1952 & ESI Act 1948 & rules thereof Central & State Governments.

5. आपको निर्देशित किया जाता है की तुरन्त प्रभाव से कनिष्ठ कार्यपालक (अभि० -सिविल), भारतीय विमानपत्तन प्राधिकरण, सिविल एयरपोर्ट, पन्तनगर को संपर्क करें जोकि आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact **Jr. Executive (Engg-Civil), Civil Airport, Pantnagar** immediately who will arrange to hand over the site to you.

6. कृपया ध्यान रहे कि कार्य पूरा करने की समयावधि 03 माह होगी और यह इस पत्र के निर्गत होने के दसवें दिन से माना जायेगा।

[Signature]
8/11/22



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

Please note that the time allowed for carrying out the work shall be **03 months** and same shall be reckoned from the 10th day of issue of this letter.

7. सविदा के संदर्भ में सामान्यतः कोई भी पत्राचार कार्य प्रभारी अभियन्ता को सम्बोधित करते हुये किया जाना चाहिए।

Any further correspondence in connection with this contract should normally be addressed to the Engineer-In-Charge.

8. नागर विमानन सुरक्षा ब्यूरो के निर्देशों के तहत एंट्री परमिट जारी करने हेतु सम्बन्धित एंजेंसी का ई-सहज पोर्टल से सिक्योरिटी क्लियरेंस तथा बीसीएस द्वारा अनुमोदित सिक्योरिटी प्रोग्राम आवश्यक है तथा इस सम्बन्ध में नियमों का अनुपालन करना सुनिश्चित करें। आपको निर्देशित किया जाता है कि इस कार्य से जुड़े हुये लेबर, प्रोपरीटेर, इंजीनियर का पुलिस वेरिफिकेशन सुनिश्चित करें।

Security Clearance from the e-Sahaj portal of the concerned agency and security programme approved by BCAS is mandatory for issuance of Aerodrome Entry Permit (AEP) as per the instruction of Civil Aviation Security Bureau (BCAS). Hence, you are directed to get security clearance and Police Verification of Casual Labours, Proprietor, Engineers deputed for the above-mentioned work.

9. कृपया पावती भेजें एवं पत्र की अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।


Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

नोट: हिन्दी तथा अंग्रेजी संस्करण में अंतर पाये जाने पर अंग्रेजी संस्करण मान्य होगा।

Note: If any discrepancy is observed in Hindi and English Version, then English version will be followed.

भवदीय,

Yours faithfully,


(अवधेश अग्रवाल)

(Avdhesh Aggarwal)

सहा० महा० प्रबंधक (अभि० सिविल)

AGM (Engg-Civil)

भारतीय विमानपत्तन प्राधिकरण, सिविल एन्क्लेव, बरेली

AAI, Civil Enclave Bareilly

अध्यक्ष भारतीय विमानपत्तन प्राधिकरण के लिए व उनकी तरफ से

For & on behalf of the Chairman

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India

संलग्न: अनुसूची -अ

Encl: Schedule-A

BOQ

Sl.No	Description of Work / Item(s)	No. of Qty	Units		
				Rate	Amount
1.00	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge: All kinds of soil	2037.00	Sqm	80.00	162960.00
2.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 cement : 3 coarse sand (zone-III): 6 graded stone aggregate 40 mm nominal size)	301.55	Cum	4000.00	1206200.00
3.00	Providing and fixing at or near ground level precast cement concrete in kerbs, edgings etc. as per approved pattern and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), including the cost of required centering, shuttering complete.a) 1:1½:3 (1 Cement: 1½ coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	40.50	Cum	7000.00	283500.00
4.00	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge :a)bituminous road	40.00	Sqm	100.00	4000.00
5.00	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road rollerincluding making good the undulations etc. and re-rolling the subgrade and disposal of surplus earthwith lead upto 50 metres.	1980.00	Cum	60.00	118800.00
6.00	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of all dirt, scales, oil, grease and other foreign material etc. and lining out complete.(a) New work (Two or more coats)	600.00	Sqm	110.00	66000.00
7.00	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of all dirt, scales, oil, grease and other foreign material etc. and lining out complete. (a) New work (One or more coats)	600.00	Sqm	90.00	54000.00
8.00	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant atOMC, carriage of mixed material by tippers to work site, for all leads& lifts, spreading in uniform layers of specified thickness with motorgrader on prepared surfaceand compacting with vibratorypower roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-III (size range 26.5 mm to 0.075 mm) having CBR Value-20	485.00	Cum	1700.00	824500.00
9.00	Providing and laying factory made chamfered edge Cement Concretepaver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 30mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.80 mm thick C.C. paver block of M-40 grade with approved color design and pattern.	1940.00	Sqm	710.00	1377400.00
10.00	Supply of 1Cx6 sq. mm sizes 5 kV grade PVC insulated & PVC sheathed, anti-termite & anti-rodent, multi-stranded copper conductor single core Airfield lighting cable confirming to IS 1554 (Part-II) with up to date amendments and confirming to tenders technical specifications, terms & conditions etc. complete as required as per EIC	1000.00	Meter	165.00	165000.00
11.00	Supply of ESNA connector for insulated PCP sheathed copper conductor of 1Cx6 sqmm airfield lighting cables complete as required as per EIC	12.00	Each	150.00	1800.00
12.00	Laying of one number PVC insulated and PVC sheathed / XLPE AGL/power cable of 5 KV grade of 6/16 sqmm size in the existing HDPE /GI pipe etc. (Primary Cable) complete as required as per EIC	1000.00	Meter	25.00	25000.00

13.00	Providing, laying and fixing following dia G.I. pipe (50mm) (medium class) in ground complete with G.I. fittings including cutting, threading & coupling with existing pipe i/c trenching (75 cm deep) and re-filling & making good the damage etc as required. a) 50 mm dia	120.00	Meter	500.00	60000.00
14.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. a) 63 mm dia (OD-63 mm & ID-51 mm nominal)	880.00	Meter	110.00	96800.00
15.00	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having licking arrangement and watering pipe etc. (with charcoal/coke and salt) as required.	2.00	Job	5000.00	10000.00
16.00	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	20.00	Meter	275.00	5500.00
17.00	Providing and fixing 6 SWG dia G.I. Wire on surface or in recess for loop earthing as required	1000.00	Meter	20.00	20000.00
18.00	Dismantling existing & re Installation, Testing and Commissioning of Elevated Type Medium Intensity apron/Taxiway edge Light Fixtures including , alignment of fitting, making terminations with connectors etc. complete as required as per EIC	12.00	Each	250.00	3000.00
		Total Rs. 4484460.00			

Avadesh
16/11/22
(Avadesh Agrawal)

AGM (E-C)

AAI, Civil Enclave Bareilly

Signature Not Verified

Digitally signed by ASHUTOSH S RAUT
Date: 2022.11.16 15:52:29 IST
Location: eProcurement System for Central PSUs