

By Speed post

No:- AAI/AYO/Jt.GM(E)/BHS/2022-23/223 - 231

Date -08.11.2022

सेवा में,
मेसर्स गैन्नन डंकर्ले एंड कंपनी लिमिटेड।
सामग्री प्रबंधन प्रभाग
16/1, अर्ल स्ट्रीट, फ्लैट नंबर एन-1 (पहली मंजिल),
कोलकाता - 700026

To,
M/s Gannon Dunkerley & CO.LTD.
Material Handling Division
16/1, Earle Street, Flat No. N-1 (1st Floor)
Kolkata - 700026

विषय:- अयोध्या हवाई अड्डे का विकास, उत्तर प्रदेश
उपशीर्ष: अयोध्या हवाई अड्डे पर बैगेज हैंडलिंग सिस्टम का डिजाइन, निर्माण, आपूर्ति, स्थापना, परीक्षण और
कमीशनिंग।

निविदा आईडी: 2022_AAI_126808_1

Name of work: Development of Ayodhya Airport, Uttar Pradesh,

SH: Design, fabrication, supply, installation, testing & commissioning of Baggage
Handling System at Ayodhya Airport.

TENDER ID: 2022_AAI_126808_1

संदर्भ :-आपकी ई-निविदा जो दिनांक 23.09.2022 को खोली गयी।

Ref:-Your E-tender opened on 23.09.2022

महोदय/Sir,

1. उपरोक्त कार्य के लिए आप की मदद निविदा आपके द्वारा उद्धृतित राशि रु.84,59,264.00 - (चौरासी लाख
उत्सठ हजार दो सौ चौसठ मात्र) (जी.एस.टी.छोड़कर) जो कि अनुमानित लागत रु. 98,26,098.00 -(अठानवे
लाख छब्बीस हजार अठानवे मात्र) (जी.एस.टी.छोड़कर) से 13.91% कम है, को अध्यक्ष, भारतीय विमानपत्तन
प्राधिकरण की ओर से स्वीकार किया जाता है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman,
Airports Authority of India, at the item rates quoted by you totaling to Rs. 84,59,264.00
(Rupees Eighty Four Lakhs Fifty Nine Thousand Two hundred Sixty Four only) (Excluding
GST) which is 13.91% (Thirteen point Nine One percent) below the estimated cost put to
tender of Rs. 98,26,098.00 (Rupees Ninety Eighty Lakhs Twenty Six Thousand Ninety
Eight only) (Excluding GST).

2. आपसे अनुरोध है कि कृपया दिनांक 18.11.2022 तक अयोध्या हवाई अड्डा, अयोध्या पर संयुक्त महाप्रबंधक (अभि-वि)
के कार्यालय में उपस्थित रहकर संविदा करार पर हस्ताक्षर करने तथा करार की कार्यवाही पूर्ण करने का कष्ट करें।
यह संविदा करार 100/- रुपये (सौ रुपये मात्र) के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका
खर्च आपके द्वारा वहन किया जायेगा।

You are requested to attend the office of the Jt. General Manager (Engg-Elect), AAI, Ayodhya
Airport, Ayodhya by 18.11.2022 to sign and complete the contract agreement. The
contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/-
(Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. संविदा करार के पेज नंबर 75 पर धारा नं. 1A के अनुसार आपके निविदा के साथ प्राप्त धरोहर राशि रुपये
1,96,522.00 /-(रुपये एक लाख छियानवे हजार पाँच सौ बाइस मात्र) को जमानत जमा के एक हिस्से के रूप में
जमा माना जायेगा। कृपया इस कार्य दिशके जारी होने के तिथि से 10 दिनों के भीतर जमानत जमा के शेष रुपये
6,49,404/- (रुपये छः लाख उन्चास हजार चार सौ चार मात्र) इस कार्यालय में जमा कराये अन्यथा यह कांटेक्ट
डॉक्यूमेंट के पेज नंबर 75 पर धारा नं 1A के अनुसार काटा जायेगा।

o/c


28/11/2022

h

The Earnest Money amount of **Rs.1,96,522.00 (Rupees One Lakh Ninety Six Thousand Five Twenty Two Only)** received along with your tender will be treated and converted as part of security deposit as per Clause no. 1A on Page 75 of contract document. Please deposit **Rs.6,49,404/- (Rupees Six Lakh Forty Nine Thousand Four Hundred Four Only)**, towards security deposit within 10 days towards security deposit within 10 days from the date of issue of this Work Order failing which, the same will be deducted as per condition of Clause no. 1A at Page 75 of contract document.

4. आपसे अनुरोध है कि संविदा करार के पेज नंबर 109 पर धारा नं. 19 के अनुसार आप ठेका श्रमिक (विनियमन एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करें, साथ ही ठेका श्रमिक (विनियमन एवं उन्मूलन) केन्द्रीय नियमावली 1971, बालश्रम (निषेध एवं विनियमन) अधिनियम 1986, निर्माणश्रमिक (रोजगार और सेवा की हालत का विनियमन) अधिनियम 1996, भवन और अन्य निर्माणश्रमिक कल्याण उपकरण अधिनियम 1996 तथा केंद्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 109 of tender agreement and rules of Central and State Governments.

5. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ई एस आई अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अंतर्गत बनाये गये सभी नियमों एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा कराएंगे तथा पी एफ खाता कोड और ईएसआई पंजीकरण काम के वास्तविक समापन तक वैध रहे।

You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

6. आपसे यह भी अनुरोध है कि आप सहायक महाप्रबंधक (अभि-वि)-अयोध्या हवाई अड्डा, अयोध्या से अविलम्ब संपर्क करें जो कि आपको साइट हस्तांतरित करने की व्यवस्था करेंगे।

You are also directed to contact Asstt. Gen. Manager (Engg-Elect), AAI, Ayodhya Airport, Ayodhya, immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय 03 महीने होगा और इस पत्र के जारी होने के बाद दसवे दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 03 (Three) months and same shall be reckoned from the 10th day after issue of this letter.

8. आगे से इस अनुबंध के संबंध में किसी भी प्रकार के पत्राचार को अधोहस्ताक्षरकर्ता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Jt. General Manager (Engg-Elect), AAI, Ayodhya Airport, Ayodhya who will be the Engineer-In-charge of this work.


AGM/ESD
08/11/2022

0/L



9. कृपया इस पत्र की प्राप्ति-सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

संलग्न :- अनुसूची- अ

भवदीय,

— Sa —

(लाल जीत राम)

(LAL JEET RAM)

संयुक्त महाप्रबंधक (अभि-वि)

Joint General Manager (E-E)

For and on behalf of Chairman, AAI


भा.वि.प्रा., अयोध्या.हवाई अड्डा, अयोध्या

AAI, Ayodhya Airport, Ayodhya

मूलप्रति में नहीं

प्रतिलिपि:


- ED (Engg), NR, CHQ, AAI, New Delhi... For information please.
- GM(Engg), NR, CHQ, AAI, New Delhi .. For information please.
- GM(Engg), NR, RHQ, Ops Office, Rangpuri, New Delhi.. For information please.
- JGM(E-E), NR, CHQ, AAI,For information please.
- JGM(E-C), AAI, Ayodhya Airport..... For information please.
- AGM(E-E), AAI, Ayodhya Airport.....For information and follow-up please.
- Manager(E-E), Ayodhya Airport..... For information and follow-up please.



External :

- Asst. Labour Commissioner, Shivkuti, Khapradeeh Kothi, Civil Lines, Ayodhya , UP.





(लाल जीत राम)

(LAL JEET RAM)

संयुक्त महाप्रबंधक (अभि-वि)

Joint General Manager (E-E)

For and behalf of Chairman ,AAI

भा.वि.प्रा., अयोध्या.हवाई अड्डा, अयोध्या

AAI, Ayodhya Airport, Ayodhya



Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asst. General Manager (Engg. – Electrical), AAI, Ayodhya Airport.


Name of Work: Development of Ayodhya Airport. SH : Design, Fabrication, Supply, Installation, Testing & Commissioning of Baggage Handling System at Ayodhya Airport.

Contract No: 2022_AAI_126808_1

Bidder Name : BHABANI PRASUN BHATTACHARYA
GANNON DUNKERLEY & CO. LTD.

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder excluding GST Rs. P	TOTAL AMOUNT excluding GST Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	SH : I - DEPARTURE CONVEYOR					
1.01	Weighing Scale Conveyor Integrated Weighing Scale Conveyor: Design, supply, installation, testing & commissioning of following size heavy duty slider bed belt weighing scale conveyor equipped with illuminated push button for introduction of baggage into dispatch conveyor (after baggage had been weighed & tagged) complete with LCD/LED dual display type weighing scale with 4 nos. high resolutions load cells each of suitable capacity, Accuracy class C3 to C6 with 2 ply, 3mm minimum thickness polyester black colour carcass PVC smooth / rough top, flame retardant, antistatic, robust, flexible, capable of providing continuous service, and of very low friction type belt having useful width 650mm (minimum) and overall frame size 825 mm (maximum), height as per system design of OEM and functional requirement at passenger end and the other end suitably sloped for easy flow of baggage with speed as per system design of OEM and functional requirement. The bed shall be made of 3 mm thick (minimum) galvanized or epoxy coated mild steel sheet, weighing scale, drive pulley, tension adjustment, frame and supports, Trim / fascia covering / finishing, head and tail pulley, return / snub rollers, side wall / Guard with control logic and protection as per technical specifications for baggage handling system including all electrical switchgears component, cabling, connection / interconnection, Controls, cutting & drilling of holes, equipment grouting, earthing, etc., complete as required for successful operation of the system. (a) Length - 1200 mm (Nominal)	9	Each	105000.00	945000.00	INR Nine Lakh Forty Five Thousand Only
1.02	Dispatch Conveyor Dispatch Conveyor: Design, supply, installation, testing & commissioning of following size heavy duty slider bed belt dispatch conveyor complete with 2 ply, 3mm minimum thickness polyester black colour carcass PVC smooth top, flame retardant, antistatic, robust, flexible, capable of providing continuous service, and of very low friction type belt (Diamond cut Belt of 7.5 mm thickness is also acceptable), normal live load 35 kg per linear meter having useful belt width such that it fits within the frame, without much side play and shall match with that of integrated weighing conveyor and overall frame size matching with integrated weighing conveyor, height as per system design of OEM and functional requirement suitably sloped for easy transfer of baggage from one section to adjoining section with speed as per system design of OEM and functional requirement. The bed shall be made of 3 mm thick (minimum) galvanized or epoxy coated mild steel, drive pulley, tension adjustment, frame and supports, Trim / fascia covering / finishing, head and tail pulley, return rollers, side wall / Guard, Vertical baggage guide / tipping device with control logic as per technical specifications for baggage handling system including all electrical switchgears component, cabling, connection / interconnection, Controls, cutting & drilling of holes, equipment grouting, earthing, etc., complete as required for successful operation of the system. (a) Length - 1200 mm (Nominal)	9	Each	70000.00	630000.00	INR Six Lakh Thirty Thousand Only


 18/11/2022
 08/11/2022



NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
1.03	Connected and Take Away conveyor system Design, supply installation, testing and commissioning of heavy duty slider bed belt type take away conveyor system having useful belt width of 950mm and frame size 1050 mm and height 400 mm from finished floor level, Normal live load 35 Kg. per linear mtr, speed of 21-25 mtr. per min. / as per system functional requirement complete with 2 ply, 3mm minimum thickness polyester black colour carcass PVC smooth top, flame retardant, antistatic, robust, flexible, capable of providing continuous service, and of very low friction type belt. The bed shall be made of 3 mm thick (minimum) galvanized mild steel sheet, drive unit, tension adjustment, frame and supports and cross members, support spacing, Trim / fascia covering / finishing, drive pulley, head and tail pulley, take up pulley and snub rollers, return rollers, vertical baggage guide / tipping device side wall / Guard with control logic and protection as per technical specifications for baggage handling system including all electrical switchgears component, cabling, connection / interconnection, Controls, cutting & drilling of holes, equipment grouting, earthing, etc., complete as required for successful operation of the system in the departure check-in area. (Connected conveyor of 20.25 mtrs and Take away conveyor of 24.42 mtrs totalling to 45.0 mtrs approx) Lenght = 45.0 Mtr. (Approx.)	1	Job	1125000.00	1125000.00	INR Eleven Lakh Twenty Five Thousand Only
1.04	Control panel for departure conveyor system Design, supply installation, testing and commissioning of cubical type Indoor floor mounting compartmentilised, fabricated out of CRCA sheet steel of thickness 2mm duly powder coated Indoor type floor mounted with locking arrangement. The panel (IP42 protection) shall be front open able & accessible. All doors shall be provided with high quality neoprene rubber gasket, door interlock feature with incoming power supply & suitable for operation on 415 volts, 3 Phase, 50 Hz AC supply I/c. I/c. earthing, connections and comprising of the following component as required for departure conveyor system. a) Incoming Control Unit : 415 Volts 4 pole MCCB (micro processor type) of breaking capacity of 35KA (Ics = 100 Icu) with over load, short circuit protection & earth fault protection. The rating of the MCCB shall be so selected that only about 80% of its full current carrying capacity is utilized for meeting the requirement of the specific application including future load of expansion of four more check in counters. b) Incoming Protection : i) Single Phase Protection ii) Phase reversal protection iii) Under voltage protection c) Status Indication / display : Indication lamps (LED type) in different colour for Three phases & power ON with protection MCB. d). Meters (incoming) : a) Digital type Ammeter of Required range with selector switch & Current Transformers. (b) Digital type Voltmeter with selector switch and protection MCB. e). MOV & switch : Necessary Surge protection System (block 70KA minimum with Neutral protection) shall be provided at control panel of conveyor with incomer switch. f). Outgoing for each section : MPCB of suitable current rating & breaking capacity of 10 KA for each motor. g). Outgoing for rolling shutter : 1) 2 Pole MPCB of 10 KA & suitable current rating for each shutter motor. 2) Interlocking with conveyor & limit switches / sensors. 3) Auto-manual switches, separate push button for UP /DOWN mo h). Outgoing for each weighing scale conveyor & dispatch conveyor : MPCB of suitable current rating for each weighing scale conveyor & each of dispatch conveyor i). Emergency stop : i) Provision shall be made in panel & at two other locations of take away conveyor. ii) Provision shall be made at one location close to each of weighing conveyors.iii) The emergency stop button shall be "press to stop" and release type. j). Alarm / Time delay : Provision for time delay start, duly interconnected with buzzer and start the sequence of carousel. k). Interlock & Logic : A PLC based programmable logic to meet the operational requirement shall be worked out and got approved from Engineer-in-charge. Required number of sensors and other control devices shall be provided to meet the functional logical operation of conveyor along with sequential operation of feeder conveyors as required. l). Air Louvers : The control panel constructional feature shall have air louvers for proper ventilation. m). Provision for future expansion : The incomer switch rating & control panel should have provision toward addition of switch gear, controls, cabling, wirings, etc. to accommodate the weigh-scale, dispatch & take away conveyor suitable for FOUR nos. additional check in counters in future.	1	Job	300000.00	300000.00	INR Three Lakh Only
1.05	Gravity roller conveyor Design, Supply, installation, testing & commissioning of following section length having gravity rollers of length 950 mm (approx.), roller capacity 35kg per linear meter, 60/65 mm pitch/ dia or as per manufacture's recommendation, width section 1000 mm and height suitably matched and sloped, complete in all respects I/c conveyor frame section, rollers, supports as per technical specifications for baggage handling system including cutting & drilling of holes, equipment grouting etc. as required, as per the site requirement. (a) Section Length - 2000 mm	1	Each	60000.00	60000.00	INR Sixty Thousand Only


 AC/MTA
 08/11/2021



NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
2	SH :II -ARRIVAL CONVEYOR					
2.01	Endless Slat Conveyor Design, supply, installation, testing and commissioning of heavy duty endless slat type Arrival Baggage conveyor system having nominal useful width of 950 mm having rubber slats back in colour with smooth top of PVC/PU/Rubber, Antistatic, flame,retardant, height 450 mm from finished floor level and speed of 24-30 Mtr. The Carousel shall have die cast aluminium chain block friction type suitable capacity drive unit complete with overlapping slats finished chain track unit frame work tension adjustment device stainless steel side covering (inner & outer) in the passage area as well as in non passenger area , toe kick plate at inner & outer sides, Infill, rubber slat of suitable dimension with MS Slat support having live loading capacity of 35 Kg per linear, Metre, all accessories including cutting and drilling of holes, equipment grounding, earthing, necessary wiring, connection/interconnection etc. as required for successful commissioning of Baggage Conveyor System complete as required. Length 45.00 mtrs approx each.	2	Each	1890000.00	3780000.00	INR Thirty Seven Lakh Eighty Thousand Only
2.02	Arrival Feeder Belt Conveyor Design, supply, installation, testing and commissioning of heavy duty Slider Bed Departure conveyor of 1 length of 13.2 Mtr. Long conveyor measure across the centre line having frame 1050 mm (Useful width not less than 1000 mm) and 400 mm height from finished floor level for easy handling of passenger weighing 35 Kg per linear Mtr. at speed of 21 to 25 Mtr/Min. complete with PVC Belt on bed construction as specified i/c drive units and end pulleys, take up pulley/side panels with 1.6 mm thick of stainless steel and all other accessories for successful commissioning of Baggage Conveyor System as per following length, specification & drawing complete as required.	1	Job	330000.00	330000.00	INR Three Lakh Thirty Thousand Only
2.03	Control panel for arrival baggage handling system Design, supply installation, testing and commissioning of cubical type, indoor floor / frame mounting, compartmentalized, fabricated out of CRCA sheet steel of thickness 2 mm duly powder coated. The panel shall be front openable & accessible. All doors shall be provided with high quality neoprene rubber gasket. Door interlock feature with Incoming power supply shall be provided as per manufacturer standard. The type of protection for enclosure of the panel shall be minimum IP42 & suitable for operation on 415 volts, 3 Phase, 50 Hz AC supply i/c earthing, connections and comprising of the following component as required for arrival baggage handling system: Incoming Control Unit : 415 Volts TPN MCCBS of breaking capacity of 25KA (Ics=100Icu) with over load & short circuit protection. The rating of the MCCB shall be so selected that only about 80% of its full current carrying capacity is utilized for meeting the requirement of the specific application. Incoming Protection : i) Single Phase Protection ii) Phase reversal protection iii) Under voltage protection Status Indication / display : Indication lamps (LED type) in different colour for Three phases & power ON with protection MCB. Meters (Incoming) : a) Digital type Ammeter of Required range with selector switch & Current Transformers.(b) Digital type Voltmeter with selector switch and protection MCB. MOV & switch : Necessary Surge protection System (block 70KA minimum with Neutral protection) shall be provided at control panel of conveyor with incomer switch. Outgoing for Motors (s) : 1) MPCB of suitable current rating & breaking capacity of 10 KA for each motor. 2) Soft Starter for conveyor motor. Outgoing for rolling shutter : i) 2 Pole MPCB of 10 KA & suitable current rating for each shutter motor. ii) Interlocking with conveyor & limit switches / sensors. iii) Auto-manual switches, separate push button for UP /DOWN mo Emergency stop : Provision shall be made in panel & at three other locations for each	2	Job	180000.00	360000.00	INR Three Lakh Sixty Thousand Only
2.04	Draught Curtain SITC of draught curtain cover for the opening of conveyer belt, of suitable size fabricated with 3mm thick Nylon Rubber flaps, to be fixed by SS flat strip as per size of shutter opening etc. the opening size shall be as per dimensions /drawings approved by engg.-in charge, complete as required (For Arrival & Departure)	5	Job	8000.00	40000.00	INR Forty Thousand Only


 7/4/2022
 28/11/2022



NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
2.05	Rolling Shutter SITC of electrically operated rolling shutter with arrangement for auto and manual operation to suit to the opening in wall fabricated MS provided with suitable rated tubular geared single phase motor directly coupled to the shaft of the shutter, limit switch or sensor interlock with conveyer starter, complete with guide channels, wiring, earthing, painting etc. as required for the successful operation of the shutter for minimum opening size 1.5mtr (L) x 1.35mtr (W). (For Arrival - 02 Nos & Departure - 01 No)	5	Job	55000.00	275000.00	INR Two Lakh Seventy Five Thousand Only
3	SH:III-AICMC FOR THREE YEARS (AFTER DLP) All inclusive comprehensive maintenance of the entire Baggage Handling Systems as covered under the capital works including all spares, consumables, manpower etc. including preventive maintenance, trouble shooting, break down maintenance etc. as per the recommendations of the manufacturer, instructions of Engineer-in-charge, standard engineering practice and special conditions specified for maintaining the above systems in acceptable functional, operational, serviceable conditions					
3.01	For 1st year (After DLP) (Amount pre-fixed @ 2.48% of SITC cost)	1	Year	194556.00	194556.00	INR One Lakh Ninety Four Thousand Five Hundred & Fifty Six Only
3.02	For 2nd year (Amount pre-fixed @ 2.61% of SITC cost)	1	Year	204754.50	204754.50	INR Two Lakh Four Thousand Seven Hundred & Fifty Four and Paise Fifty Only
3.03	For 3rd year (Amount pre-fixed @ 2.74% of SITC cost)	1	Year	214953.00	214953.00	INR Two Lakh Fourteen Thousand Nine Hundred & Fifty Three Only
Total in Figures					8459263.50	INR Eighty Four Lakh Fifty Nine Thousand Two Hundred & Sixty Three and Paise Fifty Only
Quoted Rate in Words				INR Eighty Four Lakh Fifty Nine Thousand Two Hundred & Sixty Three and Paise Fifty Only		


 Anildas Bekal
 08/11/2022


 08.11.22
 Jt GM (E-E)
 AAI, Ayodhya.

Signature Not Verified

Digitally signed by ANILDAS BEKAL
 Date: 2024.06.24 16:15:28 IST
 Location: eProcurement System for Central PSUs

