



संख्या: AAI/KAN/E-C/ Maint. Rwy-15/2022/68

Dated: 04.01.2023

सेवा में,

मेसर्स मेहराज उद दीन राथर,
धर्म बघ, क्राल्पोरा, तहसील बी. के. पोरा,
जिला बडगाव, श्रीनगर, जेएंडके-190019

M/s Mehraj-Ud-Din Rather,
Dharam Bugh, Kralpora, Tehsil B.K. Pora,
Distt. Budgam, Srinagar, J&K-190019

Name of work: Maintenance of Area beyond Runway 15 at Kangra Airport.

संदर्भ : दिनांक 10.10.2022 को खोली गई आपकी ई-निविदा (वित्तीय निविदा)।

Reference : Your e-tender (financial bid) opened on 10.10.2022

महोदय/ Sir

1. उल्लेखित कार्य हेतु आपकी निविदा आपके द्वारा उद्धृत कुल राशि रु 6,64,530/- (छः लाख चौसठ हजार पांच सौ तीस मात्र) जी एस टी के अतिरिक्त की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि निविदा की अनुमानित लागत रु. 13,74,470/- से 51.65 प्रतिशत नीचे हैं।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you total amounting to Rs. 6,64,530/- (Rupees Six Lakh Sixty Four Thousand Five Hundred and Thirty Only) excluding GST which is 51.65% Below the estimated cost put to tender of Rs. 13,74,470/-.

2. सहायक महाप्रबंधक (अभियांत्रिकी-सिविल), भारतीय विमानपत्तन प्राधिकरण, कांगड़ा हवाई अड्डा, कांगड़ा इस कार्य के इंजीनियरिंग प्रभारी होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु 29.01.2023 तक सहायक महाप्रबंधक (अभियांत्रिकी-सिविल), भारतीय विमानपत्तन प्राधिकरण, कांगड़ा हवाई अड्डा, कांगड़ा के कार्यालय में उपस्थित हों। संविदा करार रु 100/- (मात्र सौ रुपये) के न्यायिकेतर (नॉन- ज्युडिशियल) स्टॉप पेपर पर बनाया जाएगा तथा स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी।

Assistant General Manager (Engg-Civil) AAI, Kangra Airport, Kangra shall be the Engineer-in-charge of the work. You are requested to attend the office of the Assistant General Manager (Engg-Civil) AAI, Kangra Airport, Kangra by 29.01.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of Rs. 100/- (Rupees one hundred only) and the cost of the stamp paper shall be borne by you.

3. आपकी निविदा के साथ प्राप्त रुपये 27,490/- (रुपये सताईस हजार चार सौ नब्बे मात्र) की बयाना राशि को संविदा कागजात के पृष्ठ जीसीसी-23 पर दर्ज धारा 1ए के अनुसार प्रतिभूति जमा राशि में परिवर्तित कर दिया गया है। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर प्रतिभूति जमा के रूप में शेष रु 38,963/- (रुपये अड़तीस हजार नौ सौ तिरसठ मात्र) जमा करें अन्यथा संविदा कागजात के पृष्ठ जीसीसी-23 पर दर्ज धारा 1ए के अनुसार इस राशि की कटौती आपके चालू बिलों से कर ली जाएगी।

Page 1 of 3


04/01/23

Earnest Money Amount of Rs. 27,490/- (Rupees Twenty Seven Thousand Four Hundred and Ninety only) received along with your tender has been converted as part of security deposit, as per clause of contract 1(A) page GCC-23 of the contract document. Please deposit the balance amount of Rs. 38,963/- (Rupees Thirty Eight Thousand Nine Hundred and Sixty Three Only) towards security deposit within 10 days from the date of issuing of this letter, failing which, the same will be deducted from your RAR bills as per clause of contract 1 A, Page GCC-16 of the contract document.

4. आप से अनुरोध है कि आप संविदा श्रम (विनियम एवं उन्मूलन) अधिनियम 1970 तथा संविदा श्रम (विनियम एवं उन्मूलन) केन्द्रीय नियम 1971 एवं न्यूनतम मजदूरी अधिनियम के प्रावधानों और केन्द्रीय व राज्य सरकारों के तदसंबंधी नियमों का अनुपालन करें।

You are requested to comply with the provision of contract labour (Regulation & abolition) Act of 1970 and contract labour (Regulation & Abolition) Central Rules 1971 and minimum wages Act and Rules there of Central and state Govt.

5. आपको वरिष्ठ प्रबंधक (अभियांत्रिकी-सिविल), कांगड़ा हवाई अड्डा से तत्काल संपर्क करने का भी निर्देश दिया जाता है। आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा ही किया जाएगा।

You are also directed to contact Senior Manager (Engg- Civil), Kangra Airport immediately who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य पूरा करने के लिए आपको 03 महीने का समय प्रदान किया जाता है। यह समय इस पत्र के जारी होने के दसवें दिन से प्रारम्भ माना जाएगा।

Please note that the time allowed for carrying out the work shall be 03 months. It shall be reckoned from the 10th day of issue of this letter.

7. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः इंजीनियर-प्रभारी के नाम से किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer In-Charge.

8. कृपया पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप विधिवत् हस्ताक्षर करके हमें वापस भेजें।


Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।

In case any discrepancy is found, then English version will be taken as correct.

भवदीय

Yours Faithfully


(अमित जिंदल)

(Amit Jindal)

सहा महाप्रबंधक (अभि-सि)

AGM (Engg-Civil)

संलग्नक/Encls:

1. Form-V
2. BOQ

प्रतिलिपि:

Copy to:

External:

1. Labour Commissioner, Punjab, SCO No. 47-48, Sector - 17 E Chandigarh - 160017
2. Regional Provident Fund Commissioner, SCO 4-7, Sector 17 D, Chandigarh-160017

Internal:

1. RED-NR, AAI, Operational office, Gurgaon Road, New Delhi - 37
2. GM (Engg)-NR, AAI, Operational office, Gurgaon Road, New Delhi - 37
3. GM (F&A)-NR, AAI, Operational office, Gurgaon Road, New Delhi - 37
4. Jt. GM (Engg-Civil)- NR, AAI, Operational office, Gurgaon Road, New Delhi - 37
5. Airport Director, AAI, Kangra Airport, Kangra (H.P.)-176 209
6. AGM (Engg-Elect), AAI, Kangra Airport, Kangra (H.P.)-176 209
7. Sr. Manager (Engg-Civil), AAI, Kangra Airport, Kangra (H.P.)-176 209
8. CSO, AAI, Kangra Airport, Kangra (H.P.)-176 209
9. Works file.
10. Agreement copy.


07/07/23
सहा महाप्रबंधक (अभि-सि)
AGM (Engg-Civil)

Name of work : - Maintenance of Area beyond Runway 15 at Kangra Airport.

BILL OF QUANTITIES (BOQ)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
1.00	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5 m in width as well as 10 Sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, as directed by Engineer-in-charge. All kinds of soil	300.00	cum	200.00	60000.00
2.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc, in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	300.00	cum	100.00	30000.00
3.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	2500.00	sqm	10.00	25000.00
4.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared	2500.00	sqm	15.00	37500.00
5.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	10.00	cum	6000.00	60000.00
6.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	5.00	cum	4000.00	20000.00
7.00	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	11.00	cum	5500.00	60500.00
8.00	Centering and shuttering including strutting, propping etc. and removal of form for Retaining walls, return walls, Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	20.00	sqm	200.00	4000.00
9.00	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)	23.00	cum	6000.00	138000.00
10.00	Centering and shuttering including strutting, propping etc. and removal of form for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	100.00	sqm	200.00	20000.00
11.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more	2800.00	kg	40.00	112000.00
12.00	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	41.00	Cum	10.00	410.00
13.00	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 m.	560.00	sqm	2.00	1120.00
14.00	Supplying, filling, spreading & leveling coarse sand of size range 1.5mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads & lifts, all complete as per direction of Engineer-in-charge	120.00	cum	800.00	96000.00
Total					664530.00


Print
02/01/23

FORM V

FORM OF CERTIFICATE BY PRINCIPAL EMPLOYER

Certified that AAI have engaged the applicant "M/s Mehraj-Ud-Din Rather, Dharam Bugh, Kralpora, Tehsil B.K. Pora, Distt. Budgam, Srinagar, J&K-190019" as a contractor for the work of "Maintenance of Area beyond Runway 15 at Kangra Airport". AAI undertakes to be bound by all the provisions of contract labour (Regulation and Abolition) Act, 1970, and the Central Contract Labour (Regulation and Abolition) Rules, 1971 Child labour (Prohibition & Regulation) Act, 1986, Construction workers (Regulation of Employment and condition of service) Act, 1996, Building and other Construction Workers welfare Cess Act 1906, in so far as the provisions are applicable to me in respect of the employment of contract labour by the applicant in my establishment.

Place:- Kangra (Himachal Pradesh)


04/01/23
Signature & Seal of
The Principal Employer

Date:- 04 Jan 2023