

संदर्भ सं: भाविप्रा/बि बि एसआर/इंजी(सि)/प्रोफाइल शीट कैनोपी/कार्य-आदेश संख्या- /2022-23/ दिनांक: 16.11.2022
Ref: AAI/BBSR/Engg.(C)/Profile Sheet Canopy/W.O No- /2022-23/ Date: 16.11.2022

सेवा में/To,
मेसर्स प्रशांत कुमार बेउरिया/ M/s. Prasanta Kumar Beuria,
प्लॉट संख्या - 169, मकान संख्या -1680/ Plot No.-169, House no.-1680,
नुआपटना, फूलनखरा/Nuapatna, Phulanakhara
खुर्दा/Khurda-754001

विषय: बी.पी.आई हवाई अड्डा, भुवनेश्वरमें वीआईपी और टीपी गेट पर प्रोफाइल शीट कैनोपी का प्रावधान ।
Sub: Provision of profile sheet canopy at VIP & TP gate at B.P.I. Airport, Bhubaneswar.

संदर्भ: आपकी निविदा खुलने की तारीख 21.10.2022
Ref.: Your Tender opened on 21.10.2022.

महोदय / Sir (s),

1. उपरोक्त कार्य के लिए आपका ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आप के द्वारा उद्धृत मद दर जिसकी कुल राशि रु. 22,96,290.00 (बाईस लाख छियानबे हजार दो सौ नब्बे रुपया मात्र) (जीएसटी अतिरिक्त) जो कि निविदा की लागत रु. 31,70,868.00 से 27.58% कम है, स्वीकृत किया जाता है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totalling to Rs.22,96,290.00 (Rupees Twenty-two Lakhs Ninety-six Thousand Two Hundred Ninety only) (GST extra) which is 27.58% below the estimated cost put to tender of Rs. 31,70,868.00.

2. उप महा प्रबंधक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, बि.पि.आई. हवाई अड्डा, भुवनेश्वर इस कार्य के इंजीनियर प्रभारी होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु इस पत्र के जारी किए जाने के 10 (दस) दिनों के भीतर उप महा प्रबंधक (अभि.-सिविल), भारतीय विमानपत्तन प्राधिकरण, बि.पि.आई. हवाई अड्डा के कार्यालय में उपस्थित हों। संविदा करार रु 100/- (सौ रुपये मात्र) के न्यायिकेतर (नॉन ज्युडिशियल) स्टाम्प पेपर पर बनाया जाएगा और स्टाम्प पेपर की लागत आपको वहन करनी होगी।

Dy. General Manager Engg (C), AAI, B.P.I. Airport, Bhubaneswar shall be the Engineer-in-Charge of the work. You are requested to attend office of Dy. General Manager Engg (C), AAI, B.P.I. Airport within 10 (ten) days from the date of issue of this letter, to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने के 10 दिन में सुरक्षा जमा के लिए रु 2,70,963.00 (दो लाख सत्तर हजार नौ सौ तिरसठ रुपया मात्र) जमा करवा दें, ऐसा नहीं करने पर उक्त रकम संविदा दस्तावेज के पृष्ठ 16 पर दी गई शर्त 1A के अनुसार आपके रनिंग बिल से काट ली जाएगी।

Please deposit Rs. 2,70,963.00 (Rupees Two Lakhs Seventy Thousand Nine Hundred Sixty-three only) towards Security Deposit within 10 (Ten) days from the date of issue of this letter, failing which, the same will be deducted from your running bill as per condition of Clause no. 1A on page 16 of the Contract document

Contd. in next page

स्वीकृत
16.11.2022

4. आपसे अनुरोध है कि संविदा श्रमिक (विनियमन एवं समापन) अधिनियम 1970 और संविदा श्रमिक (विनियमन एवं समापन) केन्द्रीय नियमावली 1971, अधिन, केन्द्रीय और राज्य सरकार के न्यूनतम मजदूरी अधिनियम और ई.पी.एफ.एक्ट, 1952 एवं ई. एस. आई. एक्ट नियमों का पालन करें।
You are requested to comply with provision of Contract Labour (Regulation and Abolition) Act of 1970 and contract (Regulation and Abolition) Central rules 1971, Minimum Wages Act & Rules, EPF Act, 1952 and ESI act thereof Central & State Governments.
5. आपको निर्देश दिए जाते हैं कि सहायक प्रबंधक (अभि. - सिविल), भारतीय विमानपत्तन प्राधिकरण, बि.पि.आई. हवाई अड्डा से तत्काल सम्पर्क करें जो कि आपको कार्यस्थल सुपर्द करने की व्यवस्था करेंगे।
You are also directed to contact Asst. Manager (Engg.-C) , AAI, B.P.I. Airport immediately who will arrange to hand over the site to you.
6. कृपया ध्यान दें कि कार्य को करने के लिए अनुमत समय 06 (छः) महीने होगा जो की इस पत्र के जारी होने के बाद 10 वें दिन से शुरू हो जाएगा या जो भी पहले हो, वास्तविक तिथि।
Please note that the time allowed for carrying out the work shall be 06 (Six) months and the same shall be reckoned from the 10th day after issue of this letter or actual date of start whichever is earlier.
7. संविदा के संबंध में आगे किया जाने वाला पत्राचार समान्यतः इंजीनियर प्रभारी से किया जाए।
Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.
8. कृपया इस पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दुसरी प्रति पर स्वीकारोक्ति के रुप विधिवत हस्ताक्षर करके हमें वापस भेजें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.
9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।
In case any discrepancy is found, then English version will be taken as correct.

धन्यवाद/ Thanking you.

भवदीय / Yours faithfully,

रवि शंकर
16.11.2022

(रवि शंकर)/(Ravi Shankar)

सहा महा प्रबंधक (अभि. - सिविल)

Asst. General Manager Engg. (C)

भा.वि.प्रा., बि.पि.आई. हवाई अड्डा, भुवनेश्वर

AAI, B.P.I. Airport, Bhubaneswar

संलग्न / Encl: 1. अनुसूची "A" / Schedule "A"

2. फार्म - III और VII /Form- III & VII.

प्रतिलिपि / Copy to:

N.O.O.

External:

1. Labour Commissioner (Central), Kendriya Shrama Sadan, Plot No. N-7/6 & 7, IRC Village, Behind ISCON Temple, Nayapalli, Bhubaneswar – 15, Odisha.
2. Commissioner of Income tax (TDS), Ayakar Annex Building, Rajaswa Vihar, Sahid Nagar, Bhubaneswar - 751007.
3. Regional Provident Fund Commissioner, Vabisyanidhi Bhawan, Janpath, Unit IX, Bhubaneswar, Odisha.
4. The Regional Commissioner, Employee State Insurance Corporation, Panchadeep Bhawan, Janpath, Unit IX, Bhubaneswar, Odisha.

रवि शंकर
16.11.2022

(रवि शंकर)/(Ravi Shankar)

सहा महा प्रबंधक (अभि. - सिविल)

Asst. General Manager Engg (C)

भा.वि.प्रा., बि.पि.आई. हवाई अड्डा, भुवनेश्वर

AAI, B.P.I. Airport, Bhubaneswar

Internal:

1. विमानपत्तन निदेशक, भा.वि.प्रा., बि.पि.आई. हवाई अड्डा, भुवनेश्वर ।
2. संयुक्त महा प्रबंधक (बित्त), भा.वि.प्रा., बि.पि.आई. हवाई अड्डा, भुवनेश्वर ।
3. उप महा प्रबंधक (अभि. - सिविल), भा.वि.प्रा., बि.पि.आई. हवाई अड्डा, भुवनेश्वर ।
4. सहायक महा प्रबंधक (अभि. - सिविल), भा.वि.प्रा., बि.पि.आई. हवाई अड्डा, भुवनेश्वर ।

1. Airport Director, AAI, B.P.I. Airport, Bhubaneswar.
2. Jt. General Manager (Finance), AAI, B.P.I. Airport, Bhubaneswar.
3. Dy. General Manager (Engg. - Civil), AAI, B.P.I. Airport, Bhubaneswar.
4. Asst. Manager (Engg. Civil), AAI, B.P.I. Airport, Bhubaneswar.

रवि शंकर
16.11.2022

(रवि शंकर)/(Ravi Shankar)

सहा महा प्रबंधक (अभि. - सिविल)

Asst. General Manager Engg (C)

भा.वि.प्रा., बि.पि.आई. हवाई अड्डा, भुवनेश्वर

AAI, B.P.I. Airport, Bhubaneswar

FORM – III


(Under rule 21 (2) of the Contract Labour (Regulation & Abolition) Central Rules, 1971; and Rule 7 (3) of the Inter State Migrant Workmen (Regulation of Employment and Conditions of Service) Central Rules, 1980

FORM OF CERTIFICATE BY PRINCIPAL EMPLOYER

Certified that:

I have engaged the applicant (name of the contractor) M/s. Prasanta Kumar Beuria, Plot No.-169, House no.-1680, Nuapatna, Phulanakhara, Khurda-754001 as a contractor in my establishment for the work **“Provision of profile sheet canopy at VIP & TP gate at B.P.I. Airport, Bhubaneswar”** to be carried out from the 10th day after issue of this letter or actual date of start whichever is earlier.

1. I undertake to be bound by all the provisions of the Contract Labour (Regulation & Abolition) Act, 1970 (37 of 1970) and the Contract Labour (Regulation & Abolition) Central Rules, 1971* / the Inter State Migrant Workmen Regulation of Employment and Condition of Service) Central Rules, 1980 * in so far as the provisions are applicable to me in respect of the Employment of Contract Labour/ Inter State Migrant Workmen * by the applicant in my establishment.
2. The engagement of contract labour in the said work is not prohibited under sub section (1) of section 10 of the Contract Labour (Regulation & Abolition) Act, 1970 (37 of 1970) or an award or a settlement.*


Signature of Principle Employer
Airports Authority of India,
B.P.I. Airport, Bhubaneswar

Place: Bhubaneswar Airport

Date: .11.2022


FORM- VII

(Under rule 25 (2) (viii) and rule 81 (3) of the Contract Labour (Regulation & Abolition) Central Rules, 1971; and rule 26 (3) and 239 (1) of the Building and Other Construction Workers (Regulation of Employment and Condition of Service) Central Rules, 1998

Notice of commencement of work

1	Name of the Principal Employer under the Contract Labour (Regulation & Abolition) Act, 1970 (37 of 1970) / Employer under the Building and Other Construction Workers (Regulation of Employment and Condition of Service) Act, 1996 (27 of 1996)*	Asst. General Manager (Engg. Civil), Airports Authority of India, B.P.I. Airport, Bhubaneswar
2	LIN/ PAN No.	-
3	Email Id	-
4	Mobile No.	-
5	Name of the Contractor under the Contractor Labour (Regulation & Abolition) Act, 1970 (37 of 1970) (if applicable)	M/s. Prasanta Kumar Beuria, Plot No.-169, House no.-1680, Nuapatna, Phulanakhara, Khurda-754001
6	LIN/ PAN No.	ARFPB1430M
7	Email Id	-
8	Mobile No.	9437231421
9	No. and date of certificate of Registration / License	-
10	Name of person in-charge of the work	Shri. Samir Kumar Naskar Dy. General Manager (Engg. Civil), Airports Authority of India, B.P.I. Airport, Bhubaneswar
11	LIN/PAN No. of person in-charge of the work	-
12	Email Id of person in-charge of the work	samir68@aai.aero
13	Mobile No. of person in-charge of the work	9836917496
14	The nature of work involved and the facilities, including any plant and machinery provided in the case of a building or other construction work.	Provision of profile sheet canopy at VIP & TP gate at B.P.I. Airport, Bhubaneswar
15	The arrangement for the storage of explosives, if any, to be used in the building or other construction work.	Not Applicable

I/ we hereby intimate that the work **Provision of profile sheet canopy at VIP & TP gate at B.P.I. Airport, Bhubaneswar** shall commence with effect from to be carried out from the 10th day after issue of this letter or actual date of start whichever is earlier.


Signature of the Principal Employer

To

The Labour Commissioner (Central), Kendriya Shrama Sadan, Plot No. N-7/6 & 7, IRC Village, Behind ISCON Temple, Nayapalli, Bhubaneswar – 15, Odisha.

**AIRPORTS AUTHORITY OF INDIA
B.P.I. AIRPORT, BHUBANESWAR
(CIVIL ENGINEERING WING)**

BILL OF QUANTITY

Name of Work: Provision of profile sheet canopy at VIP & TP gate at B.P.I. Airport, Bhubaneswar

Sl. No.	Description of Work / Item(s)	Units	Qty	Rate	Amount
1.00	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum	25.00	550.00	13750.00
2.00	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	Cum	100.00	100.00	10000.00
3.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	Cum	5.00	3900.00	19500.00
4.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	Cum	10.00	3500.00	35000.00
5.00	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	Cum	40.00	4500.00	180000.00
6.00	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cum	5.00	5000.00	25000.00
7.00	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	Sqm	85.00	155.00	13175.00
8.00	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	50.00	300.00	15000.00
9.00	Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	120.00	300.00	36000.00
10.00	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls- Under 20 cm wide	Mtr.	70.00	300.00	21000.00
11.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	4350.00	70.00	304500.00

श्रीवेंकट
16/11/2022

Sl. No.	Description of Work / Item(s)	Units	Qty	Rate	Amount
12.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	325.00	70.00	22750.00
13.00	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 7.5 average compressive strength in foundation and plinth in :Cement mortar 1:6 (1 cement : 6 Coarse sand) all complete as per direction of E.I.C.	Cum	10.00	3900.00	39000.00
14.00	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 7.5 average compressive strength in super structure above plinth level up to floor V level in :Cement mortar 1:6 (1 cement : 6 Coarse sand) all complete as per direction of E.I.C.	Cum	20.00	4700.00	94000.00
15.00	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	Sqm	80.00	150.00	12000.00
16.00	15 mm cement plaster on the rough side of single or half brick wall of mix :1:6 (1 cement: 6 fine sand)	Sqm	80.00	180.00	14400.00
17.00	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	Sqm	20.00	170.00	3400.00
18.00	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Sqm	200.00	100.00	20000.00
19.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes	Kg	10000.00	105.00	1050000.00
20.00	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	Kg	300.00	73.00	21900.00
21.00	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	330.00	535.00	176550.00
22.00	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :Ridges plain (500 - 600mm)	Mtr.	40.00	360.00	14400.00
23.00	Extra for providing and fixing wind ties of 40x 6 mm flat iron section.	Mtr.	140.00	110.00	15400.00
24.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work	Sqm	600.00	100.00	60000.00

2192.50
16/11/2022

Sl. No.	Description of Work / Item(s)	Units	Qty	Rate	Amount
25.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	50.00	150.00	7500.00
26.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	110.00	74.00	8140.00
27.00	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	Mtr	35.00	255.00	8925.00
28.00	Providing Engineering consultancy services from reputed and approved professional consultant for structural design and drawing for the sheds: i) At TP Gate (approx. 15m x 6.5m and 6 m height) ii) At VIP Gate (approx. 15m x 7.5m and 6 m height) All the proposed structure including roofing sheet should be designed to withstand maximum wind speed for coastal region climate (cyclone/storm) as per IS-875 (Part-3) 2015. All the structural design and drawings shall be got vetted/approved from any AICTE accredited Govt. Engineering College. The consultant is required to submit minimum 03 sets of design calculation and drawings after vetting for final approval.	Job	1.00	55000.00	55000.00

Total = Rs. 2296290.00

(Rupees Twenty-two Lakh Ninety-six Thousand Two Hundred Ninety only)

N.B: The rates are exclusive of applicable GST.

रवि शंकर
16/11/2022

(रवि शंकर)/(Ravi Shankar)
सहा महा प्रबंधक (अभि. - सिविल)
Asst. General Manager (Engg.Civil)
भाविप्रा,बि.पि.आई.हवाई अड्डा,भुवनेश्वर
AAI, B.P.I. Airport, Bhubaneswar

Signature Not Verified

Digitally signed by BIDURA CHANDRA SAHOO
Date: 2025.10.22 18:19:42 IST
Location: eProcurement System for Central PSUs