

(पंजीकृत डाक)

संदर्भ: भा.वि.प्रा./रापु./अभि(सि)/स.म.प्र./लोकलाइजर/2022/3084-97

दिनांक:- 14.12.2022

सेवा में,

मैसर्स एमडी रियाजुद्दीन,
प्लॉट नंबर-67, विमपुर एयरपोर्ट,
पीओ न्यू बापूजी नगर,
पीएस-एयरफील्ड, भुवनेश्वर,
खुर्दा, ओडिशा,

To,

M/s MD Riyajuddin,
Plot no.-67, Vimpur Airport,
PO. New Bapuji Nagar,
Ps.-Airfield, Bhubaneswar,
Khurda, Odisha

विषय: स्वामी विवेकानंद हवाई अड्डा, रायपुर में लोकलाइजर हट का निर्माण और अन्य संबंध सिविल कार्य।

निविदा क्रमांक : 2022_AAI_133404_1

Sub: Construction of Localizer Hut and other associated civil works at S.V. Airport, Raipur.

Tender ID: - 2022_AAI_133404_1

संदर्भ: आपकी ई-निविदा जो दिनांक 02.12.2022 को खोली गयी।

Ref: Your E-tender opened on 02.12.2022

महोदय/Sir,

- उपरोक्त कार्य के लिए आपकी मदद दर निविदा आपके द्वारा उद्धरित राशि रु. 73,28,164.00/- (रुपये तिहत्तर लाख अट्ठाईस हजार एक सौ चौंसठ मात्र) जो कि अनुमानित लागत रु. 1,02,44,000/- (जी.एस.टी. छोड़कर) से 28.46% नीचे है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs 73,28,164.00/- (Rupees Seventy Three Lakhs Twenty Eight Thousand One Hundred Sixty Four only) (Excluding GST) which is 28.46% Below the estimated cost put to tender of Rs. 1,02,44,000/- (Excluding GST).

- आपसे अनुरोध है कि कृपया दिनांक 07.01.2023 तक स्वामी विवेकानंद हवाई अड्डा, रायपुर पर अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित रहकर संविदा करार तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। यह संविदा करार 100/- रुपये (सौ रुपये मात्र) के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका खर्च आपके द्वारा वहन किया जायेगा।

You are requested to attend the office of the undersigned at Swami Vivekananda Airport, Raipur by 07.01.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

- आपके निविदा के साथ प्राप्त धरोहर राशि रुपये 2,05,000/- (रुपये दो लाख पांच हजार मात्र) है। कृपया संविदा करार के पेज नंबर जी.सी.सी-16 पर धारा नं. 1A के अनुसार इस कार्यादेश के जारी होने के तिथि से 10 दिनों के भीतर जमानत जमा के रुपये 5,27,816/-



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

(रुपये पांच लाख सत्ताईस हजार आठ सौ सोलह मात्र) इस कार्यालय में जमा कराये अन्यथा यह निविदा दस्तावेज के पेज नंबर जी.सी.सी-16 पर धारा नं. 1A के अनुसार काटा जायेगा।

The Earnest Money amount of Rs. 2,05,000/- (Rupees Two Lakhs Five Thousand Only) received along with your tender. Please deposit Rs. 5,27,816/- (Rupees Five Lakhs Twenty Seven Thousand Eight Hundred Sixteen Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at Page GCC-16 of tender document.

4. आपसे अनुरोध है कि संविदा करार के पेज नंबर जी.सी.सी-50 पर धारा नं. 19 के अनुसार आप टेका श्रमिक (विनिमय एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करें, साथ ही टेका श्रमिक (विनिमय एवं उन्मूलन) केन्द्रीय नियमावली 1971, बाल श्रम (निषेध एवं विनिमय) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की हालत का विनिमय) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकरण अधिनियम 1996 तथा केन्द्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 50 of GCC of tender and rules of Central and State Governments.

5. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ई.एस.आई. अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अंतर्गत बनाये गये सभी नियमों एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा करायेंगे तथा पीएफ खाता कोड और ई.एस.आई. पंजीकरण काम के वास्तविक समापन तक वैध रहें।

You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

6. आपसे यह भी अनुरोध है कि आप प्रबंधक (अभि.-सि) से अविलम्ब संपर्क करें जो कि आपको साइट हस्तांतरित करने की व्यवस्था करेंगे।

You are also directed to contact Manager (Engg-C) immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय 06 (छः) महीने होगा और इस पत्र के जारी होने के बाद दसवें दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 06 (Six) months and same shall be reckoned from the 10th day after issue of this letter.

8. आगे से इस अनुबंध के संबंध में किसी प्रकार के पत्राचार को अधोहस्ताक्षरकर्ता/प्रभारी अभियंता को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Undersigned/Engineer-in-charge.

9. कृपया इस पत्र की प्राप्ति-सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

संलग्न: अनुसूची-अ

भवदीय,

—Sd—

(विनय कुमार ताम्रकार)
सहा. महाप्रबंधक (अभि.-सि)
भा.वि.प्रा., एस.व्ही. हवाई अड्डा, रायपुर
के लिए एवं तरफ से अध्यक्ष
भारतीय विमानपत्तन प्राधिकरण

मूलप्रति में नही

प्रतिलिपि:

1. क्षेत्रीय कार्यापालक निदेशक, पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
2. महाप्रबंधक (अभि), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
3. महाप्रबंधक (वित्त), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
4. संयुक्त महाप्रबंधक (अभि-सि), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा कोलकाता-52।
5. सहायक महाप्रबंधक (सर्तकता), पू.क्षे., भा.वि.प्रा., ने.सु.च.बो.अं. हवाई अड्डा, कोलकाता-52।
6. सहायक श्रम आयुक्त (सी), डी-6, आदर्श सोसाइटी, सेक्टर-1, अवंती विहार, रायपुर।
7. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि कार्यालय, ब्लॉक-डी, स्कीम नं.-32, इंदिरा गांधी व्यावसायिक परिषद, पंडरी, रायपुर (छ.ग.)-492004।

प्रतिलिपि:

1. विमानपत्तन निदेशक, भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
2. उपमहाप्रबंधक (वित्त), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
3. सहायक महाप्रबंधक (अभि-सि)-I, भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
4. सहायक महाप्रबंधक (अभि-वि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
5. प्रबंधक (अभि-सि), भा.वि.प्रा., स्वामी विवेकानंद हवाई अड्डा, रायपुर।
6. कार्यालय प्रति।

(विनय कुमार ताम्रकार)
14.12.2021

सहा. महाप्रबंधक (अभि.-सि)

Schedule-A

Name of Work: Construction of Localizer Hut and other associated civil works at S.V. Airport, Raipur.

Sl.No	Description of Work / Item(s)	Units	No. of Qty	Rate	Amount
1	Providing and fixing of one no. prefabricated frangible hut (design as per criteria mentioned in ICAO's Aerodrome Design Manual (Doc 9157) Part-6) made of sandwich panel of 2mm thick FRP/ GRP sheet at the outer sides and middle part consists of PU foam of density 40 kg/m³ having total thickness 40 mm. which has to be installed in to the operational area.the prefabricated frangible hut shall consist of following- a) of size 8.0m x 5.0m and 3.0 m height at the wall and 3.50 meter height at the ridge Provision of one number of partition wall with partially Glass door & locking arrangement. Provision of one number of main door on the longer side wall with necessary locking arrangement. provision of drain/gutter at both end having width of 100 mm . b) of size 2.0 m x 2.0 m and 3.0 m height in one wall and other wall is 3.5 meter height (FFM) Provision of one number of main door with necessary locking arrangement. c) of size 2.2 m x 2.2 m and 3.5 m height (Toilet) Provision of holes as per approved drawing on walls for electrical cables, split air conditioning system , Communication cables including necessary fixing arrangement for electric fittings, fixtures & NAV ADIS installations in cabin as per approved drawing. The exterior of the hut shall be painted with design of white and red squares (2 feet X 2 feet) as per direction of E-I-C. The cost of the hut is inclusive of design, earlier/newly vetting of design by IIT/NIT/Govt. Engg. College of any size, fabrication, transportation, all taxes including service tax and commissioning of the hut at the proposed site as per drawing and specification over a Cement Concrete platform (Required civil work shall be paid separately) All activities shall be executed as per approved Drawing and direction of Engineer-in-charge.	Job	1	1716321	1716321.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 min width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soils.	Cum	150	107	16050.00
3	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : All kinds of soil. Pipes, cables etc, not exceeding 80 mm dia.	Mtr	300	209	62700.00
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	80	211	16880.00
5	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	40	705	28200.00
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	a) 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	Cum	65	4400	286000.00
	b) 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cum	180	3800	684000.00
7	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost or centering, shuttering, finishing and reinforcement -All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	15	5015	75225.00

8	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement. 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	10	5434	54340.00
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	Cum	18	4345	78210.00
10	Centering and shuttering including strutting, propping etc. and removal of form for:				
	a) Foundations, footings, bases of columns, etc. for mass concrete	Sqm	101	175	17675.00
	b) Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	124	245	30380.00
	c) Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	31	303	9393.00
11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars	Kg	5700	77	438900.00
12	Brick work with Fly Ash Bricks or class designation 5.0 in cement mortar 1:4 (1 cement : 4 coarse sand) in foundation and plinth :	Cum	36	3434	123624.00
13	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	172	111	19092.00
14	Providing and fixing 1 mm thick M.S. sheet sliding-shutters, with frame and diagonal braces of 40x40x6 mm angle iron, 3 mm M.S gusset plates at the junctions and corners, 25 mm dia pulley, 40x40x6 mm angle and Tiron guide at the top and bottom respective	Sqm	6	3721	22326.00
15	Cement concrete pavement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including finishing complete.	Cum	63	4100	258300.00
16	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc complete. Size of Tile 600x600 mm	Sqm	40	1460	58400.00
17	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110 mm diameter	Mtr	20	315	6300.00
18	12 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand)	Sqm	151	171	25821.00
19	15 mm cement plaster on the rough side of single or half brick wall of mix: 1:6 (1 cement: 6 fine sand)	Sqm	111	191	21201.00
20	6 mm cement plaster of mix: 1:3 (1 cement: 3 fine sand)	Sqm	144	161	23184.00
21	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory \ compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	390	675	263250.00
22	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	Sqm	5890	9	53010.00
23	Providing and laying non-pressure NP2 class (light duty) RC.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 150 mm dia. R.CC pipe	Mtr	100	375	37500.00
24	Supplying and stacking at site. Good earth	Cum	102	299	30498.00
25	Demolishing R.C.C. work by mechanical means and stockpiling at designated locations and disposal of dismantled materials up to a lead of 1 kilometre, stacking serviceable and unserviceable material separately including cutting reinforcement bars.	Cum	22	707	15554.00

26	Excavating, supplying & Construction of sub-grade with approved material gravelly soil / Moorum (inclusive of royalty) obtained from borrow pits (outside airport premises) with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2 of moth specification, minimum CBR value of 15% as per IS 2720 (part 16) as directed by Engineer-in-charge and as per particular specification.	Cum	4545	525	2386125.00
27	Providing and fixing G.I. pipes complete with GL fittings including trenching and refilling etc. 150 mm dia. nominal bore	Mtr	80	2100	168000.00
28	Providing and fixing HDPE pipes etc. all complete including trenching and refilling etc. 160 mm dia nominal bore	Mtr	80	1214	97120.00
29	Providing and fixing HDPE pipes etc. all complete including trenching and refilling etc. 110 mm dia nominal bore	Mtr	130	725	94250.00
30	Supplying of epoxy Resin/Hardener of make Pidilite or approved equivalent for fixing of antena bolts etc. all complete as per direction & satisfaction of Engineer-in-charge.	Each	20	345	6900.00
31	Supplying & fitting PVC water storage tank (capacity of 1000 litter) of approved make or equivalent including Cutting holes of required sizes and connecting to water supply lines as required all complete as per direction & satisfaction of Engineer-in-charge.	Each	1	9200	9200.00
32	Supplying & fixing at ground PVC pipe of 100 mm dia and length 1.00 mtr (thickness as required) all complete as per direction & satisfaction of Engineer-in-charge.	Each	220	311	68420.00
33	Constructing soak pit 1.20x1.20x1.20 m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	Each	1	17165	17165.00
34	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	Each	1	8650	8650.00
			Total		7328164.00

14.12.2022

Signature Not Verified

Digitally signed by VINAY KUMAR
TAMRAKAR

Date: 2023.03.31 17:03:54 IST

Location: eProcurement System for Central
PSUs