



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

भाविप्रा/भोपाल/अभि.-सि./डब्ल्यू-02/ड्रेन,सिक्कूरिटीहट,दीवाल/2022-23

दिनांक: 14.12.2022

सेवामें/ To,
मेसर्स बिलिफ बिल्डकॉन प्राइवेट लिमिटेड

A-29 न्यू फ्रेंड्स सोसाइटी चूनाभट्टी

भोपाल (म.प्र.) 462016

मोबाइल :- 8236999999, 0755-4201850

ईमेल - vejay@belief.co.in

M/s BELIEF BUILDCON PRIVATE LIMITED

A-29 NEW FRIENDA SOCIETY CHUNABHATTI

BHOPAL (M.P) 462016

Mob :- 8236999999, 0755-4201850

email :- vejay@belief.co.in

विषय :- राजा भोज हवाई अड्डे भोपाल में परिचालन क्षेत्र में आरसीसी नाली और कवर, सुरक्षा झोपड़ियों और चारदीवारी का विस्तार का प्रावधान का कार्य.

Subject:- Provision of RCC drain & Covers, Security huts & Augmentation of boundary wall in operational area at Raja Bhoj Airport Bhopal

संदर्भ:- आपकी निविदा संख्या 2022_AAI_134979_1 दिनांक 06/12/2022 को खोला गया।

Ref: Your E-tender No. 2022_AAI_134979_1, opened on dated 06/12/2022.

महोदय/Dear Sir (S),

1. अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से उपरोक्त वर्णित कार्य का आपकी मद मूल्यों पर आधारित ई-निविदा राशि ₹1,45,97,652.00/- (रुपये एक करोड़ पैंतालीस लाख सतानवे हजार छह सो बावन मात्र) (बिना जीएसटी) तथा ₹1,72,25,229.00 (18% जीएसटी जोड़कर) होगी, जोकि अनुमानित लागत ₹2,41,03,695.00 (रुपये दो करोड़ इकतालीस लाख तीन हजार छह सो पचानवे मात्र) (बिना जीएसटी) तथा (जी एस टी) के साथ 2,84,42,360.00 (रुपये दो करोड़ चौरासी लाख बयालीस हजार तीन सो साठ मात्र) से (-)39.44% (उनतालीस दशमलव चार चार प्रतिशत) कम हैं, स्वीकृत की जाती हैं।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rate quoted by you totaling to ₹1,45,97,652.00/- (Rupees One Crore Forty Five Lakh Ninety Seven Thousand Six Hundred Fifty two Only) (without GST) and Rs 1,72,25,290.00/- (Rupees One Crore Seventy two Lakh Twenty Five Thousand Two hundred Ninety only) (including GST @18%) which is (-) 39.44 % (Thirty Nine point four four Percent) below the estimated cost put to tender i.e., ₹2,41,03,395.00/- (Rupees Two Crore Forty one Lakh Three Thousand Three Hundred Ninety five Only) without GST and ₹ 2,84,42,360.00/- (Rupees Two Crore Eighty four Lakh Forty two Thousand Three hundred sixty only) including GST @18%.

2. संयुक्त महाप्रबंधक अभियांत्रिकी (सिविल) भाविप्रा राजा भोज एयरपोर्ट भोपाल इस कार्य के इंजीनियर प्रभारी होंगे तथा सहा. महाप्रबंधक अभियांत्रिकी (सिविल) इंजीनियर प्रभारी के प्रतिनिधि रहेंगे। आपसे अनुरोध है कि आप संयुक्त महाप्रबंधक अभियांत्रिकी (सिविल) कार्यालय भाविप्रा राजाभोज एयरपोर्ट भोपाल में दिनांक 29/12/2022 तक उपस्थित होकर करारनामे पर हस्ताक्षर कर पूरा करें। यह करारनामा ₹500.00/- (पाँच सौ रुपये) मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जायेगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।

Jt.GM Engg (Civil), AAI, Raja Bhoj Airport, Bhopal, shall be the Engineer-in-Charge of the work and AGM Engg Civil to be the representative of Engineer-in-Charge and execute the work on behalf of Engineer-in-Charge. You are requested to attend the office of Jt.GM Engg. (Civil), AAI Raja Bhoj Airport, Bhopal by 29/12/2022 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value ₹ 500.00 (Rupees Five Hundred only) and the cost of the stamp paper shall be borne by you.

पृष्ठ सं/page no. 01

- 3- आपकी निविदा के साथ प्राप्त धरोहर राशि ₹ 4,82,074.00 (रुपये चार लाख बयासी हजार चौहतर मात्र) CPP पोर्टल के माध्यम से मुक्त हो जाएगी इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा निधि राशि ₹ 14,59,765.00/- (केवल चौदह लाख उनसठ हजार सात सौ पैसठ रुपये) जमा करें। असफल होने पर अनुबंध की पृष्ठ संख्या जी.सी.सी. - 16 पर क्लॉज संख्या 1 (अ) की शर्तों के अनुसार सुरक्षा निधि राशि को बिलों से काटा जायेगा।

The earnest money will be refunded to you through CPP Portal for an amount of Rs 4,82,074.00 (Rupees Four Lakh Eighty two thousand Seventy four Only) received along with your tender. Please deposit amount of ₹ 14,59,765.00/- (Rupees Fourteen Lakh Fifty nine Thousand seven Hundred Sixty five Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted from your R/A bills as per condition of Clause no 1 A at page no GCC -16 of contract document.

4. आपसे निवेदन है कि आप विभिन्न लागू वैधानिक अधिनियमन जैसे कर्मचारी भविष्य निधि व विविध प्रावधान अधिनियम 1952, कर्मचारीराज्य बीमा(ESI) अधिनियम, 1948, ठेका श्रमिक (रोजगार व सेवा की शर्त) अधिनियम, 1979 न्युनतम मजदुरी अधिनियम , 1948, मजदुरी भूगतान अधिनियम, 1936, श्रमिक प्रतिपूर्ति अधिनियम, 1923 एवं अन्य संगतनियम व अधिनियम, अनुदेश इत्यादि जो समय समय पर जारी/प्रवर्तित किया जाते हैं। उक्त वैधानिक अधिनियम व प्रावधानों का नियमित अनूपालन व इनके अंतर्गत सारी विधिक बाध्यताओं का पूर्ण प्रेक्षण आपका एकल दायित्व होगा।

You are requested to comply with the provisions under various applicable statutory enactments including the employees Provident Fund & Miscellaneous Provisions Act, 1952, the Employees State Insurance (ESI) Act, 1948, the Contract Labour (Regulation & Abolition) Act, 1970, the Inter-State Migrant workmen (Regulation of employment & conditions of Service) Act, 1979, the Minimum Wages Act, 1948, the Payment of Wages Act, 1936, the workmen's Compensation Act, 1923 and other relevant Act, Rules and Regulations, instructions etc. issued/enforced from time to time. It shall be your sole liability to abide with and fully observing the legal obligations under the aforesaid statutory acts and provisions.

- 5- आपको निर्देश दिया जाता है कि आप तुरंत सहा. महाप्रबंधक अभियांत्रिकी (सिविल) से संपर्क करें जो आपको साइट को सौंपने की व्यवस्था करेंगे।

You are also directed to contact AGM Engg Civil immediately who will arrange to hand over the site to you.

- 6- कृपया ध्यान दें कि काम करने का अनुमानित समय **12 (बारह) माह** हैं जो कि इस पत्र को जारी करने के **दसवे दिन** से मान्य होगा।

Please note that the time allowed for carrying out the work shall be **12 (Twelve) Months** and same shall be reckoned from the 10th day after issue of this letter.

7- यह संदर्भित पत्र अनुबंध का एक हिस्सा होगा ।

This letter under reference shall form part of Agreement

8- इस अनुबंध के संबंध में आगे का कोई भी पत्राचार प्रभारी अभियंता के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.

9- कृपया अपनी अभिस्वीकृति भेजे तथा सहमति के लिये डुप्लीकेट कापी, जोकि इस पत्र के साथ संलग्न है, हस्ताक्षर करके अधोहस्ताक्षरी को भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

10- यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को ही सही रूप में लिया जाएगा।

In case any discrepancy is found then English version will be taken as correct.

संलग्नक/ Encl.-Schedule 'A'(BOQ)

भवदीय/Yours faithfully

संयुक्त महाप्रबंधक अभियांत्रिकी (सिविल)

Jt.GM (Engineering Civil)

राजा भोज विमानतल भोपाल,

Raja Bhoj Airport, Bhopal

कृते तथा ओर से

For and on behalf of

अध्यक्ष, भाविप्रा,


The Chairman, AAI

मूलप्रति से अतिरिक्त / N.O.O

1. महाप्रबंधक (अभि.-परियोजना),
भारतीय विमानपत्तन प्राधिकरण, जबलपुर हवाई अड्डा, जबलपुर 482005.----- आपकी जानकारी हेतु।
General Manager (Engg-Project),
Airports Authority of India, Jabalpur Airport, Jabalpur-482005----- For Information please
2. क्षेत्रीय श्रम आयुक्त (केन्द्रीय),
निर्माण सदन, सी.जी.ओ. कॉम्प्लेक्स रूम नंबर 306,
तीसरा माला, अरेरा हिल्स, भोपाल-462016.
The Regional Labour Commissioner(Central),
Nirman Sadan. C.G.O. Complex, Room No. 306.
3rd floor, Arera hills Bhopal-462016.
3. क्षेत्रीय भविष्य निधि आयुक्त, मध्यप्रदेश,
भविष्य निधि भवन, 59-अरेरा हिल्स, भोपाल-462011
The Regional Provident Fund Commissioner (M.P.)
Bhavishy Nidhi Bhavan, 59-Arera Hills, Bhopal-462011

आंतरिक/INTERNAL

1. विमानपत्तन निदेशक, भाविप्रा.राजा भोज विमानतल, भोपाल. जानकारी हेतु।
The Airport Director, AAI, Raja Bhoj Airport, Bhopal..... for information please.
2. सहायक महाप्रबंधक - (वित्त) भाविप्रा. राजा भोज विमानतल. भोपाल.
Asstt.GM (Finance), AAI, Raja Bhoj Airport Bhopal.
3. मुख्य सुरक्षा अधिकारी, भाविप्रा, राजा भोज विमानतल, भोपाल पास जारी करने के लिए
Chief Security Officer, AAI, Raja Bhoj Airport Bhopal
4. सहायक महाप्रबंधक (सिविल)/ प्रबंधक (सिविल) भाविप्रा, राजा भोज विमानतल, भोपालआवश्यक कार्यवाही हेतु
AGM (E-C)/Manager (E-C) AAI, Raja Bhoj Airport Bhopal.....for necessary action.
5. वरिष्ठ प्रबंधक विधुत भाविप्रा, राजा भोज विमानतल, भोपालआवश्यक कार्यवाही हेतु
Senior Manager (E-E) AAI, Raja Bhoj Airport Bhopal.....for necessary action
6. कार्यालय प्रतिलिपि/ For office copy



संयुक्त महाप्रबंधक अभियांत्रिकी (सिविल)

Jt.GM (Engineering Civil)

Item Wise BoQ

Tender Inviting Authority: AGM (ENGG-CIVIL) RAJA BHOJ AIRPORT BHOPAL

Name of Work: Provision of RCC drain & Covers, Security huts & Augmentation of boundary wall in operational area at Raja Bhoj Airport Bhopal

Contract No: AAI/BHOPAL/ENGG-C/CW-02/RAIN, SECURITY HUT/B/W

Name of the Bidder/ Bidding BELLEF BUILDCON PRIVATE LIMITED

PRICE SCHEDULE

(DOMESTIC TENDERS - RATES ARE TO GIVEN IN RUPEES (INR) ONLY)

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only.)

Sl. No.	Item Description	Item Code / Make	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. p	TOTAL AMOUNT Without Taxes col (13) = (4) x (7) in Rs. p	TOTAL AMOUNT In Words	TEXT #
1	2	3	4	5	7	13	15	
1.01	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	item1	1946.00	cum	123.00	239358.00	INR Two Lakh Thirty Nine Thousand Three Hundred & Fifty Eight Only	
1.02	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead with airport Premises and lift upto 1.5 m, as directed by Engineer-in-charge. Ordinary rock	item2	414.00	cum	248.00	102672.00	INR One Lakh Two Thousand Six Hundred & Seventy Two Only	
1.03	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	item3	691.00	cum	152.00	105032.00	INR One Lakh Five Thousand & Thirty Two Only	
1.04	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	item4	61.00	cum	3683.00	224653.00	INR Two Lakh Twenty Four Thousand Six Hundred & Sixty Three Only	

1.05	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	item5	213.00	cum	3163.00	673719.00	INR Six Lakh Seventy Three Thousand Seven Hundred & Nineteen Only
1.06	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-II): 3 graded stone aggregate 20 mm nominal size)	item6	25.00	cum	4182.00	104550.00	INR One Lakh Four Thousand Five Hundred & Fifty Only
1.07	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-II): 3 graded stone aggregate 20 mm nominal size)	item7	45.00	cum	5093.00	229185.00	INR Two Lakh Twenty Nine Thousand One Hundred & Eighty Five Only
1.08	Centering and shuttering including strutting, propping etc. and removal of form for :Foundations, footings, bases of columns, etc. for mass concrete	item8	4521.00	sqm	154.00	696234.00	INR Six Lakh Ninety Six Thousand Two Hundred & Thirty Four Only
1.09	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform	item9	295.00	sqm.	383.00	112985.00	INR One Lakh Twelve Thousand Nine Hundred & Eighty Five Only
1.10	Centering and shuttering including strutting, propping etc. and removal of form for :lintels, beams, plinth beams, girders, bressumers and cantilevers	item10	481.00	sqm	304.00	146224.00	INR One Lakh Forty Six Thousand Two Hundred & Twenty Four Only
1.11	Centering and shuttering including strutting, propping etc. and removal of form for :Columns, Pillars, Piers, Abutments, Posts and Struts	item11	735.00	sqm	402.00	295470.00	INR Two Lakh Ninety Five Thousand Four Hundred & Seventy Only
1.12	Centering and shuttering including strutting, propping etc. and removal of form for :Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like	item12	153.00	sqm	154.00	23562.00	INR Twenty Three Thousand Five Hundred & Sixty Two Only
1.13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars of grade Fe-500D or more.	item13	45470.00	kg	63.00	2864610.00	INR Twenty Eight Lakh Sixty Four Thousand Six Hundred & Ten Only

1.14	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermomechanically Treated bars of grade Fe-500D or more.	item14	6084.00	kg	63.00	383292.00	INR Three Lakh Eighty Three Thousand Two Hundred & Ninety Two Only
1.15	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor	item15	609.00	cum	4798.00	2921982.00	INR Twenty Nine Lakh Twenty One Thousand Nine Hundred & Eighty Two Only
1.16	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. Concrete of M25 grade with minimum cement content of 330 kg /cum	item16	20.00	cum	5040.00	100800.00	INR One Lakh Eight Hundred Only
1.17	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6	item17	341.00	cum	3329.00	1135189.00	INR Eleven Lakh Thirty Five Thousand One Hundred & Eighty Nine Only

1.18	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Above plinthCement mortar 1:6	Item18	116.00	cum	4144.00	480704.00	INR Four Lakh Eighty Thousand Seven Hundred & Four Only
1.19	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Item19	7959.00	kg.	55.00	437745.00	INR Four Lakh Thirty Seven Thousand Seven Hundred & Forty Five Only
1.20	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	Item20	2970.00	kg	77.00	228690.00	INR Two Lakh Twenty Eight Thousand Six Hundred & Ninety Only
1.21	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Item21	2300.00	kg	71.00	163300.00	INR One Lakh Sixty Three Thousand Three Hundred Only
1.22	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with : 4.0 mm thick glass panes	Item22	21.00	sqm	470.00	9870.00	INR Nine Thousand Eight Hundred & Seventy Only
1.23	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110mm diameter	Item23	150.00	Mtr	160.00	24000.00	INR Twenty Four Thousand Only
1.24	12 mm cement.....1:6	Item24	1460.00	sqm	147.00	214620.00	INR Two Lakh Fourteen Thousand Six Hundred & Twenty Only
1.25	15 mm cement plaster 1:6	Item25	1480.00	sqm	170.00	251600.00	INR Two Lakh Fifty One Thousand Six Hundred Only
1.26	6 mm cement.....1:3	Item26	1230.00	sqm	127.00	156210.00	INR One Lakh Fifty Six Thousand Two Hundred & Ten Only
1.27	Neat cement punning.	Item27	70.00	sqm	34.00	2380.00	INR Two Thousand Three Hundred & Eighty Only
1.28	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm)	Item28	4285.00	sqm	49.00	209965.00	INR Two Lakh Nine Thousand Nine Hundred & Sixty Five Only
1.29	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Item29	471.00	sqm	66.00	31086.00	INR Thirty One Thousand & Eighty, Six Only

1.30	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within airport Premises as per direction of Engineer - in-charge.	item30	117.00	Cum	878.00	102726.00	INR One Lakh Two Thousand Seven Hundred & Twenty Six Only
1.31	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within airport Premises as per direction of Engineer-in-charge. In cement mortar	item31	270.00	Cum	849.00	229230.00	INR Two Lakh Twenty Nine Thousand Two Hundred & Thirty Only
1.32	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	item32	4824.00	Kg.	2.00	9648.00	INR Nine Thousand Six Hundred & Forty Eight Only
1.33	Dismantling barbed wire / concertina coil/ G.I. Chain-link fencing or flexible wire rope in fencing including making rolls and stacking within 50 metres lead..	item33	12072.00	Kg.	15.00	181080.00	INR One Lakh Eighty One Thousand & Eighty Only
1.34	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	item34	1050.00	metre	152.00	159600.00	INR One Lakh Fifty Nine Thousand Six Hundred Only
1.35	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	item35	20.00	Sqm	143.00	2860.00	INR Two Thousand Eight Hundred & Sixty Only
1.36	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm) With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm)	item36	26.00	sqm	510.00	13260.00	INR Thirteen Thousand Two Hundred & Sixty Only

1.37	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 micron epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purins, rafters and trusses and including cutting to size and shape wherever required.	Item 37	732.00	Sqm	336.00	245952.00	INR Two Lakh Forty Five Thousand Nine Hundred & Fifty Two Only
1.38	Providing and placing in position 150 mm thick factory made machine batched & machine mixed Precast RCC Rectangular Covers on drains of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 12 mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways, in two layer neat cement punning on finished surface, properly encased on all edges with 1.6 mm thick, 150 mm wide MS sheet duly painted over priming coat, reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks, holes for entry of rain water into the drain etc i/c cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge.	Item 38	470.00	Sqm	2626.00	1234220.00	INR Twelve Lakh Thirty Four Thousand Two Hundred & Twenty Only
1.39	Removing from boundary wall/barricading and refixing of old iron profile sheets. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purins, rafters and trusses and including cutting to size and shape wherever required. (iron profile sheets supply by AAI)	Item 39	100.00	Sqm	45.00	4500.00	INR Four Thousand Five Hundred Only
1.40	Credit for taking away Concerteena coil with RBT wire / barbed wire / G.I. Chain-link fencing including removing the same from the site as and where basis. (qty same as item no.33)	Item 40	12072.00	Kg.	11.00	-132792.00	INR Minus One Lakh Thirty Two Thousand Seven Hundred & Ninety Two Only
1.41	Credit for taking away M.S Angle including removing the same from the site as and where basis.	Item 41	4824.00	Kg.	11.00	-53064.00	INR Minus Fifty Three Thousand & Sixty Four Only
1.42	Credit for taking away old brick from the site. (old brick from dismantling of b/w for credit)	Item 42	72000.00	Each	1.00	-72000.00	INR Minus Seventy Two Thousand Only
1.43	Credit for taking away of pre-coated galvanised iron profile sheets	Item 43	6297.00	Kg.	9.00	-56673.00	INR Minus Fifty Six Thousand Six Hundred & Seventy Three Only
2	Electrical Items :						

2.01	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 4 way, Double door	Item44	5.00	Each	456.30	2281.50	INR Two Thousand Two Hundred & Eighty One and Paise Fifty Only
2.02	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel/PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. Group C	Item45	10.00	Point	889.20	8892.00	INR Eight Thousand Eight Hundred & Ninety Two Only
2.03	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	Item46	20.00	Meter	1726.20	34524.00	INR Thirty Four Thousand Five Hundred & Twenty Four Only
2.04	Wiring for circuit/ sub main wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Item47	10.00	Meter	149.40	1494.00	INR One Thousand Four Hundred & Ninety Four Only
2.05	Supplying and fixing metal box of 150mm X 75mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in FRLSont including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps piano type switch, connection, painting etc. as required.	Item48	10.00	Each	360.00	3600.00	INR Three Thousand Six Hundred Only
2.06	Supplying and fixing metal box of 180mm X 100mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in FRLSont including providing and fixing 6 pin 5/6 & 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required.	Item49	5.00	Each	540.00	2700.00	INR Two Thousand Seven Hundred Only
2.07	Supply of wall mounted fan, 400 mm sweep suitable for operation on 240V, 50Hz A.C. supply with pull code control operations and high speed motor etc. complete as required.	Item50	5.00	Each	3307.50	16537.50	INR Sixteen Thousand Five Hundred & Thirty Seven and Paise Fifty Only

2.08	Supply of following Wattage LED street light fitting with minimum efficiency of 110 lumens/Watt suitable for 140-270 V, AC, 50 HZ, PF >= 0.95, luminaire should have High pressure die cast Aluminium /Standard alloy housing. Luminaire should have Air vents in housing for proper thermal management, Min IP protection should be IP 65. Total power consumption of fitting (including driver loss) should not more than 110 % of rated capacity of LED Light fitting, complete with all accessories as required. 90 W	Item51	10.00	Each	6220.80	62208.00 INR Sixty Two Thousand Two Hundred & Eight Only
2.09	Supply of 18 Watt BATTEN LED TUBE LIGHTS complete with all accessories as required.	Item52	5.00	Each	1080.00	5400.00 INR Five Thousand Four Hundred Only
2.10	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent / LED Fittings of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall with suitable size steel fastener, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	Item53	5.00	Each	360.00	1800.00 INR One Thousand Eight Hundred Only
2.11	Installations, testing, commissioning of street light luminaire complete with all accessories on 40 mm dia (M class) GI bracket of 1.5 mtr long complete with 2 nos. 25 mm X 3mm M.S. flat iron clamps, bolts and nuts including drilling holes for steel fastener, including connection with 1.5 sq. mm mm FRLS PVC insulated, copper conductor, single core cable and earthing complete etc as required.	Item54	10.00	Each	1514.70	15147.00 INR Fifteen Thousand One Hundred & Forty Seven Only
2.12	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	Item55	10.00	Each	72.90	729.00 INR Seven Hundred & Twenty Nine Only
2.13	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole and neutral	Item56	5.00	Each	211.50	1057.50 INR One Thousand & Fifty Seven and Paise Fifty Only
2.14	Supplying and laying of 3 core 6 sq. mm copper conductor flexible cable in MS conduit with saddle complete etc. as required.	Item58	75.00	Mtr	40.50	3037.50 INR Three Thousand & Thirty Seven and Paise Fifty Only
Total					14597652.00	INR One Crore Forty Five Lakh Ninety Seven Thousand Six Hundred & Fifty Two Only
Total in Words					INR One Crore Forty Five Lakh Ninety Seven Thousand Six Hundred & Fifty Two Only	

Signature Not Verified
Digitally signed by Neera Kumar Chourasia
Date: 2023.02.07 14:52:29 IST
Location: eProcurement System for Central PSUs