

Ref. No: AAI/IMP/ENGG (E-C)/Recarpeting/W.O.14/2022-23/9744

Date: 09.01.2023

To,
M/s L.K. & SONS
H.O. THOUBAL WANGKHEM,
MANIPUR-795138

Subject Re-carpeting of Apron, Isolation bay, service lane including GSE area and major repairs to Taxiway at Imphal Airport

Ref Your e-tender opened on 14.12.2022 (Bid No 2022_AAI_135688_1)


Sir,

1. Your tender for the work mentioned above is accepted by competent authority on behalf of the Chairman, Airports Authority of India at the item rate quoted by you totalling to **Rs.6,66,28,635.00 (Rupees Six Crores Sixty Six Lakh Twenty Eight Thousand Six Hundred and Thirty Five only) (Excluding GST)** which is **32.65% below** the estimated cost of **Rs.9,89,24,338.00**.
2. Joint General Manager (Engg.-C), AAI, Imphal Int. Airport, Imphal, shall be Engineer-in-charge of the work. You are requested to attend the office of the Joint General Manager (Engg.-C), AAI, Imphal Int. Airport, Imphal, within 15 days from the stipulated date of start of the work to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of the stamp paper shall be borne by you.
3. Please deposit **Rs. 13,52,945/- (Rupees Thirteen Lakh Fifty Two Thousand Nine Hundred Forty Five only)**, towards security deposit within 10 days from the date of issue of this letter failing which the same will be deducted from your running bills as per clause 1 (A) of GCC of the tender document.
4. Within 30 days of issue of acceptance letter, you shall submit to AAI, a performance Guarantee as per condition of Clause 1 on page 15 of GCC for amount of Rs. **19,98,859/- (Rupees Nineteen Lakh Ninety Eight Thousand Eight Hundred Fifty Nine only)** in the form of a Bank Guarantee on the proforma appended at appendix- XI on page 108 of GCC of the contract document.
5. You are requested to comply with the provision of contract labour (Regulation & Abolition) Act of 1970 and contract labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction workers Welfare CESS Act 1996 as specified in GCC of Tender and rule of Central and State Government.
6. You are also directed to contact Asst. General Manager (E-C), AAI, Imphal Int. Airport, Imphal, immediately who will arrange to hand over the site to you.
7. Please note that the time allowed for carrying out the work is 10 (Ten) months including three months for rainy season and same shall be reckoned from the 10th day of issue of this letter.

8. Any further correspondence in connection with this contract should normally be addressed to Joint General Manager (Engg.-C), AAI, Imphal Int. Airport, Imphal, Manipur-795140.
9. This work order is allotted the number **AAI/IMP/JGM(E-C)/Recarpeting/W.O.14/2022-23** which shall be quoted by you for all future correspondence in connection with this work.
10. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Encl: Schedule -A

Yours faithfully,



09/10/23

Joint General Manager (E-C)
For and on behalf of the Chairman
AIRPORTS AUTHORITY OF INDIA

SCHEDULE - A

Name of Work: Recarpeting of Apron, Isolation bay, service lane including GSE area and major repairs to Taxiway at Imphal Airport.

Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
1.01	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge: bituminous road	750.00	sqm	350.00	262500.00
1.02	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material within all lifts and lead upto 1km (by mechanical means).	1820.00	Sqm	6.00	10920.00
1.03	Raking out joints in poly sulphide sealant including taking out backer rod and joint filler and preparing the surface for re-pointing with bitumen mix filler, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	270.00	sqm	60.00	16200.00
1.04	Providing and filling in position bitumen mix filler of proportion 80 kg. of hot bitumen, 1 kg. of cement and 0.25 cubic metre of coarse sand for expansion joints.	111.00	cum	29000.00	3219000.00
1.05	Providing and applying primer coat with bitumen emulsion SS1 grade conforming to IS:8887 on prepared surface of granular Base including clearing of surface and spraying at the rate of 0.70 kg/sqm using mechanical means complete in all respects as per direction of Engineer-In-Charge. The contractor shall quote his rates assuming quantity of bitumen emulsion as 0.70 Kg/Sqm. If the actual quantity of bitumen emulsion varies from bitumen assumed above, necessary cost adjustment for deviation in the quantity of bitumen emulsion shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen exclusive of GST shall only be considered for payment.	750.00	sqm	60.00	45000.00
1.06	Providing and applying tack coat using bitumen emulsion (Rapid setting) complying with IS:8887, spraying the bitumen with mechanically operated spray unit at the rate specified below, cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-In-Charge. If the actual quantity of bitumen varies from the quantity specified, necessary cost adjustment for deviation in the quantity of bitumen shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen exclusive of GST shall only be considered for payment. 0.20 Kg/Sqm on existing bituminous surface	42153.00	sqm	15.00	632295.00
1.07	Providing and applying tack coat using bitumen emulsion (Rapid setting) complying with IS:8887, spraying the bitumen with mechanically operated spray unit at the rate specified below, cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-In-Charge. If the actual quantity of bitumen varies from the quantity specified, necessary cost adjustment for deviation in the quantity of bitumen shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen exclusive of GST shall only be considered for payment. 0.30 Kg/Sqm on existing concrete surface	40000.00	sqm	20.00	800000.00
1.08	Providing and laying of Hot Mix Dense Bituminous Macadam (DBM) using crushed stone aggregate of quality, size and grading as specified and filler as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-inCharge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 shall be taken as 110 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material].	2110.00	cum	10000.00	21100000.00
1.09	Providing, laying and fixing of self adhesive glass fiber reinforcement grid of high modulus fibre glass of approved make of mesh size not exceeding 12.5mm x 12.5mm. The selfglass fibre reinforcement after laying over the pavement shall be pressed down fully with a rubber tired roller and glued to pavement surface. The grid being self adhesive does not require tack coat. The longitudinal overlap should not be less than 250mm and transverse overlap i.e at the end of the roll should not be less than 150mm. The items should be completed in all respect to the satisfaction of Engineer-in-charge.	34123.00	Sqm	140.00	4777220.00

9

Name of Work: Recarpeting of Apron, Isolation bay, service lane including GSE area and major repairs to Taxiway at Imphal Airport.

SI.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
1.10	Providing and laying of Hot Mix Semi Dense Asphaltic Concrete (SDAC) using crushed stone aggregate of quality, size and grading as specified and filler as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-inCharge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 content shall be taken as 120 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material].	1744.00	cum	10100.00	17614400.00
1.11	Providing and laying of Hot Mix Dense Asphaltic Concrete (DAC) using crushed stone aggregate of quality, size and grading as specified and filler as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-inCharge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 content shall be taken as 135 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% cement by weight of aggregates as filler material.]	1744.00	cum	10150.00	17701600.00
1.12	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of all dirt, scales, oil, grease and other foreign material etc. and lining out complete. New work (Two or more coats)	2900.00	sqm	155.00	449500.00
TOTAL					66628635.00

(Rupees Six Crores Sixty Six Lakh Twenty Eight Thousand Six Hundred and Thirty Five Only)


09/01/23

Jt. General Manager (E-C)
AAI, Imphal Int. Airport

Signature Not Verified

Digitally signed by CHANDAM TOMBA
SINGH
Date: 2023.01.11 11:22:04 IST
Location: eProcurement System for Central
PSUs