



सेवा में/ To

मेसर्स मोना जेनरेटर सर्विसेज प्रा. लिमिटेड./

M/s. Mona Generator Services Pvt. Ltd.,

1-ए, बेसमेंट, 30-31 / 1-A, Basement, 30-31,

राजा हाउस, / Raja House,

नेहरू प्लेस, / Nehru Place,

नई दिल्ली - 110019 / New Delhi - 110019.

Email ID : monagenerators123@yahoo.com /

vivekkumarsingh87500@gmail.com

कार्य का नाम/ Name of Work:- हबली हवाईअड्डे पर प्रस्तावित एफटीओ को पुराने एप्रन से जोड़ने वाले 10.5 मीटर चौड़े लिंक टैक्सी ट्रैक का निर्माण। एसएच:- एफटीओ के लिए बिजली आपूर्ति व्यवस्था का प्रावधान और प्रस्तावित एफटीओ स्थान से मौजूदा बिजली केबलों का डायवर्जन। / Construction of 10.5 meter wide link taxi track connecting Old apron to the proposed FTO at Hubballi Airport. SH:- Provision of Power supply arrangements for FTO and Diversion of Existing power cables from proposed FTO Location.

संदर्भ/ Ref: 1) AAI Tender Id :- 2022_AAI_135758_1

2) Your E-Tender (Financial Bid) opened on 04.01.2023.

महोदय/ Dear Sir,

1. अध्यक्ष, भा. वि. प्रा. की ओर से उपरोक्त कार्य हेतु आपकी निविदा को कुल बातचीत की गई राशि रु.45,45,277.00 (Excluding GST) केवल पैंतालीस लाख पैंतालीस हजार दो सौ सतहतर (जीएसटी छोड़कर) जो अनुमानित लागत रु. 59,07,109.00 से 23.05% नीचे है, एतद्वारा स्वीकार किया जाता है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 45,45,277.00 (Rupees Forty Five Lakhs Forty Five Thousand Two Hundred and Seventy Seven Only) which is 23.05% Below the justified cost of Rs. 59,07,109.00 (Rupees Fifty Nine Lakhs Seven Thousand One Hundred and Nine Only) Excluding GST.

2. सहायक महाप्रबंधक (इंजिनियरिंग-विद्युत) एएआई, हुबल्ली हवाई अड्डा इस कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने के लिए निर्धारित दिनांक:30.01.2023 तक सहायक महाप्रबंधक (इंजी-विद्युत) भा.वि.प्रा हुबल्लि हवाई अड्डा, हुबल्लि के कार्यालय में उपस्थित हों। संविदा करार को रुपये100 /- (केवल एक सौ रूपए) मूल्य के एक गैर न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा और स्टॉप पेपर के मूल्य को आपके द्वारा वहन किया जाएगा।



Asst. General Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi shall be the Engineer -In-Charge of this work. You are requested to attend the office of Asst. General Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi by 30.01.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees Hundred Only) and the cost of the stamp paper shall be borne by you.

3. बयाना राशि जमा राशि रु. 1,18,142.00 प्राप्त हुआ और उसे निविदा नियम और शर्तों के अनुसार वापस कर दिया जाएगा। आपको एतद्वारा सलाह दी जाती है कि इस पत्र के जारी होने की तिथि के बाद 10 दिनों के भीतर सुरक्षा जमा के रूप में 4,54,528.00 (रुपये चार लाख चौवन हजार पांच सौ अट्ठाईस मात्र) जमा करें, ऐसा न करने पर निविदा के अनुसार काट लिया जाएगा। अनुबंध दस्तावेज़ के पृष्ठ जीसीसी-18 की शर्त खंड 1 ए।

The Earnest Money Deposit Amount of **Rs.1,18,142.00** received and same shall be refunded as per tender terms & conditions. You are hereby advised to deposit **Rs.4,54,528.00 (Rupees Four Lakhs Fifty Four Thousand Five Hundred and Twenty Eight Only)** towards security deposit within 10 days after the date of issue of this letter, failing which the same will be deducted as per Tender Condition Clause 1 A of page GCC-18 of contract document.

4. आपसे अनुरोध है कि ठेका श्रम (विनियमन एवं उन्मूलन) अधिनियम 1970, ठेका श्रम (विनियमन एवं उन्मूलन) केन्द्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिकों (रोजगार और विनियमन का अधिनियम) के प्रावधानों का पालन करने का अनुरोध किया जाता है सेवा की शर्तों अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण अधिनियम 1996, जैसा कि केंद्र और राज्य सरकारों के निविदा और 55 जीसीसी के नियमों के पृष्ठ संख्या 49 पर खंड - 19 में निर्दिष्ट है।

You are requested to comply with the provisions of contract labor (Regulation and abolition) act of 1970 and contract labor (Regulation and abolition) Central rules 1971, Child labor (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other construction workers welfare Cess Act 1996 as specified in Clause-19 on Page No.54 to 60 of GCC of tender and rules of Central and State Governments.

5. आपको यह भी निदेश दिए जाते हैं कि आप प्रबंधक (इंजिनियरिंग-विद्युत), हब्बल्ली हवाई अड्डा, हब्बल्ली से तुरंत संपर्क करें जो आपको साइट सौंपने के लिए व्यवस्था करे

You are also directed to contact Manager (Engg-Electrical), AAI, Hubballi Airport, Hubballi immediately who will arrange to hand over the site to you.



6. कृपया कृपया ध्यान दें कि कार्य करने के लिए अनुमत समय 04 (चार) महीने होगा और इसकी गणना दिनांक 28.01.2023 से की जाएगी।

Please note that the time allowed for carrying out the work shall be **04 (Four) Months** and same shall be reckoned from **28.01.2023**.

7. अनुबंध के संबंध में किसी भी आगे के पत्राचार को आमतौर पर असिस्ट को संबोधित किया जाना चाहिए। सहायक महाप्रबंधक (इंजी-इलेक्ट), हुबल्ली हवाई अड्डा, जो इस काम के इंजीनियरिंग-इंचार्ज होंगे।

Any further correspondence in connection with the contract should normally be addressed to the Asst. General Manager (Engg- Elect), Hubballi Airport, who will be the Engineer-In-charge of this work.

8. कृपया पावती भेजें एवं इस पत्र के साथ संलग्न इसकी प्रतिलिपि पर हस्ताक्षर करते हुए उसे स्वीकृति के तौर पर अधोहस्ताक्षरी को भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as token of acceptance.

9. यदि हिंदी संस्करण में कोई व्याकरण संबंधी त्रुटि है, तो अंग्रेजी संस्करण हिंदी संस्करण का स्थान ले लेगा।

If any grammatical mistakes in Hindi version, the English version will supersede Hindi version.

भवदीय/Yours faithfully,

सहा. महाप्रबंधक (इंजिनियरिंग-विद्युत)/ Asst. Gen. Manager (Engg- Elect)
कृते एवं अध्यक्ष की ओर से/ For and on behalf of the Chairman,
भा.वि.प्रा/ Airports Authority of India,
हुबल्ली हवाई अड्डा/Hubballi Airport, Hubballi

संलग्न/ Encl:

1. Schedule of Quantities

Schedule of Quantity

Name of Work : Construction of 10.5 meter wide link taxi track connecting Old apron to the proposed FTO at Hubballi Airport. SH:- Provision of Power supply arrangements for FTO and Diversion of Existing power cables from proposed FTO Location.

Item No	Description of Item	Unit	QTY	Rate	Amount
1	SH-1: CABLES AND CABLING Supplying of following sizes aluminium conductor armoured XLPE insulated, PVC sheathed power cable for working voltage upto & i/c 1.1 KV. as per IS : 7098 (Part-I), 1988 with latest amendments.				
1.1	3.5 C x300 Sqmm	Mtr	580	1 234.00	7 15 720.00
1.2	3.5 Cx185 sqmm	Mtr	1120	823.00	9 21 760.00
1.3	3.5 C x 240 sq.mm	Mtr	480	1 114.00	5 34 720.00
1.4	3.5 Cx 120 Sqmm	Mtr	300	687.00	2 06 100.00
2	Supplying and laying of 90 mm dia PE 63 grade PN4 rating HDPE pipe conforming to IS 4984 including all accessories direct in ground (75 cm below ground level) excavation and refilling the trench complete as required.	Mtr	2260	315.00	7 11 900.00
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/HUME/STONE WARE/METAL/HDPE pipe as required.				
3.1	a) Above 95 sq. mm and upto 185 sq. mm	Mtr	1360	60.00	81 600.00
3.2	b) Above 185 sq. mm and upto 400 sq. mm	Mtr	900	100.00	90 000.00
4	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of Pvc insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV Grade as required.				
4.1	3.5 C x300 Sqmm	Set	4	6 200.00	24 800.00
4.2	3.5 C x 185 sq.mm	Set	4	4 800.00	19 200.00
4.3	4 Cx 120 Sqmm	Set	2	4 700.00	9 400.00
5	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
5.01	3.5 C x300 Sqmm	Set	4	1 180.00	4 720.00
5.02	3.5 C x240 Sqmm	Set	4	930.00	3 720.00
5.03	3.5 C x 185 sq.mm	Set	4	620.00	2 480.00
5.04	3.5 C x120 Sqmm	Set	2	400.00	800.00
6	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.	Each	26	1 250.00	32 500.00

Item No	Description of Item	Unit	QTY	Rate	Amount
7	SH- 2 SITC of LT Panel Supply, installation, testing & commissioning of LT Panel, cubicle & modular type, made of 2 mm thick sheet steel for frame work and covers, 3mm thick for gland plates, totally enclosed, form 4, IP 42, free standing, floor mounting, dust and vermin proof, indoor, compartmentalised, including cross ventilation, powder coated, painting, suitable for operation on 3 Phase and neutral , 415v, 50 Hz AC system with Al.busbars extensible on both sides, fabrication shall be done in transportation sections, entire panel shall have a common copper earth bar of size 25mm x 5mm at the rear with 2 nos, earth stud, control wiring with 2.5 sq.mm. PVC insulated copper conductor, cable alloys, cable gland plates in two half, interconnections & rotary handle operating machanisam from a firm having CPRI certification with test certificates for similar panel (required for short circuit rating, temperature rise and IP classification) including supply & installation of following items and as per technical specification.BUS BAR 600 A TPN Al Busbars. INCOMERS 400 A, FP 36kA MCCB with microprocessor based adjustable release with OL & SC protection - 2 Nos. 4A, C curve SP MCB - 6 Nos. RYB indication lamp, LED type - 6 Nos. (0-500)V voltmeter, Acc. class 1 with 90 deg defl. scale - 2 Nos. (0-400)A ammeter Acc. class 1 with 90 deg defl. scale - 2 Nos. 6A 3 pole voltmeter selector switch - 2 Nos. Ammeter selector switch- 2 Nos. 400/5A 15VA class 1 resin cast CT(Rectangular Type) - 6nos Energy meter-3ph having RS 485 communication facilities - 2Nos. MFM (V,A,F,PF,KW,KVA,KWH) having RS 485 communication facilities - 2Nos. ON/OFF/TRIP indication lamp, LED type - 6 Nos. Surge protector of Class C, 3P+N of 40 KA - 2Nos. Bus coupler 400 A, FP 36kA MCCB with out release - 1 Nos. ON-OFF-TRIP indication lamps- 3 nos. 400 A TPN busbar chamber with high conductivity Aluminium bus bars with heat shrinkable coloured sleeves and I/c DMCISMC busbars supports at required intervals. Out goings 250A, FP 36kA MCCB with Thermal Magnetic based adjustable release with OL & SC protection - 4 Nos. 125A, FP 36kA MCCB with Thermal Magnetic based adjustable release with OL & SC protection - 4 Nos. 63A, FP 36kA MCCB with Thermal Magnetic based adjustable release with OL & SC protection - 6 Nos.	Each	1	7 24 538.00	7 24 538.00

Item No	Description of Item	Unit	QTY	Rate	Amount
8	OUT DOOR FEEDER PILLER Supply, installation, testing and commissioning of cubicle type Out door feeder panel fabricated using 2 mm thick CRCA sheet steel for frame work and covers, 3mm thick for gland plates, totally enclosed free standing, double door, dust free, damp and vermin proof and water proof outdoor (IP 54), powder coated, painting, suitable for operation on 3 Phase and neutral , 415v, 50 Hz AC system, including supply & fixing the following items and interconnections, wiring with suitable size wires/cables and rotary handle operating machanisam from a firm having CPRI certification with test certificates for similar panel (required for short circuit rating, temperature rise and IP classification) including all works for foundation like excavation, PCC, brick work pedestal, plastering, finishing etc. and as per specifications as required. INCOMMER 250 A, 4P 36kA MCCB with microprocessor based adjustable release with OL & SC protection - 1 No. 4A, C curve SP MCB - 3 Nos. RYB indication lamp, LED type - 3 Nos. (0-500)V voltmeter, Acc. class 1 with 90 deg defl. scale - 1 No. (0-250)A ammeter Acc. class 1 with 90 deg defl. scale - 1 Nos. 6A 3 pole voltmeter selector switch - 1 No. Ammeter Selector Switch -1 Nos 250/5A 10VA class 1 resin cast CT - 3nos ON/OFF/TRIP indication lamp, LED type - 3Nos. BUSBARS 4P aluminum bus bars of 250 A capacity with heat shrinkable coloured sleeves i/c SMC bus bars supports at required intervals complete for cross section, size supports & their spacing etc. for withstanding fault level of 35 KA for 1 sec.250 A TPN busbar chamber with Aluminium busbar. Out goings 63A, 4P 36kA MCCB with microprocessor based adjustable release with OL & SC protection - 2 No 63A, 4P 10kA MCB - 2 Nos.	Each	1	2 92 934.00	2 92 934.00
9	Providing, laying and fixing of 300 mm dia RCC Socket Spun type Hume pipe NP-2 class, in ground, in existing trench complete as required as per site requirement.	Mtr	20	750.00	15 000.00
10	Construction of brick masonry chamber in cement mortar 1:6 (1 cement : 6 coarse sand) with foundation concrete 1:5:10 mix (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:6 (1 cement : 6 coarse sand) finished with a floating coat of neat cement complete as per site requirement. (chamber size 1500mm x 1500mm and 1500mm and deep With common burnt clay F.P.S. non-modular brick)	Each	4	27 120.00	1 08 480.00

Item No	Description of Item	Unit	QTY	Rate	Amount
11	Supply and fixing of chequered plate of 5 mm thick including cutting to required size using gas cutter and lay the same over the chamber, fixing of nosing angle and supporting handle for chequered plate, related civil works, finishing etc. and painting with two coats of enamel paint over one coat of Zinchromate primer complete as required as per site requirement.	Kg	361	105.00	37 905.00
12	Dismantling of existing 6mtr height perimeter light poles i/c disconnection of all connections, cables, termination box's and light fittings from the poles and handed over to AAI store complete as required as per site requirement.	Each	2	1 000.00	2 000.00
13	Installation, testing and commissioning of existing 6mtr height perimeter light poles including foundation, all connections, terminations, fixing of loop in and loop out box's and light fittings complete as required as per site requirement.	Job	2	2 500.00	5 000.00
Total					45 45 277.00

(Rupees Forty Five Lakhs Forty Five Thousand Two Hundred and Seventy Seven Only)

Note : Plus GST as applicable.

N.S.P./16 18/01/23

सहा. महाप्रबंधक (इंजिनियरिंग-विद्युत)/ Asst. General Manager (Engg - Elect)
भा.वि.प्रा/ Airports Authority of India,
हबबल्ली हवाई अड्डा/ Hubballi Airport, Hubballi.

Signature Not Verified

Digitally signed by N SOLOMON
PRABHAKAR

Date: 2024.04.05 17:20:48 IST

Location: eProcurement System for Central
PSUs