



संदर्भ संख्या: भाविप्रा/गोंदिया/अभि-सि/का.आ.-01/2023/ 09-19
Ref. No.: AAI/GONDIA/ENGG(C)/WO-01/2023/

दिनांक: 05.01.2023
Date : 05.01.2023
ई-मेल / स्पीड पोस्ट

प्रति,

मेसर्स बी.एन.एस. इंफ्रास्ट्रक्चर,
प्लॉट नंबर 98, ओम नगर,
वोक्स कूलर्स के बाजू में, कोराडी रोड,
नागपुर (महाराष्ट्र) - 440 030
ई-मेल : bnsinfrastructure@gmail.com

To,

M/s. BNS Infrastructure,
Plot No. 98, Om Nagar,
Opp. Wox Coolers, Koradi Road,
Nagpur (Maharashtra) - 440 030
Email : bnsinfrastructure@gmail.com

कार्य का नाम : नियाटाम, गोंदिया में PASS (प्रोसिजरल अप्रोच एंड एरिया कंट्रोल सिम्युलेटर) प्रयोगशाला का निर्माण.
उपशीर्षक : सिविल कार्य।

Name of Work : Construction of PASS (Procedural Approach & Area Control Simulator) Lab at NIATAM, Gondia. SH: Civil works.

संदर्भ : ई-निविदा आई डी नं. 2022_AAI_135882_1, दिनांक : 26.12.2022 को खोली गई।

Reference : E-Tender ID No. 2022_AAI_135882_1, Opened on Dt. 26.12.2022.

महोदय / Dear Sir (s),

1. उपर उल्लेखित कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है, आपके द्वारा बताए गए मद मूल्यों/ प्रतिशत मूल्य पर आपकी ई-निविदा राशि कुल रु. 27,04,873.42/- (सत्ताईस लाख चार हजार आठ सौ तिहत्तर और बयालीस पैसे मात्र) (जी.एस.टी. के बिना) है, जो कि ई-निविदा की अनुमानित लागत राशि रु. 40,04,445/- से 32.45% नीचे है।

Your E-Tender for the above mentioned work is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates/ percentage rate quoted by you totaling to Rs. 27,04,873.42/- (Rupees Twenty Seven Lakhs Four Thousand Eight Hundred Seventy Three and Forty Two paise only) (Exclusive GST) which is 32.45% below the Estimated cost put to tender of Rs. 40,04,445/-.

2. सहायक महाप्रबंधक (अभि- विद्युत)/प्रभारी सिविल, भाविप्रा, बिरसी विमानतल, गोंदिया इस कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप करारनामे पर हस्ताक्षर करने एवं करारनामे को पूरा करने के लिए दिनांक 30.01.2023 तक सहायक महाप्रबंधक (अभि- विद्युत)/प्रभारी सिविल, भाविप्रा, बिरसी विमानतल, गोंदिया के कार्यालय में उपस्थित हो। ठेके का करारनामा रु.100/- (सौ रुपए मात्र) के नोनजुडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा स्टैम्प पेपर का खर्च आपके द्वारा उठाया जाएगा।

Asst. General Manager (Engg-Elect.)/In-Charge Civil, AAI, Birsi Airport, Gondia shall be the Engineer-In-Charge of this work. You are requested to attend the office of Asst. General Manager (Engg- Elect)/In-Charge Civil, AAI, Birsi Airport, Gondia by 30.01.2023 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One Hundred Only) and the cost of stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के अंदर जमानत राशि रु. 2,70,488/- (रु. दो लाख सत्तर हजार चार सौ अठास्सी, मात्र) जमा करे अन्यथा इसे ठेके के दस्तावेज के पृष्ठ GCC-16 पर दी गई शर्त क्लोज 1 'A' के अनुसार आपके चल बिल से काट लिया जाएगा।
Please deposit Rs. 2,70,488/- (Rupees Two Lakhs Seventy Thousand Four Hundred & Eighty Eight only) towards Security Deposit within 10 Days from the date of issue of this letter, failing which, the same will be deducted as per condition of Clause No. 1'A' at page no. 16 of the Contract Document.

(Signature)
05/01/23

जारी / Contd.....2




अनवरत पृष्ठ / Continuation sheet.....

- [2] -

4. निविदा के संविदा की सामान्य शर्तों के पृष्ठ 49 पर दी गई शर्त क्लोज 19 के अनुसार आपसे निवेदन है की आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम अनुबंध श्रम नियम (नियम तथा उन्मूलन), 1971 के केंद्रीय नियम श्रम नियम (नियमन तथा उन्मूलन), अधिनियम 1986, बाल मजदूर (निषेध और नियमन), अधिनियम 1996 बांधकाम मजदूर (रोजगार और सेवा की स्थिति के विनियम), अधिनियम 1996 भवन एवम अन्य निर्माण श्रमिक कल्याण उपकर, के अनुसार राज्य सरकार के नियमों के प्रावधानों का अनुपालन करें।
You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation & Abolition) Central Rule 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no. 49 of GCC of tender and rules of Central and State Government.
5. आपको यह निर्देश दिया जाता है कि प्रबंधक (अभि.-सिविल) से शीघ्र संपर्क करें जो आपको साईट सौंपने की व्यवस्था करेंगे।
You are directed to contact to Manager (Engg-Civil) immediately who will arrange to handover the site.
6. कृपया नोट कर लें कि काम करने का अनुमानित समय **चार (04) माह** है जो कि इस कार्यदेश के जारी होने के दसवें दिन से गिना जाएगा।
Please note that the time allowed for carrying out the work shall be **04 (Four) Months**, which shall be reckoned from the 10th day of issue of this order.
7. इस ठेके से संबंधित आगे का कोई भी पत्राचार सहायक महाप्रबंधक (अभि- विद्युत)/प्रभारी सिविल, भाविप्रा, बिरसी विमानतल, गोंदिया, महाराष्ट्र-441601 के पते पर किया जाएगा।
Any further correspondence in connection with the contract should normally be addressed to Asst. General Manager (Engg-Elect.)/In-Charge Civil, AAI, Birsi Airport, Gondia, Maharashtra-441601.
8. भाविप्रा का महाराष्ट्र राज्य के लिए GSTIN क्र. 27AAACA6412D1Z8 है।
The GSTIN Registration No. of AAI is 27AAACA6412D1Z8 for Maharashtra State.
9. कृपया पावती भेजे तथा स्वीकृती टोकन के रूप में इस पत्र की हस्ताक्षरित प्रति इस कार्यालय में भेजें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing to the undersigned as a token of acceptance.
10. यदि अंग्रेजी और हिंदी पाठ में कोई अंतर पाया जाता है तो अंग्रेजी विवरण सही माना जाएगा।
If there is any discrepancy between English and Hindi, then meaning derived in English will be taken as correct.

भवदीय / Yours Faithfully

संलग्न : Item Rate BOQ (8 Pages)


[देवेन्द्र पुरी गोस्वामी / DEVENDRA PURI GOSWAMI]
सहा. महाप्रबंधक (अभि-वि)/प्रभारी सिविल / Asst. Gen. Manager (Engg-E)/IC Civil
कृते तथा ओर से अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण
For and on behalf of Chairman, Airports Authority of India
बिरसी विमानतल, गोंदिया / Birsi Airport, Gondia

Item Rate BoQ

Validate

Print

Help

Tender Inviting Authority: AGM(E-E)/In-Charge (Civil Section), AAI, Birsi Airport, Gondia

Name of Work: Construction of PASS (Procedural Approach & Area Control Simulator) Lab at NIATAM, Gondia. SH: Civil works.

Contract No: 2022_AAI_135882_1

Name of the Bidder/ Bidding Firm / Company :	BNS INFRASTRUCTURE
--	--------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	BASIC RATE In Figures (excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (excluding GST) in Rs. P	TOTAL AMOUNT in Words	TEXT #
Sl. No.	Item Description	Quantity	Units					
1	2	4	5	13		53		55
1	Cutting and dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material as per direction of Engineer-in-charge.	40.00	sqm	54.00		2160.00	INR Two Thousand One Hundred & Sixty Only	
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	3.30	cum	360.00		1188.00	INR One Thousand One Hundred & Eighty Eight Only	
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	60.00	cum	540.00		32400.00	INR Thirty Two Thousand Four Hundred Only	
4	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	100.00	kg	9.00		900.00	INR Nine Hundred Only	
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	90.00	cum	5400.00		486000.00	INR Four Lakh Eighty Six Thousand Only	

Done by 05/01/23
 (अभि-वि.) AGM (E-E)
 सहा. महाप्र. / A.A.I.
 भा. वि. प्रा. गोंदिया
 बिरसी विमानतल, GONDIA
 Birsi Airport, GONDIA

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (excluding GST) in Rs. P	TOTAL AMOUNT In Words	TEXT #		
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-II) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	3.24	cum	6003.00	19449.72	INR Nineteen Thousand Four Hundred & Forty Nine and Paise Seventy Two Only			
7	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	2.35	cum	7002.00	16454.70	INR Sixteen Thousand Four Hundred & Fifty Four and Paise Seventy Only			
8	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	1.50	cum	7200.00	10800.00	INR Ten Thousand Eight Hundred Only			
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	26.00	cum	7460.00	193960.00	INR One Lakh Ninety Three Thousand Nine Hundred & Sixty Only			
10	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	135.00	sqm	540.00	72900.00	INR Seventy Two Thousand Nine Hundred Only			
11	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	50.00	sqm	540.00	27000.00	INR Twenty Seven Thousand Only			
12	Centering and shuttering including strutting, propping etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts	26.00	sqm	540.00	14040.00	INR Fourteen Thousand & Forty Only			


 05/01/23
 (अभि-वि.) AGM (E.E.)
 सहा. महा. प्र. / A.A.I.
 मा. वि. प्रा. विमानतल, गोंदिया
 बिरसी विमानतल, GONDIA
 Birsi Airport.

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #	NUMBER #	TEXT #	TOTAL AMOUNT In Words	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (excluding GST) in Rs. P	TOTAL AMOUNT In Words	TEXT #			
13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	370.00	kg	72.00	26640.00	INR Twenty Six Thousand Six Hundred & Forty Only				
14	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	2600.00	kg	75.60	196560.00	INR One Lakh Ninety Six Thousand Five Hundred & Sixty Only				
15	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	480.00	sqm	306.00	146880.00	INR One Lakh Forty Six Thousand Eight Hundred & Eighty Only				
16	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand)	65.00	sqm	306.00	19890.00	INR Nineteen Thousand Eight Hundred & Ninety Only				
17	6 mm plaster on cement concrete or reinforced cement concrete work with white cement based polymer modified self curing mortar of approved make as per the direction of Engineer-In-Charge.	135.00	sqm	306.00	41310.00	INR Forty One Thousand Three Hundred & Ten Only				
18	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	680.00	sqm	90.00	61200.00	INR Sixty One Thousand Two Hundred Only				
19	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	900.00	sqm	18.00	16200.00	INR Sixteen Thousand Two Hundred Only				
20	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	230.00	sqm	108.00	24840.00	INR Twenty Four Thousand Eight Hundred & Forty Only				
21	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work	550.00	sqm	63.00	34650.00	INR Thirty Four Thousand Six Hundred & Fifty Only				
22	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	320.00	sqm	45.00	14400.00	INR Fourteen Thousand Four Hundred Only				

05/01/23
 देवेंद्र कुमार शर्मा, (अ.प्र.) AGM (F & E)
 मा. वि. प्र. / A.A.I.
 बिरसी विमानतल, गोंदिया
 Birsai Airport, GONDIA

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (excluding GST) in Rs. P	TOTAL AMOUNT In Words	TEXT #
23	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion: Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	180.00	Kg	504.00	90720.00	INR Ninety Thousand Seven Hundred & Twenty Only	
24	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	170.00	kg	540.00	91800.00	INR Ninety One Thousand Eight Hundred Only	

Done
05/01/23

सहायक (अभि-वि) AGM (E-E)
भा. वि. प्र. / A.A.I.
विरसो विमानतल, गोंडिया
BIRSA Airport, GONDIA

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (excluding GST) To be entered by the Bidder	TOTAL AMOUNT (excluding GST) in Rs. P	TOTAL AMOUNT in In Words	TEXT #		
25	Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides	10.00	sqm	1008.00	10080.00	INR Ten Thousand & Eighty Only			
26	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	23.00	sqm	1107.00	25461.00	INR Twenty Five Thousand Four Hundred & Sixty One Only			
27	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg. for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. With stainless steel cover plate minimum 1.25 mm thickness	4.00	nos.	6300.00	25200.00	INR Twenty Five Thousand Two Hundred Only			
28	Marble stone flooring with 18 mm thick marble stone, as per sample of marble approved by Engineer-in-charge, over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry, including rubbing and polishing complete with : Udaipur green marble	2.00	sqm	1530.00	3060.00	INR Three Thousand & Sixty Only			

Date: 05/01/23
 सा. वि. प्र. (अभि-वि.) AGM (F E)
 सा. वि. प्र. / A.A.I.
 बिरसी विमानतल, गुजरात
 Birsi Airport, GUJARAT

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures (excluding GST) To be entered by the Bidder Rs. P	TOTAL AMOUNT (excluding GST) in Rs. P	TOTAL AMOUNT In Words
33	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 300x10 mm	3.00	nos.	90.00	270.00	INR Two Hundred & Seventy Only
34	Providing and fixing factory made uPVC white colour sliding glazed door comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension uPVC extruded glazing beads, uPVC extruded interlock and uPVC extruded inline sash adaptor (if required), EPDM gasket, wool pile, zinc alloy (white powder coated) handle with key on one side of extreme panels along with zinc plated mild steel multi point locking having transmission gear with keeps, zinc alloy (white powder coated) crescent lock (if required), stainless steel (SS 304 grade) body with adjustable double nylon rollers (weight bearing capacity to be 120 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes, wire mesh and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Note: For uPVC frame and sash extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Two track two panels sliding door made of (big series) frame 67 x 50 mm & sash 46 x 82 mm both having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension. (Area of door above 2.00 sqm upto 5.00 sqm)	12.00	sqm	6750.00	81000.00	INR Eighty One Thousand Only

Date 05/12/23
 महा.महा.प्र. (अभि-वि) AGM (F.E.)
 भा.वि.प्रा. / A.A.
 बिरसी विमानतट
 Birsi Airport, ...

NUMBER #	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER # BASIC RATE In Figures (excluding GST) To be entered by the Bidder Rs. P	NUMBER # TOTAL AMOUNT (excluding GST) in Rs. P	TEXT # TOTAL AMOUNT In Words
Sl. No.						
35	Providing and fixing panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick : Float glass panes. 5.0 mm thick glass panes (weight not less than 12.50 kg/sqm).	12.00	sqm	1530.00	18360.00	INR Eighteen Thousand Three Hundred & Sixty Only
36	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	100.00	sqm	1440.00	144000.00	INR One Lakh Forty Four Thousand Only
37	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	31.00	sqm	1530.00	47430.00	INR Forty Seven Thousand Four Hundred & Thirty Only
38	Providing and Laying UPVC water pipes (I.S:4985) of 10 Kg/cm2 including all fittings e.g. bends, junctions, elbow, f-tee, m-tee, offsets, access pieces etc. jointing with solvent cement complete. Rates includes any type of fittings required for the provision of Garden Hydrant point in main ring of the Hydrant pipe in different location complete in with trenching, refilling and testing of joints complete as per direction of the engineer in charge: 100 mm outer dia	10.00	mtr	270.00	2700.00	INR Two Thousand Seven Hundred Only
	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	70.00	kg	126.00	8820.00	INR Eight Thousand Eight Hundred & Twenty Only
					2704873.42	INR Twenty Seven Lakh Four Thousand Eight Hundred & Seventy Three and Paise Forty Two Only
Total in Words		INR Twenty Seven Lakh Four Thousand Eight Hundred & Seventy Three and Paise Forty Two Only				

Signature Not Verified

Digitally signed by DEVEN DRA PURI
GOSWAMI

Date: 2023.02.08 12:54:11 IST

Location: eProcurement System for
Central PSUs

Devel
2023.02.08 / A.A.1
Bids
Bids
Bids