



सं: भा.वि.प्रा./बिजीएम/इंजि-वि/2022-23/WO-08/480/
No.: AAI/BGM/ENGG-E/ 2022-23/WO-08/

दिनांक: 13/01/2023

Date: 13/01/2023

सेवा में/To,

मैसर्स. अवस्थी इलेक्ट्रिक वर्क्स,
M/s. Awasthi Electric Works,
107/265 Brahma Nagar Kanpur,
Uttar Pradesh-208012
Email ID: aewknp@gmail.com
Mobile No. 9415101606

कार्य का नाम:- डीजी मेट पर एचवीएसी लोड का प्रावधान और बेलगावी हवाईअड्डे पर स्टैंडबाय एचटी पावर सप्लाय केबल का प्रावधान।

Name of work:- Provision of HVAC load on DG Sets and provision of standby HT power supply cable at Belagavi Airport.

Tender ID:- 2022_AAI_136477_1

संदर्भ: १) आपका ई-निविदा दिनांक 27/12/2022 from 12:00 hrs को खोला गया ई - निविदा (वित्तीय बोली)

Ref: 1) Your E-Tender Envelope-II (Financial Bid) was opened on 27/12/2022 from 12:00 hrs

२) ई-टेंडर लिफाफा - I 22/12/2022 from 11:00 Hrs को खोला गया

2) E-Tender Envelope - I was opened on 22/12/2022 from 11:00 Hrs.

महोदय/ Sir (s),

1. ऊपर उल्लिखित कार्य के लिए आपका टेंडर रु. **6,95,875/-** (रुपए: छह लाख पंचानबे हजार आठ सौ पचहत्तर मात्र) जीएसटी को छोड़कर, जो की अनुमानित लागत रु. **9,75,573/-** (GST को छोड़कर) से **28.67%** कम है। भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है। जीएसटी लागू होने पर अतिरिक्त भुगतान किया जाएगा।

1. Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 6,95,875/- (Rupees Six lakhs Ninety Five Thousand Eight Hundred and Seventy Five only) excluding GST** which is **28.67% below** the estimated cost put to tender of **Rs. 9,75,573/- (excluding GST)**, GST shall be paid extra as applicable.

2. सहायक महाप्रबंधक (इंजीनियरिंग-ई), एएआई, बेलगावी हवाई अड्डे के कार्य के इंजीनियर-इन-चार्ज होंगे। आपसे अनुरोध है कि आप इस पत्र के जारी होने की तारीख से **10 दिनों** के भीतर के कार्यालय में अनुबंध पर हस्ताक्षर करने और पूरा करने के लिए महाप्रबंधक (इंजीनियरिंग-ई), एएआई, बेलगावी हवाई अड्डा, बेलगावी में उपस्थित हों। अनुबंध समझौते को रु. **100/-** के गैर-न्यायिक स्टाम्प पेपर (केवल एक सौ रुपये) पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।

2. Assistant General Manager (Engg-E), AAI, Belagavi Airport shall be the Engineer-in-Charge for the work. You are requested to attend the office of Asst. General Manager (Engg-E), AAI, Belagavi Airport, Belagavi, within **10 days** from the date of issue of this letter to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100/- (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.



३. रुपये की बयाना राशि **19,511/-** (रुपए उन्नीस हजार पाँच सौ ग्यारह मात्र) आपके टेंडर के साथ प्राप्त किया गया है, जोकि सीपीपी पोर्टल में अनुबंध के पुरस्कार के बाद एजेंसी को वापस कर दिया जाएगा। वर्क ऑर्डर पैरा संख्या 8 के अनुसार चालू बिलों में 10% की दर से जमानत राशि रोकी जाएगी और एससीसी-33 के निविदा दस्तावेज पेज नं. 154।
3. The earnest money amount of **Rs. 19,511/-** (Rupees Nineteen Thousand Five Hundred and Eleven only) received along with your tender, will be returned to the agency after Award of Contract in CPP Portal. Security Deposit @ 10% will be withheld in running bills as per work order para no. 8 and SCC-33 at page no. 154 of tender document.
4. काम पूरा होने की अवधि **02 महीना** है जिसकी गणना दिनांक **22/01/2023** अर्थात इस पत्र के जारी होने के **10th** दिन से की जाएगी।
4. Period of completion of the work is **02 Months** which shall be reckoned from **22/01/2023** i.e. 10th day after issue of this letter.
5. कार्य इंजीनियर-इन-चार्ज के निर्देशानुसार निष्पादित किया जाएगा और एजीएम (ई-ई) द्वारा अनुमोदित किया जाएगा, जो इस काम के लिए इंजीनियर-इन-चार्ज होगा। इंजीनियर-इन-चार्ज द्वारा अनुमोदित सामग्री की आपूर्ति नहीं की जाएगी।
5. The work shall be executed as per the direction of Engineer-In-Charge and shall be approved by the AGM (E-E), who will be Engineer-In-Charge for this job. Material not approved by the Engineer-In-Charge shall not be supplied.
6. काम पूरा होने पर, आपके द्वारा या आपके अधिकृत प्रतिनिधि और अभियंता-प्रभारी या उनके प्रतिनिधि द्वारा संयुक्त रूप से प्रत्येक आइटम को मापा जाएगा, और माप बुक में दर्ज किया जाएगा।
6. On completion of work, each item of work shall be jointly measured by you or your authorized representative and the Engineer-In-Charge or his representative, and shall be entered into the measurement book.
7. कार्य बिल के संतोषजनक समापन पर अभियंता-प्रभारी को निम्नलिखित दस्तावेजों के साथ प्रस्तुत किया जाएगा और भुगतान के लिए उसी पर कार्रवाई की जाएगी।
7. On satisfactory completion of work bill shall be submitted along with the following documents to the Engineer-In-Charge and the same shall be processed for payment.
 - क। मापन पुस्तक संयुक्त रूप से आपके और इंजीनियर-प्रभारी या उनके प्रतिनिधि द्वारा हस्ताक्षरित है।
 - a. Measurement book jointly signed by you and Engineer-In-Charge or his representative.
 - ख। डिलीवरी चलान, यदि कोई हो।
 - b. Delivery challan, if any.
 - ग. जी.एस.टी चलान।
 - c. GST Invoice.
 - घ। अन्य प्रासंगिक दस्तावेज, यदि कोई हो।
 - d. Other relevant documents such as test certificate etc.



8. सुरक्षा जमा @ 10% बिल से काट लिया जाएगा और बारह (12) महीने की गारंटी और दोष देयता अवधि के सफल समापन के बाद ही जारी किया जाएगा।
8. The security deposit @ 10% shall be deducted from the bills and will be released only after successful completion of the guarantee and defects liability period of Twelve (12) months.
9. एजेंसी को काम शुरू होने की तारीख से दोष देयता अवधि (डीएलपी) तक ठेकेदार सभी जोखिम (सीएआर) नीति और कामगार मुआवजा नीति (डब्ल्यूसीपी) प्रस्तुत करनी चाहिए।
9. Agency shall submit Contractors All Risk (CAR) Policy and Workmen Compensation Policy (WCP) from date of commencement of work upto Defects Liability Period (DLP).
10. एजेंसी पीईआरटी/बीएआर/गतिविधि/माइल स्टोन चार्ट जमा करेगी जिसमें काम शुरू होने से लेकर पूरा होने तक सभी कार्य गतिविधियों को स्पष्ट रूप से दिखाया जाएगा।
10. Agency shall submit PERT/BAR/Activity/Mile Stone chart clearly showing all work activities from the start of work to completion.
11. इस वर्क ऑर्डर अवार्ड पत्र को भा.वि.प्रा./बिजीएम/इंजि-वि/2022-23/WO-08/ दिनांक: 13/01/2023 नंबर आवंटित किया जाता है, जो इस पुरस्कार पत्र के संबंध में भविष्य के सभी पत्राचार के लिए आपके द्वारा उद्धृत किया जाएगा।
11. This work order award letter is allotted the number AAI/BGM/ENGG-E/2022-23/WO-08/ Dated: 13/01/2023 which shall be quoted by you for all future correspondence in connection with this award letter.

अनुलग्नक: मात्रा की अनुसूची
Encl: Schedule of Quantities

Thanking You

Yours faithfully,

सहायक महाप्रबंधक (अभि-वि)/ Asst. General Manager (Engg-E),
भा.वि.प्रा, बेळगावि हवाई अड्डा/ AAI, Belagavi Airport
कृते तथा ओर से, अध्यक्ष, भा.वि.प्रा/ for and on behalf of Chairman, AAI

SCHEDULE OF QUANTITIES

Tender Inviting Authority: AGM (Engg-E), AAI, Belagavi Airport

Name of Work: Provision of HVAC load on DG Sets and provision of standby HT power supply cable.

Contract No: 2022_AAI_136477_1

Name of the Bidder/ Bidding Firm / Company :	AWASTHI ELECTRIC WORKS					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excl GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excl GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Supply of XLPE insulated PVC sheathed aluminium conductor armoured power cable of 11 KV grade (11 KV earthed system) of size 3C x 95 Sq.mm conforming to IS 7098 (Part-II) 1985 with upto date ammendments.	210	Metre	978.00	205380.00	INR Two Lakh Five Thousand Three Hundred & Eighty Only
2	Supply of 1.1KV grade 3.5C 400 Sq.mm. armoured aluminium conductor XLPE insulated and PVC sheathed cable conforming to IS - 7098 (Part - I) 1988 respectively with upto date ammendments.	130	Metre	2089.00	271570.00	INR Two Lakh Seventy One Thousand Five Hundred & Seventy Only
3	Laying of one number XLPE insulated and PVC sheathed power cable of 11 KV grade of size 3C 95 Sq.mm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.	150	Metre	540.00	81000.00	INR Eighty One Thousand Only
4	Laying of one number XLPE insulated and PVC sheathed power cable of 11KV grade of size 3C 95 Sq.mm in the existing RCC / HUME / METAL pipe as required.	25	Metre	125.00	3125.00	INR Three Thousand One Hundred & Twenty Five Only
5	Laying of one number XLPE insulated and PVC sheathed power cable of 11KV grade of size 3C 95 Sq.mm in the existing masonry open duct as required.	35	Metre	110.00	3850.00	INR Three Thousand Eight Hundred & Fifty Only
6	Laying and fixing of one number XLPE insulated and PVC sheathed armoured power cable of 1.1 KV grade of size above 185 sq. mm and upto 400 sq. mm on cable tray as required.	90	Metre	250.00	22500.00	INR Twenty Two Thousand Five Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excl GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excl GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
7	Laying of one number XLPE insulated and PVC sheathed armoured power cable of 1.1 KV grade of size above 185 sq.mm and upto 400 sq.mm. in the existing masonry open duct as required.	40	Metre	135.00	5400.00	INR Five Thousand Four Hundred Only
8	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for 3 core 95 Sqmm, XLPE aluminium conductor cable of 11 KV grade as required.	1	Each	17500.00	17500.00	INR Seventeen Thousand Five Hundred Only
9	supplying and making indoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for 3 core 95 Sqmm, XLPE aluminium conductor cable of 11 KV grade as required.	3	Each	12500.00	37500.00	INR Thirty Seven Thousand Five Hundred Only
10	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for 3.5C 300 Sqmm, XLPE insulated and PVC sheathed aluminium conductor cable of 1.1 KV grade as required.	1	Each	6500.00	6500.00	INR Six Thousand Five Hundred Only
11	Supplying and making end termination with brass compression gland and aluminium lugs for 3.5C 300 Sq. mm. size of XLPE insulated and PVC sheathed armoured aluminium conductor cable of 1.1 KV grade as required.	1	Each	1650.00	1650.00	INR One Thousand Six Hundred & Fifty Only
12	Supplying and making end termination with brass compression gland and aluminium lugs for 3.5C 400 Sq. mm. size of XLPE insulated and PVC sheathed armoured aluminium conductor cable of 1.1 KV grade as required.	4	Each	1850.00	7400.00	INR Seven Thousand Four Hundred Only
13	Supply of digital insulation tester with multi range test voltages upto 5000 V, Rishabh make, AIT 501 model or equivalent make.	1	Each	32500.00	32500.00	INR Thirty Two Thousand Five Hundred Only
Total in Figures					695875.00	INR Six Lakh Ninety Five Thousand Eight Hundred & Seventy Five Only
Quoted Rate in Words		INR Six Lakh Ninety Five Thousand Eight Hundred & Seventy Five Only				

Signature Not Verified

Digitally signed by SUDHAKARA NAIK
Date: 2023.05.20 13:00:41 IST
Location: eProcurement System for Central PSUs



[Handwritten Signature]
AGM (Engg. & Equip.)
AAI, Bhopal Airport
2023