



सं: भा.वि.प्रा./विजीएम/इंजि-वि/2022-23/WO-09/488/
No.: AAI/BGM/ENGG-E/ 2022-23/WO-09/

दिनांक: 06/02/2023
Date: 06/02/2023

सेवा में/To,

मैसर्स. जीके इलेक्ट्रिकल्स एंड इंजीनियर्स,
M/s. GK ELECTRICALS AND ENGINEERS,
PLOT NO 5 AND 6 LOKSHAHI COLONY
NEW ST COLONY N-2 CIDCO
AURANGABAD, Maharashtra-431006
Email: gkelectricalsengg@gmail.com
Contact no.: 9404982906

कार्य का नाम:- बेलगावी हवाई अड्डे पर एसटीपी में सीवेज पम्पिंग सिस्टम और संबद्ध कार्यों का प्रावधान।

Name of work:- Provision of Sewage Pumping System and Allied Works in STP at Belagavi Airport.

Tender ID:- 2022_AAI_136934_1

संदर्भ: १) आपका ई-निविदा दिनांक 17/01/2023 from 10:00 hrs को खोला गया ई - निविदा (वित्तीय बोली)

Ref: 1) Your E-Tender Envelope-II (Financial Bid) was opened on 17/01/2023 from 10:00 hrs

२) ई-टेंडर लिफाफा - I 09/01/2023 from 11:00 Hrs को खोला गया

2) E-Tender Envelope - I was opened on 09/01/2023 from 11:00 Hrs.

महोदय/ Sir (s),

- ऊपर उल्लिखित कार्य के लिए आपका टेंडर रु. 9,77,738/- (रुपए: नौ लाख सतहत्तर हजार सात सौ अड़तीस मात्र) जीएसटी को छोड़कर, जो की अनुमानित लागत रु. 10,38,008/- (GST को छोड़कर) से 5.81% कम है। भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है। जीएसटी लागू होने पर अतिरिक्त भुगतान किया जाएगा।
- Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 9,77,738/- (Rupees Nine lakhs Seventy Seven Thousand Seven Hundred and Thirty Eight only) excluding GST** which is **5.81% below** the estimated cost put to tender of **Rs. 10,38,008/- (excluding GST)**, GST shall be paid extra as applicable.
- सहायक महाप्रबंधक (इंजीनियरिंग-ई), एएआई, बेलगावी हवाई अड्डे के कार्य के इंजीनियर-इन-चार्ज होंगे। आपसे अनुरोध है कि आप इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर के कार्यालय में अनुबंध पर हस्ताक्षर करने और पूरा करने के लिए महाप्रबंधक (इंजीनियरिंग-ई), एएआई, बेलगावी हवाई अड्डा, बेलगावी में उपस्थित हों। अनुबंध समझौते को रु. 100/- के गैर-न्यायिक स्टाम्प पेपर (केवल एक सौ रुपये) पर निष्पादित किया जाएगा और स्टाम्प पेपर की लागत आपके द्वारा वहन की जाएगी।
- Assistant General Manager (Engg-E), AAI, Belagavi Airport shall be the Engineer-in-Charge for the work. You are requested to attend the office of Asst. General Manager (Engg-E), AAI, Belagavi Airport, Belagavi, within **10 days** from the date of issue of this letter to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100/- (Rupees One Hundred only)** and the cost of the stamp paper shall be borne by you.



३. रुपये की बयाना राशि 20,760/- (रुपए बीस हजार सात सौ साठ मात्र) आपके टेंडर के साथ प्राप्त किया गया है, जोकि सीपीपी पोर्टल में अनुबंध के पुरस्कार के बाद एजेंसी को वापस कर दिया जाएगा। बर्क ऑर्डर पैरा संख्या 8 के अनुसार चालू बिलों में 10% की दर से जमानत राशि रोकी जाएगी और जिसीमी-१४ (iv) के निविदा दस्तावेज पेज नं. २८।
3. The earnest money amount of **Rs. 20,760/-** (Rupees Twenty Thousand Seven Hundred and Sixty only) received along with your tender, will be returned to the agency after Award of Contract in CPP Portal. Security Deposit @ 10% will be withheld in running bills as per work order para no. 8 and **GCC-14 (iv)** at page no. **28** of tender document.
4. काम पूरा होने की अवधि 03 महीना है जिसकी गणना दिनांक 15/02/2023 अर्थात इस पत्र के जारी होने के 10th दिन से की जाएगी।
4. Period of completion of the work is **03 Months** which shall be reckoned from **15/02/2023 i.e. 10th day** after issue of this letter.
5. कार्य इंजीनियर-इन-चार्ज के निर्देशानुसार निष्पादित किया जाएगा और एजीएम (ई-ई) द्वारा अनुमोदित किया जाएगा, जो इस काम के लिए इंजीनियर-इन-चार्ज होगा। इंजीनियर-इन-चार्ज द्वारा अनुमोदित सामग्री की आपूर्ति नहीं की जाएगी।
5. The work shall be executed as per the direction of Engineer-In-Charge and shall be approved by the AGM (E-E), who will be Engineer-In-Charge for this job. Material not approved by the Engineer-In-Charge shall not be supplied.
6. काम पूरा होने पर, आपके द्वारा या आपके अधिकृत प्रतिनिधि और अभियंता-प्रभारी या उनके प्रतिनिधि द्वारा संयुक्त रूप से प्रत्येक आइटम को मापा जाएगा, और माप बुक में दर्ज किया जाएगा।
6. On completion of work, each item of work shall be jointly measured by you or your authorized representative and the Engineer-In-Charge or his representative, and shall be entered into the measurement book.
7. कार्य बिल के संतोषजनक समापन पर अभियंता-प्रभारी को निम्नलिखित दस्तावेजों के साथ प्रस्तुत किया जाएगा और भुगतान के लिए उसी पर कार्रवाई की जाएगी।
7. On satisfactory completion of work bill shall be submitted along with the following documents to the Engineer-In-Charge and the same shall be processed for payment.
 - क। मापन पुस्तक संयुक्त रूप से आपके और इंजीनियर-प्रभारी या उनके प्रतिनिधि द्वारा हस्ताक्षरित है।
 - a. Measurement book jointly signed by you and Engineer-In-Charge or his representative.
 - ख। डिलीवरी चलान, यदि कोई हो।
 - b. Delivery challan, if any.
 - ग. जी.एस.टी चलान।
 - c. GST Invoice.
 - घ। अन्य प्रासंगिक दस्तावेज, यदि कोई हो।
 - d. Other relevant documents such as test certificate etc.



8. सुरक्षा जमा @ 10% बिल से काट लिया जाएगा और बारह (12) महीने की गारंटी और दोष देयता अवधि के सफल समापन के बाद ही जारी किया जाएगा।
8. The security deposit @ 10% shall be deducted from the bills and will be released only after successful completion of the guarantee and **defects liability period of Twelve (12) months.**
9. एजेंसी को काम शुरू होने की तारीख से दोष देयता अवधि (डीएलपी) तक ठेकेदार सभी जोखिम (सीएआर) नीति और कामगार मुआवजा नीति (डब्ल्यूसीपी) प्रस्तुत करनी चाहिए।
9. Agency shall submit Contractors All Risk (CAR) Policy and Workmen Compensation Policy (WCP) from date of commencement of work upto Defects Liability Period (DLP).
10. एजेंसी पीईआरटी/बीएआर/गतिविधि/माइल स्टोन चार्ट जमा करेगी जिसमें काम शुरू होने से लेकर पूरा होने तक सभी कार्य गतिविधियों को स्पष्ट रूप से दिखाया जाएगा।
10. Agency shall submit PERT/BAR/Activity/Mile Stone chart clearly showing all work activities from the start of work to completion.
11. इस वर्क ऑर्डर अवार्ड पत्र को भा.वि.प्रा./बिजीएम/इंजि-वि/2022-23/WO-09/ दिनांक: 06/02/2023 नंबर आबंटित किया जाता है, जो इस पुरस्कार पत्र के संबंध में भविष्य के सभी पत्राचार के लिए आपके द्वारा उद्धृत किया जाएगा।
11. This work order award letter is allotted the number AAI/BGM/ENGG-E/2022-23/WO-09/ Dated: 06/02/2023 which shall be quoted by you for all future correspondence in connection with this award letter.

अनुलग्नक: मात्रा की अनुसूची
Encl: Schedule of Quantities

Thanking You

Yours faithfully,

06/02/2023.

सहायक महाप्रबंधक (अभि-वि)/ Asst. General Manager (Engg-E),
भा.वि.प्रा, बेलगावि हवाई अड्डा/ AAI, Belagavi Airport
कृते तथा ओर से, अध्यक्ष, भा.वि.प्रा/ for and on behalf of Chairman, AAI

SCHEDULE OF QUANTITIES

Tender Inviting Authority: Assistant General Manager (Engg-E), AAI, Belagavi Airport.

Name of Work: Provision of Sewage Pumping System and Allied Works in STP at Belagavi Airport.

Contract No: 2022_AAI_136934_1

Name of the Bidder/ Bidding Firm/ Company :	MS GK ELECTRICALS AND ENGINEERS					
<u>PRICE SCHEDULE</u> (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excl GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excl GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Out door Feeder Pillar-MCC Panel Supply, installation, testing and commisioning of outdoor feeder pillar type MCC Panel, cubicle type, design from CRCA sheet steel of 2 mm thick for frame work and covers, totally enclosed, protection free standing, Pedestal mounting, outdoor dust & vermin proof (min IP-66), Cubicles with hinged door, Form-3b construction and Aluminium Plate Tags, Affixed danger board- size 200 mm x 150 mm, Three languages (Local, Hindi, English), suitable for operation on 3 Phase and neutral, 415V, 50 Hz AC supply system interconnections with suitable size of copper leads/solid aluminium strips.					
1.01	Detailed Circuit diagram with a laminate Coat/Aluminium Plate on inside of Panel, coated with approved shade powder coat, Iron angle/Channel frame work with necessary cable alley, heat shrink sleeved bus bar and bus bar chamber, cubicles for all switches & Switch gear, interconnection using suitable size copper leads/solid aluminium strips, Cable termination Shrouding with transparent hylam / mica sheet of not less than 10mm, cable terminals blocks, cable entry through bottom cable gland Plate-3 mm , entire panel shall have a common earth bar of suitable size at the rear with 2 Nos. earth stud, with Base channel MS channel Base of 75 mm x 5mm I beam, PCC Pedestial mounted with spacing of atleast 500mm between ground level and panel.Curved canopy to ensure immediate drain of Rain water, Lifting Hooks, Uppermost Handle Height shall be at 1.7 mtr limit. The panel shall be fabricated from a firm having CPRI certification with test certificates for similar panel (required for short circuit rating, temperature rise and IP classification) as per drawing & Technical specification. INCOMER: Duty & Stand-by 63A , 3P + NL 50kA MCCB with Thermal Magnetic based adjustable release with OL & SC protection - 2 No. (Make: LT DNO-100M or equivalent) Rotary operating mechanism and terminal extension spreaders with door interlock for all the MCCB's. SPD's of type 2 class C - 2 Set. Shunt release coil METERING CUBICLE: Digital MFM (V,A,F,PF,KW,KVA,KWH & THD) With RS 485 communication facilities - 2 No. Suitable Class CT- 63/5A 15VA class 1-6 Nos SP MCB, 6Amps for Control-3 Nos ON/OFF/TRIP indication lamp, LED type - 6 Nos.					

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excl GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excl GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1.02	63A-CHANGE OVER SWITCH WITH INTERLOCK - 1 Nos BUSBARS 4P aluminum bus bars of suitable capacity with heat shrinkable coloured sleeves i/c SMC bus bars supports at required intervals complete for cross section, size supports & their spacing etc. for withstanding fault level of 35 KA for 1 sec. Under voltage/Over voltage relay Phase Reverse Protection relay OUT GOING: DOL sewage Cutter Pump:-2 Cubicle 16 AMPS 3 POLE, MCB, 10 KA, "C" CURVE - 2 Nos 12 AMPS POWER CONTACTOR, 3 POLE -2 Nos OVERLOAD RELAY RANGE: 4.5-7.5 AMPS -2 Nos AUXILARY CONTACT BLOCK 1 NO + 1NC -2 Nos PUSH BUTTON WITH ELEMENT ON/OFF -4 Nos AUXILARY CONTACTOR 2 NO + 2NC -2 Nos (For level sensor and Automatic Pump interchange function) AUXILARY CONTACTOR 2 NO + 2NC -2 Nos (For level sensor and Automatic Pump interchange function) PUSH BUTTON WITH ELEMENT ON/OFF -4 Nos LOCAL /REMOTE SELECTION SELECTOR SWITCH -2 Nos SINGLE PHASING PREVENTOR -2 Nos EMERGENCY PUSH BUTTON WITH CONTACT -2 Nos LED INDICATION LAMPS, ON/OFF/TRIP -6 Nos 6 AMPS, SP, MCB FOR CONTROL-2 Nos DOL Venturi Aerator -4 Cubicle 10 AMPS 3 POLE, MCB, 10 KA, "C" CURVE -4 Nos 09 AMPS POWER CONTACTOR, 3 POLE -4 Nos OVERLOAD RELAY RANGE: 3-5 AMPS 4 Nos					
1.03	AUXILARY CONTACT BLOCK 1 NO + 1NC -4 Nos AUXILARY CONTACTOR 2 NO + 2NC -4 Nos PUSH BUTTON WITH ELEMENT ON/OFF -8 Nos LOCAL /REMOTE SELECTION SELECTOR SWITCH -4 Nos SINGLE PHASING PREVENTOR -4 Nos EMERGENCY PUSH BUTTON WITH CONTACT -4 Nos LED INDICATION LAMPS, ON/OFF/TRIP -12 Nos 6 AMPS, SP, MCB FOR CONTROL -4 Nos SPARE -2 Cubicle Spare Cubicle - 16 A, 4P, 'C' type MCB (10KA) - 1 Nos. including Terminal Blocks,Interconnection wiring etc in Outgoing cable chamber. Spare Cubicle - 6 A, 2 pole 'C' type MCB (10KA) -4 Nos. including Terminal Blocks,Interconnection wiring etc in Outgoing cable chamber. Control Wiring shall be Halogen Free Fire Retardent Wier withstanding 105 Deg C. Alarm Cubicle Buzzer for Trip Alarm-1 Nos combined for Audible alert common for all six starters MCB, DP-10 Amp for control	1	JOB	198000.00	198000.00	INR One Lakh Ninety Eight Thousand Only
2	Providing and laying in position cement concrete 1:3:6 (1 cement : 2 coarse sand : 6 graded stone aggregate 40 mm nominal size) in feeder pillar based pedestals, including form work, CC Bed of 150mm Thickness and protusion of 200mm all around to avoid vegetation, excavation and refilling etc complete as required.	1	JOB	4888.00	4888.00	INR Four Thousand Eight Hundred & Eighty Eight Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excl GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excl GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
3	Supply, erection, installation, testing and commissioning of sewage submersible Mixer/agitator for sewage sump of 3.85 Meter width X 4.00 Meter breadth x 5 Meter Depth (3HP) including mounting and lifting system as per technical specifications etc complete as required.	4	Each	44800.00	179200.00	INR One Lakh Seventy Nine Thousand Two Hundred Only
4	Supply, installation, testing and commissioning of Submersible Sewage Cutter Pump of 2-3HP, atleast 3.5 LPS @12 Mtr Head suitable to operate on 3 PH, 4 Wire, 415 V, 50 HZ with Horizontal outlet of 40 mm dia with Material of construction confirming Technical specification etc complete as required.	2	Each	78868.00	157736.00	INR One Lakh Fifty Seven Thousand Seven Hundred & Thirty Six Only
5	Supply of UPVC plumbing materials as per specification etc., complete as required.					
5.01	2 Inch Flange with Gasket - End Cap Open (SCH 80)	14	Nos	488.00	6832.00	INR Six Thousand Eight Hundred & Thirty Two Only
5.02	2 inch inner dia UPVC pipe (SCH 80).	36	Mtr	488.00	17568.00	INR Seventeen Thousand Five Hundred & Sixty Eight Only
5.03	2 inch UPVC Elbow 90° (SCH 80)	6	Nos	109.00	654.00	INR Six Hundred & Fifty Four Only
5.04	2 inch UPVC TEE (SCH 80)	1	Nos	143.00	143.00	INR One Hundred & Forty Three Only
5.05	2 inch NRV UPVC Ball type (flange type) PN 1.0	2	Nos	138.00	276.00	INR Two Hundred & Seventy Six Only
5.06	2 inch Ball valve - Forged Brass Ball valve lever operated.	3	Nos	1380.00	4140.00	INR Four Thousand One Hundred & Forty Only
5.07	50 mm water meter, Outdoor, Flanged full bore, Class B, Union type	1	Nos	12800.00	12800.00	INR Twelve Thousand Eight Hundred Only
6	Erection of sewage delivery piping work from Sewage submersible pump outlet till collection well in STP including erection of piping, threading, cutting and fixing plumbing accessories such as gaskets, flanges, end plugs, Ball NRV, Ball Valves, Flowmeter, Pipe nipples (supplied in Item #5) common discharge pipeline inter connecting sewage pumps (2nos), clamping with U-bolt clamps, anchoring with suitable size nut bolt or anchor fasteners fixed in pedestal beams made of CC (1:3:6 mix) of suitable size raised upto Pipe outlet level and support plumbing including accessories safe enough to handle the vertical/horizontal vibrations caused by pumped liquid from motor outlet etc. complete as required.	1	JOB	18000.00	18000.00	INR Eighteen Thousand Only
7	Supplying of following size cables as per technical specification etc. complete as required.					
7.01	4C X 35 Sq.mm, Aluminium conductor, XLPE insulated and FRLSHF Sheathed Armored of 1.1KV grade as per IS.7098	190	Mtr	425.00	80750.00	INR Eighty Thousand Seven Hundred & Fifty Only
7.02	4C X 1.5 Sq.mm Stranded Copper conductor, Armoured Sheathed PVC Insulated, FRLS Sheathed cable.	40	Mtr	245.00	9800.00	INR Nine Thousand Eight Hundred Only
7.03	2C X1.0 Sq.mm Annealed Bare Cu Flexible, Tinned Cu Braided (Screened), Un-armoured, PVC Insulated, 1100Volts.	20	Mtr	118.00	2360.00	INR Two Thousand Three Hundred & Sixty Only
8	Supplying and making end termination with Brass Compression and Aluminium/copper lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 35 sq. mm (32mm)	2	Set	450.00	900.00	INR Nine Hundred Only
9	Supplying HDPE pipe confirming to IS-4984, complete etc as required. 50 mm, PN-6, PE 63	340	Mtr	75.00	25500.00	INR Twenty Five Thousand Five Hundred Only
10	Laying of following size DWC HDPE pipe/HDPE ISI marked complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63 mm DIA	220	Mtr	100.00	22000.00	INR Twenty Two Thousand Only
11	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade & 5 KV grade of following size in the existing RCC/HUME/STONE WARE/METAL/DWC/HDPE pipe as required. Upto 35 sq. mm	230	Mtr	10.00	2300.00	INR Two Thousand Three Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excl GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excl GST)	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
12	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.	6	Each	350.00	2100.00	INR Two Thousand One Hundred Only
13	Supply & Fixing of Cable Junction Boxes with cable connectors for termination of cable of following Size weather proof, outdoor type, Knock-out for cable entry, pole/wall mounted including MS clamp/anchor bolts including accessories to ensure non-ingress of water of suitable size etc. complete as required. Polycarbonate cable Junction Box of Size (HxWxD)-93 x 93 x 62 mm weather proof, outdoor type Make: Hensel, Model: KF 0202 G	4	Set	3500.00	14000.00	INR Fourteen Thousand Only
14	Provision of Fabricated Chequered plate (1 Mtr x 1.1 Mtr Approx.) cover including Channel, Paiting and Grouting etc sewage treatment plant (STP) etc complete as required.	1	Job	3500.00	3500.00	INR Three Thousand Five Hundred Only
15	Provision of suitable debris collection bar screen of Stainless steel, 304 grade, 2.5mm thick including SS frame and associated civil works i.e. chipping, fixing C- channel frame for sliding of bar screen, smooth finishing in existing chamber of dimension (width X breadth X depth) - 1 X 1 X 2 Mtr (Approx.) complete etc as required.	1	Job	18000.00	18000.00	INR Eighteen Thousand Only
16	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	2	Set	5800.00	11600.00	INR Eleven Thousand Six Hundred Only
17	Providing and laying of 6 SWG GI wire inside excavated cable trench/humepipe for loop earthing etc complete as required.	230	Mtr	25.00	5750.00	INR Five Thousand Seven Hundred & Fifty Only
18	Providing and fixing 25 mm X 5 mm GI strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required.	10	Mtr	538.00	5380.00	INR Five Thousand Three Hundred & Eighty Only
19	Supply, installation, testing, comissioning, of 5 HP, 3-Ph, 50Hz open well submersible pump (atleast 10LPS@25 Mtr Head) in Openwell of depth 20 Mtr (approx) along with starter panel, erection of water delivery line, interconnecting with and modification of existing GI pipe line, electrical and plumbing works with accessories such as guide wire for lifting & lowering of pump, HDPE Pipe (PE63, PN8)-2.5", Hose Nipple, Hose clip, UPVC Elbow, Tee, MTA, FTA, Gun Metal ball valve, UPVC Pipe-2.5" Teflon tape-12mm, UPVC Solution, Union, Gasket+Yarn, sundries etc complete as required. (PUMP Make: Kirloskar Model: KOS-527 or Equivalent, Starter Make: BCH Model: Shakti-CPEYSAKZ or Equivalent).	1	Job	118000.00	118000.00	INR One Lakh Eighteen Thousand Only
20	Supply, installation, testing, comissioning of 5 HP, 3-Ph, 50Hz open well submersible pump including dismantling of existing Submersible pump, GI Delivery pipe from the sump of depth 5 Mtr, erection of UPVC water delivery line, interconnecting with leftover GI pipe line, routing of cable, plumbing works with accessories such as guide wire for lifting & lowering of pump, Flange,Elbow, pipe, ball valve, MAPT,Reducer coupler, Gasket,Union, Gasket+Yarn, sundries such as Teflon tape, Solution,Nut bolts, cable Tags etc complete as required. (PUMP Make: Kirloskar Model: KOS-527 or Equivalent, Equivalent).	1	Job	55561.00	55561.00	INR Fifty Five Thousand Five Hundred & Sixty One Only
Total in Figures					977738.00	INR Nine Lakh Seventy Seven Thousand Seven Hundred & Thirty Eight Only
Quoted Rate in Words		INR Nine Lakh Seventy Seven Thousand Seven Hundred & Thirty Eight Only				

Signature Not Verified

Digitally signed by SUDHAKARA NAIK
Date: 2023.05.20 12:35:24 IST
Location: eProcurement System for Central PSUs



[Handwritten Signature]
AGM (ENGG-E)
AAI, Belagavi Airport