



संख्या / No: AAI/BD/AGM(E-E)/CW-08/2022-23/131

दिनांक / Date: 12-01-2023

सेवा मे / To,

M/s. Anirban Enterprise,  
1080, Jessore Road,  
Kolkata - 700098

E-Mail: bosetandra16@gmail.com

**विषय/Subject:** Misc. Capital works (SH-II: Replacement of light fittings in Pre-SHA area of Terminal Building at Bagdogra Airport.

**संदर्भ / Ref :** 1) E-Tender ID No.: 2022\_AAI\_137059\_1

प्रिय महोदय / Dear Sir(s),

1. उपर्युक्त कार्य हेतु आपका निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गए मद मूल्यों पर आपकी उद्धृत राशि कुल रु. 7,52,965/- (जी.एस.टी. छोड़कर), जो कि टेंडर की न्यायोचित राशि रु. 11,25,076.00 से 33.07% नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 7,52,965.00** (Rupees Seven Lakhs Fifty-Two Thousand Nine Hundred and Sixty-Five only) excluding GST, which is 33.07% (Thirty-Three-point zero seven percent) below the Justified Cost of Rs. 11,25,076.00 (excluding GST).

2. सहायक महाप्रबंधक (अभि.-विद्युत), भा.वि.प्रा., बागडोगरा हवाईअड्डा, बागडोगरा-734421, इस कार्य के लिए प्रभारी इंजीनियर होंगे। आपसे निवेदन है कि आपकी ओर से आप अथवा आपके द्वारा अधीकृत प्रतिनिधि नियुक्त करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 06.02.2023 तक सहायक महाप्रबंधक (अभि.-विद्युत) के कार्यालय में करार पर हस्ताक्षर करने एवं उसको पूरा करने हेतु उपस्थित हो। ठेके का करारनामा रु. 100/- (रुपया एक सौ मात्र) के नॉन ज्युडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा तथा स्टाम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Assistant General Manager (Engg. -Elect.), AAI, Bagdogra Airport, Bagdogra-734421 shall be the Engineer-in-Charge of the work. You are requested to attend the office of Assistant General Manager (Engg. -Elect.), AAI, Bagdogra Airport, Bagdogra - 734421 by **06.02.2023** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

3. आपके निविदा से साथ प्राप्त बयाना राशि रु. 22,502/- को संविदा दस्तावेज के पृष्ठ 16 | GCC पर दी गई क्लॉज़ जी.सी.सी. 1(ए) के अनुसार सुरक्षा जमा के हिस्से के रूप में परिवर्तित कर दिया गया है। कृपया इस पत्र के 10 दिन में सुरक्षा जमा के लिए रु. 52,795/- जमा करवा दें, ऐसा नहीं करने पर संविदा दस्तावेज के पृष्ठ 16 | GCC पर दी गई क्लॉज़ जी.सी.सी. 1(ए) के अनुसार आपके रनिंग बिल से काट ली जाएगी।

The earnest money amount of Rs. 22,502/- (Rupees Twenty-Two Thousand Five Hundred and Two only) received along with your tender has been converted as part of security deposit as per GCC clause 1(A) on page 16 | GCC of the contract document. Please deposit Rs. 52,795 /- (Rupees Fifty-Two Thousand Seven Hundred and Ninety-Five only) towards Security Deposit within 10 days from issue of this letter, failing which, the same will be deducted from your running bills as per GCC clause 1(A) on page 16 | GCC of the contract document.

4. आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम श्रम अनुबंध नियम तथा 1971 के केंद्रीय नियम (नियमन तथा उन्मूलन) एवं केन्द्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन अवश्य करें।

You are requested to comply with the provision of Contract Labour (Regulation & Abolition) Act 1970 and Contract Labour (Regulation & Abolition) Central Rules 1971 and minimum wages act and rules thereof Central and State Governments.

5. कृपया ध्यान दें कि कार्य को पूरा करने के लिए अनुमानित समय 04(चार) महीने होगा और इसकी गणना इस पत्र के जारी होने के 10वें दिन के बाद से गिना जाएगा।

Please note that the time allowed for carrying out the work shall be 04 (Four) months and same shall be reckoned from the 10th day after issue of this letter.

6. आपको निर्देश दिया जाता है कि आप तुरंत सहायक महा प्रबंधक (अभि.-विद्युत), भा.वि.प्रा., बागडोगरा हवाईअड्डा, बागडोगरा-734421 से मिले वह आपको साईट सौंपने की व्यवस्था करेंगे ।

You are directed to contact with the Assistant General Manager (Engg. -Elect.), AAI, Bagdogra Airport, Bagdogra-734421 who will arrange to hand over the site to you.

7. इस ठेके के संबंध में आगे का कोई भी पत्राचार इंजीनियर-इन-चार्ज को किया जाएगा ।

Any further correspondence in connection with the contract should normally be addressed to the Engineering-in-Charge.

8. कृपया पावती भेजे और स्वीकृति प्रतिलिपि के तौर पर संलग्नित पत्र की हस्ताक्षरित प्रति इस कार्यालय को अवश्य भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

9. यदि अंग्रेजी और हिन्दी पाठ में कोई असंगति पाया जाता है तो अंग्रेजी पाठ को सही माना जाएगा।

If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

संलग्न/Encl : i) Schedule of work.

निष्ठा पूर्वक/Yours faithfully,

 12/01/23

(शुभ्र शान्त घोष /Subhra Santa Ghosh)

सहायक महा प्रबंधक (अभि.-विद्युत),

Assistant General Manager (Engg. -Elect.),

ए.ए.आई./बागडोगरा विमानतल

AAI, Bagdogra Airport.

सिलिगुड़ी-734421/Siliguri-73421

AIRPORTS AUTHORITY OF INDIA  
ENGINEERING ELECTRICAL WING  
BAGDOGRA AIRPORT

**SCHEDULE OF QUANTITY**


**Name of Work: Mis. Capital Works (SH-II:Replacement of light fittings in Pre-SHA area of Terminal Building at Bagdogra Airport.)**

| Sl.No | Description of Work                                                                                                                                                                                                                                                                                                                                                      | Quantity | Units | Rate (Rs) | Amount (Rs)   |
|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------|---------------|
| 1     | Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.<br>Group C             | 10       | Point | 1050.00   | ₹ 10,500.00   |
| 2     | Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc as required.<br>Group C       | 115      | Point | 700.00    | ₹ 80,500.00   |
| 3     | Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.                                                                                                                                                                                                        |          |       |           |               |
| 3.1   | 3 x 1.5 sq. mm                                                                                                                                                                                                                                                                                                                                                           | 200      | Metre | 72.00     | ₹ 14,400.00   |
| 3.2   | 3 x 2.5 sq. mm                                                                                                                                                                                                                                                                                                                                                           | 30       | Metre | 95.00     | ₹ 2,850.00    |
| 3.3   | 3 x 4 sq. mm                                                                                                                                                                                                                                                                                                                                                             | 100      | Metre | 136.00    | ₹ 13,600.00   |
| 4     | Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.                                                                                                                                   |          |       |           |               |
| 4.1   | 20 mm                                                                                                                                                                                                                                                                                                                                                                    | 200      | Metre | 120.00    | ₹ 24,000.00   |
| 4.2   | 25 mm                                                                                                                                                                                                                                                                                                                                                                    | 100      | Metre | 135.00    | ₹ 13,500.00   |
| 5     | Supplying and fixing suitable size GI box with modular plate and cover in FRLS on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.                                                                                                                          | 14       | Each  | 275.00    | ₹ 3,850.00    |
| 6     | Supplying and fixing call bell/ buzzer suitable for single phase, 230 volts, complete as required.                                                                                                                                                                                                                                                                       | 2        | Each  | 175.00    | ₹ 350.00      |
| 7     | Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. As required.                                                                                                                                                                                                                                          | 60       | Each  | 35.00     | ₹ 2,100.00    |
| 8     | SITC of surface/recessed type 2' x 2' (minimum 36W) LED type downlighter suitable to operate on 50 Hz 1Ø AC supply complete with all accessories and tube/lamp/LED Strip etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required (Technical specification attached). | 160      | Each  | 1200.00   | ₹ 1,92,000.00 |
| 9     | SITC of surface mounted Mirror LED batten type light(minimum 10W) suitable to operate on 50 Hz 1Ø AC supply complete with all accessories and tube/lamp/LED Strip etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required (Technical specification attached).        | 20       | Each  | 205.00    | ₹ 4,100.00    |
| 10    | Supply of surface/recessed type 2' x 2' (minimum 36W) LED type downlighter suitable to operate on 50 Hz 1Ø AC supply ready to be installed at site (Technical specification attached).                                                                                                                                                                                   | 25       | Each  | 1200.00   | ₹ 30,000.00   |
| 11    | Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable etc. as required.                                                                                                                                                         | 74       | Each  | 125.00    | ₹ 9,250.00    |

| Sl.No                   | Description of Work                                                                                                                                                                                                                                                                                                                              | Quantity | Units | Rate (Rs) | Amount (Rs)          |
|-------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------|----------------------|
| 12                      | Supplying and fixing extra down rod of 10 cm length G.I. pipe ,15 mm dia, heavy gauge including painting etc. as required. (Note : More than 5 cm length shall be rounded to the nearest 10 cm and 5 cm or less shall be ignored)                                                                                                                | 1500     | Each  | 30.00     | ₹ 45,000.00          |
| 13                      | Supply of ceiling mounted exhaust fan having min sweep dia 130 mm, min air delivery 150 m³/h suitable for single phase AC operation, complete with all accessories as required and ready to be installed at site.                                                                                                                                | 10       | Each  | 2500.00   | ₹ 25,000.00          |
| 14                      | Providing and fixing of suitable size rigid U-PVC pipe on wall/ above false ceiling with suitable clamping/support for outlet of ceiling mounted exhaust fan as per site conditions and as directed by EIC.(for BOQ SI No 13)                                                                                                                    | 50       | Metre | 325.00    | ₹ 16,250.00          |
| 15                      | SITC of stainless steel automated hand dryer suitable for single phase, 230 volts, complete as required.                                                                                                                                                                                                                                         | 18       | Each  | 12000.00  | ₹ 2,16,000.00        |
| 16                      | Supplying and fixing of 8 way, double door single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)                          | 2        | Each  | 1800.00   | ₹ 3,600.00           |
| 17                      | Supplying and fixing of 4 way (4 + 12), Double door, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) | 2        | Each  | 2200.00   | ₹ 4,400.00           |
| 18                      | Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.                                                                                           |          |       |           |                      |
| 18.1                    | Single pole                                                                                                                                                                                                                                                                                                                                      | 36       | Each  | 175.00    | ₹ 6,300.00           |
| 18.2                    | Single pole and neutral                                                                                                                                                                                                                                                                                                                          | 2        | Each  | 375.00    | ₹ 750.00             |
| 18.3                    | Triple pole and neutral                                                                                                                                                                                                                                                                                                                          | 2        | Each  | 950.00    | ₹ 1,900.00           |
| 19                      | Dismanting of existing light fitting of various wattage / fan (ceiling/wall/exhaust) and keeping the same in AAI store (within 50 Mtr. distance) as per site condition and as directed by E.I.C.                                                                                                                                                 | 250      | Each  | 75.00     | ₹ 18,750.00          |
| 20                      | Dismanting of existing intelligent addressable multi criteria detector/conventional detector/Hooter-cum strobe/Response indicator/isolator/modules etc and keeping the same in AAI store (within 50 Mtr. distance) as per site condition and as directed by E.I.C.                                                                               | 128      | Each  | 55.00     | ₹ 7,040.00           |
| 21                      | ITC of intelligent addressable multi criteria detectors/Hooter-cum strobe/MCPs etc complete as required as per site condition and as directed by E.I.C                                                                                                                                                                                           | 80       | Each  | 75.00     | ₹ 6,000.00           |
| 22                      | ITC of isolator modules as per site condition and as directed by E.I.C                                                                                                                                                                                                                                                                           | 4        | Each  | 75.00     | ₹ 300.00             |
| 23                      | ITC of Response Indicator as per site condition and as directed by E.I.C                                                                                                                                                                                                                                                                         | 15       | Each  | 45.00     | ₹ 675.00             |
| <b>Total Amount Rs.</b> |                                                                                                                                                                                                                                                                                                                                                  |          |       |           | <b>₹ 7,52,965.00</b> |

(Total Amount: Rupees Seven Lakh Fifty Two Thousand Nine Hundred Sixty Five Only )

\* Note: GST will be paid on production of actual tax invoice as per prevailing rates Govt. Of India

  
 Asstt. Gen. Manager (Engg-Elect)  
 AAI, Bagdogra Airport  
 Bagdogra-734421

**Signature Not Verified**

Digitally signed by SUBHASH CHANDRA  
 BASAK  
 Date: 2023.05.23 13:20:26 IST  
 Location: eProcurement System for Central  
 PSUs