



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

No:- AAI/AYO/Jt.GM(E)/DVOR-LLZ_Cable/2022-23/456-463 Date -01.02.2023

सेवा में,
मेसर्स मनीष इलेक्ट्रिकल्स,
कल्पना नगर, 7 नंबर चौराहा के पास,
मोरार, ग्वालियर - 474 006

To,
M/s. Manish Electricals,
Kalpana Nagar, Near 7 No. Chouraha,
Morar, Gwalior - 474 006

विषय:- अयोध्या हवाई अड्डे का विकास.

उपशीर्ष: अयोध्या एयरपोर्ट पर एलटी पावर, लोकलाइजर के लिए ऑप्टिकल फाइबर केबल, ग्लाइड पाथ और डीवीओआर की आपूर्ति एवं बिछाना।

निविदा आईडी: 2022_AAI_137111_1

Name of work: Development of Ayodhya Airport.

SH-Supply and laying of LT Power, Optical Fibre Cable for Localizer, Glide path and DVOR at Ayodhya Airport.

TENDER ID: 2022_AAI_137111_1

संदर्भ :-आपकी ई-निविदा जो दिनांक (वित्तीय बोली) 12.01.2023 को खोली गयी।

Ref:-Your E-tender Financial bid opened on 12.01.2023

महोदय/Sir,

उपरोक्त कार्य के लिए आप की मदद दर निविदा आपके द्वारा उद्धरित राशि रु. 1,46,64,905.00 (केवल एक करोड़ छियालीस लाख चौंसठ हजार नौ सौ पांच रुपये) (जी.एस.टी.छोड़कर) जो कि अनुमानित लागत रु. 1,78,27,748.00 (केवल एक करोड़ अठहत्तर लाख सत्ताईस हजार सात सौ अड़तालीस रुपये) (जी.एस.टी.छोड़कर) से 17.74% कम है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totalling to Rs. 1,46,64,905.00 (Rupees One Crore Forty Six Lakhs Sixty Four Thousand Nine hundred Five only) (Excluding GST) which is 17.74 % (Seventeen point Seven Four percent) below the estimated cost put to tender of Rs.1,78,27,748.00 (Rupees One Crore Seventy Eight Lakhs Twenty Seven Thousand Seven Hundred Forty Eight only) (Excluding GST).

1. आपसे अनुरोध है कि कृपया दिनांक 10.02.2023 तक अयोध्या हवाई अड्डा, अयोध्या पर अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित रहकर संविदा करार पर हस्ताक्षर करने तथा करार की कार्यवाही पूर्ण करने का कष्ट करें। यह संविदा करार 100/- रुपये (सौ रुपये मात्र) के गैर-न्यायिक स्टैम्प पेपर पर निष्पादित किया जायेगा, जिसका खर्च आपके द्वारा वहन किया जायेगा।

You are requested to attend the office of the Jt. General Manager (Engg-Elect), AAI, Ayodhya Airport, Ayodhya by 10.02.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred only) and the cost of the stamp paper shall be borne by you.

01/02/2023

0/c

01.02.23
Jgm(E)



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

2. संविदा करारके पेज नंबर 36 पर धारा नं. 1A के अनुसार आपके निविदा के साथ प्राप्त धरोहर राशि रुपये **3,56,555.00** (केवल तीन लाख छप्पन हजार पांच सौ पचपन रुपये) को जमानत जमा के एक हिस्से के रूप में जमा माना जायेगा। कृपया इस कार्यदिश के जारी होने के तिथि से 10 दिनों के भीतर जमानत जमा के शेष रुपये **11,09,935.00** (केवल ग्यारह लाख नौ हजार नौ सौ पैंतीस रुपये) इस कार्यालय में जमा कराये अन्यथा यह कांटेक्ट डॉक्यूमेंट के पेज नंबर 34 पर धारा नं 1A के अनुसार काटा जायेगा।

The Earnest Money amount of **Rs. 3,56,555.00 (Rupees Three Lakh Fifty Six Thousand Five Hundred Fifty Five Only)** received along with your tender will be treated and converted as part of security deposit as per Clause no. 1A on Page 36 of contract document. Please deposit **Rs. 11,09,935.00 (Rupees Eleven Lakh Nine Thousand Nine Hundred Thirty Five Only)**, towards security deposit within **10 days** towards security deposit from the date of issue of this Work Order failing which, the same will be deducted as per condition of Clause no. 1A at Page 34 of contract document.

3. आपसे अनुरोध है कि संविदा करार के पेज नंबर 64 पर धारा नं. 19 के अनुसार आप ठेका श्रमिक (विनियमन एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करे, साथ ही ठेका श्रमिक (विनियमन एवं उन्मूलन) केन्द्रीय नियमावली 1971, बालश्रम (निषेध एवं विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की हालत का विनियमन) अधिनियम 1996, भवन और अन्यनिर्माण श्रमिक कल्याण उपकरण अधिनियम 1996 तथा केंद्र और राज्य सरकारों के अधिनियमों के प्रावधानों का पूर्णतः अनुपालन करेंगे।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause no. 19 on Page no. 64 of GCC of tender and rules of Central and State Governments.

4. आपसे यह भी अनुरोध है कि आप कर्मचारी भविष्य निधि और विविध प्रावधान अधिनियम, 1952 और ई एस आई अधिनियम, 1948 (सभी संशोधनों सहित) एवं उस के अंतर्गत बनाये गये सभी नियमों एवं प्रावधानों का पूर्णतः अनुपालन करेंगे तथा क्षेत्रीय पीएफ आयुक्त द्वारा आबंटित पीएफ खाता कोड संख्या एवं ई.एस.आई. कॉर्पोरेशन द्वारा आबंटित ई.एस.आई. रजिस्ट्रेशन नंबर भी इस कार्यालय में जमा करायेंगे तथा पी एफ खाता कोड और ईएसआई पंजीकरण काम के वास्तविक समापन तक वैध रहे।

You are also requested to comply with all the provision of the employees Provident Fund & Misc. Provision Act, 1952 and ESI Act, 1948 amended from time to time and rules framed there under and furnish the PF account code number allotted by Regional PF Commissioner and ESI Registration number allotted by ESI Corporation and continue to have valid PF account code and ESI registration number till actual completion of the work.

5. आपसे यह भी अनुरोध है कि आप सहायक महाप्रबंधक (इंजी-वि) अयोध्या हवाई अड्डा, अयोध्या से अविलम्ब संपर्क करें जो कि आपको साइट हस्तांतरित करने की व्यवस्था करेंगे।

You are also directed to contact Asstt. Gen. Manager (Engg-Elect), AAI, Ayodhya Airport, Ayodhya, immediately who will arrange to hand over the site to you.

Asstt. Gen. Manager (Engg-Elect)
01/02/2023

01.02.23
JGM(E)



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

6. कृपया ध्यान दें कि काम करने के लिए अनुमति देने का समय 02 (दो) महीने होगा और इस पत्र के जारी होने के बाद दसवे दिन से माना जायेगा।

Please note that the time allowed for carrying out the work shall be 02 (Two) months and same shall be reckoned from the 10th day after issue of this letter.

7. अनुबंध के संबंध में कोई और पत्राचार सामान्य रूप से जेटी को संबोधित किया जाना चाहिए। महाप्रबंधक (इंजीनियरिंग-इलेक्ट), एएआई, अयोध्या एयरपोर्ट, अयोध्या जो इस कार्य के प्रभारी अभियंता होंगे।

Any further correspondence in connection with the contract should normally be addressed to the Jt. General Manager (Engg-Elect), AAI, Ayodhya Airport, Ayodhya who will be the Engineer-In-charge of this work.

8. कृपया इस पत्र की प्राप्ति-सूचना और स्वीकृति के प्रतीक रूप में इस पत्र की दूसरी प्रति हस्ताक्षर करने के बाद अधोहस्ताक्षरकर्ता को वापस भेज दें।

Please acknowledge the receipt and return the duplicate copy of this letter after signing it to the undersigned as a token of acceptance.

संलग्न :- अनुसूची-अ

[Handwritten signature]
01/02/2013

भवदीय,
[Handwritten signature]
01.02.21
(लाल जीत राम)
(Lal Jeet Ram)

संयुक्त महाप्रबंधक (अभि-वि)
Joint General Manager (E-E)
भा.वि.प्रा., अयोध्या.हवाई अड्डा, अयोध्या
AAI, Ayodhya Airport, Ayodhya

मूलप्रति में नहीं
प्रतिलिपि:

1. कार्यपालक निदेशक (Engg), NR, , भा.वि.प्रा.(उत्तरी क्षेत्र), नई दिल्ली / ED (Engg), NR, CHQ, AAI, New Delhi... For information please.
2. महाप्रबंधक(इंजी), उत्तर.क्षे., भा.वि.प्रा. (उत्तरी क्षेत्र), नई दिल्ली | / GM(Engg), NR, AAI, RHQ, Ops Office, Rangpuri, New Delhi.. For information please.
3. महाप्रबंधक(Finance), उत्तर.क्षे., भा.वि.प्रा. (उत्तरी क्षेत्र), नई दिल्ली | / GM(Finance), NR, AAI, RHQ, Ops Office, Rangpuri, New Delhi.. For information please.
4. संयुक्त महाप्रबंधक (E-C), भा.वि.प्रा., अयोध्या एयरपोर्ट / J JGM(E-C), AAI, Ayodhya Airport.....For information please.
5. Deputy Labour Commissioner, Q4CG+33P, Civil Line, Faizabad, Uttar Pradesh 224001.
6. क्षेत्रीय आयुक्त, उप क्षेत्रीय कार्यालय, ईपीएफओ कार्यालय, यूनाइटेड टॉवर, दूसरी - तीसरी मंजिल, 53, लीडर रोड, इलाहाबाद, उत्तर प्रदेश / Regional Commissioner, Sub Regional Office, EPFO Office, United Tower, 2nd - 3rd Floor, 53, Leader Road, Allahabad, UTTAR PRADESH
7. AGM(E-E), AAI, Ayodhya Airport.....For information and follow-up please.

[Handwritten signature]
01.02.21
(लाल जीत राम)
(Lal Jeet Ram)

संयुक्त महाप्रबंधक (अभि-वि)
Joint General Manager (E-E)
भा.वि.प्रा. अयोध्या.हवाई अड्डा, अयोध्या

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Assistant Gen Manager (Engg-Elect.), Airports Authority of India, Ayodhya.

Name of Work: "Development of Ayodhya Airport.SH:Supply and laying of LT Power ,Optical Fibre Cable for Localizer, Glide path and DVOR at Ayodhya Airport."

Contract No: 2022_AAL 137111

Name of the Bidder/ Bidding Firm / Company

M/s.Manish Electricals

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR	BASIC RATE In Figures To be entered by the Bidder (Excluding GST)	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	9	
1	Supply of 3.5/4 core 1.1 KV grade XLPE insulated, armoured armoured Aluminium Conductor Cable conforming to IS 7098 (Part-I) 1988 amended upto date of sizes 3.5x300 sqmm.	Item No. 1	5000	Mtr	INR	1109.00	5545000.00	INR Fifty Five Lakh Forty Five Thousand Only	
2	Supply of 3.5/4 core 1.1 KV grade XLPE insulated, armoured armoured Aluminium Conductor Cable conforming to IS 7098 (Part-I) 1988 amended upto date of sizes 3.5x95 sqmm.	Item No. 2	3300	Mtr	INR	381.00	1257300.00	INR Twelve Lakh Fifty Seven Thousand Three Hundred Only	
3	Supplying and laying of following size HDPE pipe PE 80/PN6 Grade ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 4984 complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 160 mm Outer dia and thickness as per standard	Item No. 3	5000	Mtr	INR	790.00	3950000.00	INR Thirty Nine Lakh Fifty Thousand Only	

9/2/2023
21.02.23
JHGM(E)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency In INR	BASIC RATE In Figures To be entered by the Bidder (Excluding GST)	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words	TEXT #	
1	2	3	4	5	6	7	8	9		
14	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required. Above 35 sq. mm and upto 95 sq. mm	Item No. 14	50	Mtr	INR	30.00	1500.00	INR One Thousand Five Hundred Only		
15	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray cable tray with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc as required. 300 mm width X 50 mm depth X 1.6 mm thickness	Item No. 15	50	Mtr	INR	1200.00	60000.00	INR Sixty Thousand Only		
16	Supply and making end termination with brass compression gland i/c proper socketing etc. as reqd for 1.1 KV grade XLPE Al. cond.cable of sizes 3.5x300 sqmm	Item No. 16	4	Set	INR	1000.00	4000.00	INR Four Thousand Only		
17	Supply and making end termination with brass compression gland i/c proper socketing etc. as reqd for 1.1 KV grade XLPE Al. cond.cable of sizes 3.5x95 sqmm	Item No. 17	8	Set	INR	450.00	3600.00	INR Three Thousand Six Hundred Only		
18	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X50 cm at the top with a thickness of 10cm including inscription duly engraved as required.	Item No. 18	236	Each	INR	400.00	94400.00	INR Ninety Four Thousand Four Hundred Only		
19	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3½ X 300 sq. mm	Item No. 19	10	Each	INR	4000.00	40000.00	INR Forty Thousand Only		
20	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3½ X 95 sq. mm	Item No. 20	6	Each	INR	3000.00	18000.00	INR Eighteen Thousand Only		
21	Constructing masonry Chamber 60x60x75 cm, inside in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for Power cable and Fibre Cable, with and RCC top slab1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) , i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design :With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	Item No. 21	28	Each	INR	12000.00	336000.00	INR Three Lakh Thirty Six Thousand Only		


 01.02.23
 JGM (E)


 01/02/23

NUMBER #	TEXT #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR	BASIC RATE in Figures To be entered by the Bidder (Excluding GST)	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words		
1	2	3	4	5	6	7	8	9		
23	Design, Fabrication, Supply, Installation, Testing & Commissioning of Indoor LT panel, cubicle type, made out of 2 mm thick CRCA sheet, totally enclosed, IP 42, free standing. Floor mounting, dust and vermin proof, indoor, compartmentalised, suitable for operation on 3 phase and neutral, 415 V, 50 Hz AC system, including internal wiring with suitable size wires/cable, interconnection, duly powder coated painting etc., including supply & installation of following switchgears, metering instruments and accessories in the LT Panel as required:- A) INCOMERS 1) 63A, FP, 35 kA (Ics = 100% of Icu), MCCB with thermal magnetic release, adjustable thermal & adjustable magnetic setting, spreader links, extended rotary mechanism and having over load and short circuit protections - 02 sets 2) 63 A, FP, 16KA Motorized Automatic Transfer Switch with Protection and having Auto-manual Selection Switch suitable for operation on 440V, 50 Hz, AC supply - 01 No. 3) 63 A TPN, 16KA MCCB-01 No 4) Three Phase Surge Protection Device of rating T2/50KA-01 No 5) HRC Fuse-63A B) OUTGOING 1) 64 A, FP, 25 kA (Ics = 100% of Icu) MCCB with thermal magnetic release, adjustable thermal & adjustable magnetic setting, spreader links, rotary handle etc. - 02 Set 2) 40A, TPN MCCB-01 No. 3) 32 A DP RCBO(100MA) - 4 Nos. 4) 20A DP MCCB-01 No 5) Three Phase Surge Protection Device of rating T2/50KA-01 No C) METERING 1) Digital voltmeter (0-500 V) with inbuilt selector switch and protection MCB - 02 sets 2) Digital ammeter (0-100 A), three phase with suitable CTs, selector switch and protection MCB - 02 sets 3) LED type Indication Lamp (R-Y-B) with protection MCB - 02 sets (01 set = 3 lamp) D) Aluminium Bus Bar -100ATPN, 415V, 50Hz AC, 16KA For 1sec	Item No. 23	2	Set	INR	136000.00	272000.00	INR Two Lakh Seventy Two Thousand Only		

07/02/23
Dm/102/23

Amg
01.02.23
Jgm (E)

NUMBER #	TEXT #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency In INR	BASIC RATE In Figures To be entered by the Bidder (Excluding GST)	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	9	
24	Design, Fabrication, Supply, Installation, Testing & Commissioning of Outdoor Feeder Pillar, cubicle type, made out of 2 mm thick CRCA sheet, totally enclosed, IP 55, free standing, Floor mounting, dust and vermin proof, indoor, compartmentalised, suitable for operation on 3 phase and neutral, 415 V, 50 Hz AC system, including internal wiring with suitable size wires/cable, interconnection, duly powder coated painting etc., including supply & installation of following switchgears, metering instruments and accessories in the Feeder Pillar as required:- A) INCOMERS 1) 125A, FP, 35 kA (Ics = 100% of Icu), MCCB with thermal magnetic release, adjustable thermal & adjustable magnetic setting, spreader links, extended rotary mechanism and having over load and short circuit protections - 02 sets B) OUTGOING 1) 100 A, FP, 25 kA (Ics = 100% of Icu) MCCB with thermal magnetic release, adjustable thermal & adjustable magnetic setting, spreader links, rotary handle etc. - 04 Set 2) 63A, FP, 25 kA (Ics = 100% of Icu) MCCB with thermal magnetic release, adjustable thermal & adjustable magnetic setting, spreader links, rotary handle etc. - 02 Set C) METERING 1) Digital voltmeter (0-500 V) with inbuilt selector switch and protection MCB - 02 sets 2) Digital ammeter (0-100 A), three phase with suitable CTs, selector switch and protection MCB - 02 sets 3) LED type indicator Lamp (R-Y-B) with protection MCB - 02 sets (01 set = 3 lamp) D) Bus Coupler with interlocking arrangement of suitable size. E) Aluminium Bus Bar -100ATPN,415V,50Hz AC,16KA For 1sec	Item No. 24	1	Set	INR	140000.00	140000.00	INR One Lakh Forty Thousand Only	


 01/02/23
 5am (E)


 01.02.23
 5am (E)

NUMBER #	TEXT #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR	BASIC RATE In Figures To be entered by the Bidder (Excluding GST)	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words						
1	2	3	4	5	6	7	8	9						
25	Design, Fabrication, Supply, Installation, Testing & Commissioning of Outdoor Feeder Pillar, cubicle type, made out of 2 mm thick CRCA sheet, totally enclosed, IP 55, free standing, Floor mounting, dust and vermin proof, indoor, compartmentalised, suitable for operation on 3 phase and neutral, 415 V, 50 Hz AC system, including internal wiring with suitable size wires/cable, interconnection, duly powder coated painting etc., including supply & installation of following switchgears, metering instruments and accessories in the Feeder Pillar as required:- A) INCOMERS 1) 125A, FP, 35 kA (Ics = 100% of Icu), MCCB with thermal magnetic release, adjustable thermal & adjustable magnetic setting, spreader links, extended rotary mechanism and having over load and short circuit protections - 02 sets B) OUTGOING 1) 63A, FP, 25 kA (Ics = 100% of Icu) MCCB with thermal magnetic release, adjustable thermal & adjustable magnetic setting, spreader links, rotary handle etc. - 02 Set 2) 40 A, FP, 25 kA (Ics = 100% of Icu) MCCB with thermal magnetic release, adjustable thermal & adjustable magnetic setting, spreader links, rotary handle etc. - 04 Set C) METERING 1) Digital voltmeter (0-500 V) with inbuilt selector switch and protection MCB - 02 sets 2) Digital ammeter (0-100 A), three phase with suitable CTs, selector switch and protection MCB - 02 sets 3) LED type Indicator Lamp (R-Y-B) with protection MCB - 02 sets (01 set = 3 lamp) D) Bus Coupler with interlocking arrangement of suitable size. E) Aluminium Bus Bar -125A TPN,415V,50Hz AC,16KA For 1sec	Item No. 25	2	Set	INR	125000.00	250000.00	INR Two Lakh Fifty Thousand Only						
26	Providing and laying of 6 SWG dia G.I. guard Wire in existing HDPE pipe in ground as required.	Item No. 26	6200	Mtr	INR	20.00	124000.00	INR One Lakh Twenty Four Thousand Only						
27	Earthing with GI earth plate 600 mm x 600 mm x 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. With chrcoal/ coke and salt as required.	Item No. 27	6.00	Set	INR	7500.00	45000.00	INR Forty Five Thousand Only						
28	Supplying and laying 25 mm X 5 mm G.I strip at 0.50 metre below ground as strip earth electrode, including connection/ terminating with G.I. nut, bolt, spring, washer etc. as required. (Joining shall be done by overlapping and with 2 sets of G.I. nut bolt & spring washer spaced at 50mm)	Item No. 28	15.00	Mtr	INR	480.00	7200.00	INR Seven Thousand Two Hundred Only						

affinity
01.02.23
- 1000 (1.1)

01.02.23
01/02/23

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency In INR	BASIC RATE In Figures To be entered by the Bidder (Excluding GST)	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words		
1	2	3	4	5	6	7	8	9		
29	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	Item No. 29	15.00	Mtr	INR	690.00	10350.00	INR Ten Thousand Three Hundred & Fifty Only		
30	Providing and fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required.	Item No. 30	15.00	Mtr	INR	600.00	9000.00	INR Nine Thousand Only		
Total In Figures										
Quoted Rate in Words										
INR One Crore Forty Six Lakh Sixty Four Thousand Nine Hundred & Five Only										

2023/06/27 12:24:02
ANILDAS BEKAL

Signature Not Verified

Digitally signed by ANILDAS BEKAL
Date: 2023.06.27 12:24:02 IST
Location: eProcurement System for Central PSUs

Aug 01.02.2023
Jt GM (E) AAI
AYODHYA -