

संदर्भ सं.: भा.वि.प्रा./ भुवनेश्वर/ उप महाप्रबंधक (अभि - विद्युत)/WO-51/2022-23/ 1229-38

दिनांक: 23.02.2023.

सेवा में/To,

स्पीडपोस्ट द्वारा / By Speed Post

e-mail:balajiengineering.rajesh@gmail.com

मेसर्स बालाजी इंजीनियरिंग

M/s Balaji Engineering

फ्लैट नंबर 18, तीसरी मंजिल, क्वीन कैसल,

Flat No. 18, 3rd Floor, Queen's Castle,

7 वीं स्ट्रीट लक्ष्मी नगर, नंगनल्लौर

7th Street Lakshmi Nagar, , Nanganallaur,

चेन्नई -600061/ Chennai - 600061

कार्य का नाम रे -लोकेशन ऑफ़ सीसीआर एंड रे -रूटिंग ऑफ़ जीएलएफ केबल्स एट न्यू सीसीआर पावर हाउस
एट बि.पि. आई. एयरपोर्ट, भुवनेश्वर ।

Name of Work: Re-Location of CCR and Re-Routing of GLF Cables at New CCR Power House
at B.P.I. Airport, Bhubaneswar.

महोदय/Dear Sir(s),

Ref: Your e-Tender opened dated 08.02.2023 for Tender ID No. 2022_AAI_137705_1.

1. उपरोक्त कार्य के लिए आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आप द्वारा उद्धरित मद दर जिसकी कुल राशि रु. 3,09,98,950.00 (तीन करोड़ नौ लाख अठानवे हजार नौ सो पचास रुपया मात्र) जीएसटी को छोड़कर जो कि निविदा की अनुमानित लागत रु. 3,75,53,418.00. से 17.45% कम है, स्वीकृत की जाती है।

Your e-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at item rates quoted by you totaling to Rs.3,09,98,950.00 (Rupees Three Crore Nine Lakhs Ninety Eight Thousand Nine Hundred and Fifty Only) Excluding GST which is 17.45% (Seventeen Point Four Five Percent) below the Justified cost of Rs.3,75,53,418.00.

2. उप महाप्रबंधक (अभि-विद्युत), भारतीय विमानपत्तन प्राधिकरण, बी.प.अ. हवाई अड्डा, भुवनेश्वर इस कार्य के इंजीनियरिंग प्रभारी होंगे। आपसे अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु दिनांक 06.03.2023 के अंदर उप महाप्रबंधक (अभि- विद्युत), भारतीय विमानपत्तन प्राधिकरण, बी.प.अ. हवाई अड्डा, भुवनेश्वर के कार्यालय में उपस्थित हों। संविदा करार रु 100/- (सौ रुपये मात्र) के न्यायिकेतर (नॉन ज्युडिशियल) स्टाम्प पेपर पर बनाया जाएगा और स्टाम्प पेपर की लागत आपको वहन करनी होगी।

Dy. General Manager Engg. (E), AAI, B.P. International Airport Bhubaneswar, shall be the Engineer-in-Charge of the work. You are requested to attend the office of the Dy. General Manager Engg. (E), AAI, B.P. International Airport, Bhubaneswar by 06.03.2023 to sign and complete the agreement.

The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100.00 (Rupees One Hundred only) and the cost of stamp paper shall be borne by you.

.Cont-2...

कार्यालय निदेशक विमानपत्तन, बिजु पटनायक अंतरराष्ट्रीय एयरपोर्ट, भुवनेश्वर -751020, दूरभाष-0674-2596300, फैक्स- 0674-2596317/302
Office of the Airport Director, Biju Patnaik International Airport, Bhubaneswar-751020, Phone: 0674-2596300, Fax: 0674-2596317/302

टी. के. बाला / T. K. BALA

उप महाप्रबंधक (अभि-विद्युत) / DGM (Engg.-Elect.)

भा.वि.प्रा./बि.प.अ. हवाई अड्डा, भुवनेश्वर-751020

AAI, B.P.I. Airport, Bhubaneswar-751020



Page-2

3. कृपया इस पत्र के जारी होने के 10 दिन के भीतर सुरक्षा जमा के लिए रु. **30,99,895.00** (तीस लाख नित्यानवे हजार आठ सो पचानवे रुपया मात्र) जमा करवा दें, ऐसा नहीं करने पर उक्त रकम संविदा दस्तावेज के पृष्ठ 16 पर दी गई शर्त 1A के अनुसार आपके रनिंग बिल से काट ली जाएगी।

Please deposit Rs. **30,99,895.00** (Rupees Thirty Lakhs Ninety Nine Thousand Eight Hundred and Ninety Five Only) towards Security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted as per conditions of Clause No - 1A page 16 of Clauses of the contract document.

4. आपसे अनुरोध है कि संविदा श्रमिक (विनियमन एवं समापन) अधिनियम 1970 और संविदा श्रमिक (विनियमन एवं समापन) केन्द्रीय नियमावली 1971 बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण वर्कर्स (रोजगार और सेवा की शर्त का विनियमन) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण अपकर अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ संख्या 68 पर धारा 19 में जीसीसी आफ निविदा निर्दिष्ट है तथा केन्द्रीय और राज्य सरकारों के नियमों का अनुपालन करें।

You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules-1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare cess Act 1996 as specified in Clause-19 On Page No.68 of GCC of Tender and rules of Central and State Governments.

5. आपको निदेश दिए जाते हैं कि आप वरिष्ठ प्रबंधक (अभी.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, बी.प.अ. हवाईअड्डा से तत्काल सम्पर्क करें जो कि आपको कार्यस्थल हस्तान्तर करने की व्यवस्था करेंगे।

You are also directed to contact the Sr.Manager Engg (E), AAI, B.P. International Airport, Bhubaneswar immediately, who will arrange to handover the site to you.

6. पया यह नोट कर लें कि काम पूरा करने का समय **03** (तीन) महीने है, जिसे इस पत्र के जारी होने की तारीख से 10 दिन बाद गिना जाएगा।

Please note that the time allowed for carrying out the work shall be **Three (03) Months** and same shall be reckoned from 10th day after the date of issue of this letter.

Cont...3

 23/02/2023

Page-3

7. कृपया ध्यान दें कि त्रुटि की देयता अवधि कार्य पूरा होने की तारीख से बारह महीने की होगी।

Please note that the defect liability period shall be **Twelve Months** from the date of completion of work.

8. संविदा के संबंध में आगे किया जाने वाला पत्राचार सामान्यतः प्रभारी इंजीनियर से किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer - in - Charge.

9. कृपया इस पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप में विधिवत हस्ताक्षर करके हमें वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to undersigned as a token of acceptance.

धन्यवाद / Thanking you,

भवदीय / Yours Faithfully,

उप महाप्रबंधक (अभी. - विद्युत)/Dy.GM. Engg. (Elect.)

भा.वि.प्रा., बी.प.अ. हवाईअड्डा, भुवनेश्वर / AAI, B.P. I. Airport, Bhubaneswar

कृते अध्यक्ष, भाविप्रा, नई दिल्ली

संलग्न / Encl: 1. शिड्यूल ऑफ क्वान्टिटीज / Schedule of quantities.

Copy to:-

N.O.O. (External) :

1. Labour Commissioner (Central), Kendriya Shrama Sadan, Plot no. N-7/6 & 7, IRC Village, Behind ISCON Temple, Nayapalli, Bhubaneswar - 15, Odisha.
2. Regional Provident Fund Commissioner, Vabisanidhi Bhawan, Janpath, Unit IX, Bhubaneswar, Odisha.
3. The Regional Commissioner, Employee State Insurance Corporation, Panchadeep Bhawan, Janpath, Unit IX, Bhubaneswar, Odisha.

आंतरिक / Internal :

1. महाप्रबंधक (अभि. - विद्युत) भा.वि.प्रा., एनएससीबीआई. हवाई अड्डा, कोलकाता
The General Manager (Engg. - Elect), AAI, NSCBI Airport, Kolkata
2. विमानपत्तन निदेशक, भा.वि.प्रा., बी.प.अ. हवाईअड्डा, भुवनेश्वर।
The Airport Director, AAI, B.P. International Airport, Bhubaneswar.
3. संयुक्त महाप्रबंधक (वित्त व लेखा), भा.वि.प्रा., बी.प.अ. हवाईअड्डा, भुवनेश्वर।
The Jt. General Manager (F&A), AAI, B.P. International Airport, Bhubaneswar
4. वरिष्ठ प्रबंधक (अभि. - विद्युत) भा.वि.प्रा., बी.प.अ. हवाई अड्डा, भुवनेश्वर।
The Sr. Manager (Engg. - Elect), AAI, B.P. International Airport, Bhubaneswar
5. अनुबन्ध फाइल / Agreement Copy.
6. कार्य फाइल / The Works File.

उप महाप्रबंधक (अभि. - विद्युत)/Dy.GM. Engg. (Elect.)

भा.वि.प्रा., बी.प.अ. हवाईअड्डा, भुवनेश्वर / AAI, B.P. I. Airport, Bhubaneswar
कृते अध्यक्ष, भाविप्रा, नई दिल्ली

verified
by
SME

AIRPORTS AUTHORITY OF INDIA
ELECTRICAL ENGINEERING WING
B.P.I AIRPORT, BHUBANESWAR

Schedule of Quantity

Name of work:- Re-Location of CCR & Re-Routing of GLF Cables at New CCR Power House at B.P.I. Airport, Bhubaneswar.

Item No	Description of Items	Unit	Qty	Rate	Amount
1	2	3	4	5	6
1	Supply of following sizes 5 KV grade PVC insulated & PVC sheathed, antitermite & anti-rodent, multi-stranded copper conductor double core (2C) Airfield lighting cable confirming to IS 1554 (Part-II) with up to date amendments and confirming to tenders technical specifications, terms & conditions etc. complete as required.				
a	2C X 16 Sqmm	Meter	7060	390.00	2753400.00
b	2C X 6 sqmm	Meter	15270	220.00	3359400.00
2	Supply of 16 Sqmm plug & receptacle of type I, class B connector & suitable field attachment with 5 KV grade XLPE insulated PE sheathed single core copper conductor cable as specified in specification & as required.	Set	12	450.00	5400.00
3	Supply of 6 Sqmm plug & receptacle of type I, class B connector & suitable field attachment with 5 KV grade XLPE insulated PE sheathed single core copper conductor cable as specified in specification & as required.	Set	15	450.00	6750.00
4	Supplying of 1100V grade multicore stranded Aluminium Conductor XLPE insulated core laid up, extruded inner sheath of PVC, galvanised steel strip armoured & overall PVC sheathed armoured cables confirming to IS-7098 (PT-I) with upto date amendments of followigs sizes:				
a	3½ X 95 sq. mm	Meter	190	450.00	85500.00
b	3½ X 35 sq. mm	Meter	4380	180.00	788400.00
c	3½ X 185 sq. mm	Meter	6730	800.00	5384000.00
5	Providing and fixing of 2.5 sq. mm copper conductor, multi core, extruded PVC inner sheath insulated, PVC sheathed, armoured control cable of 1.1 kV grade confirming to IS 1554 (part-I) with up to date amendments and confirming to tenders technical specifications, terms & conditions etc. complete as required with no. of cores as mentioned below:				
a	10 core control cable	Meter	4960	280.00	1388800.00
b	100 core control cable	Meter	2010	2500.00	5025000.00
6	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.		10		
a	3½ X 95 sq. mm	Set	10	750.00	7500.00
b	3½ X 35 sq. mm	Set	28	450.00	12600.00
c	3½ X 185 sq. mm	Set	6	900.00	5400.00
7	Dismantling, shifting , re-Installation, testing and commissioing of existing CCR 4 Kw/ 7.5 Kw / 20 KW /30 CCRs from etc existing location to new location complete including grouting as per site requirement and as per direction of EIC etc complete as required.	Job	18	5000.00	90000.00


टी. के. बाल / **T. K. BALA**
 उप महाप्रबंधक (अभि. विद्युत) / DGM (Engg.-Elect.)
 आदिप्रा/वि.प.अ.हवाईअड्डा, भुवनेश्वर-751020
 AA1, B.P.I. Airport, Bhubaneswar-751020

Item No	Description of Items	Unit	Qty	Rate	Amount
1	2	3	4	5	6
8	Dismantling shifting re-Installation, testing and commissioning of capacity 160 kva UPS with bank for runway light from etc existing location to new location complete including grouting as per site requirement and as per direction of EIC etc complete as required.	Job	2	10000.00	20000.00
9	Supply of C.I isolating transformer housing box, water tight round type, metal container of outside size 330 mm height 450 mm made of 10 mm thick cast iron moulding all round, except the top surface, which is 15 mm thick, cast iron moulding suitable to receive a light fitting base plate on the top and underground housing associated with transformer power cable and having a clear hole at three side surface centre 75 mm above bottom surface suitable to receive of 63 mm dia (outer dia) HDPE/G. I. pipe and including check nuts as required and another hole at 175 mm from the bottom of the CI box to receive one no. 15 mm dia, "B" class, GI pipe and check nut as required. The box should have two SS earth bolts of M10 x 30 mm tapped inside near the hole away from the hole centre and having a drain hole at the bottom suitably tapped to receive 15 mm dia, "B" class GI pipe and having clear opening of 220 mm at the top surface and 6 nos. M10 tapped hole at the hole centre 260 mm to receive fitting base plate and bolts with blanking plate of MS of Min. thickness of 10mm complete as required as per the drawings.				
a	Double Hole Type (For feeder cable)	Each	5	5000.00	25000.00
10	Design, Supply, Installation, Testing & Commissioning of Remote control desk with mimic display for visual lighting aids in Control tower desk made out of 14SWG MS sheet suitable for following ground lighting circuits i/c brilliancy control switches and other installation, on/off switches and indication lamps i/c terminal junction box (suitable for 102 cores of 1.5 sq. mm copper cable), supply & making end terminations of remote control cables, etc. and confirming to tenders technical specifications, terms & conditions etc. complete as required. & as per direction of Engineer-in-charge. a. Rwy Ckt-1 & 2 - (30 kW CCR) spare. - 02 nos +01 b. Approach 14 (Cat -I apprch) - (30 KW) - 02 no +01 spare. c. Approach 32- (7.5 KW) - 01 no +01 spare. d. Apron edge lights & Taxi-A,B,C,D, E, F, Isolation Bay, PTT Ckt-1 & 2, (4 KW CCR) - 09 no.+04 spare e. PAPI- (4 KW) - 02 no. f. Beacons Lights - 01 nos g. Landing H - 01 no. h. WDI (Lights) - 03+ 01 Spare i. AFL masts lights - 11 nos.+ 4 Spare	Job	1	150000.00	150000.00
11	Supply, Installation, Testing & Commissioning of mimic back up indication board for visual lighting aids in CCR hall, connection of control cables etc. i/c terminal junction box (suitable for 102 cores of 1.5 sq. mm copper cable), and confirming to tenders technical specifications, terms & conditions etc. complete as required.	Job	1	125000.00	125000.00


 टी. के. भाटिया / T. K. BHATIA
 उप महाप्रबंधक (अग्नि विद्युत) / DGM (Engg.-Elect.)
 भाविप्रा/वि.प.अ.हवाईअड्डा, भुवनेश्वर-751020
 A.N.I.B.P.I.Airport, Bhubaneswar-751020

Item No	Description of Items	Unit	Qty	Rate	Amount
1	2	3	4	5	6
12	Design, Fabrication, Supply, Installation, Testing and Commissioning of online UPS system of 1 x 160KVA, 3ph, 50Hz having 100% unbalanced load with 30 minutes power backup on full load working on floating system along with necessary bypass system for UPS for GLF system. UPS should be dust and vermin proof duly painted and with ventilation ducts, floor mounted, forced air cooling, with provision of Isolation Transformer at output including supply and installation of VRLA maintenance free batteries suitable for 30 minutes backup time for UPS on full load and capable of giving desired output of 3 phase 415 V 50 Hz suitable to operate as per existing Runway lighting system of Bhubaneswar Airport with all controls and surge protection system conforming to standards IEC 62040-1, IEC 62040-2, IEC 62040-3 and IS: 16242-1 and necessary upto date amendments etc. and as per tender condition and as complete as required as per site as directed by Engineer in Charge.	Job	1	950000.00	950000.00
13	Installation of transformer housing boxes with a base concrete of 1:3:6 of size 630 x 630 x 100 mm thick all round concrete of 1:2:4, 150 mm thick, the top sloped with 1:2:4 cement including providing and fixing 250 mm long 15 mm dia "B" Class GI pipe with check nut for drainage of water including excavation of side shoulder and refilling etc complete as required.	Job	5	2500.00	12500.00
14	Constructing brick masonry chamber of size 1200x1200x1200mm of size in cement mortar 1:4 (1 cement :4 coarse sand) inside cement plaster 15 mm thick with cement mortar 1:3 (1 cement: 3 Coarse sand) finished with floating coat of neat cement foundation concrete 1:3:6(1 cement: 3 coarse sand:6 graded stone aggregate 40 mm nominal size) all complete as per standard design with cover of 10 mm thick MS chequered plate in two piece with 12 mm rod handle in order to easy handling and as per Tender specifications and as per directions of Engineer-In-charge.	Each	27	18000.00	486000.00
15	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required.				
a	upto 35 Sqmm	Meter	3640	20.00	72800.00
b	Above 95 sq. mm and upto 185 sq. mm	Meter	6520	30.00	195600.00
16	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing masonry open duct as required.				
a	upto 35 Sqmm	Meter	40	25.00	1000.00
b	Above 95 sq. mm and upto 185 sq. mm	Meter	60	35.00	2100.00
17	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray / wall surface as required.				
a	Upto 35 sq. mm	Meter	700	50.00	35000.00
b	Above 35 sq. mm and upto 95 sq. mm	Meter	190	70.00	13300.00
c	Above 95 sq. mm and upto 185 sq. mm	Meter	150	75.00	11250.00
18	Laying of one no. PVC insulated & PVC sheathed AFL cable of 5 KV grade size upto 16 sqmm in the existing RCC/ METAL/HDPE pipe as required.	Meter	21350	20.00	427000.00


 Dr. K. K. Bala / Dr. K. K. Bala
 उप महाप्रबंधक (अभि. विभाग) / DGM (Engg.-Elect.)
 भाविप्रा/वि.प.अ.एवार्डअड्डा, भुवनेश्वर-751020
 AAI, B.P.I. Airport, Bhubaneswar-751020

Item No	Description of Items	Unit	Qty	Rate	Amount
1	2	3	4	5	6
19	Laying of one number PVC insulated and PVC sheathed / XLPE power/control/AFL cable of upto 5KV grade size upto 16 sqmm in the existing masonry open duct as required.	Meter	280	25.00	7000.00
20	Laying of one number PVC insulated and PVC sheathed / XLPE power/control/AFL cable of upto 5KV grade size upto 16 sqmm on wall surface / Cable Tray as required.	Meter	700	25.00	17500.00
21	Making connections of 5 kV grade, 6 & 16 sq. mm copper conductor AFL cables with ESNA connector i/c crimping & fixing, applying HT tape complete as required.	Jobs	27	250.00	6750.00
22	Extra for Excavation of the cable trenches in hard rock instead of soft soil not exceeding 1.5 metres in width, and lift upto 1.5 metres, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 metres.	Cum	70	500.00	35000.00
23	Supplying and laying of following size HDPE pipe ISI marked PE 100 PN-6 along with all accessories like socket, bend, couplers etc. conforming to IS 4984:2016 complete with fitting and cutting, jointing etc. direct in ground (50 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 90 mm dia (OD-90mm & ID-75 mm)	Meter	21790	250.00	5447500.00
24	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (50 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. , complete as required. 40 mm dia (OD-40 mm & ID-32 mm nominal).	Meter	140	150.00	21000.00
25	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. in the existing trench, complete as required. 40 mm dia (OD-40 mm & ID-32 mm nominal).	Meter	1700	65.00	110500.00
26	Supply and Laying of HDPE pipe of 125 mm dia , PE 100, PN 6 by along with all accessories like socket, bend, couplers etc. conforming to IS 4984:2016 complete with fitting and cutting, jointing etc. direct in ground (50 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. complete as required.	Meter	3820	350.00	1337000.00
27	Supply and Laying of HDPE pipe of 125 mm dia , PE 100, PN 6 conforming to IS 4984:2016 by HDD method including preparing & setting up plant & machinery including jointing reaming and pulling of HDPE pipe 1.2 mtr below the ground as per technical specification and site condition etc as required as per direction of E-I-C.	Meter	2500	800.00	2000000.00
28	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	Set	25	5000.00	125000.00
29	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	Mtr.	150	450.00	67500.00


Dr. K. BALA
 उप महाप्रबंधक (अभियंता) / DGM (Engg.-Elect.)
 भाविप्रा/वि.प.अं.रुवाईअड्डा, भुवनेश्वर-751020
 AAI,B.P.I.Airport, Bhubaneswar-751020

Item No	Description of Items	Unit	Qty	Rate	Amount
1	2	3	4	5	6
30	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	Meter	150	150.00	22500.00
31	Supplying & laying of 6SWG dia GI wire along with 5 Kv grade GLF cable for loop earthing etc. as required.	Meter	200	30.00	6000.00
32	Cutting of paved surface (flexible/ rigid) and laying of 50 mm dia GI pipe at a depth of atleast 200 mm including making the surface good with cement concrete (1:2:4) complete as required.	Meter	200	600.00	120000.00
33	Route marker: Providing and fixing of round shape frangible type route marker made up of PVC of 100 cm height fixed to suitable PCC foundation (Min size 15 X 15 X 10 cm cubic block) and painted with florescent colour (Red/White). Note: GLF Cable /LT Cable/Control Cable should be marked on Pipe with florescent colour.	Each	135	500.00	67500.00
34	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray (galvanisation thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts etc as required				
a	300 mm width X 50 mm depth X 1.6 mm thick	Meter	120	900.00	108000.00
b	150 mm width X 50 mm depth X 1.6 mm thick	Meter	120	450.00	54000.00
35	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray "bends" (galvanisation not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts etc as required				
a	300 mm width X 50 mm depth X 1.6 mm thick	Each	5	1000.00	5000.00
b	150 mm width X 50 mm depth X 1.6 mm thick	Each	5	500.00	2500.00

Total Rs. 30998950.00
Say 30998950.00

Note

1. GST Extra Applicable
2. AAI GSTIN:-21AAACA6412D1ZK

(Rupees Three Crore Nine Lakhs Ninety Eight Thousand Nine Hundred & Fifty Only)


23/02/2023
Dy. General Manager Engg(E)
AAI, B.P.I. Airport Bhubaneswar

Signature Not Verified

Digitally signed by RUDRA PRASAD
ACHARYA
Date: 2023.08.09 00:51:14 IST
Location: eProcurement System for Central
PSUs