



भारतीय विमानपत्तन प्राधिकरण,
Airports Authority of India
सिविल एन्क्लेव, बरेली-243122 (उ. प्र.)
Civil Enclave, Bareilly-243122, (U.P.)

संख्या:- भाविप्रा/बीएलवाई/ए0जी0एमअभि.(वि)/का0आ0-02/हाईमास्ट/2022-23/
Ref:- AAI/BLY/AGM(E-E)/W.O-02/ High Mast / 2022-23/681 - 686

दिनांक :- 28.02.2023

Date :- 28.02.2023

(By Speed post/ E mail)

सेवा में /To,

मेसर्स जेनेसिस
43ए जयंतीपुर, सुलेमसराय, धूममनगंज
प्रयाराज उत्तर प्रदेश-211011

M/s. Genesis
43A Jayantipur, Sulem sarai,
Dhoomanganj, Prayagraj,
Uttar Pradesh-211011

कार्य का नाम :- वाइडनिंग एण्ड स्ट्रेंथनिंग ऑफ एगजिसटिंग एपरन एण्ड टेक्सी एट बरेली एयरपोर्ट ।

उपशीर्ष :- एस आई टी सी ऑफ़ एग्रन फ्लड लाइट मास्ट ।

Name of Work: - Widening and Strengthening of Apron and Taxi at Bareilly Airport.

SH: SITC of Apron Flood Light Mast.

संदर्भ :- 1) आपका टेंडर आई0डी0 (2022_AAI_137855_1) खोला गया दिनांक - 20.01.2023

Your tender ID. - (2022_AAI_137855_1) opened on dated - 20.01.2023

महोदय / Sir,

1. उपरोक्त कार्य हेतु आपका आफर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताये गये मद मूल्यों पर आपका ऑफर कुल रुपये **16,57,000/-** (रुपये सोलह लाख सत्तावन हजार केवल) (जी0एस0टी0 अतिरिक्त) है। जोकि टैण्डर की अनुमानित/न्यायसंगत राशि रू0 **21,31,560/-** से **22.26** प्रतिशत कम है।

Your offer for the work mentioned above work is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs./ **16,57,000-** (Rupees. sixteen lakh fifty seven Thousand only) (GST Extra). Which is **22.26%** below the justified cost put to tender of Rs. **21,31,560/-**

2. सहा0 महा0 प्रबन्धक (इंजी-विद्युत) भाविप्रा, सिविल एयरपोर्ट, बरेली कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप करारनामों पर हस्ताक्षर करने के लिए दिनांक 15.03.2023 तक अधोहस्ताक्षरकर्ता के कार्यालय में उपस्थित हो तथा करारनामों को पूरा करें। ठेके का करारनामा 100/-रुपये के नोनज्यूडिशियल स्टाम्प पेपर पर निष्पादित किया जाएगा, तथा स्टाम्प पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Assist. General Manager Engg. (Elect.), AAI, Civil Airport, Bareilly- 243122, shall be the Engineer in charge of the work. You are requested to attend the office of undersigned by 15.03.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees Hundred only) and the cost of the stamp paper shall be borne by you.

3. आपके इ-टेंडर के साथ प्राप्त धरोहर राशि रुपये 42,931/- ठेके के सामान्य भातों पर दी गयी भात 1(A) के अनुसार जमानत राशि में परिवर्तित कर दी जायेगी। कृपया इस पत्र के जारी होने के 15 दिनों के जारी/Contd...

28.2.23 AAI (E-E)

भीतर सिक्क्यूरिटी डिपोजिट के लिए रुपये 1,65,700/- (रु. एक लाख पैंसेठ हजार सात सौ मात्र) जमा कर दे, अन्यथा ठेके के करारनामे में दी भारत के अनुसार इतनी राशि आपके रनिंग बिलों से काट ली जाएगी।

The earnest money amount of Rs. 42,931/- received along with your e-tender will be treated and converted as part of Security Deposit as per GCC Clause 1(A) of the contract document. Please deposit Rs 1,65,700/- (Rupees one Lakh Sixty five Thousand seven Hundred Only) towards security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted from your running bills as per condition of the contract.

4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केन्द्रीय नियम (रेगुलेशन एवं अबोलिशन) एवं न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अब तक के संशोधन के साथ अनुपालन करें।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments with upto date amendments.

5. आपको निर्देश दिया जाता है कि आप तुरंत प्रबन्धक (इंजी-विधुत), भाविप्रा, सिविल एन्क्लेव, बरेली से मिलें वह आपको साईट सौपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का समय 75 दिन है जोकि दिनांक 06.03.2023 से गिना जाएगा।

You are also directed to contact Manager Engg. (E), AAI, Civil Enclave, Bareilly immediately who will arrange to hand over the site to you. Please note that the time allowed for carrying out the work shall be 75 days which shall be reckoned from dated 06.03.2023.

6. इस ठेके के संबंध में आगे का कोई भी पत्राचार सहा0 महाप्रबन्धक (इंजी-विधुत), भाविप्रा, सिविल एयरपोर्ट, बरेली, 243122 उत्तर प्रदेश के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the Asstt. Gen. Manager Engg. (E), AAI, Civil Airport, Bareilly, - 243122, U.P.

7. उक्त कार्य का त्रुटि दायित्व अवधि 12 (बारह) महीने होगी।


The defects liability period of the contract is 12 (Twelve) months.

8. कृपया पावती भेंजे।

Please acknowledge the receipts

नोट : हिंदी या अंग्रेजी संस्करण में अंतर या अस्पष्टता के मामले में अंग्रेजी संस्करण मान्य होगा

Note : In case of difference or ambiguity in Hindi or English Version, the English version will Prevail.


18.2.2023

भवदीय / Yours Faithfully,

सहायक महा प्रबन्धक (अभि.-विधुत),

Assistant General Manager Engg.(Elect.),

कृते तथा ओर से अध्यक्ष,

For and on behalf of Chairman,

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India.

Civil Airport, Bareilly -243122

संलग्न / Enclosed - शिडयूल ऑफ क्वान्टिटी (2 पृष्ठ) / S.O.Q. Schedule. "A" (2 Pages).

जारी / Contd...

SCHEDULE OF QUANTITY

Schedule "A"

Name of Work : Widening and Strengthening of the Apron and Taxi Track at Bareilly Airport. SH:- SITC of Apron Flood Light Mast

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Amount
1.00	Design, SITC of 20 mtr. High mast , GI Polygon continuously tapered in one /two sections suitable for wind speed as per applicable IS 875 Parts- 3, with raising lowering system comprising , head frame, luminaries carriage suitable to install min 10 luminaries in Asymmetrical arrangement as per lighting Design, double drum winch, 6mm diameter SS wire rope , trailing Cu. cable suitable current carrying capacity between top carriage and the base terminal (inside mast) including supplying & laying of required length of 1.1 KV grade of suitable size XLPE insulated PVC sheathed armoured Aluminium conductor power cable between Feeder Pillar of High Mast and Base Terminal in DWC HDPE pipe of suitable size alongwith supplying & making end termination with heavy duty Brass compression gland , with connector, intergal power tool motor, manual handle ,lightning Arrestor , junction box ,weather proof and vandal resistant door flush with the exterior surface containing a terminal plate thick backlite sheet with 32 Amp heavy duty connector for loop in loop out cable terminations etc. complete as required including of followings..... i) Supply of LED floodlight type 400 W LED (BAJAJ MAKE :PRAZE WBJFL 400 W LED or equivalent as per list of approved make) (Clamps, bolts etc as required to mount on lantern carriage to hold fittings) -min 7 Nos. ii) Supply of LED type double dome aviation obstruction light -01 Nos iii) Supply of outdoor stand mounted feeder pillar, Installation of the feeder pillar by grouting the stand in concrete, dust and vermin proof with 2 Nos. (1No for Incoming supply and 1 No for spare) 32A TPN MCB incomer , single dial time switch ,22A TP contactor for the automatic switching of luminaries, power tool control with suitable contactors and raise and lower push button, terminals for incomer 35 sqmm and outgoing 16 & 2.5 sq.mm -01 set	2.00	Job	405000.00	810000.00
2.00	Design of foundation, including excavation in soil and RCC (M 25 grade) , bolts, nuts, washers, anchor plates ,rigid flange plate and common template as per OEM recommendations etc complete as required for 20 mtr High mast, and considering safe soil bearing capacity 10T/sqmt at 2 mtr depth.	2.00	Job	99000.00	198000.00
3.00	SITC of Integral LED flood light luminaries 400 W, its control Driver/Accessories, Clamps, bolts etc as required to mount on Existing 20 Mtr High Mast, including all minor works i.e. counter weight, raising and lowering luminaries carriage etc complete as required. (BAJAJ MAKE :PRAZE WBJFL 400 W LED or equivalent as per list of approved make)	8.00	Each	18000.00	144000.00
4.00	Supply of following size of 1.1 KV grade, ARMOURED,XLPE insulated PVC sheathed Aluminium conductor cable conforming to IS: 7098 part -I amended upto date (i).4CX 25 sq mm	500.00	Mtr	260.00	130000.00

(V2)

28.2.2023
AGM (EE)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Rate	Amount
5.00	Laying of one number PVC insulated and PVC sheathed/ XLPE 4 core aluminium conductor cable of 1.1 KV grade of size not exceeding 35 Sq. mm in the existing RCC/HUME/METAL/HDPE Pipe as required.	280.00	Mtr	40.00	11200.00
6.00	Supply and laying 80 mm dia medium class GI pipe direct in ground including excavation existing pavement size of 75cm (depth), and refilling etc as required.	40.00	Mtr	700.00	28000.00
7.00	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. (i). 4C X 25 sq. mm	4.00	Set	350.00	1400.00
8.00	Supply and laying of 63 mm outer Dia ISI marked Double Walled Corrugated high density polyethylene pipe (DWC-HDPE) having corrugation on the outer wall conforming to IS 14930 Part II complete with necessary fittings for jointing for protection of 1.1 KV grade under ground cable including excavation in hard soil and refilling etc. including removing Pavers Block, PCC(position cement concrete) 1:5:10(1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and refixing Pavers Block complete as required. (i). 63 mm dia (OD-63 mm & ID-51 mm nominal)	40.00	Mtr	510.00	20400.00
9.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63 mm dia (OD-63 mm & ID-51 mm nominal)	270.00	Mtr	320.00	86400.00
10.00	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	2.00	Set	9900.00	19800.00
11.00	Providing and fixing 25mm x 5mm GI strip on surface or in recess for connections etc as required.	52.00	Mtr	150.00	7800.00
12.00	Supply of 5 kv Type C without metallic screen, Cross-linked polyethylene 6 Sqmm, unshielded round stranded, bare copper class 2 with Polyethylene (PE) outer sheath cable as required as per the technical specification. UN-SHIELDED, PRIMARY CABLE 1CX 6SQ MM	1000.00	Mtr	200.00	200000.00
(Rupees Sixteen Lakhs Fifty Seven Thousand Only)				Total	1657000.00

Signature Not Verified

Digitally signed by RAVINDRA KUMAR
Date: 2024.04.12 16:16:00 IST
Location: eProcurement System for Central PSUs

Cy
28.2.2023
Assistant General Manager (Engg.-E)
AAI, CE Bareilly

(2/2)