



भारतीय विमानपत्तन प्राधिकरण

गया विमानपत्तन, गया - 823004.

AIRPORTS AUTHORITY OF INDIA

Gaya Airport, Gaya-823004.



आई.एस.ओ.9001-2008 प्रमाणित

दुतगामीडाक Speed Post

संदर्भ सं. भा.वि.प्रा./गया/स.महा.प्र. (अभि0-सि0)/वाच टावर /का.आ.-06/2022.23 /2513-24 दिनांक : 24/02/2023

Ref. No: - AAI/GAYA/ AGM (E-C)/Watch Tower/W.O.-06/2022-23/

Date: 24.02.2023

सेवा में/To,

समशरा कंस्ट्रक्शन प्राइवेट लिमिटेड,

SAMASHRA CONSTRUCTION PRIVATE LIMITED,

हाउस नं.-232, देवी मंडप रोड,

H.No.-232, Devi Mandap Road,

हेसाल रांची, झारखंड-834005

Hesal Ranchi, Jharkhand-834005

विषय :- गया एयरपोर्ट गया में सीआईएसएफ के लिए ऑपरेशनल एरिया में दो वाच टावर का निर्माण एवं डबल गेट का प्रावधान।

Subject: - "Construction of 2 No. watch tower and provision of double gate in Operational area for CISF at Gaya Airport, Gaya"

संदर्भ : ई-निविदा खुलने की तिथि :- 03.02.2023

Ref: Your e-tender opening date: - 03.02.2023

महोदय, /Sir,

1. उपर्युक्त कार्य के लिए आपके द्वारा दी गई **रु0 43,09,684.46** जो कि कार्य की अनुमानित लागत **रु0 59,53,938/-** (जी.एस.टी. रहित) से **27.62 %** से कम है, आपके द्वारा निविदा प्रपत्र में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद द्वारा स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs. 43,09,684.46 exclusive of GST** which is **27.62 % (Twenty-Seven Decimal Six Two Percent)** below the estimated cost put to tender of **Rs. 59,53,938/- (Fifty-Nine Lacs Fifty-Three Thousand Nine Hundred Thiry-Eight Only)**.

2. सहायक महाप्रबंधक, अभियांत्रिकी (सिविल), भारतीय विमानपत्तन प्राधिकरण, गया हवाईअड्डा, गया इस कार्य के प्रभारी अभियंता होंगे। आप से अनुरोध है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **06.03.2023** तक सहायक महाप्रबंधक, अभियांत्रिकी (सिविल), भारतीय विमानपत्तन प्राधिकरण, गया हवाईअड्डा, गया के कार्यालय में उपस्थित हों। संविदा करार **रु0 1000/- (रुपये एक हजार मात्रा)** के न्यायिकेतर (नॉन-जुडिशल) स्टॉप पेपर पर बनाया जाएगा तथा स्टॉप पेपर की लागत आपके द्वारा वहन की जाएगी।

Asstt. General Manager (E-C), Airports Authority of India, Gaya Airport, Gaya shall be the Engineer-in-charge of the work. You are requested to attend the office of the Asstt. General

4/2/23
24.02.23



भारतीय विमानपत्तन प्राधिकरण

गया विमानपत्तन, गया - 823004.

AIRPORTS AUTHORITY OF INDIA

Gaya Airport, Gaya-823004.



आई.एस.ओ.9001-2008 प्रमाणित

Manager (E-C), Airports Authority of India, Gaya Airport, Gaya by **06.03.2023** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value of **Rs. 1000/- (Rupees One Thousand only)** and the cost of the stamp paper shall be borne by you.

3. कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर प्रतिभूति जमा राशि **रु० 4,30,968 /-** जमा करें अन्यथा यह राशि आपके चालू बिलों से संविदा सामान्य शर्त 1A के तहत काट ली जाएगी एवं आपके निविदा के साथ प्राप्त बयाना राशि **रु० 1,19,079 /-** आपको ऑनलाइन माध्यम से (निविदा में वर्णित प्रावधानों के अनुसार) वापस की जाएगी।

Please deposit **Rs 4,30,968/-** towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted from your running bills as per clause 1A of GCC and Earnest Money amount of **Rs. 1,19,079/-** shall be refunded to your source account (as per provisions mentioned in the tender) through online mode.

4. आपसे अनुरोध है कि 1970 के अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम और अनुबंध श्रम (विनियमन और उन्मूलन) और केंद्रीय नियम 1971 बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ताओं (रोजगार और सेवा की शर्त का विनियमन) अधिनियम 1996, बिल्डिंग और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि केंद्रीय और राज्य सरकार के निविदा और नियमों के अनुबंध दस्तावेज में निर्दिष्ट है।

You are requested to comply with the provision of contract labour (Regulation & abolition) Act of 1970 and contract labour (Regulation & abolition) Central Rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction workers Welfare Cess Act 1996 as specified in Contract Document of tender and Rules of Central and State Govt.

5. आपको प्रबंधक अभियांत्रिकी (सिविल) भारतीय विमानपत्तन प्राधिकरण, गया हवाईअड्डा, से तत्काल संपर्क करने का भी निर्देश दिया जाता है जो आपको कार्य स्थल (साइट) सौंपने का व्यवस्था करेंगे।

You are requested to contact Manager (E-C) Airports Authority of India, Gaya Airport, immediately, who will arrange to hand over the site to you.

6. कृपया नोट करें कि कार्य पूरा करने के लिए आपको **06 महीने** का समय प्रदान किया जाता है जो इस पत्र के जारी होने की तिथि से दसवें दिन 06.03.2023 से प्रभावी मानी जाएगी।

Please note that the time allowed for carrying out the work shall be **06 (Six) Months** and same shall be reckoned from 06.03.2023.

4/3/23
24.02.23



भारतीय विमानपत्तन प्राधिकरण

गया विमानपत्तन, गया - 823004.

AIRPORTS AUTHORITY OF INDIA

Gaya Airport, Gaya-823004.



आई.एस.ओ.9001-2008 प्रमाणित

7. संविदा के संबंध में भविष्य में किसी भी प्रकार का पत्र व्यवहार सामान्यतः प्रभारी-अभियंता के नाम से किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-Charge.

8. कृपया पत्र की पावती भेजें तथा साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप विधिवत् हस्ताक्षर करके हमें वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होगी।

In Case any discrepancy is found, then English version will be taken as correct.

भवदीय / Yours faithfully

परशुराम
24.02.23

(परशुराम / Parshuram)

सहायक महाप्रबंधक, (अभियांत्रिकी सिविल)

Asstt. General Manager (E-C)

भाविप्रा, गया हवाईअड्डा, गया

AAI, Gaya Airport, Gaya

के लिए एवं तरफ से अध्यक्ष

For and on behalf of Chairman

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India

संलग्नक:-अनुसूची-'अ'

Enclosure: Schedule 'A'

SCHEDULE- A

Name of Work: Construction of 2 No. watch tower and provision of double gate in Operational area for CISF at Gaya Airport, Gaya

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
	SH:- A) Civil Work:-						
1.00	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	213.00	cum	180	38340.00	151.93	32361.09
2.00	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	101.00	cum	150	15150.00	212.12	21424.12
3.00	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil	81.00	cum	50	4050.00	29.58	2395.98
4.00	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	30.00	cum	1800	54000.00	1598.3	47949.00
5.00	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	53.00	cum	4500	238500.00	4678.32	247950.96
6.00	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Foundations, footings, bases of columns, etc. for mass concrete	41.00	Sqm	180	7380.00	227.73	9336.93
7.00	Centering and shuttering including strutting, propping etc. and removal of form for Suspended floors, roofs, landings, balconies and access platform	103.00	Sqm	300	30900.00	566.89	58389.67
8.00	Centering and shuttering including strutting, propping etc. and removal of form at heights : Lintel, Plinth Beam, Beam	180.00	Sqm	300	54000.00	449.9	80982.00
9.00	Centering and Shuttering including strutting, propping etc. and removal of form for all heights : Columns, pillars, piers, Abutments, Posts and Struts	255.00	Sqm	250	63750.00	594.77	151666.35
10.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	3037.00	Kg.	80	242960.00	66.29	201322.73

423212
24.02.23
S. S. S. S. S.

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
11.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	4539.00	Kg.	80	363120.00	66.29	300890.31
12.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in : Cement mortar 1:6 (1 cement : 6 coarse sand)	50.00	cum	6000	300000.00	2954.4	147720.00
13.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	66.00	cum	7000	462000.00	6129.53	404548.98
14.00	Half brick masonry with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in foundation and plinth in : cement mortar 1:4 (1 cement : 4 coarse sand)	6.00	Sqm	500	3000.00	619.66	3717.96
15.00	Extra for providing and placing in position 2 Nos 6mm dia. M.S. bars at every third course of half brick masonry.	3.00	Sqm	100	300.00	63.66	190.98
16.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3197.00	Kg.	85	271745.00	57.83	184882.51
17.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	1904.00	Kg.	90	171360.00	59.53	113345.12
18.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	2077.00	kg	90	186930.00	44.48	92384.96
19.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	878.00	kg	88	77264.00	114.55	100574.90
20.00	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	148.00	Sqm	500	74000.00	329.52	48768.96

4223215

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
21.00	Providing and laying Ceramic glazed floor tiles of size 300x300 mm thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc.,complete.	7.00	sqm	800	5600.00	748.14	5236.98
22.00	Providing and fixing precoated galvanised iron profile sheets (size,shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	152.00	Sqm	590.00	89680.00	496.63	75487.76
23.00	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm)	105.00	Mtr.	400.00	42000.00	333.22	34988.10
24.00	12 mm cement plaster. i) 1:6 (1 cement: 6 Coarse sand)	198.00	Sqm	200.00	39600.00	217.68	43100.64
25.00	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand)	198.00	Sqm	220	43560.00	250.77	49652.46
26.00	12 mm cement plaster finished with a floating coat of neat cement of mix :1:3 (1 cement: 3 fine sand)	160.00	Sqm	200	32000.00	267.19	42750.40
27.00	6 mm cement plaster of mix : i) 1:3 (1 cement: 3 fine sand)	90.00	Sqm	180	16200.00	187.13	16841.70
28.00	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade i) New work (two or more coats) over and including water thinnable priming coat with cement primer	240.00	Sqm	50	12000.00	120.21	28850.40

422215
24.02.23

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
29.00	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	325.00	Sqm	80	26000.00	123.39	40101.75
30.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade i) Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	950.00	Sqm	80	76000.00	126.64	120308.00
31.00	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	8.00	CUM	1200	9600.00	927.62	7420.96
32.00	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	14.00	CUM	1500	21000.00	2165.42	30315.88
33.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead and taking away serviceable brick as per direction of Engineer-in-charge. In cement mortar	25.00	cum	1000	25000.00	904.36	22609.00
34.00	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	1500.00	cum	3	4500.00	2.36	3540.00
35.00	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	19.00	cum	5500	104500.00	189.57	3601.83
36.00	Providing and fixing water closet squatting pan (Indian type W.C.pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	1.00	Each	2000	2000.00	4276.00	4276.00

422/215
24.02.23

SI.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
37.00	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern,with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass,including painting of fittings and cutting and making good the walls and floors wherever required :Range of two half stall urinals with 5 litre P.V.C. automatic flushing cistern	1.00	Each	3000	3000.00	7490.00	7490.00
38.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap	1.00	Each	2500.00	2500.00	2193.00	2193.00
39.00	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm dia nominal bore	25.00	Metre	150.00	3750.00	224.92	5623.00
40.00	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 20 mm dia nominal bore	25.00	Metre	200.00	5000.00	276.08	6902.00
41.00	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 25 mm dia nominal bore	25.00	Metre	250.00	6250.00	363.28	9082.00
42.00	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.40 mm dia nominal bore	100.00	Metre	400.00	40000.00	536.27	53627.00
43.00	Providing and fixing brass bib cock of approved quality :15 mm nominal bore	2.00	Each	500.00	1000.00	224.00	448.00
44.00	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :40 mm nominal bore	4.00	Each	600.00	2400.00	523.00	2092.00
45.00	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :15 mm nominal bore	2.00	Each	300.00	600.00	258.00	516.00
46.00	Providing and fixing gun metal non- return valve of approved quality (screwed end) :40 mm nominal bore Vertical	2.00	Each	800.00	1600.00	776.00	1552.00
47.00	Providing and fixing uplasticised PVC connection pipe with brass unions :15 mm nominal bore	2.00	Each	50.00	100.00	63.00	126.00

452213
24.02.23

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
48.00	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :15 mm nominal bore	10.00	Each	80.00	800.00	194.00	1940.00
49.00	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :20 mm nominal bore	10.00	Each	100.00	1000.00	213.70	2137.00
50.00	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :40 mm nominal bore	10.00	Each	200.00	2000.00	386.80	3868.00
51.00	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support i/c fittings & fixtures for tank shall be paid separately.	500.00	Litre	10.00	5000.00	7.17	3585.00
52.00	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore	3.00	Each	500.00	1500.00	370.00	1110.00
53.00	Providing and fixing PTMT grating of approved quality and colour. Rectangular type with openable circular lid 150 mm nominal size square 100 mm diameter of the inner hinged round grating	2.00	Each	50.00	100.00	125.50	251.00
54.00	Providing and laying non-pressure NP2 class (light duty) R.C.C.pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :250 mm dia. R.C.C. pipe	20.00	Metre	600.00	12000.00	599.85	11997.00
55.00	Providing and laying non-pressure NP2 class (light duty) R.C.C.pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :600 mm dia. R.C.C. pipe	65.00	Metre	1000.00	65000.00	1551.61	100854.65

422225
24.02.23

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
56.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : a) For fixed portion i) Powder coated aluminium (minimum thickness of powder coating 50 micron)	375.00	Kg	350.00	131250.00	344.84	129315.00
57.00	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). i) Powder coated aluminium (minimum thickness of powder coating 50 micron)	300.00	Kg	400.00	120000.00	522.51	156753.00
58.00	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): i) With float glass panes of 5.0mm thickness	11.00	Kg	500.00	5500.00	980.27	10782.97
59.00	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment).	100.00	kg.	650.00	65000.00	414.76	41476.00
60.00	Carry out boring at required depth having 450 mm diameter for reinforcement cement concrete pile excluding the cost of steel reinforcement	112.00	Mt	120.00	13440.00	109.97	12316.64

42215
24.02.23

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
61.00	Providing and laying in position specified grade of reinforced cement concrete, using minimum cement of 384 kg, excluding the cost of centering, shuttering, finishing and reinforcement, All works upto plinth Level 1:1.65:3 (1 cement : 1.65 coarse sand : 3 coarse aggregate)	35.00	cum	7000.00	245000.00	6060.31	212110.85
62.00	Providing and laying in position specified grade of reinforced cement concrete, using minimum cement of 384 kg, excluding the cost of centering, shuttering, finishing and reinforcement, All works above plinth Level, 1:1.65:3 (1 cement : 1.65 coarse sand : 3 coarse aggregate)	42.00	cum	7000.00	294000.00	6915.21	290438.82
63.00	Providing, Laying and jointing of PVC Pipe and special SN-8 for under ground drainage system as per IS-15328, complete in all respect. 160 mm Dia PVC SN-8	80.00	Mtr.	600.00	48000.00	840.48	67238.40
	SH:- B) Electrical Work:-						
64.00	Supply of 1200 mm sweep ceiling fan suitable to operate on 230V, single phase, AC supply along with all accessories except regulator as required.Make :- As per AAI Approved Make list.	5.00	Each	1500.00	7500.00	2530.40	12652.00
65.00	Supply of 400 mm sweep wall fan suitable to operate on 230V, single phase, AC supply along with all accessories including regulator as required.Make :- As per AAI Approved Make list.	3.00	Each	1200.00	3600.00	4217.33	12651.99
66.00	Supply of min 225 mm sweep exhaust fan suitable to operate on 230V, single phase, AC supply along with all accessories as required.Make :- As per AAI Approved Make list.	2.00	Each	1200.00	2400.00	1687.00	3374.00
67.00	Supply of 20 watt LED Tube light Fitting with electronics power driver suitable for 230 V + 10% , 50Hz AC supply.Make :- As per Technical Specification	15.00	Each	200.00	3000.00	1272.73	19090.95
68.00	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. (Group C).	25.00	Point	1000.00	25000.00	84.36	2109.00
69.00	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	50.00	Mtr	100.00	5000.00	168.68	8434.00
70.00	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required.(i)2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	50.00	Mtr	50.00	2500.00	168.68	8434.00

422/212
24.02.23

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
71.00	Supplying and fixing stepped type electronic fan regulator on the existing modular plate & switch box including connections but excluding modular plate etc. as required.Make :- As per AAI Approved Make list.	5.00	Each	200.00	1000.00	421.80	2109.00
72.00	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required 1 or 2 Module (75mmX75mm)	10.00	Each	100.00	1000.00	253.00	2530.00
73.00	Supplying and fixing following modular switch/ socket on the existing existing modular plate & switch box including connections but excluding modular plate etc. as required						
73.10	5A /6 A Switch	20.00	Each	20.00	400.00	126.50	2530.00
73.20	Telephone socket outlet	2.00	Each	20.00	40.00	632.50	1265.00
74.00	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required	5.00	Each	50.00	250.00	253.00	1265.00
75.00	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	2.00	Each	300.00	600.00	3374.00	6748.00
76.00	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required. 25 mm	20.00	Mtr	100.00	2000.00	421.70	8434.00
77.00	Installation, testing and commissioning of ceiling fan, wall fans & exhaust including wiring the down rod of standard length (up to 30 cm) with 1.5 sq. mm. FRLSH PVC insulated copper conductor, single core cable etc. as required.	10.00	Each	100.00	1000.00	680.80	6808.00
78.00	Installation, testing and commissioning of pre-wired, fluorescent fitting /LED Fitting / LED Lumaire / fitting of all types, complete with all accessories and tube / lamp etc. directly on ceiling/ wall/Surafce/ MS structure etc. , including connections with 1.5 sq. mm FRLSH PVC insulated, copper conductor, single core cable and earthing etc. as required.	21.00	Each	100.00	2100.00	40.14	842.94

422215
24.02.23

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B1ZP)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
79.00	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) (i) 6 way (4 + 18), Double door	1.00	Each	1000.00	1000.00	12652.00	12652.00
80.00	Supplying and fixing 6 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of Single pole in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make :- As per AAI Approved Make list.	18.00	Each	200.00	3600.00	759.11	13663.98
81.00	Supplying and fixing 63 amps. rating, 415 Volts, 'C' Series, Four Pole miniature circuit breaker suitable for inductive load in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make :- As per AAI Approved Make list.	1.00	Each	300.00	300.00	2699.00	2699.00
82.00	Laying of one number PVC insulated and PVC sheathed/ XLPE power cable of 1.1 kv grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required.						
82.10	Above 35 sq. mm and upto 95 sq. mm	100.00	Mtr.	100.00	10000.00	8.43	843.00
83.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required.						
83.10	Above 35 sq. mm and upto 95 sq. mm	20.00	Mtr.	80.00	1600.00	210.85	4217.00
84.00	Laying and fixing of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 kv grade of following size on wall surface as required.						
84.10	Upto 35 sqmm.	15.00	Mtr.	100.00	1500.00	281.13	4216.95
84.20	Above 35 sq. mm and upto 95 sq. mm	15.00	Mtr.	100.00	1500.00	281.13	4216.95
85.00	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.. Make :- As per AAI Approved Make list.						
85.10	3.5 core X 70 sq. mm	2.00	Each	1000.00	2000.00	10121.50	20243.00
86.00	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	4.00	Each	3900.00	15600.00	4217.25	16869.00

422/212
24.02.23

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Cupid Enterprises(GSTN-23AAIFC2788B12P)		SAMASHRA CONSTRUCTION PRIVATE LIMITED (GSTN-NA)	
				Rate	Amount	Rate	Amount
87.00	Supply, Installation, Testing Commissioning of Maintenance Free Copper coated Earth rod of min 3 mtrs length having the dia of min 14 mm along with Earth Enhancing Materails for providing earthing to CISF antenna by achieving desired resistivity.	1.00	Each	1900.00	1900.00	42172.00	42172.00
88.00	Providing and laying earth connection from earth electrode with 4.00 mm dia copper wire in 15 mm dia G.I. pipe from earth electrode including connection with copper thimble excavation and re-filling as required.	50.00	Mtr.	190.00	9500.00	506.06	25303.00
89.00	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	15.00	Mtr.	50.00	750.00	1124.60	16869.00
90.00	Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, G.I. tube, having single prong at top, with 85 mm dia 6 mm thick G.I. base plate including holes etc. complete as required.	4.00	Each	200.00	800.00	2108.50	8434.00
91.00	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or on surface of wall for lightning conductor complete as required (For horizontal run).	50.00	Mtr.	50.00	2500.00	1012.12	50606.00
92.00	Providing and fixing G.I. tape 20 mm X 3 mm thick on parapet or on surface of wall for lightning conductor complete as required (For vertical run).	50.00	Mtr.	100.00	5000.00	1012.12	50606.00
93.00	Jointing copper / G.I. tape (with another copper/ G I tape, base of the finial or any other metallic object) by riveting / nut bolting/ sweating and soldering etc as required.	10.00	Each	50.00	500.00	843.40	8434.00
94.00	Providing and fixing testing joint, made of 20 mm X 3 mm thick G.I. strip, 125 mm long, with 4 nos. of G.I. bolts, nuts, chuck nuts and spring washers etc. complete as required.	4.00	Each	88.00	352.00	3162.75	12651.00
Total in Figures					4399571.00		4309684.46
Lowest Amount Quoted BY: SAMASHRA CONSTRUCTION PRIVATE LIMITED(4309684.46)					L-2		L-1

42225
24.02.23

BOQ- 11 of 11

Signature Not Verified

Digitally signed by PARSHU RAM
Date: 2023.08.22 13:15:04 IST
Location: eProcurement System for Central PSUs