



75
आज़ादी का
अमृत महोत्सव

भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

संदर्भ सं.: भा.वि.प्रा./इंजी.(ई)/एसएपी प्रोजेक्ट/2022-23/डब्ल्यू.ओ.04/

दिनांक : 16.03.2023

AAI/Engg.(E)/SAP Project/2022-23/W.O.04/ 4068

सेवा में

To,

भारती रेफ्रिजेशन वर्क्स
A-97 दशरथ पुरी, डबरी पालम रोड
नयी दिल्ली-110045

M/s Bharti Refrigeration Works
A-97, Dashrath Puri, Dabri Palam Road
New Delhi-110045
Email id: info@bhartirefrigeration.com

विषय: सफदरजंग हवाई अड्डे, नई दिल्ली में डीजीसीए, बीसीएस, एएआईबी, ऐरा और एएआई के लिए संयुक्त परिचालन कार्यालयों का निर्माण। उप शीर्षक: रसोई उपकरण का प्रावधान।

संदर्भ - आपकी वित्तीय बोली सं. 2020_AAI_139264 30.01.2023 को खोला गया।

Subject: Construction of combined operational offices for DGCA, BCAS, AAIB, AERA and AAI at Safdarjung Airport, New Delhi. SH. Provision of Kitchen Equipment.

Ref: Your Financial Bid no. 2020_AAI_139264 opened on 30.01.2023

महोदय/Dear Sir(s),

उपरोक्त कार्य के लिए आपकी निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आप द्वारा उद्धरित मद दरजिसकी कुल राशि रु. 32,49,800.00/- (बत्तीस लाख उनचास हजार आठ सौ रुपये मात्र) जीएसटी को छोड़कर जो कि निविदा की अनुमानित लागत रु. 36,17,391.00/- से 10.16% कम है, स्वीकृत की जाती है।

Your e-Tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at item rates bid by you totaling to **Rs. 32,49,800.00 (Rupees Thirty-Two Lakh Forty-Nine Thousand and Eight Hundred only-)** Excluding GST which is 10.16% below the estimated cost put to tender of **Rs. 36,17,391.00/-**

1. संयुक्त महाप्रबंधक (अभि-विद्युत), परियोजना प्रोजेक्ट, एएआई, सफदरजंग एयरपोर्ट, नई दिल्ली 110003] इस कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कि आप / आपके द्वारा अधिकृत प्रतिनिधि संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु दिनांक 26.03.2023 तक संयुक्त महाप्रबंधक (अभि-विद्युत), परियोजना DGCA प्रोजेक्ट, एएआई, सफदरजंग एयरपोर्ट, नई दिल्ली 110003 के कार्यालय में उपस्थित हों। संविदा करार रु 100.00 (सौ रुपये मात्र) के न्यायिकेतर (नॉन ज्युडिशियल) स्टाम्प पेपर (नई दिल्ली) पर बनाया जाएगा और स्टाम्प पेपर की लागत आपको वहन करनी होगी।

Jt. General Manager Engg (E), Project, AAI, Safdarjung Airport, New Delhi - 110003, shall be the Engineer-in-Charge of the work. You are requested to attend / depute your authorized representative to the office of the **Jt. General Manager Engg. (E)**, DGCA Project, AAI, Safdarjung Airport, New Delhi - 110003 by 26.03.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper (New Delhi) of value **Rs.100.00** (Rupees One Hundred only) and the cost of stamp paper shall be borne by you.

राजीव गांधी भवन
Rajiv Gandhi Bhawan

सफदरजंग हवाई अड्डा नई दिल्ली- 110003
Safdarjung Airport, New Delhi-110003

दस्तावेज : 011-24632950
Phone : 011-24632950

[Signature]
Anand

2. बयाना राशि रु. आपकी बोली के साथ प्राप्त 72,348.00 /- (रुपए बहत्तर हजार तीन सौ अड़तालीस मात्र) को पृष्ठ ओ पर खंड 1 (ए) की शर्तों के अनुसार सुरक्षा जमा के हिस्से के रूप में माना और परिवर्तित किया जाएगा। निविदा के जीसीसी 18। कृपया इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर सुरक्षा जमा के रूप में 2,52,632/- (केवल दो लाख बावन हजार छह सौ बत्तीस रुपये मात्र) जमा करें, ऐसा न करने पर खंड संख्या 1(ए) पृष्ठ संख्या पर। निविदा दस्तावेज के जीसीसी 18 की शर्त के अनुसार कटौती की जाएगी।

The earnest money amount Rs. 72,348.00 /- (Rupees Seventy Two Thousand Three Hundred Forty Eight only) received along with your bid will be treated and converted as part of security deposit as per conditions at Clause 1 (A) on page o. GCC 18 of the tender. Please deposit 2,52,632/- (Rupees Two Lakhs Fifty Two Thousand Six Hundred & Thirty Two Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no 1 (A) at page no. GCC 18 of tender document.

3. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन एवं उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन एवं उन्मूलन) केन्द्रीय नियमावली 1971 बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार और सेवा की शर्त का विनियमन) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकार अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ संख्या जी.सी.सी- 49 पर धारा-19 में निर्दिष्ट है तथा केन्द्रीय और राज्य सरकारों के नियमों का अनुपालन करें।

You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules-1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare cess Act 1996 as specified in Clause-19 On Page No. GCC-49 of Tender document and rules of Central and State Governments.

4. आपको निदेश दिए जाते हैं कि आप प्रबंधक (अभि.-विद्युत), परियोजना परियोजना प्रोजेक्ट, एएआई, सफदरजंग एयरपोर्ट, नई दिल्ली 110003 से तत्काल सम्पर्क करें जो कि आपको कार्यस्थल हस्तांतरण करने की व्यवस्था करेंगे। You are also directed to contact the Manager (Engg.-Elect.), AAI DGCA Project, AAI, Safdarjung Airport, New Delhi -110003 immediately, who will arrange to handover the site to you.

5. कृपया यह नोट कर लें कि काम पूरा करने का समय 3 (तीन) महीने है, जिसे इस पत्र के जारी होने की तारीख के बाद दसवे दिन से गिना जाएगा।

Please note that the time allowed for carrying out the work shall be 3(three) Months and same shall be reckoned from 10th day after the date of issue of this letter.

6. संविदा के संबंध में आगे किया जाने वाला पत्राचार सामान्यतः प्रभारी अभियंता से ही किया जाए।

Any further correspondence in connection with this contract should normally be addressed to the Engineer – in – Charge.

7. कृपया इस पत्र की पावती भेजें तथा इसके साथ में संलग्न इस पत्र की दूसरी प्रति पर स्वीकारोक्ति के रूप में विधिवत हस्ताक्षर करके अधोहस्ताक्षरी वापस भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to undersigned as a token of acceptance.



8. कृपया ध्यान दें कि यदि उपरोक्त में हिंदी और अंग्रेजी संस्करण के प्रावधान में कोई अंतर / विसंगति या विरोधाभास है, तो अंग्रेजी संस्करण मान्य होगा।

Please note if there is any difference / discrepancy or contradiction in the provision of Hindi and English version in above, the English version shall prevail.

9. जीएसटी प्रावधानों का अनुपालन न करने और किसी इनपुट क्रेडिट के अवरुद्ध होने की स्थिति में, एएआई की क्षतिपूर्ति करना आपकी जिम्मेदारी होगी।

In case of non-compliance of GST provisions and blockage of any input credit, it shall be your responsibility to indemnify AAI.

10. जीएसटी को छोड़कर दरों में सभी कर शामिल हैं। हालांकि, जीएसटी, जैसा लागू हो, अनुबंध के नियमों और शर्तों के अनुसार वैध जीएसटी चालान के खिलाफ एजेंसी द्वारा एएआई को प्रदान की गई किसी भी कर योग्य आपूर्ति/सेवाओं/निर्माण के लिए ठेकेदार को भुगतान किया जाएगा।

The rates are inclusive of all taxes but excluding of GST. However, GST, as applicable, shall be paid to the contractor for any taxable supply/ services/ construction rendered by the agency to AAI against a valid GST invoices as per terms and conditions of the contract.

11. उपरोक्त संदर्भित पत्र/दस्तावेज समझौते के भाग होंगे।


The above referred letter/ documents shall form part of the agreement.

12. सभी इनपुट क्रेडिट आपके द्वारा एएआई को दिए जाएंगे

All input credits will be passed on the AAI by you.

AAI GST No.- 07AAACA6412D2Z9

संलग्नक / Enclosure: मदों की सूची / Schedule of Quantity.


(आनंद कुमार)

सहायक महाप्रबंधक (अभियांत्रिकी-विद्युत)

(Anand Kumar)

Astt. General Manager (Engg. -E)

कृते एवं अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से

For & on behalf of Chairman, Airports Authority of India

Tender Inviting Authority: AAI

Name of Work: Construction of Combined Operational Offices of DGCA, BCAS, AAIB, AERA and AAI at Safdarjung Airport, Ne

Contract No:

SCHEDULE OF WORK / ITEM(S)						Bharti Refrigeration Works(GSTN-06AEMP00002P2ZS)		J B Equipments(GSTN-07AAIFJ3191P1ZS)		Muskan Equipments Co.(GSTN-07AAJPR6760K1Z3)	
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate		Rate	Amount	Rate	Amount	Rate	Amount
1.00	Fabricating, Providing, Installing, Testing & Commissioning of Dirty Dish Landing Table of size (1500mm x 700mm x 850mm+150), 16 Gauge, S.S. Top, front turned up 30mm, turned down 50mm & in 12mm. 150mm High Rear splash. right side locakable with already exisiting as pre Dish washer. Top and body secured 38mm x 38mm x 3mm Thick S.S. welded angle frame work / hut type welded channel frame work. 200mm round hole for garbage. 4 no. 38mm Dia S.S. legs. With S.S. adjustable bullet feet. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set			15000.00	15000.00	23500.00	23500.00	15000.00	15000.00
2.00	Fabricating, Providing, Installing, Testing & Commissioning of Two Sink Pre wash unit of size 1500mm x 700mm x 850mm + 150mm(back splash) , 16 Gauge S.S. Top. 150mm High Rear splash. Top and body secured 38mm x 38mm x 3mm Thick S.S. welded angle frame work / hut type welded channel frame work. 4 no. 38mm Dia. S.S. legs. With S.S. adjustable bullet feet. Centre of unit One (2) no.450mm x 450mm x 300mm deep 16 Gauge. S.S. sink. 25mm Dia S.S. pipe cross bracing welded to legs at Rear & both sides. Front open. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set			25000.00	25000.00	29000.00	29000.00	22000.00	22000.00
3.00	Fabricating, Providing, Installing, Testing & Commissioning of Pre Rinse Spray Unit of wall mounted Hose with Overhead Spring & Spray Valve Assembly. Finger hook of 3/8" NPT X 18" Riser, Lever handles with color coded indexes and spring check eternal cartridges. Self-Closing Pre-Rinse Spray Valve w/ Rubber Bumper & 1.42 GPM Flow Control Spray Face. Wall Mounted. Water Cold & Hot-12mm including accessories deck mounting assembly complete as required as per technical specification.	1.00	Set			40000.00	40000.00	26000.00	26000.00	18000.00	18000.00
4.00	Fabricating, Providing, Installing, Testing & Commissioning of Dishwasher (Hood Type) Able to run at two speeds at the capacity of 60 racks per hour. Unit suitable to handle 500 X 500 racks . Full SS Construction. With Electronic control. Suitable for operation on incoming soft water sanitizing. Automatic water fill. Unit should be equipped with rinse pressure pump, drain pump and with rinse agent dispenser. Tank should be with rounded edges . Should be with self cleaning cycle. 200mm High Adjustable SS Legs including accessories. Unit suitable for Pass the Thermo level, Corner Installation and complete as required as per technical specification.	1.00	Set			193000.00	193000.00	225000.00	225000.00	175000.00	175000.00
5.00	Fabricating, Providing, Installing, Testing & Commissioning of Unloading table with with 2 nos under pipe shelf of size 1100mm x 700mm x 850mm + 150mm, 150mm High Rear splash.16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick S.S. welded angle frame work / hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 2 nos under pipe shelves. All sheets to be pre- polished plastic coated 304 grade complete as required as per technical specification..	1.00	Set			14700.00	14700.00	19000.00	19000.00	16000.00	16000.00
6.00	Fabricating, Providing, Installing, Testing & Commissioning of Clean Dish Rack 5 Tier of size 900mm x 500mm x 1800mm and Shelving shall be arranged as shown in the layout plan. 1800mm high overall on SS adjustable feet, constructed of 38mm x 38mm x 16 Gauge SS pipe. Each to have five shelves at equal distance of 18 Gauge SS with channels. Shelves to be bolted / fixed at each corner. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification.	2.00	Set			15000.00	30000.00	29000.00	58000.00	16000.00	32000.00

7.00	Supply & Fixing garbage bin with Color as Blue/ Yellow/ Green, with plastic material capacity of minimum 80 Ltr. with each set has 3 bin complete as required as per technical specification.	4.00	Set
8.00	Fabricating, Providing, Installing, Testing & Commissioning of Stainless steel Drain Through Grating of Size 900mm x 700mm x 150mm, Grating outer bearing bar Frame work of 25mm x 3 mm thick welded construction flushed with finished floor complete installation, Grating anti skid , lateral/Horizontal cross member of size 25mm x 2.5mm thick, Pressure locked & under side common graced to be welded & rest in to S.S. trough. Grating with hairline finishing, 150mm Deep 18 Gauge. S.S. trough channel shape, Suitable construction for rest Grating. Base of trough sloped towards floor drain. Provided 100mm Dia cutout & integral flange for entry into floor drain on cutout, 100 mm dia. Location of floor drain & trough height/size & waste dia to be verify at site complete as required as per technical specification..	1.00	Set
9.00	Fabricating, Providing, Installing, Testing & Commissioning of stainless steel Pot Rack of size (1100mm x 600mm x 1650mm) with four (4) no stainless steel pipe shelves. First shelf 150 (Above finished floor) A.F.F., Second 850 A.F.F. Third shelf 1450mm A.F.F. & Fourth 3 side crossing at 1650mm A.F.F. Shelf outer 32mm round / square S.S pipe and inner 25mm round / square. S.S pipe welded to outer tube at 80mm distance. (4) no. 38mm round / square S.S. pipe. All Pipe S.S. 304 Grade complete as required as per technical specification.	2.00	Set
10.00	Fabricating, Providing, Installing, Testing & Commissioning of Mobile Dirty Dish Trolley of Size 750mm x 600mm x 900mm and 18 Gauge. S.S. top channel shape. Four (4) no. 38mm dia uprights on Castors. All sides turned up 150mm & handled outside welded to S.S legs. Four (4) no. heavy duty 100mm dia Non-marking rubberized castors all with brakes. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
11.00	Fabricating, Providing, Installing, Testing & Commissioning of Sink Unit of size (450mm x 400mm x 250mm) Unit shall drop in suitable to top Counter. Internal 350mm x 350mm x 200mm deep 16 Gauge S.S. sink, S.S. wall Brackets. Secured to top with acorn Nuts & Bolts & Bracket secured to wall with anchor fasteners. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification..	2.00	Set
12.00	Fabricating, Providing, Installing, Testing & Commissioning of Preparation Table size of 1350mm x 700mm x 850mm + 150mm. 150mm High Rear splash.16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hut type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 3 side cross bracing 25 mm round pipe. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification.	2.00	Set
13.00	Fabricating, Providing, Installing, Testing & Commissioning of Two Sink Vegetable washing unit of size 1250mm x 700mm x 850mm + 150mm, 16 Gauge S.S. Top. 150mm High Rear splash.Top and body secured 38mm x 38mm x 3mm Thick S.S. welded angle frame work hut type welded channel frame work. 4 no. 38mm Dia. S.S. legs. With S.S. adjustable bullet feet. Centre of unit One (2) no.500mm x 500mm x 300mm deep 16 Gauge. S.S. sink. 25mm Dia S.S. pipe cross bracing welded to legs at Rear & both sides. Front open. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
14.00	Supply, Installing, Testing & Commissioning of Vegetable-cutter made up of Aluminium alloy and S/S construction with Ventilated motor for continuous operation,suitable for easy processing for soft products like moz-zarella cheese. Safe operation with interlock switches on product pusher, with 6 blades,lid and collect-ing tray. Large number of discs available for every purpose with max Power 515W & 0.7 HP Power source 1ph/3ph Disc revolutions r.p.m. 300 complete as required as per technical specification.(Model TM2 All/INOX or equivalent)	1.00	Set

7900.00	31600.00	10000.00	40000.00	2200.00	8800.00
28000.00	28000.00	13000.00	13000.00	18000.00	18000.00
17000.00	34000.00	23000.00	46000.00	20000.00	40000.00
13500.00	13500.00	18000.00	18000.00	14500.00	14500.00
8000.00	16000.00	9000.00	18000.00	12500.00	25000.00
12000.00	24000.00	23000.00	46000.00	13500.00	27000.00
21000.00	21000.00	27000.00	27000.00	18000.00	18000.00
89300.00	89300.00	115000.00	115000.00	25000.00	25000.00

15.00	Supply, Installing, Testing & Commissioning of min 900 W mixer, grinder with most powerful motor with Double Ball Bearings with 22000 rpm, Chutney Jar as 400 ml, Liquidizing Jar with minimum 1.5 L, minimum 3 nos. of jars with plastic body, 230-240 V AC three no. (03) speed setting with maximum power consumption 900 W complete as required as per technical specification. (Make Sujata or equivalent)	1.00	Set
16.00	Fabricating, Providing, Installing, Testing & Commissioning of Pulverizer, Runs easily. The dry/wet stainless steel body, 24 hours running capacity, Easy to maintain, Attractive in finish, special air cooling system for motor with minimum 2 HP and complete as required as per technical specification.	1.00	Set
17.00	Fabricating, Providing, Installing, Testing & Commissioning of Potato Peeler, cap-10kg, having overall, Potato peeler shall be of vertical design suitable for mounting on the floor. Machine shall be divided in two sections, Top peeling assembly and the bottom for motor drive housing, all made of Stainless Steel as per technical specification with 1.0 HP motor and complete as required as per technical specification. All sheets to be pre-polished plastic coated 304 grade.	1.00	Set
18.00	Fabrication, Installing, Testing & Commissioning of a kneading machine of minimum 25 kg atta made up of heavy duty cast iron with gear box mounted on the top the mixing bowl of SS sheet min 18 swg with handle the dough kneading machine is comes with single attachment the machine is operated electrically with min 2 HP Motor on single phase complete as required as per technical specification..	1.00	Set
19.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table with Sink Unit of size 1350mm x 600mm x 850mm + 150mm, 16 Gauge S.S. Top. 150mm High Rear splash. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hut type welded channel frame work, 4 no. 38mm Dia. S.S. legs. With S.S. adjustable bullet feet. Centre of unit One (1) no. 400mm x 400mm x 250mm deep 16 Gauge. S.S. sink. with one under shelf 18 gauge. welded to legs at Rear & both sides. Front open. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
20.00	Fabricating, Providing, Installing, Testing & Commissioning of Masala Grinder (Tilting) of conventional 10 liters capacity wet grinder with twin roller construction minimizes spillage with Vertical construction to occupy less space unit with 1.0 HP motor with on single phase, wet grinder in stainless steel Wired including accessories Power chord and complete as required as per technical specification.	1.00	Set
21.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table with Sink Unit of size 1800mm x 700mm x 850mm + 150mm, 16 Gauge S.S. Top. 150mm High Rear splash. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hut type welded channel frame work.. 4 no. 38mm Dia. S.S. legs. With S.S. adjustable bullet feet. Centre of unit One (1) no. 500mm x 500mm x 300mm deep 16 Gauge. S.S. sink. with one under shelf 18 gauge welded to legs at Rear. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification..	1.00	Set
22.00	Fabricating, Providing, Installing, Testing & Commissioning of Two Door Under Counter of size 1400mm x 700mm x 850mm. 18 Gauge SS top/ SS 304 interior and exterior. 150mm High Rear splash. All sides turned down 50mm & in 12mm. Top and body secured to 12/25mm x 100mm x 25/12mm, 1.2 mm Thick S.S. hut type welded channel frame work. Underside of the top shall be sound proof, 2nos. SS removable & adjustable shelves. 2 nos. sufring doors with insulation. Accommodates 1/1 G.N pan. Ambient temperature 43 deg C. Internal Temp 2 Deg C to 4 Deg C, Air-cooled, Digital read out thermometer, cord with time delay, auto start, Forced draft cooling. 38mm Dia S.S. tubular legs, with S.S. adjustable bullet feet, 50mm thick P.U. foam on all sides, Drip tray with heating (for condensate water evaporation). All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set

6200.00	6200.00	11000.00	11000.00	6000.00	6000.00
21000.00	21000.00	23000.00	23000.00	18000.00	18000.00
25000.00	25000.00	26000.00	28000.00	30000.00	30000.00
39000.00	39000.00	49000.00	48000.00	45000.00	45000.00
16500.00	16500.00	28000.00	28000.00	16000.00	16000.00
43000.00	43000.00	45000.00	45000.00	45000.00	45000.00
22000.00	22000.00	32000.00	32000.00	22000.00	22000.00
60700.00	60700.00	70000.00	70000.00	95000.00	95000.00

23.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With 2 under size of 1350mm x 700mm x 850+150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
24.00	Fabricating, Providing, Installing, Testing & Commissioning of gas operated S S Cladded Mobile Tandoor of size 750mm X 750mm X 850+150mm, 150mm High Rear splash, 16 Gauge S.S. Top, Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work, Exterior 18 Gauge S.S. cladding, Interior 18 Gauge 304 grade. M.S. cladding, 40mm thick Mineral wool insulation, Front S.S. Ash removable opening with shutter, (4) no. heavy duty 100mm Dia Non marking rubberized castors all with brakes, 2 No. Top sheets to be prepolished plastic coated S.S and complete as required as per technical specification.	1.00	Set
25.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table with 2 under size of 600mm x 750mm x 850++150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hut type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
26.00	Fabricating, Providing, Installing, Testing & Commissioning of Two Burner Range with under shelf of size (1300mm x 750mm x 850mm+150mm). 16 Gauge S.S. Top. 150mm High Rear Splash, Back Splash to be Covered with 20 Gauge S.S. Sheet. Top and body secured 38mm x 38mm x 3mm & 25mm x25mm Thick M.S. welded angle frame work, hat type welded channel frame work. Exterior 18 Gauge S.S. cladding. Built in pressure Controller regulator. 38mm x 38mm x 16 Gauge S.S. Square pipe legs with S.S. adjustable bullet feet. 25mm x 25mm S.S. square pipe Under shelf. 2 No. 400mm x 400mm Cast iron Grate (Removable). Two (2) no. 22 Gauge S.S. drip tray with Integral handle. Auto Ignition. Two (2) no. H.P burner rated @70,000 B.T.U's/Hr. with pilot lamp. 100mm setback Body/legs for Gauges pipe routing. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	3.00	Set
27.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table with 2 under size of 900mm x 750mm x 850++150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
28.00	Fabricating, Providing, Installing, Testing & Commissioning of Single Sink Unit with one underself crossing of size 600mm x 700mm x 850mm + 150mm , 16 Gauge S.S. Top. 150mm High Rear splash. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work.. 4 no. 38mm Dia. S.S. legs. With S.S. adjustable bullet feet. Centre of unit One (1) no.400mm x 400mm x 250mm deep 16 Gauge. S.S. sink. 25mm Dia S.S. pipe cross bracing welded to legs at Rear & both sides. Front open. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
29.00	Fabricating, Providing, Installing, Testing & Commissioning of Exhaust Hood of size 2900mm X 900mm X 500mm External and internal parts to be manufactured in SS 202, 18Gauge Welded Body Construction, Removable 22 Gauge S.S "V" section, measuring 510*510*50 mm thick, in full length with bottom of filters set in continuous channel, Grease gutter on rear and side in each piece, as per requirement, of flushed glass lights. All sheets to be prepolished plastic coated 202 grade complete as required as per technical specification.	1.00	Set

15500.00	15500.00	23000.00	23000.00	18000.00	18000.00
21000.00	21000.00	27000.00	27000.00	21000.00	21000.00
8000.00	8000.00	11500.00	11500.00	9000.00	9000.00
19500.00	58500.00	23000.00	69000.00	18000.00	54000.00
10000.00	10000.00	16000.00	16000.00	12000.00	12000.00
12000.00	12000.00	12500.00	12500.00	14000.00	14000.00
46400.00	46400.00	53000.00	53000.00	49000.00	49000.00

30.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table with Sink Unit of size 1350mm x 700mm x 850mm + 150mm , 16 Gauge S.S. Top. 150mm High Rear splash. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 no. 38mm Dia. S.S. legs. With S.S. adjustable bullet feet. Centre of unit One (1) no. 4500mm x 450mm x 300mm deep 16 Gauge. S.S. sink. with one under shelf 18 guase welded to legs at Rear. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
31.00	Fabricating, Providing, Installing, Testing & Commissioning of Idli steamer of min 54 idlies operated the unit will be double walled Completely out of 18 swg. Ss sheet with insulation in between. The idly trays to be out of 18 swg. Ss with 16 swg. Aluminium Drip tray under each ss idli tray. The unit will have one door. The doors will Also be insulated with steam effective rubber gasket beading ½ " ss valve Control will be provided for steam control and safety valves will be Provided in the steam pipe. The steamer is operated on a low- pressure steam boiler fitted underneath. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
32.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With 2 under size of 600mm x 600mm x 850++150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm T.nick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
33.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With under size of 1350mm x 700mm x 850+150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
34.00	Fabricating, Providing, Installing, Testing & Commissioning of Two Door Under Counter Refer of size 1400mm x 700mm x 850mm. 18 Gauge SS top/ SS 304 interior and exterior. 150mm High Rear splash. All sides turned down 50mm & in 12mm. Top and body secured to 12/25mm x 100mm x 25/12mm, 1.2 mm Thick S.S. hat type welded channel frame work. Underside of the top shall be sound deadened. 2nos. SS removable & adjustable shelves. 2 nos. sufring doors with insulation. Accommodates 1/1 G.N pan. Ambient temperature 43 deg C. Internal Temp 2 Deg C to 4 Deg C, Air-cooled, Refrigerant "kirlskar/ techumseh" with complete unit (Gas: R-134 A) Digital read out thermometer. cord with time delay auto start, Forced draft cooling. 38mm Dia S.S. tubular legs, with S.S. adjustable bullet feet, 50mm thick P.U. foam on all sides, Drip tray with heating (for condensate water evaporation). All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
35.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With 2 under size of 700mm x 750mm x 850++150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
36.00	Fabricating, Providing, Installing, Testing & Commissioning of Single Sink Unit with 3 side crossing of size 600mm x 700mm x 850mm + 150mm , 16 Gauge S.S. Top. 150mm High Rear splash. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work.. 4 no. 38mm Dia. S.S. legs. With S.S. adjustable bullet feet. Centre of unit One (1) no.400mm x 400mm x 250mm deep 16 Gauge. S.S. sink. 25mm Dia S.S. pipe cross bracing welded to legs at Rear & both sides. Front open. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set

17000.00	17000.00	26000.00	26000.00	18000.00	18000.00
38000.00	38000.00	26000.00	26000.00	21000.00	21000.00
7000.00	7000.00	10000.00	10000.00	9000.00	9000.00
13500.00	13500.00	23000.00	23000.00	18000.00	18000.00
60700.00	60700.00	70000.00	70000.00	70000.00	70000.00
8500.00	8500.00	12500.00	12500.00	10000.00	10000.00
11000.00	11000.00	13000.00	13000.00	14000.00	14000.00

37.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With 2 under size of 700mm x 750mm x 850+150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
38.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With under size of 1350mm x 700mm x 850mm. 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom & middle shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
39.00	Fabricating, Providing, Installing, Testing & Commissioning of gas operated Chapatti Plate With Puffer of size (1500mm X 750mm X850mm+150mm). 16mm thick M.S. Griddle Plate with front. gutter & S.S. grease drawer. Plate and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. Exterior 20 Gauge. S.S. cladding. Built in pressure Controller regulator. 38mm x 38mm x 16 Gauge S.S. Square pipe legs with adjustable bullet feet. 25mm x 25mm S.S. square pipe Under shelf. Four (4) no. "V" type H.P. burner with pilot lamp. 100mm setback Body/legs for Gauges pipe routing. Smooth Plate complete as required as per technical specification.	1.00	Set
40.00	Fabricating, Providing, Installing, Testing & Commissioning of Mobile Chapatti Collection Trolley of Size 600mm x 750mm x 850mm and 14 Gauge. S.S. top channel shape. Four (4) no. 38mm dia uprights on Castors. Two (2) no 18 Gauge S.S pan with All sides turned up 100mm & hemmed outside welded to S S legs. Four (4) no. heavy duty 125mm dia Non-marking rubberized castors all with brakes. Under sides of top shall be reinforced with 25 X 100 X 25 16 Gauge S.S inverted channel including accessories. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
41.00	Fabricating, Providing, Installing, Testing & Commissioning of Griddle Plate of size (1100mm X 750mm X850mm. 16mm thick M.S. Griddle Plate with front. gutter & S.S. grease drawer. Plate and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hut type welded channel frame work. Exterior 20 Gauge. S.S. cladding. Built in pressure Controller regulator. 38mm x 38mm x 16 Gauge S.S. Square pipe legs with adjustable bullet feet. 25mm x 25mm S.S. square pipe Under shelf. Three (2) no. "V" type H.P. burner with pilot lamp. 100mm setback Body/legs for Gauges pipe routing. Smooth Plate complete as required as per technical specification.	1.00	Set
42.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With 2 under size of 700mm x 750mm x 850+150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom & middle shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
43.00	Fabricating, Providing, Installing, Testing & Commissioning of Exhaust Hood of size 4210 mm X 2100mm X 500mm External and internal parts to be manufactured in SS 202, 18Gauge Welded Body Construction, Removable 22 Gauge S.S "V" section, measuring 510*510*50 mm thick, in full length w/bottom of filters set in continuous channel, Grease gutter on rear and side in each piece. All sheets to be pre-polished plastic coated 202 grade complete as required as per technical specification.	1.00	Set

8500.00	8500.00	12500.00	12500.00	10000.00	10000.00
13500.00	13500.00	23000.00	23000.00	18000.00	18000.00
35000.00	35000.00	45000.00	45000.00	25000.00	25000.00
11000.00	11000.00	18000.00	18000.00	14000.00	14000.00
27500.00	27500.00	36000.00	36000.00	20000.00	20000.00
8500.00	8500.00	12500.00	12500.00	10000.00	10000.00
157000.00	157000.00	130000.00	130000.00	35000.00	35000.00

44.00	Fabricating, Providing, Installing, Testing & Commissioning of 320 Ltr Two Door Vertical Refrigerator of size 720mm x 750mm x 2050mm Exterior/Interior 20 Gauge S.S. cladding, 50mm thick puff insulation. Body secured to 12/25mm x 100mm x 25/12mm 22 gauge Thick S.S. welded channel frame work. Two (2) Nos. half size Insulated self closing type S.S doors, complete with handle, Gasket & Locking arrangement hinged at front, three (3) wire shelves removable S.S welded wire. Ambient temperature 43 deg C. Internal temp is 0 deg to + 4Deg Celsius. Air-cooled refrigerant with complete unit (Gas: R-134 A) Digital read out thermometer, cord with time delay auto start, Forced draft cooling, 38mm Dia S.S. tubular legs, with S.S. adjustable bullet feet, 50mm thick P.U. foam on all sides, Drip tray with heating, (for condensate water evaporation). All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	2.00	Set
45.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With 2 under size of 1200mm x 600mm x 850+150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom & middle shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
46.00	Supply, Installation, testing, commissioning of table top weighing scale with following features; Operating Temperature: 0 to 50 deg C Accuracy: 2 g Weighing Capacity: 20 kg Warranty: 1 Year Display Type: Digital Battery Voltage: 6 V Frequency: 50 Hz Material: Stainless Steel Power Supply: Mains & Battery Operated complete as required as per technical specification.	1.00	Set
47.00	Fabricating, Providing, Installing, Testing & Commissioning of SS Storage Rack 5 Tier of size 900mm x 500mm x 1800mm and Shelving shall be arranged as shown in the layout plan. 1800mm high overall on SS adjustable feet, constructed of 38mm x 38mm x 16 Gauge SS pipe. Each to have five shelves at equal distance of 18 Gauge SS with channels. Shelves to be bolted / fixed at each corner. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	5.00	Set
48.00	Fabricating, Providing, Installing, Testing & Commissioning of Mobile Ingredient Bin (Atta Maida Bin) of size (450mm x 300mm x 700mm). 18 Gauge Welded body constructions. All corners coved 20mm radius. 18 Gauge S.S. Half open able centre hinged lid with integral Handle. S.S. hat type channel Base. Four (4) No. 100mm High castor two with brakes. Rubber corner bumper on all four sides. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	4.00	Set
49.00	Fabricating, Providing, Installing, Testing & Commissioning of SS Dunnage Rack of size 1200mm x 600mm x 200mm with sectional 18 guage SS rods at equal distance ,500 high overall on SS adjustable feet, constructed of 38mm x 38mm x 16 Gauge SS pipe. Shelves to be bolted / fixed at each corner. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification.	2.00	Set
50.00	Fabricating, Providing, Installing, Testing & Commissioning of Platform Weighing Scale 600mm x 600mm x 900mm Freestanding electronic digital scale, S.S weighing platform of size approx. 550 mm w X 550 mm. Unit suitable to weigh up to 300 Kgs with 40 Gms increments, digital pillar mounted display, rechargeable battery backup , bottom structure is metal powder coated rust free Stainless steel platter. Electrical power-0.03 kw in 220-50-1ph including accessories Power cord. RS-232 Serial interface and complete complete as required as per technical specification.	1.00	Set

65000.00	130000.00	75000.00	150000.00	70000.00	140000.00
13000.00	13000.00	20000.00	20000.00	16000.00	16000.00
3000.00	3000.00	9000.00	9000.00	6500.00	6500.00
15000.00	75000.00	22000.00	110000.00	16000.00	80000.00
13500.00	54000.00	18000.00	72000.00	14000.00	56000.00
7000.00	14000.00	14500.00	29000.00	8000.00	16000.00
7800.00	7800.00	14000.00	14000.00	12000.00	12000.00

51.00	Fabricating, Providing, Installing, Testing & Commissioning of Onion / Potato Bin of size 750mm x600mm x900mm, 25mm x 25mm 14 gauge stainless steel outer frame work, have caster arrangements with lock and have perforation all around, have a false bottom, front, top rear & sides 4mm & 6mm thick stainless steel wire mesh. In rectangular form with hinged lid on the top with locking arrangement. The stainless steel sheet will be perforated all over to dip potatoes and onion airy and fresh. The bins will be mounted on four nos. heavy castor wheels providing and placing in position of Onion Potato Storage Bins complete as required as per technical specification.	1.00	Set
52.00	Fabricating, Providing, Installing, Testing & Commissioning of SS Vegetable Rack 5 Tier of size 900mm x 500mm x 1800mm and Shelving shall be arranged as shown in the layout plan. 1800mm high overall on SS adjustable feet, constructed of 38mm x 38mm x 16 Gauge SS pipe. Each to have five shelves at equal distance of 18 Gauge SS with channels. Shelves to be bolted / fixed at each corner. All sheets to be pre-polished plastic coated 304 grade complete as required as per technical specification.	3.00	Set
53.00	Supply , installation, testing & commissioning of 400 Ltrs deep freezer operable with AC 230 V, 50 Hz, temperature range < -18 degree C, PUF Thickness 60 mm, with UV grade plastic material for long lasting appearance, door lock arrangement, anti corrosive body, caster wheel for easy mobility , spring loaded hinges for effortless usage with complete as required as per technical specification.	2.00	Set
54.00	Fabrication , installation and testing of 9 compartment MS staff locker 2000mmx600mmx 100 mm overll size with compartmentalised shelf complete as required as per technical specification.	2.00	Set
55.00	Fabricating, Providing, Installing, Testing & Commissioning of Plat Pickup Counter of size 1100mm x 700mm + 300mm x 850mm. 18 Guase Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hut type welded channel frame work. 4 No. 38mm Dia. S.S. legs with adjustable bullet feet. Full width 18 Gauge S.S. Bottom shelves. 3 side Covering 20 Guase, All Sheets to Be Pre-Polished Plastic Coated 304 Grade S.S. and complete as required as per technical specification.	2.00	Set
56.00	Fabricating, Providing, Installing, Testing & Commissioning of Hot bain marie of size 2100mm x 675mm + 300mm x 850mm. (6 Nos. 1/1 GN Pan - 5 NOS HOT & 1 NO. NORMAL TEMP.) 18 Guase Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm Dia. S.S. legs with adjustable bullet feet. Full width 18 Gauge S.S. Bottom shelves. 3 side Covering 20 Guase, bain marie double walled insulated puf type glass wool. Electric load: Heating element shall be 3 kw - 440 V -3Ø. There shall be water inlet of 12mm dia and waste connection with valve of 38mm dia. All sheets to be pr-polished plastic coated 304 grade S.S and complete as required as per technical specification.	1.00	Set
57.00	Fabricating, Providing, Installing, Testing & Commissioning of Ambient bain marie of size 800mm x 700mm + 300mm x 850mm. (2 Nos. 1/1 GN Pan) 18 Guase Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 38mm Dia S.S. tubular legs, with S.S. adjustable bullet feet, All sheets to be pr- polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
58.00	Providing, Installing, Testing & Commissioning of display Unit (Refrigeration) of size (1200mm x 700 mm x 1300mm) 20 Gauge SS 304 Body. Internal temp +3 Deg C to + 14 Deg C. (Suitable temp for Pastry & Cake). Three (3) no. full length glass shelf. All interiors to be of S. S. Forced draft cooling. Light arrangement as per ID . With Humidity control. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
59.00	Supply, installation, testing & commissioning of VISI cooler with pre-coated metallic inner and outer cabinet for durability and enhanced cooling ,Castor wheels for easy movement,Corrosion-free aluminium door frame,LED lighting for better visibility,Adjustable shelves,Eco-friendly refrigerant complete as required as per technical specification.	1.00	Set

14000.00	14000.00	18500.00	18500.00	14000.00	14000.00
15000.00	45000.00	23000.00	69000.00	18000.00	54000.00
27400.00	54800.00	32500.00	65000.00	32000.00	64000.00
19000.00	38000.00	10000.00	20000.00	24000.00	48000.00
22500.00	45000.00	28000.00	56000.00	20000.00	40000.00
60000.00	60000.00	76000.00	76000.00	65000.00	65000.00
27000.00	27000.00	18000.00	18000.00	24000.00	24000.00
58000.00	58000.00	60000.00	60000.00	54000.00	54000.00
35000.00	35000.00	75000.00	75000.00	45000.00	45000.00

60.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table With 2 under size of 1600mm x 600mm n x 850+150mm, 150mm High Rear splash, 16 Gauge S.S. Top. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 No. 38mm x38mm S.S. square pipe legs with adjustable bullet feet. Full with 18 Gauge S.S. Bottom & middle shelves. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	2.00	Set
61.00	Fabricating, Providing, Installing, Testing & Commissioning of Work Table with Sink Unit of size 1350mm x 700mm x 850mm + 150mm , 16 Gauge S.S. Top. 150mm High Rear splash. Top and body secured 38mm x 38mm x 3mm Thick M.S. welded angle frame work, hat type welded channel frame work. 4 no. 38mm Dia. S.S. legs. With S.S. adjustable bullet feet. Centre of unit One (1) no. 4500mm x 450mm x 300mm deep 16 Gauge. S.S. sink. with two under shelf 18 guase welded to legs at Rear. All sheets to be pr- polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
62.00	Fabricating, Providing, Installing, Testing & Commissioning of Salamander (Wall Mounted) of size 750 mm x 400 mm x 350 mm. S.S. Body construction. Complete with concealed fuel riser. Unit shell be Wall Mounted. S.S. Grid to be self spring adjustable at 3 locking positions with S.S. front & Back. Outer and internal 20 Gauge S.S. cladding. Suitably insulated, heating elements clamped on underside of top. high heat broiling thermostat. On-off controls on right. Electric Power:- 3.0 kw. Power Supply:- 220.50.1HP including accessories Power Cord with Plug including accessories. All sheets to be pr-polished plastic coated 304 grade complete as required as per technical specification.	1.00	Set
63.00	Supply & Instalation of 20 Ltrs. solo MICROWAVE OVEN with maximum Output Power 700 Watt single phase 240V operable with reheating feature complete as required as per technical specification.	43.00	Set
64.00	Supply & Installation of 1600W INDUCTION PLATE with 7 Pre-Defined Cooking,Soft-Touch Control with Digital Display,Higher Rated IGBT,Vessel Sensor & Auto Cut-Off,Timer 0-4 hrs,Efficient Cooling System Function complete as required as per technical specification.	43.00	Set
65.00	Supply, installation, testing , commissioning of minimum 195 Litres refrigerator toughened Glass Shelves 5 Star Energy Rating Reciprocatory Compressor Built-in Stabilizer Removable Gasket complete as required as per technical specification.(	43.00	Set
66.00	Supply, installation, testing , commissioning of jumbo size twin flying insect killer made up of mild steel with 2 nos. 40W lamps with minimum size of 50"x 6.5"x 20" covering area upto 1000 sqft , suitable to collect the dead insacts in the catchment tray at the bottom for easy disposal complete as required as per technical specification.	5.00	Nos.
67.00	Supply, Installation, Testing and Commissioning of Air curtain of 1.2 mtr. (approx.) Length having ABS body, single speed, continuous rating motor & maximum noise level 55 dB suitable for operating on 230V +5%, 50 Hz AC supply including provision of control switchgears for interlocking / synchronizing the operation of sliding doors, etc. as required and as per enclosed specification. Note: Air curtain will be operational only when sliding gates are in open position.	6.00	Nos.

17500.00	35000.00	26000.00	52000.00	22000.00	44000.00
17000.00	17000.00	23000.00	23000.00	18000.00	18000.00
113000.00	113000.00	115000.00	115000.00	16000.00	16000.00
5800.00	249400.00	7000.00	301000.00	13500.00	590500.00
2800.00	120400.00	3000.00	129000.00	2500.00	107500.00
12500.00	537500.00	20000.00	660000.00	13500.00	590500.00
3100.00	15500.00	8500.00	42500.00	4500.00	22500.00
15300.00	91800.00	23000.00	138000.00	18000.00	108000.00

Total in Figures

3249800.00

4179000.00

3411800.00