

Government eProcurement System
Created By: RISHI RAJ BAGRE
Created Date/Time: 19-Jan-2023 04:19 PM
Tender Title: Replacement of Inset Type GLF Fittings and Modification of GLF System at D.A.B.H. Airport, Indore.
Tender ID: 2022_AAI_139295_1

Tender Inviting Authority: <AGM(E-E) DABH AIRPORT,INDORE>
Name of Work: <Replacement of Inset Type GLF Fittings and Modification of GLF System at D.A.B.H. Airport, Indore >

Contract No: <AAI/ID/ENGG(E)/eNIT-13/2022-23>

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Balaji Engineering(GSTN-33ADGPV2628A1ZV)		AMA Private Limited(GSTN-27AAACA1016F1ZE)		Vardhman Airport Solutions Pvt Ltd(GSTN-07AAECN5914F1ZK)		Techno Electricals(GSTN-24AAGFT9086M1ZG)		Manish Electricals(GSTN-23ABLPm9012E1ZW)		Anil Kumar Sharma(GSTN-01AIWPS0647K1ZU)		YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED(GSTN-NA)		L1 Amount	L1 Vendor
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
1.00	Supply of 2 x 105 W Inset type Bi-directional High Intensity Runway Edge Light fittings, complete with prism assembly, optical assembly, 'O' ring seal, pressure relief test plug, 6.6 A halogen lamps, filters (White/ Yellow OR White/ White) , shallow base, die cast aluminium inner body & outer cover and other accessories etc. meeting ICAO standards complete as required.	23.00	Nos.	60000.00	1380000.00	55000.00	1265000.00	52000.00	1196000.00	57500.00	1322500.00	62000.00	1426000.00	59000.00	1357000.00	56500.00	1299500.00	1196000.00	Vardhman Airport Solutions Pvt Ltd
2.00	Supply of 3 x 105 W Inset type Bi-directional High Intensity Runway End/ Threshold Light fittings, complete with prism assembly, optical assembly, 'O' ring seal, pressure relief test plug, 6.6 A halogen lamps, filters (Green/ Red) , shallow base, die cast aluminium inner body & outer cover and other accessories etc. meeting ICAO standards complete as required.	15.00	Nos.	60000.00	900000.00	58000.00	870000.00	60000.00	900000.00	63000.00	945000.00	64000.00	960000.00	65000.00	975000.00	61200.00	918000.00	870000.00	AMA Private Limited
3.00	Supply of 2 x 105 W Inset type Uni-directional High Intensity Runway Threshold Light fittings, complete with prism assembly, optical assembly, 'O' ring seal, pressure relief test plug, 6.6 A halogen lamps, filters (Green) , shallow base, die cast aluminium inner body & outer cover and other accessories etc. meeting ICAO standards complete as required.	27.00	Nos.	60000.00	1620000.00	58000.00	1566000.00	52000.00	1404000.00	57500.00	1552500.00	59600.00	1609200.00	59000.00	1593000.00	58700.00	1584900.00	1404000.00	Vardhman Airport Solutions Pvt Ltd
4.00	Supply of Omni-directional inset type medium intensity LED Taxiway edge light fitting with blue LED meeting ICAO standards complete with lens, filters, shallow base etc. complete as required.	35.00	Nos.	4000.00	140000.00	38000.00	1330000.00	35000.00	1225000.00	41000.00	1435000.00	46000.00	1610000.00	30000.00	1050000.00	42000.00	1470000.00	140000.00	Balaji Engineering
5.00	Supply of following size 5KV grade PVC/XLPE insulated & PVC sheathed stranded copper conductor Airport lighting cable confirming IS 1554 (Part-II)/IS 7098 (Part-II) with upto date amendent and confirming to particular specification etc. as required.																		
5.10	1X6 sqmm	2000.00	Mtr.	95.00	190000.00	92.00	184000.00	100.00	200000.00	95.00	190000.00	88.00	176000.00	90.00	180000.00	85.00	170000.00	170000.00	YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED
5.20	1x16 sq.mm.	2000.00	Mtr.	240.00	480000.00	185.00	370000.00	220.00	440000.00	207.00	414000.00	198.00	396000.00	180.00	360000.00	187.00	374000.00	360000.00	Anil Kumar Sharma

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Balaji Engineering(GSTN-33ADGPV2628A1ZV)	AMA Private Limited(GSTN-27AAACA1016F1ZE)	Vardhman Airport Solutions Pvt Ltd(GSTN-07AAECN5914F1ZK)	Techno Electricals(GSTN-24AAGFT9086M1ZG)	Manish Electricals(GSTN-23ABLPm9012E1ZW)	Anil Kumar Sharma(GSTN-01AIWPS0647K1ZU)	YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED(GSTN-NA)									
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	L1 Amount	L1 Vendor		
6.00	Supply of 61 core x 1.50 sq.mm., 1.1 KV grade PVC sheathed, XLPE insulated, armoured, copper conductor control cable conforming to IS 7098 (Part-I) with upto date amendents etc. as required.	1250.00	Mtr.	1700.00	2125000.00	1250.00	1562500.00	1200.00	1500000.00	1370.00	1712500.00	1650.00	2062500.00	1400.00	1750000.00	1245.00	1556250.00	1500000.00	Vardhman Airport Solutions Pvt Ltd
7.00	Supply of 6 core x 1.50 sq.mm. copper conductor XPLE insulated, PVC sheathed industrial grade unarmoured cable conforming to IS 7098 (Part-I) with upto date amendents etc. as required.	100.00	Mtr.	350.00	35000.00	65.00	6500.00	150.00	15000.00	150.00	15000.00	250.00	25000.00	220.00	22000.00	111.00	11100.00	6500.00	AMA Private Limited
8.00	Supply, installation, testing, commissioning of Guidance signage board (IP 65 protection) complying ICAO standard of various sizes fabricated from anodized aluminium profile structure & 2 mm thick aluminium sheet, 4mm thick non-specular surface polycarbonate signage sheet, symbols of sign shall be made of self-adhesive 3M film applied on face of polycarbonate sheet and All reflector sheet for light reflection if required. Board shall be illuminated with linear LED's & driver(s) i/c all other accessories, suitable to operate on 2.8 Amp to 6.6 Amp AC constant current as incoming supply, mounting legs with breakable coupling & base frame, crimping & molding secondary leads with connector kit of OEM approved, etc. with all accessories, providing cement concrete foundation of suitable size & depth for each unit, providing pedestal up to 1.5mtr all around the signage with 1:2.4 CC of 150mm thick & finish with neat cement plaster, connections / interconnections with isolating transformers complete as required and conforming to tenders technical specifications etc. complete as required.	7.00	Sq. Mtr.	32000.00	224000.00	40000.00	280000.00	40000.00	280000.00	48525.00	339675.00	38000.00	266000.00	45000.00	315000.00	52000.00	364000.00	224000.00	Balaji Engineering
9.00	Supply of 15 Watt, 6.6A/ 6.6 A, 5 KV Grade 50 Hz. Isolating transformer suitable to operate upto 7.5 Watt, LED light of medium intensity light fitting encapsulated in polyester resin finally moulded in neoprene rubber with primary and secondary connection as specified in particular specifications.	50.00	Nos.	3000.00	150000.00	2550.00	127500.00	2750.00	137500.00	2950.00	147500.00	2900.00	145000.00	2800.00	140000.00	2850.00	142500.00	127500.00	AMA Private Limited
10.00	Supply of 150 Watt, 6.6A/ 6.6 A, 5 KV Grade 50 Hz. Isolating transformer suitable to operate upto 80 Watt, LED Signage Board encapsulated in polyester resin finally moulded in neoprene rubber with primary and secondary connection as specified in particular specifications.	6.00	Nos.	3500.00	21000.00	4000.00	24000.00	4750.00	28500.00	4500.00	27000.00	4600.00	27600.00	5000.00	30000.00	4510.00	27060.00	21000.00	Balaji Engineering
11.00	Supply of 300 Watt 20/6.6 A Amps 5 KV grade 50 Hz isolating transformers, series type encapsulated in neoprene rubber with primary and secondary leads as specified in particular specifications suitable for 300 Watt Threshold & End light fittings.	15.00	Nos.	5500.00	82500.00	5500.00	82500.00	6500.00	97500.00	6000.00	90000.00	6200.00	93000.00	6000.00	90000.00	6200.00	93000.00	82500.00	Balaji Engineering, AMA Private Limited

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Balaji Engineering(GSTN-33ADGPV2628A1ZV)		AMA Private Limited(GSTN-27AAACA1016F1ZE)		Vardhman Airport Solutions Pvt Ltd(GSTN-07AAECN5914F1ZK)		Techno Electricals(GSTN-24AAGFT9086M1ZG)		Manish Electricals(GSTN-23ABLPm9012E1ZW)		Anil Kumar Sharma(GSTN-01AIWPS0647K1ZU)		YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED(GSTN-NA)		L1 Amount	L1 Vendor
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
12.00	Supply of C.I. Isolating Transformer housing box, water tight round type,metal container of outside size 330 mm, height 300 mm made of 10mm thick cast iron moulding suitable to receive a light fitting/ CI base plate on the top and underground housing associated with transformer power cable and having clear hole centre at one/ two side surface, 170 mm above bottom surface suitable to receive one /two nos. of 50mm dia "B" class GI pipe and one no. hole at suitable height for 25 mm dia GI pipe for laying secondary lead and including check nuts as required. The box should have two SS earth bolts of M10 x 30mm tapped inside near the hole (4" away from the hole centre) and having a drain hole at the bottom suitably tapped to receive 15mm dia "B" class GI pipe and having clear opening of 220 mm at the top surface and 6 nos. M10 tapped hole at the hole centre 260 mm to receive fitting base plate and bolts complete as required.																		
12.10	Single Hole Type	4.00	Nos.	5000.00	20000.00	4900.00	19600.00	4500.00	18000.00	5300.00	21200.00	5200.00	20800.00	4000.00	16000.00	4500.00	18000.00	16000.00	Anil Kumar Sharma
12.20	Double Hole Type	25.00	Nos.	5000.00	125000.00	4900.00	122500.00	4500.00	112500.00	5300.00	132500.00	5300.00	132500.00	4200.00	105000.00	4500.00	112500.00	105000.00	Anil Kumar Sharma
13.00	Supply of 10 mm. thick round MS dummy plate of dia 330 mm. and having 6 nos. M10 tapped hole at the hole centre 260 mm. suitable for fixing over above CI Housing Boxes, alongwith supply of 6 Nos. Stainless Steel M10x40 bolts and suitable neoprene gasket etc. complete as required.	42.00	Set	1200.00	50400.00	750.00	31500.00	700.00	29400.00	920.00	38640.00	800.00	33600.00	750.00	31500.00	1150.00	48300.00	29400.00	Vardhman Airport Solutions Pvt Ltd
14.00	Supply of 5KV grade plug & suitable receptacle (essna connector) of type-1 class B connector & suitable field attachment suitable for 6 sq. mm. 5KV grade PVC/ XLPE insulated PVC sheathed single core stranded copper conductor cable as required.	30.00	Set	450.00	13500.00	425.00	12750.00	350.00	10500.00	425.00	12750.00	450.00	13500.00	550.00	16500.00	600.00	18000.00	10500.00	Vardhman Airport Solutions Pvt Ltd
15.00	Supply of 63 mm. dia. (OD-63 mm. & ID- 51 mm. nominal) DWC HDPE pipe ISI marked alongwith all accessories like socket, bend, couplers etc.conforming to relevant IS as required.	1000.00	Mtr.	100.00	100000.00	60.00	60000.00	60.00	60000.00	75.00	75000.00	68.00	68000.00	80.00	80000.00	59.00	59000.00	59000.00	YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED
16.00	SITC of 500 mm. x 500 mm. x 350 mm. (depth) cable termination box for 61 core x 1.50 sq.mm. copper conductor control cable, made up of 16 SWG MS sheet steel duly powder coated painted in approved shade, with suitable asbestos connectors for making connection of control wires of incoming and outgoing control cables, 2 mm. thick gland plate, with hinged door and locking arrangement, suitable fixing arrangement etc. as required. The termination box to be installed on wall with suitable arrangement/ anchor fastener etc. in approved manner complete as required.	2.00	Job	10000.00	20000.00	10000.00	20000.00	5500.00	11000.00	9000.00	18000.00	12000.00	24000.00	5000.00	10000.00	32000.00	64000.00	10000.00	Anil Kumar Sharma

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Balaji Engineering(GSTN-33ADGPV2628A1ZV)		AMA Private Limited(GSTN-27AAACA1016F1ZE)		Vardhman Airport Solutions Pvt Ltd(GSTN-07AAECN5914F1ZK)		Techno Electricals(GSTN-24AAGFT9086M1ZG)		Manish Electricals(GSTN-23ABLP M9012E1ZW)		Anil Kumar Sharma(GSTN-01AIWPS0647K1ZU)		YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED(GSTN-NA)		L1 Amount	L1 Vendor
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
17.00	Installation of Transformer housing boxes in finished shoulder area of taxi/apron having size of 330mmX300mm by core cutting in concrete/asphalt area of size 340mm dia., up to 375mm deep, grouting the box by Dobefill 50mm thick and top to be sloped with 1:2:4 cement concrete, disposal of excavated material within 50 mtrs lead, providing and fixing 150mm long 15mm dia "B" class GI pipe at base with check nut for drainage of water. The boxes to be aligned in such way that the hole centers fall in straight line etc. complete as required	25.00	Job	2000.00	50000.00	3200.00	80000.00	1500.00	37500.00	5500.00	137500.00	2200.00	55000.00	5000.00	125000.00	4000.00	100000.00	37500.00	Vardhman Airport Solutions Pvt Ltd
18.00	Installation of Transformer housing boxes with a base concrete of 1:3:6 of size 630x630x100 mm thick all round concrete of 1:2:4, 150mm thick,the top sloped with 1:2:4 cement concrete including providing and fixing 250 mm long 15mm dia "B" class GI pipe with check nut for drainage of water including excavation of side shoulder and refilling (wherever the transformers boxes are to be installed in a line the same has to be aligned in such a way that the centre fall in a straight line) etc. complete as required.	4.00	Job	2000.00	8000.00	3500.00	14000.00	1500.00	6000.00	3000.00	12000.00	1200.00	4800.00	5000.00	20000.00	1500.00	6000.00	4800.00	Manish Electricals
19.00	Installation, Testing and Commissioning of inset type runway edge/ end/ threshold light fittings in existing void/ core, created after removing existing fitting, including installation of Shallow base precisely matching holes of secondary lead pipes, filling dobefil and hardener all around the shallow base for suitable mounting of the inset fitting, levelling, making connections, fixing inset light fitting over the shallow base alongwith all accessories, alignment, testing, commissioning etc. complete as required.	55.00	Job	7000.00	385000.00	5700.00	313500.00	5500.00	302500.00	5400.00	297000.00	4800.00	264000.00	5000.00	275000.00	5500.00	302500.00	264000.00	Manish Electricals
20.00	Installation, Testing and Commissioning of Omni-directional Inset type LED Taxiway/ Apron edge light beside existing CI transformer housing box located on apron/ taxiway edge, after making suitable size void by core cutting in bitumin/ PQC pavement area of apron/ taxiway edge for installation and fixing the shallow base with dobefil and hardener inclusive of connection with secondary cable, transformer etc., including making suitable size hole on the CI transformer housing box for entry/ exit of secondary lead, kerf cutting of suitable width and depth between inset type fitting and CI transformer housing box and providing & laying 2 core x 2.5 sq.mm. secondary lead of suitable length in 25 mm. dia medium class GI, in the kerf including refilling the same by suitable sealing material etc., levelling, making connections, fixing inset light fitting over the shallow base alongwith all accessories, testing, commissioning etc. complete as mentioned in the technical specifications and as per instructions of E-I-C.	17.00	Job	7000.00	119000.00	5700.00	96900.00	5250.00	89250.00	4500.00	76500.00	4500.00	76500.00	4000.00	68000.00	5200.00	88400.00	68000.00	Anil Kumar Sharma

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Balaji Engineering(GSTN-33ADGPV2628A1ZV)		AMA Private Limited(GSTN-27AAACA1016F1ZE)		Vardhman Airport Solutions Pvt Ltd(GSTN-07AAECN5914F1ZK)		Techno Electricals(GSTN-24AAGFT9086M1ZG)		Manish Electricals(GSTN-23ABLPm9012E1ZW)		Anil Kumar Sharma(GSTN-01AIWPS0647K1ZU)		YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED(GSTN-NA)		L1 Amount	L1 Vendor
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount		
21.00	Installation, Testing and Commissioning of Omni-directional Inset type LED Taxiway/ Apron edge light beside existing CI transformer housing box located on apron/ taxiway edge, after making suitable size void by core cutting in bitumin/ PQC pavement area of apron/ taxiway edge for installation and fixing the shallow base with dobefil and hardener inclusive of connection with secondary cable, transformer etc., kerf cutting of suitable width and depth between inset type fitting and CI transformer housing box and providing & laying 2 core x 2.5 sq.mm. secondary lead of suitable length in 25 mm. dia medium class GI pipe, in the kerf including refilling the same by suitable sealing material etc., levelling, making connections, fixing inset light fitting over the shallow base alongwith all accessories, testing commissioning etc. complete as mentioned in the technical specifications and as per instructions of E-I-C.	25.00	Job	7000.00	175000.00	5700.00	142500.00	5250.00	131250.00	4500.00	112500.00	4500.00	112500.00	4000.00	100000.00	5200.00	130000.00	100000.00	Anil Kumar Sharma
22.00	Cutting groove of size 120 mm. wide and 150 mm. deep (or as required) with saw cutting/ Bitumin/ Concrete cutting machine, laying of 63 mm. dia OD HDPE pipe, refilling and finishing the surface with 1:1:2 cement concrete and a layer of ready mix bitumin/ road bond for bituminous surface, etc. complete as required.	650.00	Mtr.	450.00	292500.00	300.00	195000.00	225.00	146250.00	400.00	260000.00	650.00	422500.00	700.00	455000.00	400.00	260000.00	146250.00	Vardhman Airport Solutions Pvt Ltd
23.00	Laying of 1 no. 63 mm dia OD DWC Pipe along with all accessories like sockets, bends, couplers etc. complete with fitting, cutting and jointing etc. direct in ground including excavation, trenching (75 cm below ground level, for LT cable) and refilling the trench but excluding sand cushioning and protective covering etc. complete as required.	250.00	Mtr.	80.00	20000.00	20.00	5000.00	80.00	20000.00	120.00	30000.00	120.00	30000.00	100.00	25000.00	40.00	10000.00	5000.00	AMA Private Limited
24.00	Laying of 1 no. 63 mm dia OD DWC Pipe along with all accessories like sockets, bends, couplers etc. complete with fitting, cutting and jointing etc. direct in ground including excavation, trenching (80 cm below ground level, for AFL cable) and refilling the trench but excluding sand cushioning and protective covering etc. complete as required.	80.00	Mtr.	80.00	6400.00	20.00	1600.00	80.00	6400.00	125.00	10000.00	140.00	11200.00	100.00	8000.00	40.00	3200.00	1600.00	AMA Private Limited
25.00	Laying of one number PVC/ XLPE insulated and PVC sheathed / XLPE power cable of 5 KV grade single core of size 16 sq.mm./ 6 sq.mm. in the existing RCC/ HUME/ METAL pipe/ HDPE Pipe as required.	1280.00	Mtr.	25.00	32000.00	20.00	25600.00	15.00	19200.00	20.00	25600.00	30.00	38400.00	25.00	32000.00	12.00	15360.00	15360.00	YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED
26.00	Laying of one number PVC/ XLPE insulated and PVC sheathed / XLPE power cable of 1.1 KV grade 61 core x 1.50 sq.mm. copper conductor cable in the existing RCC/ HUME/ METAL pipe/ HDPE Pipe as required.	250.00	Mtr.	25.00	6250.00	20.00	5000.00	15.00	3750.00	20.00	5000.00	30.00	7500.00	25.00	6250.00	12.00	3000.00	3000.00	YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Balaji Engineering(GSTN-33ADGPV2628A1ZV)	AMA Private Limited(GSTN-27AAACA1016F1ZE)	Vardhman Airport Solutions Pvt Ltd(GSTN-07AAECN5914F1ZK)	Techno Electricals(GSTN-24AAGFT9086M1ZG)	Manish Electricals(GSTN-23ABLP9012E1ZW)	Anil Kumar Sharma(GSTN-01AIWPS0647K1ZU)	YPR ENGINEERING AND SOLUTIONS PRIVATE LIMITED(GSTN-NA)	L1 Amount	L1 Vendor							
				Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount	Rate	Amount				
27.00	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on surface of wall/ culvert etc. as required.																		
27.10	61 core x 1.50 sq.mm. (clamped with 25x3mm MS flat clamp)	920.00	Mtr.	80.00	73600.00	30.00	27600.00	25.00	23000.00	40.00	36800.00	90.00	82800.00	50.00	46000.00	60.00	55200.00	23000.00	Vardhman Airport Solutions Pvt Ltd
28.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade 61 core x 1.50sq.mm. copper conductor cable in existing masonry open duct as required.	30.00	Mtr.	100.00	3000.00	20.00	600.00	15.00	450.00	40.00	1200.00	30.00	900.00	50.00	1500.00	40.00	1200.00	450.00	Vardhman Airport Solutions Pvt Ltd
29.00	Making field connections by crimping of 6/16 sq.mm. plug & receptable with existing 6/16 sq.mm. single core PVC Cu. Conductor cable including filling the gap with water sealant material applying PVC insulation tape etc. complete as required.	29.00	Job	200.00	5800.00	150.00	4350.00	100.00	2900.00	85.00	2465.00	250.00	7250.00	100.00	2900.00	200.00	5800.00	2465.00	Techno Electricals
30.00	Supplying and making end termination with brass compression gland and copper lugs for 61 core x 1.50 sq.mm. of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required.	2.00	Job	200.00	400.00	900.00	1800.00	1500.00	3000.00	1000.00	2000.00	1000.00	2000.00	500.00	1000.00	600.00	1200.00	400.00	Balaji Engineering
31.00	Making connection of 1 no. CCR (located at CCR Room) with remote control desk situated at ATC Tower, in order to control the CCR from ATC Tower. The item also include providing & fixing of copper lugs/ thimbles etc. as required for making connection.	4.00	Job	5000.00	20000.00	7500.00	30000.00	400.00	1600.00	750.00	3000.00	5000.00	20000.00	1000.00	4000.00	20000.00	80000.00	1600.00	Vardhman Airport Solutions Pvt Ltd
32.00	Dismantling of existing inset type runway edge/ end/ threshold light fitting complete including removing shallow base neatly by suitable means, carefully removing connections with secondary lead etc. and safely shifting the removed fitting to AAI store etc. as required.	55.00	Job	800.00	44000.00	700.00	38500.00	140.00	7700.00	1500.00	82500.00	1000.00	55000.00	200.00	11000.00	1500.00	82500.00	7700.00	Vardhman Airport Solutions Pvt Ltd

Total in Figures

8917350.00

8916300.00

8465650.00

9582830.00

10279050.00

9301650.00

9474470.00

Lowest Amount Quoted BY: Vardhman Airport Solutions Pvt Ltd(8465650.00)

Signature Not Verified

Digitally signed by Rishi Raj Bagre

Date: 2023.01.19 17:58:51 IST

Location: eProcurement System for Central PSUs

