



इस्कॉन इंटरनेशनल लिमिटेड
(भारत सरकार का उपक्रम)
IRCON INTERNATIONAL LIMITED
(A Govt. of India Undertaking)
An Integrated Engineering and Construction Company



Katni-Singrauli Rail Doubling Project,
1st Floor, Above Maruti Suzuki Show room,
Near Jhinhari Police Station,
NH-7, Jabalpur Road, Katni 483 501(M.P.)
email - ircon.2065@ircon.org

कटनी-सिंगरौली रेल दोहरीकरण परियोजना
प्रथम तल, मारुती सुजुकी शोरूम के उपर
झिंझरी, पुलिस चौकी के समीप, नेशनल हाईवे-7,
जबलपुर रोड, कटनी - 483 501 (म.प्र.)
ई-मेल - ircon.2065@ircon.org

No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306

Date: 24.12.2022

M/s D K Chauhan.
Near SBI Colony
Gorakhpur, Jabalpur
Madhya Pradesh
Pin :- 482001

(Letter of Acceptance)

Sub: Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni – Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh, PKG 10.

Ref:

(i) Tender No.: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116
dtd 14.12.2022.

(i) Bid opened on 21.12.2022.

Your offer for the work of "Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni – Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10" submitted vide references above, has been accepted by the Competent Authority of Ircon International Limited at the total Contract Value of Rs 17,89,58,332 (Rupees Seventeen Crore Eighty Nine Lakhs Fifty Eight Thousand Three Hundred Thirty Two only) including GST @ 18% at the accepted rates of items / schedules as per Annexure-A (attached herewith) to this letter and terms and conditions, incorporating all the corrigendum and addendums issued to the tender documents.


20.12.22

Page 1 of 3



1. In term of para 7.1 (i) of Special Conditions of Contract: you are requested to submit a Performance Guarantee (P.G.) within 21 days from date of LOA in the form irrevocable bank guarantee in favor of IRCON International, Katni on the Performa annexed as Annexure-X (from any Scheduled Bank for an amount of 3% (Three percent) of the contract value, i.e., Rs 53,68,750 /- (Rupees Fifty Three Lakhs Sixty Eight Thousand Seven Hundred Fifty only).
2. The entire work is required to be completed within **06 (Six) months** from the date of issue of this letter of acceptance.
3. Your kind attention is invited to the provision of Clause 16 of Special Conditions of Contract. You are required to submit/comply the following:
 - 3.1 In terms of clause 16.1, a programme for completion of work to the Engineer for his approval within 15 days from the date of receipt of letter of acceptance considering completion period as indicated in appendix to tender. Programme so submitted and agreed by IRCON will become part of the contract agreement. (For details, refer to Para 16.1 of SCC).
 - 3.2 In terms of clause 16.2, a detailed Execution/completion Programme with milestones/Key dates based on completion period as indicated in appendix to tender. These shall be incorporated in the Contract Agreement after approval by Engineer in charge (For details, refer to Para 16.2 of SCC).
 - 3.3 In terms of Clause No 16.3: Resource Deployment Program, within 15 days of award of contract, i.e. key personnel, manpower, Plant & Machinery and Other resources deployment program. These shall be incorporated in the Contract Agreement after approval by Engineer in charge.
 - 3.4 In terms of Clause No 16.4: within 15 days of award of contract, Cash flow statement and cumulative monthly progress plan (in the form of S curve). These shall be to be incorporated in the Contract Agreement after approval by Engineer in charge.
 - 3.5 In terms of Clause No 16.5: Within 18 days of award of contract, Method statement for various activities and Quality Assurance Plan (QAP) and start the work after their approval.
 - 3.6 In terms of Clause No 16.6: Within 15 days of the award of the contract, Organization chart of the project with the CV of the key personnel's to be deployed at the project site.
4. You are requested to attend this office for signing of the Contract Agreement on or before 28 days after issue of this letter as per clause no.: 13.5 of Special Conditions of Contract.


24.12.22

5. All other terms and conditions shall be as per Tender Documents and Corrigendums and Addendums, which shall form an integral part of this contract and shall be binding on you. Your letters at reference above shall form part of the Contract Agreement. This Letter of Acceptance, along with your submitted offer, shall constitute a binding Contract between you and Ircon International Limited, till a formal agreement is drawn and executed.
6. This Letter of Acceptance is being issued in duplicate and you are requested to return one copy of this Letter of Acceptance duly accepted, signed & stamped on each page by your authorized representative.
7. You are advised to mobilize the resources to commence the work. You are requested to contact Project Head, Katni Singrauli Doubling Project for further instructions at the following address:

Katni Singrauli Doubling Project,
Ircon International Limited,
First Floor, Over Maruti Suzuki showroom,
Near Jhinhari Police Station, NH-7, Jabalpur
Road, Katni – 483501 (M.P). MO: 7470376222

Thanking You

Enclosed:

- (i) Annexure-A, Bill of quantities.

For & on behalf of
IRCON International Limited



(Akhilesh Sahu)
CGM/PH

Copy to:

- (i) AGM/C-I, AGM/Fin/, JGM/Fin for information.
- (ii) DGM/C-I for information and necessary action.

Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
SCHEDULE A					
1	Earthwork in cutting (classified) in formation, trolley refuges, side drains, level crossing approaches, platforms, catch water drains, diversion of nallah & finishing to required dimension and slopes to obtain a neat appearance to standard profile inclusive of all labour, machine & materials and removing & leading all cut spoils either to make spoil dumps beyond 10m from cutting edge or for filling in embankment with leads within 2 km on either side of cutting edge, lifts, ascent, descent, loading, unloading, all taxes / royalty, clearance of site and all incidental charges, bailing & pumping out water, if required, etc. complete as per directions of the Engineer-in-Charge. The work is to be executed as per latest / updated edition of "Guidelines for Earthwork in Railway Projects" issued by RDSO, Lucknow. Cut trees shall be property of Railways and to be deposited in the railway godown unless specified otherwise in the Special Conditions of Contract. {Note - (i) All usable earth arising from cut spoils shall be led into bank formation and Unusable spoils shall be dumped / stacked (ii) All hard rock / and boulders not fit for filling will be stacked by the contractor and will be property of the Railways.}				
1a	In all condition and classification of soil except rock	3000	Cum	189.94	5,69,820.00
1b	Soft Rock not requiring blasting in all conditions	500	cum	425.35	2,12,675.00

[Signature]
24.12.22
D4M/c

Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
2	Earthwork in filling in embankment, guide bunds, around buried type abutments, bridge gaps, trolley refuges, rain bunds, if provided, platforms etc. with earth, suitable for embankment as per RDSO latest Specifications and guidelines GE: G-14 of Soil Quality Class SQ1, excavated from outside railway boundary entirely arranged by the contractor at his own cost including all leads, lifts, ascents, descents, crossing of nallah or any other obstructions. The item shall include demarcation and setting out of profile, site clearance, removing of shrubs, roots of vegetations growth, heavy grass, benching of existing slope of old bank, all handling/re-handling, spreading in layers with motor grader, bringing the moisture content to OMC, mechanical compaction to specified density and dressing of bank to final profile as a complete job. The payment shall be made as per finished profile and the rate shall include all costs including taxes, octroi, royalty etc. except for mechanical compaction which shall be paid extra under relevant item. Cut trees shall be property of railways and to be deposited in the railway go down unless specified otherwise in the Special Conditions of Contract.	5000	cum	379.85	18,99,250.00
3	Extra for mechanical compaction of soil in embankment with contractor's rollers of suitable capacity, type and size to achieve specified density as per specification, testing as per IS codes including cost of water, T&P, consumable and all labour as a complete job. The work is to be executed as per Latest edition of "Guidelines for Earthwork in Railway Projects" issued by RDSO, Lucknow	5000	cum	25.02	1,25,100.00

[Signature]
24.12.22

[Signature]
Dumile

Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
4	Providing and laying design mix control concrete M20/M25 in piers, retaining walls, wing walls, return walls, bottom/top plug of wells and protection work etc. using well graded stone aggregate of 40 MM/20 MM nominal size. The rate is inclusive of finishing, including centering and shuttering, strutting, propping etc. and removal of form using Admixtures in recommended proportions (as per IS:9103), if approved in Mix design to accelerate or retard setting of concrete and/or improve workability without impairing strength and durability including vibrating, pumping and bailing out of water where ever required with all materials, equipment and labours complete as per specifications and direction of the Engineer in charge. Payment for reinforcement only shall be paid extra.	1200	Cum	9992.16	1,19,90,592.00
5	Providing and laying Design mix control concrete M30/M35/M40 in cast-in-situ RCC works of raft, pile cap, pier, abutment, well steining, RCC well kerb, well cap, pier cap, Jacketing, dirt wall, return wall, wing wall, fly wing wall, retaining wall, approach slab, foot path slab, wearing course, ballast retainers, RCC railing, inspection platform, pedestal, boxes and other miscellaneous works using well graded stone aggregate of 20 MM nominal size. The rate is inclusive of finishing, including centering and shuttering, strutting, propping etc. and removal of form using Admixtures in recommended proportions (as per IS:9103), if approved in Mix design to accelerate or retard setting of concrete and/or improve workability without impairing strength and durability including vibrating, pumping and bailing out of water where ever required with all materials, equipment and labours complete as per specifications and direction of the Engineer in charge. Payment for reinforcement only shall be paid extra.	3175	Cum	11988.66	38063995.50

[Signature]
24.12.22

[Signature]
Dy. M. 12

Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
	This item and rate are for concreting done for jacketing, work under this item shall be payable and shall deem to include cost of surface preparation, drilling of holes, insertion of dowel bars and grouting of holes etc, required for the work but exclude cost of dowel bars which shall be payable separately under relevant BOQ item.				
6	Providing and laying dry stone backing behind abutments, wing walls, return walls, RCC boxes with stones not less than 15 CM in any direction and not less than 15 KG (except smaller boulders required for filling voids) in weight.	500	Cum	2958.85	14,79,425.00
7	Providing and laying pitching with stone boulders weighing not less than 35Kg. Each with voids filled with spalls on slopes, laid over prepared filter media including boulder apron laid dry in front of toe of embankment complete as per drawing and technical specification (filter media to be paid separately under the relevant item)	500	Cum	2919.17	14,59,585.00
8	Providing and laying backfill material behind boulder filling of abutments, wing walls, return walls consisting of granular materials of GW, GP, SW groups as per IS 1498-1970 in required profile.	800	Cum	2282.31	18,25,848.00
9	Providing and fixing bridge plaque (750 MM base, 720 MM height triangular section with 400 MM thickness) on both sides of parapet using cement concrete of specified mix including engraving bridge number, direction of flow and other details including painting the letters with enamel paint of black colour of approved quality with white back ground as per standards of railway as directed by the engineer.	4	Each	407.31	1,629.24

[Signature]
24.12.22

[Signature]
Dy M/c


Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
10	Providing and fixing river name boards of size 2.10 M x 1.0 M made of MS sheet 6 MM thick and ISA 50 x 50 x 5 MM frame all around, fixed on rail posts erected with railway's rails fixed in cement concrete base of size 60 CM x 60 CM x 75 CM of CC 1:2:4 including painting with two coats of paint of approved quality and colour over one coat of primer, writing the name of the river in vernacular and English in black colour with yellow back ground as directed by the engineer.	4	Each	7943.20	31,772.80
11	Providing and fixing of 100 MM dia PVC pipe for weep holes in abutments, wing walls, return walls, face wall, retaining wall etc at suitable intervals as directed by the Engineer-in-charge.	200	Meter	383.84	76,768.00
12	Providing and placing sand/earth filled bags in layers for protection of existing embankment.	5000	Each	13.81	69,050.00
13	Painting of HFL, Danger level, etc., with contractor's paint, labour, tools, equipment, consumables, all leads & lifts, etc., complete as per specification and as directed by Engineer-in-charge	4	Each	226.44	905.76
14	Supplying TMT Fe-500/Fe-500D* reinforcement steel conforming to IS:1786-1985 including decoiling, straightening, cutting, bending, placing in position, binding with 1MM dia GI binding wire. Note : 1. Reinforcement, shall be measured in length for different diameters used in the works and then paid as per standard weights as per IS 1732. Wastages, overlaps, coupling, welded joints, space bars, chairs and binding wire shall not be measured and cost of these items shall be deemed to be included in the rates. 2. * For seismic zone III, IV & V, only TMT Fe-500D steel shall be used.	495	MT	116139.41	5,74,89,007.95

Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
15	Rail piling upto 5m depth to protect the existing embankment with rails of any section supplied by the employer. The rate includes driving the rails with monkey hammer or any other means into the soil to the depth as directed by the Engineer, including all tools and plants consumable like fuel, lubricant, labour, other material required.	700.00	Meter	1133.56	7,93,492.00
16	Rail piling beyond 5m depth to protect the existing embankment with rails of any section supplied by the employer. The rate includes driving the rails with monkey hammer or any other means into the soil to the depth as directed by the Engineer, including all tools and plants consumable like fuel, lubricant, labour, other materials required. (Payment under this item shall be only for the depth beyond 5m)	600	Meter	1699.65	10,19,790.00
17	Providing and laying Filter Material as per RDSO Specifications underneath pitching in slopes complete as per drawing and Technical Specification	200	cum	3823.57	7,64,714.00
18	Providing Road vehicles mentioned below for the use of Engineer/Employer as per the condition mentioned in special conditions of contract-I			0.00	-
	Tata Sumo, Bolero, Scorpio or similar SUV (upto 3000 km in one month Extra will payable in 1 (b)	8	Vehicle Per Month	92609.43	7,40,875.44
19	Providing Service such as maintaining records of files movement, receiving & sending fax maintain files computer operator maintenance etc. (semi skilled) inclusive of all taxes	8	Man Month	30241.59	2,41,932.72

Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
20	Provision of barricading with contractor's bamboos / balli vertical post of 75 to 100mm dia. planted at every 2m interval, projecting at least 1.5m above ground level and driven firmly (minimum 0.5m) inside ground and including painting verticals & horizontals with red luminous paints / strips at alternative bay on barricade. Barricades shall be completely removed when no longer required by engineer in-charge. (60% payment shall be made on provision of barricading at work-site)			0.00	-
	Joining with strong nylon rope in one cross and one horizontal pattern of minimum 5mm dia.	1000	Running Meter	130.74	1,30,740.00
Total Schedule A					11,89,86,968.41




Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
SCHEDULE B					
1	Providing, driving and installing Bored cast in-situ Reinforced Cement Concrete piles of specified diameter and length below pile cap in M-35 grade Design Mix Cement Concrete, using 20mm graded crushed stone aggregate and coarse sand of approved quality, to carry a safe working load not less than specified, excluding the cost of casing pipe but including the cost of shoe and length of pile to be embedded in pile cap etc. complete, concreting by machine batching, machine mixing, scaffolding, using Admixture in recommended proportion (as per IS:9103), if approved in design Mix, placing with tremie pipe, chipping off of pile top to remove laitance concrete above cut off level etc., pumping and bailing out water with all labour material complete including crossing of tracks if required, as per approved drawing, specification and direction of the Engineer in charge. Length of the pile for payment shall be measured upto the bottom of pile cap excluding the mud mat. Payment for casing pipe & reinforcement shall be paid extra.				
1a	1200mm diameter (Pro rata rate will be paid for other than 1200 dia pile if there is increase/decrease dia of pile)	670	Rmt	20811.02	1,39,43,383.40
2	Providing, fabricating and installing casing pipe for bored piles for all diameters with specified thickness of steel plate including all labour, materials, pumping and bailing out water wherever required, complete as per technical specifications as directed by Engineer in charge. This will include the weight of plate only and no cognizance will be given for fittings, i.e. rivets and welding etc.	50	MT	103906.53	51,95,326.50

Annexure A


LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022

Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni – Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
3	Conducting load testing of a single pile upto following capacity in accordance with IS:2911 (Part-IV) including installation of loading platform and preparation of pile head or construction of test cap and dismantling of test cap after test etc. with all labour, material, tool & plants, equipment, machinery, etc. complete as per drawing and specification, as directed by the Engineer				-
3a	Initial load test above 100 ton capacity upto 250 ton capacity pile (for payment pile capacity means the pile capacity given in drawings)	4	Each	117175.76	4,68,703.04
3b	Extra for every increase of 50 T in pile capacity or part thereof over 250 T (for payment pile capacity means the pile capacity given in drawings)	20	Each	20094.83	4,01,896.60
3c	Routine Load Test above 100 ton capacity upto 250 ton capacity pile (for payment pile capacity means the pile capacity given in drawings)	4	Each	99604.70	3,98,418.80
4	Lateral load testing of single pile in accordance with "IS Code of practice IS:2911 (Part-IV) for determining safe allowable lateral load of pile" with all labour, material, tool & plants, equipment, machinery, etc complete as per drawing and specification as directed by the Engineer				-
4a	Piles with lateral load capacity of above 10 ton and upto 20Ton (for payment pile capacity means the pile capacity given in drawings)	1	Each	43137.64	43,137.64
4b	Piles with lateral load capacity of above 20 ton (for payment pile capacity means the pile capacity given in drawings)	1	Each	74759.00	74,759.00
5	Pulse Echo Test (PET) for integrity testing of piles with contractor's men, materials and machines. The rate includes cost of Inspection of site, preparation of pile head and any other unforeseen cost required for the test, submission of reports in triplicate as per satisfaction of the Engineer in Charge at site	48	each	38855.66	18,65,071.68
			Total Schedule B		2,23,90,696.66
			Total Schedule A+B		14,13,77,665.07

Annexure A



LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022

Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni – Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
SCHEDULE C					
1	Supplying, fabrication, assembling of all types of steel Composite girders of specified spans with structural steel conforming to Quality "B0" Grade Designation E250 conforming to IS:2062, erection / slewing / end launching of steel girders with cranes or any other approved launching methods as per site conditions on sub-structure including provision of stud bolts / shear connectors, complete as per approved QAP and drawings conforming to IRS-B1-2001 and other relevant codes and specifications. 1. Detailed fabrication and erection drawings & launching methodology will be prepared by the contractor and got approved from Railway. 2. Rate includes fabrication of all types of battens, bracings, ties, stiffeners, packing, diaphragms, shop rivets / welding, T&F bolts, drifts, SAW, templates, jigs, fixtures, accessories, transporting various components from fabrication shop to site including loading & unloading, assembly of girders with drifts/bolts, field riveting /welding /HSFG Bolting, assembling of temporary support for side slewing, raising of girders to the bed block level, providing sliding arrangements and slewing the girder in position, lowering of girder on bearings and bed plates with all temporary arrangements or any other method of launching complete. 3. The bearing sets to be provided with the girders will be paid separately as per relevant item.				

Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
	4. Payment for addition in weight for rivets / welds shall be made as per clause 45 of IRS B-1-2001. 5. In case of composite work (welding and HSFG bolts), addition in weight shall be 1% for welding and HSFG bolts shall be paid separately under relevant item. 6. Painting of girders will be paid separately under relevant item. 7. Payment Schedule: (i) Receipt of material at site: 40% (ii) Fabrication of girders: 20% (iii) Erection/Launching: 20% (iv) Completion in all respects: 20%				
1.a	Composite Steel Girder of span length upto 36.0 mt	175	MT	165438.02	28951653.5
2	Design, manufacturing, supplying and fixing in position elastomeric bearing true to line and level conforming to IS:3400, IS:226, BS-5400 under prestressed concrete girders/ Steel Girders, for Pre-cast as well as cast-in-situ girders as per approved drawing. The rate shall include cost of load test of one no. bearing from Railway approved firms and all fixing materials, equipments, machineries, labour, taxes, loading, unloading, leading, lifting etc. complete. Rates include getting the drawing approved from Railway and cost of inspection during manufacturing from railway approved organization. (Note : 1. The rate is for finished item complete and paid only after fixing in position below the girder. 2. The volume shall be given in the drawing and no deduction shall be made for inserted steel plates etc.)	175000	Cu Cm	1.92	336000.00

[Signature]

[Signature]
Dumil

Annexure A

LOA No IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116/1306 Date: 24.12.2022
Bill of Quantity (BOQ)

Name of work-Construction of additional underpasses, fencing, ramps, retaining walls, etc. as per the mitigation measures suggested by the forest department for the Bandhavgarh Tiger Corridor in the Vijaysota-Beohari Section in Katni - Singrauli Rail Line Doubling Project under West Central Railway in the state of Madhya Pradesh PKG 10.

NIT No: IRCON/2065/KSDP/tender/Structures/ BTC/ BEHR-VST/116 dtd 14.12.2022

BOQ Item no.	Description of Item	QTY	Unit	Rate in Rs.@18% GST	Amount in Rs.@18% GST
3	Supply, fabrication and erection of bed plate of approved sizes in exact position over bed block on pier/abutments by giving full and even bearing, setting them on the layer of free flow non-shrinkable grouting compound, scrapping or chipping of bed block, if required, fabrication and fixing of HD bolts of suitable sizes alongwith nuts, washers etc., drilling holes of required size, grouting of holes by epoxy mortar after fixing HD bolts. Total work to be done during traffic block.				0.00
a	More than 18.3 mt and upto 30.5 mt clear span	1760	kg	407.81	717745.60
4	Supplying and fixing HSFG bolts of any dia and any length with suitable nuts including DTI washers conforming to IRS-B1-2001 for bridges and steel structures with contractors labour, tools and plants and lead and lift etc.,	3000	kg	478.31	1434930.00
	Applying Epoxy Poly-sulphate Paint three coats on existing bottom surface of deck slab including cleaning surface of dirt, dust & other foreign matter, sand papering, wire brushing as required with all contractor's materials tools, machinery, scaffolding, lead, lifts etc. complete as per specifications and as directed by Engineer in-charge	500	Sqm	404.76	202380.00
Total Schedule C					3,16,42,709.10

Digitally signed by

SUNIL KUMAR

MISHRA

Date: . . . IST

Location: eProcurement System for

Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

unforeseen item under USSOR 2019 related to bridge work (escalation added 1.90%)

1 LUMPSUM

20,00,000.00

17,50,20,374.17

39,37,958.42

17,89,58,332.59

TOTAL SCHEDULE (A+B+C+D)including 18% GST

Quoted price @ 2.25% above estimated cost of the works

Grand Total including GST @ 18 %

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs

Signature Not Verified
Digitally signed by SUNIL KUMAR MISHRA
Date: . . . IST
Location: eProcurement System for Central PSUs