



इरकॉन इंटरनेशनल लिमिटेड

(भारत सरकार का उपक्रम)

IRCON INTERNATIONAL LIMITED

(A Govt. of India Undertaking)

An integrated Engineering and Construction Company



No. IRCON/ 3026/MAHSR/T2/TCB-1&2_Constr./01/56

Date: 02.02.2023

M/s. Somnath Construction Co.,
A-13, Prime Bungalows, Opp. Kailesh Shikhar Appartment,
Sun Pharma Road,
Vadodara, PIN: 391410
Email: somnathcons@gmail.com , M: 9558729691.

Letter of Acceptance

Sub: Construction of Civil works involving Earthwork, GSB filling, RCC foundations, Road Works, Flooring, External Water supply, Sewerage system and other developmental works for construction of Track Construction Base TCB 1 & 2 (MAHSR km 235 & km 255 respectively) at various locations between Zaroli Village at Maharashtra-Gujarat border (MAHSR km 156.600) and Vadodara (MAHSR km 393.700) in the state of Gujarat and the union territory of Dadra and Nagar Haveli in connection with Construction of Mumbai- Ahmedabad High Speed Rail (Package-MAHSR-T2).-

Ref: (i) Tender No: IRCON/ 3026/MAHSR/T2/TCB-1&2_Constr./01 dated 30.12.2022
(ii) Bid Submitted through e procurement mode dated 20.01.2023

Dear Sir's,

We are Pleased to inform that M/s Ircon International Limited has accepted your offer for the above subject work for a total amount of **Rs. 3,63,50,814.65** (Rupees Three Crore, Sixty Three Lakh, Fifty Thousand, Eight Hundred Fourteen and Paise Sixty Five Only) inclusive of GST and other applicable taxes as per the Bill of Quantities attached at **Annexure -A**.

- 1) This letter of acceptance shall constitute a legal and binding contract between M/s Ircon International Limited and M/s. Somnath Construction Co., till such time the Contract Agreement is signed. You shall enter into and execute the contract agreement within 28 days from the date of issue of this letter of acceptance at the office of undersigned. You are requested to arrange the stamp duty papers of requisite value as per the prevailing laws for signing of contract agreement in terms of clause 12.5 of General condition of contract.
- 2) **Performance Security:** You are requested to submit the Performance security of Rs. 10,90,525.00 (3% of Contract value) initially valid up to stipulated date of completion plus 60 days, as per clause 8.0 of General Condition of Contract. The Performance Security shall be submitted within 21 days from the date of issue of Letter of Acceptance (LOA).
- 3) **Scope of Work:** As per clause 5.0 of Special Conditions of Contract.
- 4) The Letter of Acceptance shall also be treated as Work Order and no separate work order will be issued.

(1/2)

Head Office: C-4, District Centre, Saket, New Delhi 110017 INDIA

Tel: +91-11-29565666, Fax: +91-11-26854000, 26522000

Email: info@ircon.org Web: www.ircon.org

CIN - L45203DL1976GOI008171



- 5) **Completion Period:** The work shall be commenced immediately on receipt of this letter and entire work shall be completed in all respect within 6 (Six) Months in accordance with clause 10.0 of special condition of Contract.
- 6) **Program of Work:** You are advised to submit Program of Work in accordance with clause 10.0 of Special Condition of Contract within 05 days from the date of issue of this LOA.
- 7) **Defect Liability Period:** The Defect Liability Period shall be 12 months from the date of actual Completion of Works.
- 8) **Insurance:** You are requested to take insurance coverage as per para 27.0 of special condition of contract.
- 9) You are advised to register with Shramik Kalyan Portal and follow labour laws as per contract. The compliances information shall be submitted to the office of Chief General Manager on regular basis.
- 10) All the documents that are submitted/ exchanged during tender process have to be referred all time for clear understanding/ Interpretations of the contract conditions. Any deviation / conditions quoted by you, except those specifically mentioned in this LOA, stands deleted.
- 11) All other terms and conditions contained in the e-tender no. IRCON/3026/MAHSR/T2/TCB-1&2_Constr./01 dated 30.12.2022 and corrigendum (if any) shall form the integral part of the contract.
- 12) **Special Note:** Quantities provided under BOQ Schedule C are not to be exceeded during the work execution to avoid Vitiating in Contract.
- 13) The LOA is issued in duplicate. You are requested to return a signed, stamped & acceptance copy of LOA as token of receipt and unconditional acceptance of this Letter of Acceptance
- 14) You may contact Mr R K Singh, JGM/Civil, Surat @Mob No. 9821954084 for Planning & Commencing the works at Site.

Thanking you,



For and on behalf of
Ircon International Limited

(Arun V Vernekar)
General Manager/Civil

02.02.23

Encl: - As Above

Copy to:-

- i) CGM/PH for information
- ii) CGM/Civil/CO, for information
- iii) Mr R K Singh, JGM/Civil for information & n.a
- iv) DGM/Finance, Surat, for information.

GSTIN: 24AAACI0684H1ZS

(2/2)

Bill of Quantity

Name of Work: Construction of Civil works (Foundations, Flooring, Roads, Structural steel, External water supply & Sewage systems) E&M works and other Development Works for Construction of Track Construction Base (TCB) 1 & 2 at various locations between Zaroli Village at Maharashtra-Gujarat Border (MAHSR km 156.600) and Vadodara (MAHSR km 393.700) in the State of Gujarat and the Union Territory of Dadra and Nagar Haveli in connection with the Construction of Mumbai-Ahmedabad High Speed Rail Project

S. No.	Item No.	Description	Estimated Amount inclusive of 18% GST	Quoted Percentage above/Below (inc. 18% GST)	Contract Value inclusive of 18% GST	Remarks
1	A	Schedule A (DSR 2021 Items)	₹ 3,22,36,181.91	-22.02%	₹ 2,51,37,774.65	
2	B	Schedule B (DSR (E&M) 2022 Items)	₹ 10,00,000.00	-18.10%	₹ 8,19,000.00	
3	C	Schedule C (Other items)	₹ 86,61,700.00	20.00%	₹ 1,03,94,040.00	
Total Value of Work with all applicable Taxes			₹ 4,18,97,881.91		₹ 3,63,50,814.65	



Construction of Civil works (Foundations, Flooring, Roads, Structural steel, External water supply & Sewage systems) E&M works and other Development Works for Construction of Track Construction Base (TCB) 1 & 2 at various locations between Zaroli Village at Maharashtra-Gujarat Border (MAHSR km 156.600) and Vadodara (MAHSR km 393.700) in the State of Gujarat and the Union Territory of Dadra and Nagar Haveli in connection with the Construction of Mumbai-Ahmedabad High Speed Rail Project						
S. No.	Item No.	Description	Unit	Quantity	Rate inclusive of 18% GST	Amount inclusive of 18% GST
Schedule A (DSR 2021 Items)						
A1	2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqm	39,200.00	₹ 14.50	₹ 5,68,400.00
A2	16.78.3	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-III (size range 26.5 mm to 0.075 mm) having CBR Value-20	Cum	7,840.00	₹ 2,612.95	₹ 2,04,85,528.00
A3	16.55.2	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.	Cum	159.50	₹ 7,678.10	₹ 12,24,656.95
A4	16.79	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	cum	432.00	₹ 2,803.65	₹ 12,11,176.80
A5	16.40	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete	sqm	3,190.00	₹ 79.85	₹ 2,54,721.50
A6	16.30.2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications; On bituminous surface @ 0.50 Kg / sqm.	sqm	3,190.00	₹ 36.60	₹ 1,16,754.00
A7	2.27	Supplying and filling in plinth with sand or GSB (as approved by IRCON) under floors, including watering, ramming, consolidating and dressing complete	Cum.	202.40	₹ 2,161.20	₹ 4,37,426.88
A8	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in charge. All kinds of soil	Cum.	336.90	₹ 205.45	₹ 69,216.11



S. No.	Item No.	Description	Unit	Quantity	Rate inclusive of 18% GST	Amount inclusive of 18% GST
A9	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	Cum.	86.50	₹ 286.85	₹ 24,812.53
A10	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum.	122.90	₹ 7,365.15	₹ 9,05,176.94
A11	4.3	Centering and shuttering including strutting, propping etc. and removal of form work for;				
A11.1	4.3.1	Foundations, footings, bases for columns	sqm	164.32	₹ 307.95	₹ 50,602.34
A11.2	4.3.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc	sqm	244.80	₹ 669.55	₹ 1,63,905.84
A11.3	4.3.3	Columns, piers, abutments, pillars, posts and struts	sqm	88.38	₹ 804.25	₹ 71,079.62
A12	5.3.3	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
A12.1	5.3.3.1.2	Concrete of M30 grade with minimum cement content of 350 kg /cum	Cum.	39.05	₹ 8,825.35	₹ 3,44,629.92
A13	5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	3,755.00	₹ 89.65	₹ 3,36,635.75
A14	11.41.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 600x600 mm	Sqm	484.00	₹ 1,416.65	₹ 6,85,658.60
A15	18.48A	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support i/c fittings & fixtures for tank shall be paid separately.	litre	2,000.00	₹ 9.70	₹ 19,400.00



S. No.	Item No.	Description	Unit	Quantity	Rate inclusive of 18% GST	Amount inclusive of 18% GST
A16	6.1.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	252.00	₹ 6,882.00	₹ 17,34,264.00
A17	6.23	Honey-comb brick work 10 / 11.4 cm thick with common burnt clay bricks of class designation 7.5 in super structure above plinth level upto floor V level with cement mortar 1:4 (1 cement : 4 coarse sand) for Septic Tank	sqm	48.00	₹ 645.95	₹ 31,005.60
A18	13.1.2	12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand) for Septic Tank	sqm	228.00	₹ 282.00	₹ 64,296.00
A19	19.32.1	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Each	2.00	₹ 28,029.15	₹ 56,058.30
A20	26.65	Providing and fixing roofing consist of 0.8 mm thick galvanized steel deck sheet confirming to IS 277:1992 used as permanent shuttering over which MS wire mesh 3mm laid at 100x100 mm grid including edge trim covered with concrete. This metal deck will be supported on structural steel beam with shear studs. (Structural steel like Beam, column, joists etc. & concrete of different grade as per design will be paid separately).	sqm	48.00	₹ 1,630.40	₹ 78,259.20
A21	10.1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	5,100.00	₹ 93.05	₹ 4,74,555.00
A22	10.16.1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete Hot finished welded type tubes	kg	11,000.00	₹ 154.90	₹ 17,03,900.00
A23	17.2.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required; W.C. pan with ISI marked black solid plastic seat and lid	each	4.00	₹ 5,426.80	₹ 21,707.20
A24	17.4.4	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required; Range of four urinal basins with 10 litre white P.V.C. automatic flushing cistern	each	2.00	₹ 15,564.35	₹ 31,128.70
A25	23.1.1.1	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge, upto 90 metre depth below ground level. All types of soil - 300mm dia	metre	45.00	₹ 592.05	₹ 26,642.25



[Handwritten signature]



S. No.	Item No.	Description	Unit	Quantity	Rate inclusive of 18% GST	Amount inclusive of 18% GST
A26	23.3.3	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -in-charge. 200 mm nominal size dia	metre	33.00	₹ 951.30	₹ 31,392.90
A27	23.4.3	Supplying, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well screen (RMS) pipes with ribs, conforming to IS: 12818, including hire & labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge. 200 mm nominal size dia	metre	12.00	₹ 1,099.25	₹ 13,191.00
A28	All Codes	Any other item of works other than the items Given in Schedule-A, but required to be executed for successful completion of the works as deemed necessary by the engineer-in-charge will be as per delhi schedulw of rates, 2021	Lump Sum	As per DSR-21	As per DSR-21	₹ 10,00,000.00
TOTAL AMOUNT Schedule A with all applicable taxes						₹ 3,22,36,181.91
Quoted Percentage Above/Below						-22.02
Total Amount for Schedule A with all applicable Taxes						₹ 2,51,37,774.65




Construction of Civil works (Foundations, Flooring, Roads, Structural steel, External water supply & Sewage systems) E&M works and other Development Works for Construction of Track Construction Base (TCB) 1 & 2 at various locations between Zaroli Village at Maharashtra-Gujarat Border (MAHSR km 156.600) and Vadodara (MAHSR km 393.700) in the State of Gujarat and the Union Territory of Dadra and Nagar Haveli in connection with the Construction of Mumbai-Ahmedabad High Speed Rail Project						
S. No.	Item No.	Description	Unit	Quantity	Rate inclusive of 18% GST	Amount inclusive of 18% GST
	Schedule B (DSR (E&M) 2022 Items)					
B1	11.3.4	Any Item of electrical works (internal or external) Other than the items given above, but required to be executed for successful completion of the work as deemed necessary by the Engineer - in - charge will be as per Delhi Schedule of Rates (E&M), 2022	Lump Sum	As per DSR-22	As per DSR-22	₹ 10,00,000.00
	TOTAL AMOUNT Schedule B with all applicable Taxes					₹ 10,00,000.00
	Quoted Percentage Above/Below					-18.10
	Total Amount for Schedule B with all applicable Taxes					₹ 8,19,000.00




Construction of Civil works (Foundations, Flooring, Roads, Structural steel, External water supply & Sewage systems) E&M works and other Development Works for Construction of Track Construction Base (TCB) 1 & 2 at various locations between Zaroli Village at Maharashtra-Gujarat Border (MAHSR km 156.600) and Vadodara (MAHSR km 393.700) in the State of Gujarat and the Union Territory of Dadra and Nagar Haveli in connection with the Construction of Mumbai-Ahmedabad High Speed Rail Project						
S. No.	Item No.	Description	Unit	Quantity	Rate inclusive of 18% GST	Amount inclusive of 18% GST
		Schedule C (Other items)				
C1	OS-1	Construction of embankment by mechanical means with approved material to final designed cross section and levels as shown in the drawings and as per technical specification with all leads & lifts, dressing, compaction, watering etc. as directed by the Engineer in Charge all complete. The rate shall include any extra quantity of fill to top up the embankment due to settlement Suitable material from outside. (The Scope of work shall include levelling & compaction the existing ground/loose earth available at site, including royalty)	Cum.	15,540.00	₹ 472.00	₹ 73,34,880.00
C2	OS-2	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.75kg/sqm using mechanical means all complete	sqm	3,190.00	₹ 70.00	₹ 2,23,300.00
C3	OS-3	"Providing 1.2 m high fencing with 1.8m R.C.C Post placed 3m apart, embedded in cement concrete M5 (1:5:10 or higher), every 15th post and corner post shall be struttred on both sides, end post one side only, and struts embedded in cement concrete, provided with hot dipped galvanized chain link fencing (using 260 GSM heavy zinc coated G.I. wire) as per IS 2721 with mess size 40±4mm, Nominal diameter of Mesh Wire 3.15mm, Line wire diameter 4.00mm, Number of line wire is 2 No. one at top and one at bottom, with both end knuckled type and fixed with G.I. staples on turn buckles or binding wire tied to 6 mm bar ribs fixed while casting the post. Vertical Posts & Struts shall be of RCC M15 Concrete. The rate includes the cost of all materials, lead, lifts, ascend, descend, mixing, loading, transportation, unloading, taxes, royalty, etc in complete."	Rmt.	1,400.00	₹ 755.20	₹ 10,57,280.00
C4	OS-4	Supplying and installation of Kirloskar/C rompton/ Havells (or equivalent) make, as approved by IRCON, electric motor driven single phase borewell submersible pump set, MOC: Casing FG 260, Impeller : BRONZE & SHAFT : SS 410 category- 1.5, 180 mt. Head & 90 LPM discharge, 2 HP power.	Each bore	1.00	₹ 15,000.00	₹ 15,000.00
C5	OS-5	Supplying and installation of Control pannel board - DOL/ star Delta starter suitable for local & remote pump control application consisiting of MPCB, overload relay and contractors as per Type II coordination including digital voltmeter, analogue ammeter with selector switch, run hour meter, required relays & control accesories: DOL up to 2 HP	Each bore	1.00	₹ 5,000.00	₹ 5,000.00
C6	OS-6	Carrying out hydrogeological survey to locate ground water using scientific methods and appropriate equipment.	Each bore	1.00	₹ 5,000.00	₹ 5,000.00
C7	OS-7	Providing Laying and lowering a RCC SEPTIC TANK of Diameter 4 Feet and Length 8 Feet consist of 3 chambers 2 manholes inlet & outlet, Cylindrical in shape (Rate is inclusive of transporation at site, Excavation is paid seperately)	Each	1.00	₹ 21,240.00	₹ 21,240.00
		TOTAL AMOUNT Schedule C with all applicable Taxes				₹ 86,61,700.00
		Quoted Percentage Above/Below				+ 20.00
		Total Amount for Schedule C with all applicable Taxes				₹ 1,03,94,040.00



ANNEXURE-II

(to be executed on a non-judicial stamp paper of ₹100/- only)

PERFORMANCE BANK GUARANTEE (UNCONDITIONAL)

To
IRCON INTERNATIONAL LIMITED,

[Acting through _____ (Project
Incharge) & Address of the Project]

WHEREAS _____ [name and address of Contractor]
(hereinafter called "the Contractor") has undertaken, in
pursuance of Contract No. _____ dated _____
to execute the work of "....."
....." (hereinafter called "the Contract.");

AND WHEREAS it has been stipulated by you in the said Contract
that the Contractor shall furnish you with a Bank Guarantee by
a scheduled bank for the sum specified therein as performance
security for compliance with his obligations in accordance
with the Contract;

AND WHEREAS we have agreed to give the Contractor such a Bank
Guarantee;

NOW THEREFORE we hereby affirm that we are the Guarantor and
responsible to you, on behalf of the Contractor, up to a total
of _____ [amount of Guarantee],
_____ [amount in
words], such sum being payable in the types and proportions of
currencies in which the Contract Price is payable, and we
unconditionally agree and undertake to pay you, without any
demur or protest, at once, upon your first written demand and
without cavil or argument, any sum or sums within the limits
of _____ [amount of Guarantee] as mentioned in
demand letter, without requiring you to prove or to show
grounds or reasons for your such demand for the sum specified
therein, in the first letter of invocation.

We hereby waive the necessity of your demanding the said
amount under bank guarantee from the Contractor before
presenting us with the demand.



GENERAL CONDITIONS OF CONTRACT

We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.

This guarantee shall be valid upto _____ (a date 60 days from the date of completion of the work).

We, the _____ Bank further agree that this guarantee shall be invokable at our place of business at New Delhi/NCR/Project HQ (Indicate detail address of branch with Code No.)*. The branch at New Delhi/NCR/Project HQ is being advised accordingly.

This Bank Guarantee shall be operative only if it is accompanied by a separate advice sent by _____ (Name of Issuing Bank, with address) on _____ (Name of Employer's Bank, with address) IFS Code _____ through Structured Financial Messaging System (SFMS) and authenticated by the Employer's Bank.

SIGNATURE AND SEAL OF THE GUARANTOR

Name of Bank: _____
Address: _____
Date: _____

*The Bank should indicate detailed address of New Delhi/NCR/Project HQ branch along with its Code No.



Signature Not Verified

Digitally signed by ARUN V VERNEKAR
Date: 2023.05.15 18:58:33 IST
Location: eProcurement System for
Central PSUs