

14.03.2022

No. IWAI/COCH/36(4)A/2021-22/871

To,

Sri. Joby Johny,
J J Constructions,
Thozhuthungal Parambil,
Kumarapuram P O, Morakkala,
Pallikkara, Ernakulam – 683 565.

Sub: Miscellaneous Rectification works at Regional Office, IWAI, Kochi – Work Order – Reg.

Ref: (1) Tender No. IWAI/COCH/36(4)A/2021-22/19, dated 03.02.2022
(2) Your e-tender offer submitted through e-procurement site on 11.02.2022

Sir,

Reference to the tender cited above on the subject, IWAI is pleased to award the work of “Miscellaneous Rectification works at Regional Office, IWAI, Kochi”, at a total cost of Rs.2,47,568/- (Rupees two lakhs forty seven thousand five hundred & sixty eight only) (excl. GST @ 18% but including 1% Labour Welfare Cess). Details of items, specifications, quantities and item rates are given in enclosed Bill of Quantities (Annexure :1). The Terms & Conditions are as below:

Terms & Conditions:

- (i) Labour Welfare Cess @ 1% shall be deducted from the contractor's bill for remittance to appropriate Authorities.
- (ii) The time allowed for completion of the work shall be 01 (one) month from the date of issue of this work order.
- (iii) An agreement in this regard is required to be entered by you in non-judicial stamp paper of minimum value Rs. 200/-, with this Authority within 15 (fifteen) days of receipt of this order.
- (iv) An amount of Rs. 12,378/- shall be deposited towards Performance Guarantee through RTGS in the following bank particulars and submit the proof along with UTR No. at the time of concluding Contract Agreement.


Our Bank Particulars are;

Account No.	:	39360627884
Name of Account	:	Inland Waterways Authority of India
Name of the bank	:	State Bank of India, Vyttila Branch
IFSC CODE	:	SBIN0008694

- (v) The balance Security Deposit of Rs. 12,378/- will be recovered from Running Bills in accordance with specified terms and conditions towards fulfilling the Security Deposit amounting to 10% of the value of work awarded i.e. Rs. 24,756/- (Rupees twenty four thousand seven hundred and fifty six only) as per Clause No.3 of General Conditions of Contract given in the tender document.
- (vi) GST as applicable shall be separately claimed alongwith the bill.
- (vii) A joint site inspection shall be conducted prior to commence the work.
- (viii) All other terms and conditions remaining same as per the tender document.

It is requested to please communicate your acceptance of this Work Order immediately and take necessary steps for commencement of work under intimation to this office.

Yours faithfully,


(Mathew George)
Director

Encl.: As above.

olc



Bill of Quantities**Name of work : Miscellaneous Rectification works at Regional Office, IWAI, Kochi**

Sl. No.	Description	Unit	Quantity	Rate	Amount
1	Site Clearance by cutting and removing grass, bushes, all obstruction etc., from the top surface and disposal of the same as and directed by the Engineer in charge	M ²	96.00	8.00	768.00
2	Taking out existing paved footpath leading to terminal without causing any damages to the blocks and stacking the same as and where directed by the E-I-C by engaging labours with necessary compaction etc. as per the direction of Engineer-in-charge	M ²	13.50	1.00	13.50
3	Earth work in excavation on the proposed area and to get an even profile and even depth for foundation by manual or mechanical means as per direction of E-I-C. The rate shall include hire charges of machineries, labour for stacking / keeping of excavated soil.	M ³	46.08	237.00	10920.96
4	Supply of placing in position Geo- textile as per specification or equivalent filter for below revetment as per the approved specification and drawing and any other place as directed by the Engineer in charge including over lapping, sticking, stretching with all lead lift labour. Tools and plants floating crafts, divers, etc. complete.	M ²	97.80	499.00	48802.20
5	Earth work in filling the trench by soil obtained from the borrow pit made for laying geotextile layer, free from logs, stumps, roots rubbish etc., including levelling dressing, watering ramming and consolidating by approved means to the required profile under the direction of the Engineer, including all lift and leads.	M ³	46.08	628.56	28964.04
6	Re-laying of earlier removed paver blocks with strong vibratory compaction including supply of 100mm thick compacted levelled bed of 6mm stone chips, filling the joints with fine sand etc. shall be executed as per the direction of Engineer-in-charge.	M ²	13.50	441.19	5956.07
7	Filling & Levelling of excessively settled areas of the pathway with red earth and compacted to attain suitable strength including supply of red earth to the site, spreading by engaging labours with equipments like hand roller etc. as per the direction of Engineer-in-charge.	M ³	14.91	1802.23	26871.25


Sl. No.	Description	Unit	Quantity	Rate	Amount
8	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction of approved size, design & shape, laid in required colour and pattern including 100mm thick compacted levelled bed of 6mm stone chips, filling the joints with fine sand etc. shall be executed as per the direction of Engineer - in - Charge.	M ²	56.44	1100.00	62084.00
9	Taking out thick root of big tree which was cut earlier by excavating the surrounding earth at a depth of 4' with the help of labours without causing any damages to bank protection including hire charges of tools, labour charges etc., complete.	LS	LS	8323.00	8323.00
10	Supplying and fixing 0.50 mm thick, Pre-coated Aluminium Trafford sheet with nuts, screws, washers as per requirement and including transportation, cutting to required size and shape wherever required, lapping, bending for ridges, valleys etc. if any and fixing in position etc. complete.	M ²	74.75	665.49	49745.38
11	Cleaning of exsisting drainage by taking out the sand/dirt accumulated on the bottom portion & clearing of waste materials from the entire length of the drain by engaging labours including regularising the flow of water through the drain without any obstruction as per the directions of EIC .The rate shall include hire charges of tools/tackles , labour charges etc. complete	M ²	160.00	32.00	5120.00
Total cost: Rs.					247568.40

Say Rs.: 2,47,568/-

(Rupees two lakhs forty seven thousand five hundred & sixty eight only)

Note:

GST as applicable shall be indicated in addition seperately in the bill.


(Mathew George)
Director

Signature Not Verified

Digitally signed by R VENKATESAN
Date: 2022.07.04 13:23:03 IST
Location: eProcure-EPROC