

Government eProcurement System

Created By: Sidhartha Bhaskar

Created Date/Time: 06-Mar-2023 04:27 PM

Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.

Tender ID: 2023_AAL_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>

Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >

Contract No: <0231-2677706>

2023_AAL_140163_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate
1.00	CARRIAGE OF MATERIALS : By Mechanical Transport including loading ,Unloading and stacking Upto 1.00 KM. lead. Earth	1000.00	Cum	
2.00	CARRIAGE OF MATERIALS By Mechanical Transport including loading,unloading and stacking. Upto 1.00 KM. lead. Steel	6.50	tonne	
3.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All Kinds of soil	85.00	Cum	
4.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. Ordinary rock	85.00	Cum	
5.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. Hard rock (blasting prohibited)	5.00	Cum	

KANISHK ENGINEERS(GSTN-NA)	DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
	Rate	Amount	Rate	Amount
93.00	93000.00	200.00	250.00	250000.00
580.00	3770.00	2000.00	4000.00	26000.00
267.00	22695.00	220.00	150.00	12750.00
468.00	39780.00	450.00	180.00	15300.00
1350.00	6750.00	2200.00	1000.00	5000.00

L1 Amount	L1 Vendor
93000.00	KANISHK ENGINEERS
3770.00	KANISHK ENGINEERS
12750.00	M/s Suresh Construction CO
15300.00	M/s Suresh Construction CO
5000.00	M/s Suresh Construction CO

Kanishk
06.03.2023
Smt (E)

Suresh
06/03/23

Government eProcurement System
 Created By: Sidhartha Bhasme
 Created Date/Time: 06-Mar-2023 04:27 PM
 Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.
 Tender ID: 2023_AAL_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>
 Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >
 Contract No: <0231-2677706>
 2023_AAL_140163_1

SCHEDULE OF WORK / ITEM(S)				KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)		L1 Amount	L1 Vendor
Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate	Rate	Amount	Rate	Amount	Rate	Amount	
6.00	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	230.00	Cum		215.00	49450.00	260.00	59800.00	150.00	34500.00	M/s Suresh Construction CO
7.00	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Ordinary rock	345.00	Cum		635.00	219075.00	490.00	169050.00	200.00	69000.00	M/s Suresh Construction CO
8.00	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Hard rock (blasting prohibited)	690.00	Cum		1215.00	838350.00	970.00	669300.00	700.00	483000.00	M/s Suresh Construction CO
9.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	1355.00	Cum		125.00	169375.00	200.00	271000.00	100.00	135500.00	M/s Suresh Construction CO
10.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	7.00	Cum		6225.00	43575.00	6600.00	46200.00	6000.00	42000.00	M/s Suresh Construction CO


[Handwritten Signature]
 06.03.2023

Government eProcurement System Created By: Sidhartha Bhaskar Created Date/Time: 06-Mar-2023 04:27 PM Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. Tender ID: 2023_AAL_140163_1				
Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>				
Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >				
Contract No: <0231-2677706>				
SCHEDULE OF WORK / ITEM(S)				
SI.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate

11.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	86.00	Cum	
12.00	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	70.00	Sqm	
13.00	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	16.00	Sqm	
14.00	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	5.00	Cum	
15.00	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	35.00	Sqm	
16.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	100.00	kg.	

SI.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate	KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
					Rate	Amount	Rate	Amount	Rate	Amount
					5721.00	492006.00	5500.00	473000.00	5800.00	498800.00
					1799.00	125930.00	370.00	25900.00	250.00	17500.00
					5720.00	91520.00	750.00	12000.00	900.00	14400.00
					7331.00	36655.00	8500.00	42500.00	6500.00	32500.00
					1895.00	66325.00	410.00	14350.00	250.00	8750.00
					120.00	12000.00	120.00	12000.00	100.00	10000.00

L1 Amount	L1 Vendor
473000.00	DURGA ENTERPRISES
17500.00	M/s Suresh Construction CO
12000.00	DURGA ENTERPRISES
32500.00	M/s Suresh Construction CO
8750.00	M/s Suresh Construction CO
10000.00	M/s Suresh Construction CO


 06.03.2023
 3 of 13

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>

Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >

Contract No: <0231-2677706>

2023_AAL_140163_1

SCHEDULE OF WORK / ITEM(S)

SI.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate
17.00	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	3.00	Sqm	
18.00	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 250x16 mm	2.00	Each	
19.00	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150x10 mm	1.00	Each	
20.00	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm	2.00	Each	
21.00	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	1.00	Each	
22.00	Providing and fixing bright finished 100 mm mortice lock with 6 levers without pair of handles of approved quality for aluminium door, with necessary screws etc complete as per direction of Engineer- in-charge	1.00	Each	

KANISHK ENGINEERS(GSTN-NA)	DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
	Rate	Amount	Rate	Amount
	13100.00	39300.00	5200.00	15600.00
	2950.00	5900.00	600.00	1200.00
	103.00	103.00	800.00	800.00
	1821.00	3642.00	800.00	1600.00
	189.00	189.00	3500.00	3500.00
	936.00	936.00	2200.00	2200.00
			1500.00	1500.00

L1 Amount	L1 Vendor
12000.00	M/s Suresh Construction CO
1000.00	M/s Suresh Construction CO
103.00	KANISHK ENGINEERS
400.00	M/s Suresh Construction CO
150.00	M/s Suresh Construction CO
936.00	KANISHK ENGINEERS

Handwritten signature and date: 06.03.2023

Government eProcurement System Created By: Sidhartha Bhasme Created Date/Time: 06-Mar-2023 04:27 PM Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. Tender ID: 2023_AAI_140163_1				
Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>				
Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >				
Contract No: <0231-2677706>				
SCHEDULE OF WORK / ITEM(S)				
Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate

23.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	500.00	kg.	
24.00	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	25.00	kg.	
25.00	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	50.00	Sqm	
26.00	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	133.00	Sqm	
27.00	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm)	28.00	metre	

KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
Rate	Amount	Rate	Amount	Rate	Amount
128.00	64000.00	155.00	77500.00	200.00	100000.00
112.00	2800.00	180.00	4500.00	125.00	3125.00
637.00	31850.00	1450.00	72500.00	2000.00	100000.00
442.00	58786.00	650.00	86450.00	1200.00	159600.00
345.00	9660.00	750.00	21000.00	600.00	16800.00

L1 Amount	L1 Vendor
64000.00	KANISHK ENGINEERS
2800.00	KANISHK ENGINEERS
31850.00	KANISHK ENGINEERS
58786.00	KANISHK ENGINEERS
9660.00	KANISHK ENGINEERS


 06.03.2023
 T. Suresh
 Suresh

Government eProcurement System

Created By: Sidhartha Bhasme

Created Date/Time: 06-Mar-2023 04:27 PM

Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.

Tender ID: 2023_AAI_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>

Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >

Contract No: <0231-2677706>

2023_AAI_140163_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate
-------	-------------------------------	------------	-------	----------------

28.00	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	50.00	Sqm	
29.00	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	5.00	Sqm	
30.00	Applying priming coat: With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	150.00	Sqm	
31.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	155.00	Sqm	
32.00	Cleaning of under ground sump. Over Head R.C.C. Tank (independent staging) including disposal of silt and rubbish, all as per direction of Engineer-in-Charge. The cleaning shall consist following operations:- (i) Tank shall be emptied of water by pumping & bottom shall be cleaned of silt and other deposits. (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. (iii) Chlorination of RCC internal surface by liquid chlorine. (iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. (v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge.	123.00	Sqm	
33.00	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	6500.00	kg.	

KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
Rate	Amount	Rate	Amount	Rate	Amount
287.00	14350.00	430.00	21500.00	250.00	12500.00
51.37	256.85	200.00	1000.00	100.00	500.00
55.00	8250.00	65.00	9750.00	100.00	15000.00
115.00	17825.00	150.00	23250.00	200.00	31000.00
75.00	9225.00	120.00	14760.00	500.00	61500.00
23.00	149500.00	15.00	97500.00	35.00	227500.00

L1 Amount	L1 Vendor
12500.00	M/s Suresh Construction CO
256.85	KANISHK ENGINEERS
8250.00	KANISHK ENGINEERS
17825.00	KANISHK ENGINEERS
9225.00	KANISHK ENGINEERS
97500.00	DURGA ENTERPRISES

[Handwritten Signature]
06.03.2023

Government eProcurement System

Created By: Sidhartha Bhaskar

Created Date/Time: 06-Mar-2023 04:27 PM

Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.

Tender ID: 2023_AAL_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>

Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >

Contract No: <0231-2677706>

2023_AAL_140163_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate
34.00	Cutting road and making good the same including supply of extra quantities of materials i.e. aggregate, moorum screening, red bajri and labour required.	10.00	cum	
35.00	Cutting road and making good the same including supply of extra quantities of materials i.e. aggregate, moorum screening, red bajri and labour required.	30.00	cum	
36.00	Water bound macadam Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not be more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	2.00	Cum	
37.00	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	160.00	metre	
38.00	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	787.00	Sqm	

KANISHK ENGINEERS(GSTN-NA)	DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
	Rate	Amount	Rate	Amount
5335.00	53350.00	3900.00	10000.00	100000.00
2230.00	66900.00	2400.00	2500.00	75000.00
9925.00	19850.00	9500.00	7000.00	14000.00
42.00	6720.00	60.00	200.00	32000.00
48.00	37776.00	90.00	200.00	157400.00

L1 Amount	L1 Vendor
39000.00	DURGA ENTERPRISES
66900.00	KANISHK ENGINEERS
14000.00	M/s Suresh Construction CO
6720.00	KANISHK ENGINEERS
37776.00	KANISHK ENGINEERS

R. Suresh
5/3/23
06.03.2023

[Signature]
06/03/2023

Government eProcurement System

Created By: Sidhartha Bhasme

Created Date/Time: 06-Mar-2023 04:27 PM

Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.

Tender ID: 2023_AAL_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>

Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >

Contract No: <0231-2677706>

2023_AAL_140163_1

SCHEDULE OF WORK / ITEM(S)

SI.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate
39.00	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	708.30	Sqm	
40.00	Laying at or near ground level old kerb stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (Old kerb stones shall be supplied by the department free of cost)	144.00	metre	
41.00	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	80.00	Sqm	

KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
Rate	Amount	Rate	Amount	Rate	Amount
118.00	83579.40	310.00	219573.00	400.00	283320.00
79.00	11376.00	120.00	17280.00	700.00	100800.00
5050.00	404000.00	950.00	76000.00	1000.00	80000.00

L1 Amount	L1 Vendor
83579.40	KANISHK ENGINEERS
11376.00	KANISHK ENGINEERS
76000.00	DURGA ENTERPRISES

Randhi
5/3/23
06.03.2023

06/03/23

Government eProcurement System

Created By: Sidhartha Bhaskar

Created Date/Time: 06-Mar-2023 04:27 PM

Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.

Tender ID: 2023_AAI_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>

Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >

Contract No: <0231-2677706>

2023_AAI_140163_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate
-------	-------------------------------	------------	-------	----------------

42.00	Providing and fixing Polyethelene-Aluminium- Polyethelene PE-ALPE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with trenching, refilling and testing of joints complete as per direction of the engineer in charge. 2025 (25 mm OD) pipe	100.00	metre	
43.00	Providing and fixing Polyethelene-Aluminium- Polyethelene PE-ALPE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with trenching, refilling and testing of joints complete as per direction of the engineer in charge. 4050 (50 mm OD) pipe	620.00	metre	
44.00	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 20 mm nominal bore	5.00	Each	
45.00	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 40 mm nominal bore	5.00	Each	
46.00	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : 100 mm diameter Class II	4.00	Each	

KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
Rate	Amount	Rate	Amount	Rate	Amount
998.00	99800.00	410.00	41000.00	1300.00	130000.00
1516.00	939920.00	665.00	412300.00	1800.00	1116000.00
498.00	2490.00	600.00	3000.00	500.00	2500.00
1050.00	5250.00	850.00	4250.00	800.00	4000.00
7100.00	28400.00	5100.00	20400.00	8000.00	32000.00

L1 Amount	L1 Vendor
41000.00	DURGA ENTERPRIS ES
412300.00	DURGA ENTERPRIS ES
2490.00	KANISHK ENGINEERS
4000.00	M/s Suresh Constructio n CO
20400.00	DURGA ENTERPRIS ES

[Handwritten Signature]
06.03.2023
S.M.C.E.N

Government eProcurement System Created By: Sidhartha Bhasme Created Date/Time: 06-Mar-2023 04:27 PM Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. Tender ID: 2023_AAL_140163_1				
Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport> Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. > Contract No: <0231-2677706>				
SCHEDULE OF WORK / ITEM(S)				
Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate

47.00	Providing and filling sand of grading zone V or coarser grade, allround the water supply pipes (GI/PE-AL-PE/DI) in external work : 25 mm diameter pipe	100.00	metre	
48.00	Providing and filling sand of grading zone V or coarser grade, allround the water supply pipes (GI/PE-AL-PE/DI) in external work : 50 mm diameter pipe	620.00	metre	
49.00	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	25000.00	per litre	
50.00	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc if required will be paid separately) : 50 mm dia	2.00	Each	
51.00	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc if required will be paid separately) : 100 mm dia	6.00	Each	
52.00	Providing and fixing enclosed type water meter (bulk type) conforming to IS : 2373 and tested by Municipal Board complete with bolts, nuts, rubber insertions etc. (The tail pieces if required will be paid separately) : 100 mm dia nominal bore	1.00	Each	
53.00	Providing and fixing C.I. dirt box strainer for bulk type water meter with nuts, bolts, rubber insertions etc. complete conforming to IS : 2373 : 100 mm dia	1.00	Each	
54.00	Providing and laying D.I. specials of class K-12 suitable for push-on jointing as per IS : 9523 : Up to 600 mm dia	2.00	quintal	

KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
Rate	Amount	Rate	Amount	Rate	Amount
510.00	51000.00	220.00	22000.00	150.00	15000.00
510.00	316200.00	180.00	111600.00	200.00	124000.00
7.00	175000.00	7.00	175000.00	20.00	500000.00
10750.00	21500.00	6500.00	13000.00	4500.00	9000.00
13410.00	80460.00	9200.00	55200.00	7500.00	45000.00
22850.00	22850.00	10000.00	10000.00	20000.00	20000.00
2850.00	2850.00	10000.00	10000.00	10000.00	10000.00
9000.00	18000.00	18000.00	36000.00	30000.00	60000.00

L1 Amount	L1 Vendor
15000.00	M/s Suresh Construction CO
111600.00	DURGA ENTERPRISES
175000.00	DURGA ENTERPRISES, KANISHK ENGINEERS
9000.00	M/s Suresh Construction CO
45000.00	M/s Suresh Construction CO
10000.00	DURGA ENTERPRISES
2850.00	KANISHK ENGINEERS
18000.00	KANISHK ENGINEERS

Randhir
5/03/23
06.03.2023

Government eProcurement System

Created By: Sidhartha Bhasme

Created Date/Time: 06-Mar-2023 04:27 PM

Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.

Tender ID: 2023_AAI_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>

Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >

Contract No: <0231-2677706>

2023_AAI_140163_1

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate
55.00	Providing and laying D.I. Specials of Class K - 12 suitable for mechanical jointing as per IS : 9523 : Up to 600 mm dia	2.50	quintal	
56.00	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and the cost of rubber gasket : 100 mm dia pipes	300.00	joint	
57.00	Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 : 100 mm dia Ductile Iron Class K-9 pipes	2300.00	metre	
58.00	Providing and laying Double Flanged (Screwed/ Welded) Centrifugally (Spun) Ductile Iron Pipes of Class K - 9 conforming to IS : 8329 : 100 mm dia Ductile Iron Double Flanged	16.00	metre	
59.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	20.00	kg.	

KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
Rate	Amount	Rate	Amount	Rate	Amount
9000.00	22500.00	19000.00	47500.00	30000.00	75000.00
1150.00	345000.00	150.00	45000.00	150.00	45000.00
2145.00	4933500.00	995.00	2288500.00	2500.00	5750000.00
3225.00	51600.00	1755.00	28080.00	3000.00	48000.00
198.00	3960.00	500.00	10000.00	1500.00	30000.00

L1 Amount	L1 Vendor
22500.00	KANISHK ENGINEERS
45000.00	DURGA ENTERPRIS ES, M/s Suresh Constructio n CO
2288500.00	DURGA ENTERPRIS ES
28080.00	DURGA ENTERPRIS ES
3960.00	KANISHK ENGINEERS

T. Gandhi
Smt. (R)
06.03.2023

06/03/2023

Government eProcurement System
Created By: Sidhartha Bhasme
Created Date/Time: 06-Mar-2023 04:27 PM
Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.
Tender ID: 2023_AAI_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>
Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >
Contract No: <0231-2677706>
2023_AAI_140163_1

SCHEDULE OF WORK / ITEM(S)				KANISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)		L1 Amount	L1 Vendor
Sl.No	Description of Work / Item(s)	No. of Qty	Units	Estimated Rate	Rate	Amount	Rate	Amount	Rate		
60.00	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	20.00	kg.		210.00	4200.00	500.00	10000.00	1500.00	4200.00	KANISHK ENGINEERS
61.00	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	6.00	Sqm		141.00	846.00	1540.00	9240.00	5000.00	846.00	KANISHK ENGINEERS
62.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position all complete. (Structural steel shall be provided by AAI)	6500.00	kg.		125.00	812500.00	35.00	227500.00	45.00	227500.00	DURGA ENTERPRISES

(Signature)
5/3/2023
06.03.2023

Government eProcurement System
 Created By: Sidhartha Bhasme
 Created Date/Time: 06-Mar-2023 04:27 PM
 Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.
 Tender ID: 2023_AAL_140163_1

Tender Inviting Authority: <AGM Engg. Civil Kolhapur Airport>

Name of Work: <Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport. >

Contract No: <0231-2677706> 2023_AAL_140163_1

SCHEDULE OF WORK / ITEM(S)

SI.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate
-------	-------------------------------	-----------	-------	----------------

63.00	Brick work with local available size Fly ash bricks of class designation 50 in foundation and plinth in : (a) Cement Mortar 1:6 (1 Cement : 6 Coarse sand)	10.00	cum	
-------	--	-------	-----	--

KAMISHK ENGINEERS(GSTN-NA)		DURGA ENTERPRISES(GSTN-NA)		M/s Suresh Construction CO(GSTN-NA)	
Rate	Amount	Rate	Amount	Rate	Amount
170.00	1700.00	3700.00	37000.00	8000.00	80000.00

L1 Amount	L1 Vendor
1700.00	KANISHK ENGINEERS

11349906.25	6670513.00	11688495.00
-------------	------------	-------------

Total in Figures

Lowest Amount Quoted BY: DURGA ENTERPRISES(6670513.00)

Handwritten signatures and dates:
 06.03.2023
 06/03/2023
 06/03/2023

BOQ Summary Details

Tender Title: Augmentation of Water Supply and other Miscellaneous works at Kolhapur Airport.

Tender ID: 2023_AAI_140163_1

Sheet Name	SI.No	Bidder Name	Amount	Bid Rank
BoQ1	1	DURGA ENTERPRISES	6670513.00	L1
	2	KANISHK ENGINEERS	11349906.25	L2
	3	M/s Suresh Construction CO	11688495.00	L3

Kanishk
SM (EC)
06-03-2023

Downloaded
on 06/03/23
Om
Suresh
06/03/23

06/03/2023.

Signature Not Verified

Digitally signed by SIDHARTHA NAMDEO
BHASME

Date: 2023.03.20 19:52:45 IST

Location: eProcurement System for
Central PSUs