

Ref No: AAI/RHQ-SR/ENGG/AGM (E)/WO-10/2023/07

Date: 06.03.2023

To,

M/s.V.K.SAM ENGINEERING  
No.5, Rajiv Gandhi Nagar,  
Ekkaduthangal  
Chennai - 600 032.

**Name of Work : SITC of Power supply Distribution for CNS equipment from UPS in the second Floor ATS block, Chennai – P/O installation of IP radio and establishment of C-SMC, Chennai Airport. & SITC of HF receiver , HF Broadband antenna and associated accessories.**

**Sub Head : Electrical Works.**

Ref: 1. AAI Tender Id: 2023\_AAI\_140237\_1  
2. e-Tender (Price Bid) opened: 15.02.2023

Dear Sirs,

1. Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to **Rs.19,92,226.00** (Rupees Nineteen Lakhs Ninety Two Thousand Two Hundred and Twenty Six Only) Plus applicable GST @ 18% which is 25.12% below the justified cost of **Rs.26,60,555.00** Plus applicable GST @ 18%.
2. Jt. General Manager Engg (E), AAI, Administrative offices, RHQ-Southern Region, Chennai shall be Engineer – in – charge of the work. You are requested to attend this office by **20.03.2023** to sign and complete the contract agreement. The contract Agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One Hundred only). The cost of the stamp paper shall be borne by you.
3. Please deposit **Rs.1,99,223.00** (Rupees One Lakh Ninety Nine Thousand Two Hundred and Twenty Three only) towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per the Clause of 1-A of Clauses of Contract.
4. You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 and minimum wages act and rules thereof Central and State Governments.



Contd..2..

..2..

5. You are also directed to contact Asst. General Manager (Engg-E), immediately who will arrange to hand over the site to you.
6. Please note that the time allowed for carrying out the work shall be 02 (Two) Months and same shall be reckoned from **06.03.2023**.
7. Any further correspondence in connection with the contract should normally be addressed to the Jt. General Manager Engg (E), AAI, Administrative Offices, RHQ-Southern Region, Chennai.
8. On completion of work, you are requested to clearly indicate AAI GST No. 33AAACA6412D1ZF in your invoice.
9. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Thanking you,

Encl: 1) Schedule of Quantities – Schedule 'A'

2) E-Sahaj Proforma to be followed for obtaining Airport Entry permit

Yours faithfully,

Asst. General Manager Engg (E)  
For and on behalf of the Chairman  
Airports Authority of India

आर. सुजाता / R. SUJATHA

सहायक महाप्रबंधक (इंजी.-विद्युत) / Assistant General Manager (Engg.-Electrical)  
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India  
प्रचालन कार्यालय कॉम्प्लेक्स / Operational Offices Complex  
दक्षिणी क्षेत्र, चेन्नई-16 / Southern Region, Chennai-16

**AIRPORTS AUTHORITY OF INDIA  
SOUTHERN REGION  
CHENNAI AIRPORT, CHENNAI 600 027**

**SCHEDULE OF QUANTITY**

Schedule-A

**Name of work : "SITC of Power supply Distribution for CNS equipment from UPS in the second Floor ATS block, Chennai – P/O installation of IP radio and establishment of C-SMC, Chennai Airport. & SITC of HF receiver , HF Broadband antenna and associated accessories. SH: Electrical Works".**

| Sl. no | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Qty | Unit | Basic Rate in Rs. [excluding GST] | Total Amount in Rs. [with out GST] |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|-----------------------------------|------------------------------------|
|        | <b>SH-I : Works at Equipment Room, ATS Complex.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |     |      |                                   |                                    |
| 1.01   | Supply and fixing of following (item Nos. 1.02 & 1.03) type of panels having Polycarbonate PC - GFS high flexibility modular enclosure system provision for an easy upgrading of the assembly including bus bar system at any time even after many years , made of high quality (shock proof, rust free, corrosion free, acid and chemical resistant, fire retardant, self-extinguishing, having high impact against mechanical load, <b>made of halogen and silicon free recyclable material confirming to RoHS directive 2002/95/EC, UV resistant according to IEC 61439-1</b> , having high grade internally embedded gasket made of Polyurethane ( PUR ). All left or right-side enclosures should have pre-moulded knockouts for side cable entry or for future extension.<br><br>Each enclosure should have multi no of self-threaded holes to mount mounting plate or Din channel or any equipment. (Make: Hensel or Equivalent) |     |      |                                   |                                    |
| 1.02   | <b>Distribution panel details:- (Indoor &amp; Wall Mounting)</b><br><br>i) Incomer - 2 Nos of 100 Amp Double Pole MCCB,240V AC, 10kA, C- Curve with mechanical interlock arrangements, On/Off/Trip indications,with rated individual digital voltmeter and digital ammeter per each incomer.<br><br>ii) Outgoing - 20 Nos of (6-32) Amps Double pole,240 V AC, MCB, 10kA, C-Curve.<br><br>iii) Suitable capacity copper bus bar arrangements to be made inbuilt for incomers and outgoings.<br><br>iv) Provision of all necessary accessories etc., as required.                                                                                                                                                                                                                                                                                                                                                                        | 4   | Job  | 120000                            | <b>480,000.00</b>                  |

R

| Sl. no | Description                                                                                                                                                                                                                                                                                                                                                          | Qty | Unit | Basic Rate in Rs. [excluding GST] | Total Amount in Rs. [with out GST] |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|-----------------------------------|------------------------------------|
| 1.03   | <b>On Load Changeover panel details:- (Indoor &amp; Wall Mounting)</b><br>Panel with 2 Incomers and 1 Outgoing type - 100 Amp ,240V AC,2 Pole with On/Off indications per each incomer along with necessary cable entry, exit and termination complete as required.                                                                                                  | 2   | Job  | 10750                             | <b>21,500.00</b>                   |
| 1.04   | Supplying and fixing of <b>Loop-in Loop-out Box</b> made of Transparent Polycarbonate with 100A copper busbar for both Phase & Neutral, Gland & connection Provision for one incomer(4C x 16sqmm) and 5 outgoing (2C x 16sqmm), earth connection and suitable for Single Phase AC supply etc complete as required. (Make: Hensel or equivalent)                      | 5   | Job  | 6950                              | <b>34,750.00</b>                   |
| 1.05   | Supplying and fixing of thermoplastic polycarbonate enclosure box protected with mentioned capacity of MCB and socket outlet. , suitable for fixing on surface including termination of incoming cable, necessary connections, etc. as required.<br>i) 3 Pin 15A/5A socket outlet - 1 No,<br>ii) 5/6A, Double Pole, 10 kA "C" curve MCB (Make: Hensel or equivalent) | 56  | Job  | 4100                              | <b>229,600.00</b>                  |
| 1.06   | Supplying and fixing of following rating miniature circuit breaker in the existing Network / Server Racks complete with Din bar, Neutral bar, connections, testing and commissioning etc. as required                                                                                                                                                                |     |      |                                   |                                    |
| 1.07   | 10A, DP, 240/415 V, 10 kA, "C" curve                                                                                                                                                                                                                                                                                                                                 | 60  | Each | 529                               | <b>31,740.00</b>                   |
| 1.08   | 6A, DP, 240/415 V, 10 kA, "C" curve                                                                                                                                                                                                                                                                                                                                  | 80  | Each | 529                               | <b>42,320.00</b>                   |
| 1.09   | 16A, DP, 6kA, 24V DC MCB, "C" curve                                                                                                                                                                                                                                                                                                                                  | 48  | Each | 704                               | <b>33,792.00</b>                   |
| 1.10   | 1A, DP, 6kA, 24V DC MCB, "C" curve                                                                                                                                                                                                                                                                                                                                   | 64  | Each | 784                               | <b>50,176.00</b>                   |
| 1.11   | Supplying and fixing of 63A, 4Pole, 10kA breaking capacity, 'C' curve miniature circuit breaker in the existing electrical panel complete with necessary wiring connections, testing and commissioning etc. as required                                                                                                                                              | 5   | Each | 1615                              | <b>8,075.00</b>                    |
| 1.12   | Supplying and fixing of 25 mm medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.                                                                                                                                                                         | 150 | Mtr  | 135                               | <b>20,250.00</b>                   |
| 1.13   | Supply and drawing of 2 Core X16 sq.mm FRLS PVC insulated copper conductor, single core cable in the existing cable tray / PVC conduit as required. (Connection between Battery charger and Tx/Rx racks)                                                                                                                                                             | 150 | Mtr  | 267                               | <b>40,050.00</b>                   |

| Sl. no | Description                                                                                                                                                                 | Qty | Unit | Basic Rate in Rs. [excluding GST] | Total Amount in Rs. [with out GST] |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|-----------------------------------|------------------------------------|
| 1.14   | Supply of 3 Core x 10 sq.mm FRLS PVC insulated and PVC sheathed copper conductor round flexible industrial cable having 1.1 kV grade and as per IS694 complete as required. | 91  | Mtr  | 221                               | <b>20,111.00</b>                   |
| 1.15   | Supply of 2 Core x 16 sq.mm FRLS PVC insulated and PVC sheathed copper conductor round flexible industrial cable having 1.1 kV grade and as per IS694 complete as required. | 36  | Mtr  | 237                               | <b>8,532.00</b>                    |
| 1.16   | Supply of 4 Core x 16 sq.mm FRLS PVC insulated and PVC sheathed copper conductor round flexible industrial cable having 1.1 kV grade and as per IS694 complete as required. | 170 | Mtr  | 451                               | <b>76,670.00</b>                   |
| 1.17   | Supply of single core 25 sq.mm size FR PVC insulated unarmoured copper cable of 1.1 KV grade Green color for earth connection on wall surface as required.                  | 25  | Mtr  | 174                               | <b>4,350.00</b>                    |
| 1.18   | Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade upto 35 Sq.mm cable size in the existing RCC/ HUME/ METAL/ PVC pipe as required.     | 132 | Mtr  | 35                                | <b>4,620.00</b>                    |
| 1.19   | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade upto 35 Sq.mm cable on wall surface as required.                          | 265 | Mtr  | 45                                | <b>11,925.00</b>                   |
| 1.20   | Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade upto 35 Sq.mm cable on existing cable tray as required.                   | 814 | Mtr  | 45                                | <b>36,630.00</b>                   |
| 1.21   | Providing and fixing of 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.                                                                 | 31  | Mtr  | 715                               | <b>22,165.00</b>                   |
| 1.22   | Providing and fixing of 8 SWG copper wire on surface or in recess for loop earthing etc. as required.                                                                       | 175 | Mtr  | 105                               | <b>18,375.00</b>                   |
| 1.23   | Supply of 32A, DP, 240V AC , 10 kA, "C" curve                                                                                                                               | 6   | Each | 445                               | <b>2,670.00</b>                    |
| 1.24   | Supply of 10A, DP, 240V AC , 10 kA, "C" curve                                                                                                                               | 30  | Each | 525                               | <b>15,750.00</b>                   |
| 1.25   | Supply of 6A, DP, 240V AC , 10 kA, "C" curve                                                                                                                                | 30  | Each | 525                               | <b>15,750.00</b>                   |
| 1.26   | Supply of 16A, DP, 6kA, 24V DC MCB, "C" curve                                                                                                                               | 24  | Each | 690                               | <b>16,560.00</b>                   |
| 1.27   | Supply of 1A, DP, 6kA, 24V DC MCB, "C" curve                                                                                                                                | 24  | Each | 775                               | <b>18,600.00</b>                   |

*QJ*

| Sl. no   | Description                                                                                                                                                                                                                                                                                                                                            | Qty  | Unit | Basic Rate in Rs. [excluding GST] | Total Amount in Rs. [with out GST] |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|-----------------------------------|------------------------------------|
| 1.28     | Supply of following color 16 sq. mm FRLS PVC insulated copper conductor, single core cable                                                                                                                                                                                                                                                             |      |      |                                   |                                    |
| 1.29     | Red                                                                                                                                                                                                                                                                                                                                                    | 60   | Mtr  | 112.00                            | 6,720.00                           |
| 1.30     | Black                                                                                                                                                                                                                                                                                                                                                  | 60   | Mtr  | 112.00                            | 6,720.00                           |
| 1.31     | Supply of 6 sq. mm FRLS PVC insulated copper conductor, single core cable for earth connection                                                                                                                                                                                                                                                         | 50   | Mtr  | 40.00                             | 2,000.00                           |
| 1.32     | Supply of thermoplastic polycarbonate enclosure box protected with mentioned capacity of MCB and socket outlet. , suitable for fixing on surface including termination of incoming cable, necessary connections, etc. as required.<br>i) 3 Pin 15A/5A socket outlet - 1 No,<br>ii) 5/6A, Double Pole, 10 kA "C" curve MCB (Make: Hensel or equivalent) | 4    | Each | 4300.00                           | 17,200.00                          |
| 1.33     | Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed /XLPE copper conductor cable of 1.1 KV grade as required.<br><b>4 X 16 Sq.mm</b>                                                                                                                                | 8    | Set  | 125.00                            | 1,000.00                           |
| <b>2</b> | <b>SH-II : Works at RR Station, Operational Area.</b>                                                                                                                                                                                                                                                                                                  |      |      |                                   |                                    |
| 2.01     | Supply of following size of XLPE insulated PVC sheathed copper conductor armoured power cable of 1.1KV grade confirming to IS 7098PART-1 with upto date amendments.                                                                                                                                                                                    |      |      |                                   |                                    |
| 2.02     | 5C X 4 sq.mm                                                                                                                                                                                                                                                                                                                                           | 800  | Mtr  | 148.00                            | 118,400.00                         |
| 2.03     | Supply of following size of XLPE insulated PVC sheathed copper conductor armoured power cable of 1.1KV grade confirming to IS 7098 PART-1 with upto date amendments.                                                                                                                                                                                   |      |      |                                   |                                    |
| 2.04     | 5C x 10 sq. mm                                                                                                                                                                                                                                                                                                                                         | 300  | Mtr  | 761.00                            | 228,300.00                         |
| 2.05     | Supplying and laying of 40 mm OD HDPE Pipe of PE 63 PN 6 along with all accessories conforming to IS 4984 direct in ground (0.75 mtr below the ground level) including excavation and refilling the trench etc., as required.                                                                                                                          | 1000 | Mtr  | 210.00                            | 210,000.00                         |

27

| Sl. no | Description                                                                                                                                                                                                                                                                                                                                                                                  | Qty  | Unit | Basic Rate in Rs. [excluding GST] | Total Amount in Rs. [with out GST] |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|-----------------------------------|------------------------------------|
| 2.06   | Laying of one number XLPE insulated and PVC sheathed power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning , protective covering and refilling the trench etc as required.                                                                                                                                                                    |      |      |                                   |                                    |
| 2.07   | Upto 35 Sq.mm                                                                                                                                                                                                                                                                                                                                                                                | 5    | Mtr  | 305.00                            | 1,525.00                           |
| 2.08   | Laying and fixing of one number XLPE insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of following size on wall surface as required.                                                                                                                                                                                                                                              |      |      |                                   |                                    |
| 2.09   | Upto 35 Sq.mm (clamped with 1mm Thick Saddle)                                                                                                                                                                                                                                                                                                                                                | 50   | Mtr  | 50.00                             | 2,500.00                           |
| 2.10   | Laying of one number XLPE insulated and PVC sheathed power cable of 1.1KV grade of following size in the existing RCC/ HUME/ METAL/GI/HDPE pipe as required.                                                                                                                                                                                                                                 |      |      |                                   |                                    |
| 2.11   | Upto 35 Sq.mm                                                                                                                                                                                                                                                                                                                                                                                | 1000 | Mtr  | 40.00                             | 40,000.00                          |
| 2.12   | Laying of one number XLPE insulated and PVC sheathed power cable of 1.1 KV grade of following size in the existing masonry open duct as required.                                                                                                                                                                                                                                            |      |      |                                   |                                    |
| 2.13   | upto 35 Sq.mm                                                                                                                                                                                                                                                                                                                                                                                | 40   | Mtr  | 35.00                             | 1,400.00                           |
| 2.14   | Supply & fixing of size not less than 205mm X 255mm X 112mm of cable loop in loop out outdoor thermoplastic junction box of IP 66 with 4 way terminals and knockouts for cable entry of 5C x 4 Sq.mm cable, earth stud, supply and fixing of 6A 10KA C curve MCB, Din bar including fixing the box on concrete/steel structure etc complete as required (Make: HENSEL / LEGRAND /Equivalent) | 6    | Each | 3250.00                           | 19,500.00                          |
| 2.15   | Supplying and making end termination with Brass compression gland and copper lugs for Following size of XLPE insulated and PVC sheathed Copper conductor cable of 1.1 KV grade as required.                                                                                                                                                                                                  |      |      |                                   |                                    |
| 2.16   | 5C X 4sq.mm                                                                                                                                                                                                                                                                                                                                                                                  | 12   | Set  | 300.00                            | 3,600.00                           |

27

| Sl. no | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Qty | Unit | Basic Rate in Rs. [excluding GST] | Total Amount in Rs. [with out GST] |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|-----------------------------------|------------------------------------|
| 2.17   | Supplying and making end termination with brass compression gland and copper lugs for following size of XLPE insulated and PVC sheathed copper conductor cable of 1.1 KV grade as required.                                                                                                                                                                                                                                                                     |     |      |                                   |                                    |
| 2.18   | 5C X 10 sq. mm                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4   | Set  | 400.00                            | 1,600.00                           |
| 2.19   | Supply & fixing of size not less than 300mm X 300mm X 182mm of cable loop in loop out outdoor thermoplastic polycarbonate junction box of IP 66 with 5 way terminals , 20A electronic timer with 3P contactor and knockouts for cable entry and exit of 5C x 10 Sq.mm cable, earth stud, supply and fixing of 32 A 10KA C curve MCB, Din bar including fixing the box on concrete/steel structure etc complete as required (Make: HENSEL / LEGRAND /Equivalent) | 2   | Each | 19000.00                          | 38,000.00                          |
| 2.20   | Supplying and laying of "B" Class G.I pipe of 80 mm dia, i/c excavation of bituminous/ concrete road/ pavement, excavation of Soil to maximum depth of 1.2 Mtrs from ground refilling the Soil and with CC of ratio 1:3:6 on top for 0.15 Mtrs after laying Pipe and plastering, making good the same etc., as required.                                                                                                                                        | 18  | Mtr  | 1600.00                           | 28,800.00                          |
|        | Total amount excluding GST Rs.                                                                                                                                                                                                                                                                                                                                                                                                                                  |     |      |                                   | 1,992,226.00                       |
|        | Add: GST @ 18%                                                                                                                                                                                                                                                                                                                                                                                                                                                  |     |      |                                   | 358,601.00                         |
|        | Total amount i/c GST                                                                                                                                                                                                                                                                                                                                                                                                                                            |     |      |                                   | 2,350,827.00                       |

(Rupees Twenty Three Lakhs Fifty Thousand Eight Hundred and Twenty Seven Only including GST)

Asst. General Manager (Engg-Elect)  
AAI, RHQ-SR, Chennai

आर. सुजाता / R. SUJATHA

सहायक महाप्रबन्धक (इंजी.- विद्युत) / Assistant General Manager (Engg.- Electrical)  
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India  
प्रचालन कार्यालय कॉम्प्लेक्स / Operational Offices Complex  
दक्षिणी क्षेत्र, चेन्नई - 16 / Southern Region, Chennai-16

FORMAT-A  
TO BE WRITTEN ON LETTER HEAD OF THE CONCERNED  
BUSINESS ESTABLISHMENT / CONCESSIONAIRES.

APPLICATION FOR SECURITY CLEARANCE FOR COMMERCIAL ACTIVITIES IN THE  
SECURITY RESTRICTED AREA (SRA) AT THE AIRPORTS

(TO BE SUBMITTED THROUGH REGIONAL DIRECTOR, BCAS OFFICE ONLY)

Letter ref. no. of the company

Date:-----

To

The RD,

Delhi / Mumbai / Kolkata / Chennai / Ahmedabad /  
Amritsar / Guwahati / Hyderabad and Imphal. (As applicable)

Sir,

Following documents of our company / firm who intends to operate / is  
operating as Business Establishment in SRA at \_\_\_\_\_ airport  
are submitted in duplicate copies for necessary security clearance and  
background checks of our company.

- i. Copy of certificate issue by Registrar of companies or any other central  
/ state govt. Authority registering the company for similar nature of  
work.
- ii. Company's profile giving details of owner / Directors employees  
contact addresses (registered office / Branch offices) & telephone no's.
- iii. Copy of latest license fee paid to Airport Director of respective airport.
- iv. Allotment of space to the Business Establishment / Concessionaire by  
Airport Operator.
- v. Copy of valid contract / agreement with Airport Operator.
- vi. Any other security clearance from BCAS is obtained earlier, if any;
- vii. Total number of staff required

Further, I undertake that neither me nor any of the firms associate had  
been involved / Charged in any criminal case in the past.

Our / My firm have not applied for security clearance through other RD  
office, except Present application.

I further declare that all the information pertaining to background checks  
of the company given here are true and no relevant fact, is concealed by me /  
us.

Yours faithfully,

Sign\_\_\_\_\_

Name\_\_\_\_\_

Address\_\_\_\_\_

Contact Tel No.\_\_\_\_\_

Company Seal:



Annexure-II

Fax No. \_\_\_\_\_

FORMAT A-1

Name and Address of Company:  
Whether Company is Indian, Foreign or JVC:

| SI. No.                                             | 1 | 2 | 3 | 4 |
|-----------------------------------------------------|---|---|---|---|
| Name (with alias of Owner / Director / Key Persons) |   |   |   |   |
| Nationality of Owner / Director / Key Persons       |   |   |   |   |
| DoB of Owner / Director / Key Persons               |   |   |   |   |
| Present Address of Owner / Director / Key Persons   |   |   |   |   |
| Permanent Address of Owner / Director / Key Persons |   |   |   |   |
| Parentage                                           |   |   |   |   |
| PP. No. (Legible copy to enclose)                   |   |   |   |   |
| ID Proof (Legible copy to enclose)                  |   |   |   |   |
| Shareholding pattern of the company FDI, if any     |   |   |   |   |

I \_\_\_\_\_ hereby undertake that all the above particulars and Information are true and best of my knowledge and belief.

Signature  
(Name)



**Signature Not Verified**

Digitally signed by R SUJATHA  
Date: 2023.05.15 12:11:07 IST  
Location: eProcurement System for Central PSUs