



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

Ref: AAI/RHQ/NER/DGM(E-C)/DMP/ILS/WO-37/22-23/ 807-808

Date: 02-03-2023

To,

M/s NSC Project Pvt.Ltd.,
L-87 Street no. 7C,
Mahipalpur Extension,
New Delhi-110037.
Email: narbirsingh07@gmail.com
Mobile no.: 91-9811012499/91-124-4222541

Subject:- Construction of ILS (LLZ/GP) Antenna platform and provision & installation of Frangible Hut for GP & LLZ including associated works (Civil+Elect) at Dimapur Airport.

Ref: 1) Your E- tender dated: 31.01.2023 (Tender ID. 2023_AAI_140507_1)

Dear Sir (S),

1. Your E-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totalling to **Rs.2,92,19,300/-** excluding GST (**Rupees Two Crore Ninety two Lakhs Nineteen Thousand Three Hundred Only**) which is 22.95 % below the estimated cost put to tender of Rs.3,79,23,000/- (Excluding GST).
2. DGM (Engg-Civil), AAI, RHQ, NER shall be the Engineer-in-charge of the work. You are requested to attend/depute your accredited representative empowered to sign the contract agreement on your behalf, in the office of the DGM (Engg-Civil), AAI, RHQ, NER, Guwahati by 11.03.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs.100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.
3. The earnest money amount of **Rs. 7,58,460/- (Rupees Seven Lakhs Fifty Eight Thousand Four Hundred Sixty only)** received along with your tender will be treated and converted as part of security deposit as per Clause No. 1A on page no.16 of contract document. Please deposit **Rs. 21,63,470/- (Rupees Twenty one Lakhs Sixty Three Thousand Four Hundred Seventy Only)** towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at page no. 16 of contract document.
4. You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and contract labour (Regulation and Abolition) Central rules 1971 Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause 19 on page no. 49 of GCC of tender and rules of Central and State Government.

Contd. page-2



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

-2-

5. You are also directed to contact AGM (Engg-Civil), AAI, Dimapur Airport immediately who will arrange to hand over the site to you.
6. Please note that the time allowed for carrying out the work shall be **06(Six) months** and same shall be reckoned from the 10th day after the date of issue of this letter.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Yours Faithfully,

Encl: As above.

(Shibu Jose)

DGM (Engg-Civil)

AAI, NER, RHQ, Guwahati-15

**For and on behalf of the Chairman,
Airports Authority of India.**

N.O.O:

1. RED, AAI, NER, RHQ, Guwhati-15.
2. GM Engg.(Civil), AAI, NER, RHQ, Guwhati-15.
3. GM Engg.(Elect), AAI, NER, RHQ, Guwhati-15.
4. Airport Director, AAI, Dimapur Airport.
5. CNS Incharge, AAI, Dimapur Airport.
6. AGM (Engg-C), AAI, RHQ, NER, Guwahati-15
7. AGM(E-C), AAI, Dimapur Airport
8. AGM(E-E), AAI, Dimapur Airport
9. SM (Fin), AAI, Dimapur Airport.
10. Asstt. Labour Commissioner, Dimapur Nagaland.
11. AGM (Vigilance), AAI, RHQ, NER, Guwahati-15.
12. Manger (Engg-C), AAI, Dimapur Airport.
13. Agreement Copy.
14. Office copy.

-Sd-

(Shibu Jose)

DGM (Engg-Civil)

AAI, NER, RHQ, Guwahati-15

1477833/2023/O/o APD(K)

Government eProcurement System Created By: Jayprakash Yadav Created Date/Time: 14-Feb-2023 03:47 PM Tender Title: Construction of ILS, LLZ,GP Antenna platform and provision and installation of Frangible Hut for GP and LLZ including associated works Civil and Electrical at Dimapur Airport. Tender ID: 2023_AAI_140507_1
Tender Inviting Authority: AGM(E-C) AAI, Dimapur Airport.
Name of Work: "Construction of ILS (LLZ/GP) Antenna platform and provision & installation of Frangible Hut for GP & LLZ including associated works Civil and Electrical at Dimapur Airport."
Contract No: 2023_AAI_140507

SCHEDULE OF WORK / ITEM(S)

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Estimated Rate	PABSCON(GSTN-19AADFP7887K1ZD)		NSC Projects Pvt. Ltd.(GSTN-07AADCN4958N1Z11)		Look East Construction Private Limited(GSTN-13AABCI2820K1Z11)	
					Rate	Amount	Rate	Amount	Rate	Amount
1.00	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge: All kinds of soil	7900.00	sqm		60.00	474000.00	80.00	632000.00	375.00	2962500.00
2.00	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	395.00	cum		175.00	69125.00	270.00	106650.00	450.00	177750.00
3.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	50.00	cum		60.00	3000.00	220.00	11000.00	275.00	13750.00
4.00	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	400.00	cum		1500.00	600000.00	270.00	108000.00	100.00	40000.00
5.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	485.00	cum		7000.00	3395000.00	5630.00	2730550.00	9650.00	4680250.00

L1 Amount	L1 Vendor
474000.00	PABSCON
69125.00	PABSCON
3000.00	PABSCON
40000.00	Look East Construction Private Limited
2730550.00	NSC Projects Pvt. Ltd.

6.00	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work, using coarse aggregate and fine aggregate derived from natural resources, Portland Pozzolana/Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the minimum specified cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level : Concrete of M25 grade with minimum cement content of 300 kg /cum	40.00	cum
7.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	130.00	cum
8.00	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work, using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level : Concrete of M25 grade with minimum cement content of 330 kg /cum	92.00	cum

8200.00	328000.00	6490.00	259800.00	9650.00	386000.00
7800.00	1014000.00	9400.00	1222000.00	9650.00	1254500.00
8500.00	782000.00	6400.00	588800.00	9650.00	887800.00

259800.00	NSC Projects Pvt. Ltd.
1014000.00	PABSCON
588800.00	NSC Projects Pvt. Ltd.

1477833/2023/O/o APD(K)

9.00	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	315.00	sqm
10.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	9200.00	kg
11.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:4 (1 cement : 4 coarse sand)	15.00	cum
12.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	95.00	kg
13.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	140.00	kg
14.00	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS-15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. Glazed Vitrified tiles Matt/Antiskid finish of size Size of Tile 600 x 600 mm	100.00	sqm
15.00	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	20.00	sqm
16.00	Supply & installation of TATA Ezy Nest Modular Sanitation Block or equivalent made up of sandwiches panels, made of 0.6 mm thick galvanised steel with 38 mm high density EPS insulation, of size 1220x915x2025 mm, including Civil foundation, plumbing works (PVC pipes & PTMT fittings), water storage (200 lt), electrical works & fittings, tile flooring & waste disposal system, as per manufacturer specification or equivalent, inclusive of all taxes, all complete as per satisfaction of EIC.	1.00	Each

400.00	126000.00	300.00	94500.00	380.00	119700.00
95.00	874000.00	90.00	828000.00	110.00	1012000.00
8500.00	127500.00	8440.00	128600.00	7500.00	112500.00
125.00	11875.00	140.00	13300.00	145.00	13775.00
120.00	16800.00	140.00	19600.00	145.00	20300.00
1800.00	180000.00	2890.00	289000.00	1585.00	158500.00
300.00	6000.00	335.00	6700.00	470.00	9400.00
200000.00	200000.00	110000.00	110000.00	87500.00	87500.00

94500.00	NSC Projects Pvt. Ltd.
828000.00	NSC Projects Pvt. Ltd.
112500.00	Look East Construction Private Limited
11875.00	PABSCON
16800.00	PABSCON
158500.00	Look East Construction Private Limited
6000.00	PABSCON
87500.00	Look East Construction Private Limited

1477833/2023/O/o APD(K)

17.00	Supply & fixing of 1000 Ltr Bio digester (Max solid waste usage: 25-30 ltr per day) with Anaerobic microbial inoculum (200 liters) as per manufacturer specification approved by DRDO and direction of EIC.	1.00	each
18.00	Providing and fixing of prefabricated (frangible hut) of size 8m x 5m (outer to outer) and 3000 mm height along the wall and 3500 mm at the centre. It is made of 50 mm thick sandwich panel made of 2 mm thick FRP/GRP sheet at the outer sides and middle part consists of PU foam of density 40 kg/m ³ which has to be installed in to the operational area. Provision of one no. of partition wall with partially glass door of size 920 mm(w) x 2000 mm (height) & locking arrangement and provision of one no. door of size 920 mm (w) x 2000 mm (h) with locking facility at the shorter side wall with a suitable provision necessary holes on wall for passing AC conduit and suitable provision necessary holes for electrical cable and a suitable provision necessary holes for NAV-AID cable as per requirement etc. The cost of the hut is inclusive of design, vetting of design by Govt. Engg. College, fabrication, transportation and commissioning of the hut at the proposed site as per drawing given in tender document and specification over cement concrete platform (Cement Concrete platform shall be paid separately). The exterior of the hut shall be provided with design of white and red squares (2 feet x 2 feet) and as per direction of E-I-C. All complete as per attached drawing and as directed by the Engineer-in-Charge.	2.00	1 job
19.00	Providing and fixing of prefabricated (frangible hut) of size 2m x 2m (outer to outer) and 3000 mm height along one wall and 3500 mm at the opposite wall. It is made of 50 mm thick sandwich panel made of 2 mm thick FRP/GRP sheet at the outer sides and middle part consists of PU foam of density 40 kg/m ³ which has to be installed in to the operational area. Provision of one no. door of size 920 mm (w) x 2000 mm (h) with locking facility at the higher side wall with a provision of exhaust fan at higher wall and necessary hole arrangement for electrical installations and necessary hole arrangement for sanitary installations etc. The cost of the hut is inclusive of design, vetting of design by Govt. Engg. College, fabrication, transportation and commissioning of the hut at the proposed site as per drawing given in page No. 223 of tender document and specification over cement concrete platform (Cement Concrete platform shall be paid separately). The exterior of the hut shall be provided with design of white and red squares (2 feet x 2 feet) and as per direction of E-I-C. All complete as per attached drawing and as directed by the Engineer-in-Charge.	2.00	1 Job

100000.00	100000.00	45000.00	45000.00	65000.00	65000.00
2750000.00	5500000.00	1600000.00	3200000.00	450000.00	900000.00
375000.00	750000.00	400000.00	800000.00	87500.00	175000.00

45000.00	NSC Projects Pvt. Ltd.
900000.00	Look East Construction Private Limited
175000.00	Look East Construction Private Limited

1477833/2023/O/o APD(K)

20.00	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work: 150 mm dia nominal bore	1000.00	mt
21.00	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work: 50 mm dia nominal bore	350.00	metre
22.00	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	7.00	cum
23.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	38.00	cum
24.00	Construction of embankment with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting with smooth wheel roller in each 20cm layers. (NOTE: Rate is inclusive of all nothing will be paid extra.) The earth shall be taken from AA1 land.	4010.00	Cum
25.00	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	900.00	Sqm
26.00	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	160.00	Cum

3000.00	3000000.00	1450.00	1450000.00	230.00	230000.00
2000.00	700000.00	560.00	196000.00	125.00	43750.00
1800.00	12600.00	2650.00	18550.00	400.00	2800.00
800.00	30400.00	2650.00	100700.00	300.00	11400.00
315.00	1263150.00	290.00	1162900.00	525.00	2105250.00
25.00	22500.00	200.00	180000.00	365.00	328500.00
3500.00	560000.00	3820.00	611200.00	4050.00	648000.00

230000.00	Look East Construction Private Limited
43750.00	Look East Construction Private Limited
2800.00	Look East Construction Private Limited
11400.00	Look East Construction Private Limited
1162900.00	NSC Projects Pvt. Ltd.
22500.00	PABSCON
560000.00	PABSCON

1477833/2023/O/o APD(K)

27.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver/finisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge	120.00	Cum
28.00	Construction of dry lean cement concrete sub base over a prepared sub-grade with coarse and fine aggregate conforming to IS 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per specifications, cement content not to be less than 150 Kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineer-in-charge.	120.00	Cum
29.00	Providing and laying design mix cement concrete of M-30 grade, in roads/ taxi tracks/ runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Note - Cement content considered in M-30 is @ 340 kg/cum. Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete prepared with batch mixing machine	150.00	Cum
30.00	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	20.00	Cum

3800.00	456000.00	2410.00	289200.00	4550.00	548000.00
6500.00	780000.00	3100.00	372000.00	4420.00	530400.00
9000.00	1350000.00	5090.00	763500.00	8250.00	1237500.00
8400.00	168000.00	9400.00	188000.00	8250.00	165000.00

289200.00	NSC Projects Pvt. Ltd.
372000.00	NSC Projects Pvt. Ltd.
763500.00	NSC Projects Pvt. Ltd.
165000.00	Look East Construction Private Limited

31.00	Providing and fixing pre-moulded joint filler in expansion joints of RCC roads / CC pavements after making the joints dust free with high pressure air jet cleaners, all complete as per direction of the Engineer-in-Charge. (Pre-moulded joint fillers shall be made of bitumen hot sealing compound impregnated fibre board having impregnation more than 35%, conforming to IS:1838 for fibre board and IS:1834 for hot sealing bitumen compound grade A.)	680.00	per cm depth per cm width per metre length
32.00	Providing and filling in position rubberized bitumen hot sealing compound for sealing of expansion joints in roads / pavements all complete as per direction of the Engineer-in-Charge. Using grade 'A' sealing compound conforming to IS: 1834	70.00	per cm depth per cm width per metre length
33.00	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge	7400.00	Sqm
34.00	Supply of 20 W, 1200 mm length, indoor surface mounted LED batten made up of aluminium housing, integrated electronic driver along with other accessories and suitable for use on 230 volts, 50 Hz, single phase, A.C. supply complete as required as per technical specifications.	30.00	Each
35.00	Supply of 25 W LED integral street light made up of pressure die cast aluminium housing with epoxy powder coated finish, IP65 protection and having LEDs, inbuilt driver along with other accessories and suitable for use on 230 volts, 50 Hz, single phase, A.C. supply complete as required as per technical specifications.	10.00	Each
36.00	Supply of 1200 mm sweep, 5 star electrical ceiling fan without regulator complete with down rod, canopies, ball bearing, motor, blades, capacitor etc. and suitable for use on 230 volts, 50 Hz, single phase, A.C. supply as required.	2.00	Each
37.00	Supply of 300 mm dia, 900 RPM, heavy duty exhaust fan including louvers and all accessories suitable for 230 V 50 Hz single phase AC supply etc. complete as required.	2.00	Each
38.00	Supplying and fixing of 32 x 12.5 mm U-PVC trunking system on surface alongwith end caps, changeable internal/external angles, flate angles, flate junction etc as per site requirement.	150.00	Meter

100.00	68000.00	150.00	99000.00	7.00	4620.00
350.00	24500.00	150.00	10500.00	11.00	770.00
1100.00	8140000.00	1500.00	11100000.00	1250.00	9250000.00
1800.00	54000.00	900.00	27000.00	1320.00	39600.00
8800.00	88000.00	3800.00	38000.00	1850.00	18500.00
2600.00	5200.00	2500.00	5000.00	1700.00	3400.00
5000.00	10000.00	4800.00	9600.00	1850.00	3700.00
250.00	37500.00	205.00	30750.00	175.00	26250.00

4620.00	Look East Construction Private Limited
770.00	Look East Construction Private Limited
8140000.00	PABSCON
27000.00	NSC Projects Pvt. Ltd.
18500.00	Look East Construction Private Limited
3400.00	Look East Construction Private Limited
3700.00	Look East Construction Private Limited
26250.00	Look East Construction Private Limited

1477833/2023/O/o APD(K)

39.00	Supplying and fixing of 105 x 50 mm U-PVC trunking system on surface alongwith cover, joints, internal/external angles, flate angles, end cap, flate junction, holding clips, clip-on support modules with finishing plate for mounting accessories i.e switch, socket etc as per site requirement.	100.00	Meter
40.00	Supplying and drawing 3 x 1.5 sqmm of FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit/ trunking as required.	100.00	Meter
41.00	Supplying and drawing 3 x 4 sqmm of FRLS PVC insulated copper conductor, single core cable in existing surface/ recessed steel/ PVC conduit/ trunking as required.	300.00	Meter
42.00	Supplying and fixing of 20 mm size of medium class FR PVC rigid conduit alongwith accessories in surface/ recess including cutting the wall and making the good the same in case of recessed conduit as required.	50.00	Meter
43.00	Supplying and fixing 5/6 amps modular switch on the existing modular plate & switch box or PVC trunking including connections but excluding modular plate etc as required.	32.00	Each
44.00	Supplying and fixing 15/16 amp modular switch on the existing modular plate & switch box or PVC trunking including connections but excluding modular plate etc. as required.	36.00	Each
45.00	Supplying and fixing 3 pin 5/6 amp modular socket outlet on the existing modular plate & switch box or PVC trunking including connections but excluding modular plate etc. as required.	4.00	Each
46.00	Supplying and fixing 6 pin 15/16 amp modular socket outlet on the existing modular plate & switch box or PVC trunking including connections but excluding modular plate etc. as required.	36.00	Each
47.00	Supplying and fixing 2M step type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	2.00	Each
48.00	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	24.00	Each
49.00	Supplying and fixing 12 Module (200 mm x 150 mm) size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.	4.00	Each

600.00	60000.00	415.00	41500.00	475.00	47500.00
180.00	18000.00	150.00	15000.00	87.00	8700.00
350.00	105000.00	250.00	75000.00	157.00	47100.00
108.00	5400.00	40.00	2000.00	105.00	5250.00
70.00	2240.00	150.00	4800.00	40.00	1280.00
160.00	5760.00	450.00	16200.00	87.00	3132.00
190.00	760.00	180.00	720.00	127.00	508.00
210.00	7560.00	290.00	10440.00	168.00	6048.00
400.00	800.00	1320.00	2640.00	620.00	1240.00
15.00	360.00	90.00	2160.00	300.00	7200.00
1150.00	4600.00	3500.00	14000.00	320.00	1280.00

41500.00	NSC Projects Pvt. Ltd.
8700.00	Look East Construction Private Limited
47100.00	Look East Construction Private Limited
2000.00	NSC Projects Pvt. Ltd.
1280.00	Look East Construction Private Limited
3132.00	Look East Construction Private Limited
508.00	Look East Construction Private Limited
6048.00	Look East Construction Private Limited
800.00	PABSCON
360.00	PABSCON
1280.00	Look East Construction Private Limited

1477833/2023/O/o APD(K)

50.00	Supplying and fixing 3 Module (100 mm x 75 mm) size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.	2.00	Each
51.00	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	2.00	Each
52.00	Extra for fixing the louvers/ shutters complete with frame for a exhaust fan of all sizes.	2.00	Each
53.00	Installation, testing and commissioning of outdoor LED light fitting including supply and fixing of 32 mm dia x 1 m length light class GI pipe, bracket, bending, reducer and all other accessories including connections etc. complete as required.	8.00	Each
54.00	Installation, testing and commissioning of pre-wired LED fitting of all types, complete with all accessories etc. directly on wall including connection with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	24.00	Each
55.00	Installation, testing and commissioning of ceiling fan, including wiring in the existing down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earth connection etc. as required.	2.00	Each
56.00	Supplying and fixing 6 way, Double door, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (UPS MCB DB, But without MCB/RCCB/Isolator).	2.00	Each
57.00	Supplying and fixing 8 way, Double door, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (UPS MCB DB, But without MCB/RCCB/Isolator).	4.00	Each
58.00	Supplying and fixing 4 way (4 + 12), Double door, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).	2.00	Each

450.00	900.00	3200.00	6400.00	280.00	560.00
400.00	800.00	2700.00	5400.00	300.00	600.00
750.00	1500.00	2700.00	5400.00	250.00	500.00
800.00	6400.00	920.00	7360.00	230.00	1840.00
300.00	7200.00	220.00	5280.00	230.00	5520.00
400.00	800.00	2500.00	5000.00	120.00	240.00
6500.00	13000.00	7500.00	15000.00	600.00	1200.00
8800.00	35200.00	7500.00	30000.00	840.00	3360.00
12000.00	24000.00	7500.00	15000.00	4775.00	9550.00

560.00	Look East Construction Private Limited
600.00	Look East Construction Private Limited
500.00	Look East Construction Private Limited
1840.00	Look East Construction Private Limited
5280.00	NSC Projects Pvt. Ltd.
240.00	Look East Construction Private Limited
1200.00	Look East Construction Private Limited
3360.00	Look East Construction Private Limited
9550.00	Look East Construction Private Limited

1477833/2023/O/o APD(K)

59.00	Supplying and fixing single channel digital time switch in the existing MCB DB complete with connections, testing and commissioning etc. as required.	2.00	Each
60.00	Supplying and fixing 5 A to 32 A rating, 240 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of single poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.	32.00	Each
61.00	Supplying and fixing 63 A rating, four pole, 415 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.	2.00	Each
62.00	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top along with 20 A, "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket outlet and complete with connections, testing and commissioning etc. as required.	12.00	Each
63.00	Supply, Installation, Testing and Commissioning of Fire Alarm and Fire Detection system consisting of the following components: (1) Microprocessor based Fire Alarm Control Panel, 8 zone, built in 24 volt battery supply with battery charger, Mains Power Supply 230 VAC $\pm 5\%$, 50Hz, with necessary external and internal indicators and external and internal control switches (2) 03 nos of Optical type smoke detectors, 12/24 V Smoke detectors, (3) Dual LED lamp type Fire Response Indicators for (installation inside false ceilings) (4) sounder (1 nos.) (5) Auto Dialer unit with keypad having storage capacity of minimum 10 nos emergency phone nos. and one voice message (at least 20 sec recording time) and interconnection with fire alarm control panel as per specification complete along with GSM wireless terminal feature through incorporation of GSM Slot for using GSM Simcard for making incoming and outgoing calls. (5) Hooter / Buzzer 65 dB $\pm$ 5 dB, 01 no.	2.00	Job
64.00	Supplying & laying of 2x1.5 sqmm fire alarm armoured cable, 600/1000V rated with annealed copper conductor having XLPE insulation, steel wire armouring & FRLS outer sheath complete as required.	100.00	Meter
65.00	Supplying and fixing 25 mm dia MS flexible pipe with PVC coating along with all ancillaries and accessories like coupler etc. as required.	50.00	Meter

2800.00	5800.00	8500.00	17000.00	10000.00	20000.00
250.00	8000.00	200.00	6400.00	200.00	6400.00
2000.00	4000.00	800.00	1600.00	360.00	720.00
700.00	8400.00	1400.00	16800.00	1820.00	21840.00
800000.00	1600000.00	190000.00	380000.00	275000.00	550000.00
200.00	20000.00	340.00	34000.00	187.00	18700.00
90.00	4500.00	700.00	35000.00	120.00	6000.00

5600.00	PABSCON
6400.00	Look East Construction Private Limited, NSC Projects Pvt. Ltd.
720.00	Look East Construction Private Limited
8400.00	PABSCON
380000.00	NSC Projects Pvt. Ltd.
18700.00	Look East Construction Private Limited
4500.00	PABSCON

1477833/2023/O/o APD(K)

66.00	Supply of 5 star rated energy efficient, 1.5 TR, inverter type, single phase, wall mounting type split Air conditioner unit, consisting of indoor unit, out door unit, cordless remote control, refrigerant gas, standard length of refrigerant pipe, drain pipe, power cable etc. and suitable for operation on 230 V, 50 HZ, single phase AC supply etc. as per OEM standard and complete as required as per technical specifications.	12.00	Each
67.00	Installation testing and commissioning of 1.5 TR Single phase Split AC units including fixing the condenser unit by providing and fixing suitable dimension of angle iron stand duly painted and fixing of evaporator unit including fixing of liquid & suction line, wiring between indoor and outdoor units, drain piping, insulation etc. supplied with unit, first charge of refrigerant etc. complete as required as per site conditions.	12.00	Job
68.00	Supply and fixing of refrigerant copper piping of 1/4" for delivery & 1/2" for return for connection between evaporator and condenser unit with insulation in addition to standard length supplied with AC unit complete as required as per site conditions.	36.00	Meter

60000.00	720000.00	45000.00	540000.00	57500.00	690000.00
7000.00	84000.00	2800.00	33600.00	55000.00	660000.00
500.00	18000.00	900.00	32400.00	600.00	21600.00

540000.00	NSC Projects Pvt. Ltd.
33600.00	NSC Projects Pvt. Ltd.
18000.00	PABSCON

Total in Figures

34087930.00

29219300.00

30419533.00

Lowest Amount Quoted BY: NSC Projects Pvt. Ltd.(29219300.00)


 शिबु जोस/SHIBU JOSE
 उप.महाप्रबंधक (अभियंता-सिविल)
 Dy.General Manager (Engg-Civil)
 भा.वि.प्रा.क्षे.मु.उ.पू.क्षे.,लो.गो.ब.अ.हवाईअड्डा
 AAI,RHQ,NER,L.G.B.I. Airport
 गुवाहाटी/Guwahati-781015

Signature Not Verified

Digitally signed by JAYPRAKASH MAHESH YADAV
 Date: 2023.03.24 14:35:45 IST
 Location: eProcurement System for Central PSUs

