



भारतीय विमानपत्तन प्राधिकरण Airports Authority of India



संदर्भ संख्या: भा.वि.प्रा-उ.क्षेत्र/पठानकोट/अभि-वि/कार्य संख्या-4/एस.टी.पी/2022-23/904(i-vi) दिनांक: 21.02.2023

Ref. No.: AAI-NR/Pathankot/E-E/W.O.-4/STP/2022-23/904(i-vi)

Date: 21.02.2023

Through – Email / Speed Post

सेवा में,

मेसर्स एन.आर. इंजीनियर्स
360, बसंत एवेन्यू
अजंता पब्लिक स्कूल के पास
अमृतसर

M/s N.R. Engineers
212, Basant Avenue
Near Ajanta Public School
Amritsar

कार्य का नाम: :- 01 वर्ष की डी.एल.पी अवधि पूरी होने के बाद 05 वर्ष के लिए ए.आई.सी.एम.सी के अंतर्गत सिविल एन्क्लेव, पठानकोट में 10 के.एल.डी क्षमता का सीवेज ट्रीटमेंट प्लांट (एस.टी.पी) का प्रावधान।

Name of Work: Provision of Sewage Treatment Plant (STP) of 10 KLD capacity at Civil Enclave, Pathankot i/c AICMC for 05 years after Completion of DLP period of 01 year.

संदर्भ संख्या:- निविदा आईडी के लिए आईडी/आपकी बोली:- 2022_AAI_140527_1 Dtd.07.01.2023

Ref No:- Your bid for Tender ID:- 2022_AAI_140527_1 Dtd.07.01.2023

महोदय/ Sir,

1. ऊपर उल्लिखित कार्य के लिए आपकी ई-निविदा, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत मद दरों पर कुल रु. 31,28,498/- (रुपये इकतीस लाख अट्ठाईस हजार चार सौ अठानवे केवल) (जीएसटी को छोड़कर), जो कि निविदा में रखी गई उचित लागत रुपये 40,51,836/- से 22.79% कम है।

Your E-tender for the work above mentioned, is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totalling to Rs. 31,28,498/- (Rupees Thirty One lakh Twenty Eight thousand four hundred Ninety Eight Only (Excl. GST), Which is 22.79% below the Justified Cost put to the tender Rs. 40,51,836/- Only.

2. स.महाप्रबन्धक (अभि-वि) आदमपुर विमानपत्तन इस कार्य के प्रभारी अभियंता रहेंगे। आपसे निवेदन है कि आप दिनांक 10.03.2023 तक स.महाप्रबन्धक (अभि-वि) आदमपुर विमानपत्तन के कार्यालय में उपस्थित हों या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करें जो करारनामे पर हस्ताक्षर के लिए अधिकृत हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु.100/- के नोन-ज्युडीशियल स्टाम्प पेपर पर निष्पादित किया जायेगा एवं स्टाम्प पेपर का खर्च आपके द्वारा उठाया जायेगा।

Asst. General Manager (E-E) Adampur Airport shall be the Engineer-in-charge for the work. You are requested to attend the office of AGM (Engg.-E) by 10.03.2023 to sign & complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rs. Hundred Only) and cost of the paper shall be borne by you.

3. कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर प्रतिभूति जमा राशि के रूप में रु 3,12,850 /- जमा कराये, अन्यथा अनुबंध की शर्तों के अनुसार 10% राशि आपके रनिंग बिलों से काट ली जाएगी।

Please deposit Rs. 3,12,850 /- towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted @10% from running bills.

4. आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों के 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 केंद्रीय नियम अनुबंध श्रम नियम (नियमन तथा उन्मूलन एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन करें।

You are requested to comply with provisions of the contract labour (Regulation and abolition) act 1970 and contract labour (Regulation and abolition) central rules 1971 and minimum wages act and rules thereof central and state government.

5. श्रम के विभिन्न विधानों के अनुसार संबंधित अधिकारियों से लाइसेंस/अनुमति लेने व पालन करने के लिए एकमात्र दायित्व ठेकेदार (करार फर्म / कंपनी सहित) का होगा जिसमें संविदा श्रम (विनियमन एवं उन्मूलन) अधिनियम, 1970 के अंतर्गत लेबर लाइसेंस लेना भी शामिल है।

It will be the sole liability of the contractor (including the contracting firm/company) to obtain and to abide by all necessary licenses/ permissions from authorities concerned as provided under various labour legislations including the labour licence obtained as per the provisions of the contract labour (Regulation and Abolition) Act, 1970.

6. ठेकेदार को उसके द्वारा तैनात कर्मियों का नियमित और प्रभावी पर्यवेक्षण और नियंत्रण सुनिश्चित करना होगा और सविंदात्मक दायित्वों के पालन के लिए उपयुक्त दिशानिर्देश देना होगा।

The contractor shall ensure regular and effective supervision and control of the personnel deployed by him and give suitable direction for undertaking the contractual obligations.

7. आपको निर्देश दिया जाता है कि आप तुरंत सहायक प्रबंधक (अभि- वि), पठानकोट विमानपत्तन से मिले, वह आपको साइट सौंपने की व्यवस्था करेंगे।

You are hereby directed to contact Assistant Manager (E-E), Pathankot Airport immediately who will arrange to hand over the site to you.

8. कृपया नोट कर लें कि कार्य करने की अवधि 03 माह है जोकि दिनांक 27.02.2023 से गिना जाएगा

Please note that time allowed for carrying out the work shall be 03 Months and same shall be reckoned from 27.02.2023.

9. इस ठेके के संबंध में आगे का कोई भी पत्राचार सहा. महा प्रबंधक (अभि-विधुत), भा वि प्रा, आदमपुर हवाई अड्डा, जालंधर -144103 के पते पर किया जाये।

Any further correspondence in connection with the contract should normally be addressed to Assistant General Manager (Engg- Elect.), AAI, Adampur Airport, Jalandhar-144103.

10. कृपया पावती भेजे और स्वीकृति के टोकन के रूप में सलग्न इस पत्र की दूसरी प्रति हस्ताक्षर करके वापस अधोहस्ताक्षरी को भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it, to the undersigned, as a token of acceptance.

11. इस कार्य की दोष दायित्व अवधि 12 महीने की होगी। इस अवधि के दौरान किसी भी प्रकार के दोष होने पर आपको अपने खर्च पर ठीक कराना होगा जिसकी जिम्मेदारी आपकी होगी। बकाया राशि को दोष दायित्व अवधि के खत्म होने के बाद वापस की जायेगी।

You will be responsible to make good and rectify at your own expense, any defect which may develop or may be noticed within the defects liability period of 12 months which shall be reckoned from the certified date of completion. The security deposit shall be refunded only after expiry of defects liability period.

प्रीत बर्वाल
21/02/23

सहा. महा प्रबंधक (अभि-विधुत),
कृते एवं की और से
अध्यक्ष, भा. वि. प्रा.

प्रतिलिपि :- सूचनार्थ

01. सहायक श्रम आयुक्त, JW8J+JCF, न्यू अमृतसर कॉलोनी, अमृतसर-143001-
Assistant Labour Commissioner, JW8J+JCF, New Amritsar Colony, Amritsar-143001
02. क्षेत्रीय भविष्य निधि आयुक्त, भविष्य निधि भवन, 9, बसंत एवेन्यू, ओल्ड जेल रोड, अमृतसर, पंजाब
Regional Provident fund Commissioner, Bhavishya Nidhi Bhavan, 9, Basant Avenue, Old Jail Road, Amritsar, Punjab
03. विमानपत्तन निदेशक, भाविप्रा, सिविल एन्क्लेव, पठानकोट
Airport Director, AAI, Civil Enclave, Pathankot
04. संयुक्त महाप्रबंधक (वित्त), भाविप्रा, संचालन कार्यालय, गुडगांव रोड, रंगपुरी, नई दिल्ली
JGM (F), AAI, Operational Offices, Gurgaon road, Rangpuri, New Delhi
05. सहायक प्रबंधक (अभि-वि-), भाविप्रा, सिविल एन्क्लेव, पठानकोट
Assistant Manager (Engg.-E), AAI, Civil Enclave, Pathankot
06. संबंधित फाइल
Concerned File

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Assistant General Manager (Engg-Elect), AAI, Civil Enclave Adampur, Adampur -144103

Name of Work: Provision of Sewage Treatment Plant (STP) of 10 KLD capacity at Civil Enclave, Pathankot i/c AICMC for 05 years after completion of DLP period of 01 year.

Contract No: 2023_AA_140527_1

Name of the Bidder/ Bidding Firm / Company :	NR ENGINEERS						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #	NUMBER #
SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL NPV AMOUNT Without Taxes in Rs. P	TOTAL NPV AMOUNT In Words	TOTAL quoted AMOUNT Without Taxes in Rs. P
1	2	4	5	13	53	55	53
1	SH-1 : CIVIL WORKS Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	12.800	cum	181.00	2316.80	INR Two Thousand Three Hundred & Sixteen and Paise Eighty Only	2316.80
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	15.950	cum	250.00	3987.50	INR Three Thousand Nine Hundred & Eighty Seven and Paise Fifty Only	3987.50
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	11.560	cum	6000.00	69360.00	INR Sixty Nine Thousand Three Hundred & Sixty Only	69360.00

4	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	16.180	cum	7000.00	113260.00	INR One Lakh Thirteen Thousand Two Hundred & Sixty Only	113260.00
5	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	7.000	cum	7500.00	52500.00	INR Fifty Two Thousand Five Hundred Only	52500.00
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	3718.160	kg	75.00	278862.00	INR Two Lakh Seventy Eight Thousand Eight Hundred & Sixty Two Only	278862.00
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	1608.600	kg	80.00	128688.00	INR One Lakh Twenty Eight Thousand Six Hundred & Eighty Eight Only	128688.00
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand) Code	11.990	cum	6200.00	74338.00	INR Seventy Four Thousand Three Hundred & Thirty Eight Only	74338.00
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	13.340	cum	7600.00	101384.00	INR One Lakh One Thousand Three Hundred & Eighty Four Only	101384.00

10	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	49.000	sqm	260.00	12740.00	INR Twelve Thousand Seven Hundred & Forty Only	12740.00
11	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand)	40.200	sqm	303.00	12180.60	INR Twelve Thousand One Hundred & Eighty and Paise Sixty Only	12180.60
12	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	80.400	sqm	200.00	16080.00	INR Sixteen Thousand & Eighty Only	16080.00
13	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	40.200	sqm	165.00	6633.00	INR Six Thousand Six Hundred & Thirty Three Only	6633.00
14	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work	40.200	sqm	130.00	5226.00	INR Five Thousand Two Hundred & Twenty Six Only	5226.00
15	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	100.000	kg	102.00	10200.00	INR Ten Thousand Two Hundred Only	10200.00
16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	250.000	kg	150.00	37500.00	INR Thirty Seven Thousand Five Hundred Only	37500.00

17	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	16.000	sqm	630.00	10080.00	INR Ten Thousand & Eighty Only	10080.00
18	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	2.100	sqm	3030.00	6363.00	INR Six Thousand Three Hundred & Sixty Three Only	6363.00
19	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 250 mm dia. R.C.C. pipe	30.000	metre	350.00	10500.00	INR Ten Thousand Five Hundred Only	10500.00
20	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	7.090	sqm	350.00	2481.50	INR Two Thousand Four Hundred & Eighty One and Paise Fifty Only	2481.50
21	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, uttresses, plinth and string courses fillets, kerbs and steps etc.	84.530	sqm	650.00	54944.50	INR Fifty Four Thousand Nine Hundred & Forty Four and Paise Fifty Only	54944.50

22	Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts	14.000	sqm	630.00	8820.00	INR Eight Thousand Eight Hundred & Twenty Only	8820.00
23	SH II : ELECTRICAL WORKS S.I.T.C. of 10 KLD capacity FRP based package STP unit on ground, working efficiently with MBBR technology including bar screen chamber, equalization tank, air blowers, secondary settling tank, sludge holding mechanism, filter press etc. alongwith suitable capacity pumps for operation as required and control panel etc. All the tanks shall have uPVC piping system complete with valves, couplers, pressure gauges, accessories etc. The system shall be leak proof with minimum HRT of 20 hours. Tertiary treatment shall be provided with online Chlorine & UV dosing to give desired results as per Technical specifications, relevant IS codes etc complete as required. (Excavation ,PCC, Concrete and other civil works etc not included in this item scope & shall be done as per Items in SH-I civil works)	1.000	Each	1300000.00	1300000.00	INR Thirteen Lakh Only	1300000.00
24	Supply of 3.5 C X 25 sq.mm. size aluminium conductor armoured XLPE insulated PVC sheathed electric power cable for working voltage upto 1.1 KV. as per IS :7098 (Part-I) etc as required.	410.000	metre	230.00	94300.00	INR Ninety Four Thousand Three Hundred Only	94300.00
25	Supply and making end termination with brass double compression flame proof gland and aluminium lugs for 3.5C x 25 sq mm size of PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 KV grade as required.	2.000	set	250.00	500.00	INR Five Hundred Only	500.00

26	Supplying and laying of 63 mm dia (OD-63 mm & ID-51 mm nominal) size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc. complete as required.	200.000	metre	230.00	46000.00	INR Forty Six Thousand Only	46000.00
27	Earthing with G.I. earth pipe 4.5 meter long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/coke and salt as required.	2.000	set	5500.00	11000.00	INR Eleven Thousand Only	11000.00
28	Providing, laying and fixing of 100mm dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc. as required.	10.000	metre	1550.00	15500.00	INR Fifteen Thousand Five Hundred Only	15500.00
29	Supplying and laying 25 mm X 5 mm G.I strip at 0.50 meter below ground as strip earth electrode, including connection/ terminating with G.I. nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of G.I nut bolt & spring washer spaced at 50 mm).	60.000	metre	120.00	7200.00	INR Seven Thousand Two Hundred Only	7200.00
30	Providing & Fixing 25 mm X 5 mm GI strip on surface or in recess for connections etc. as required.	20.000	metre	185.00	3700.00	INR Three Thousand Seven Hundred Only	3700.00
31	Supplying and laying 6 SWG G.I wire at 0.50 meter below ground level for conductor earth electrode, including connection/ terminating with G.I. thimble etc. as required	40.000	metre	36.00	1440.00	INR One Thousand Four Hundred & Forty Only	1440.00

32	Laying & fixing of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 kV grade of following size on wall surface as required. A) Upto 35 sq.mm.	100.000	metre	33.00	3300.00	INR Three Thousand Three Hundred Only	3300.00
33	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 1.1 kV grade of following size in the existing RCC/HUME/METAL pipe/DWC pipe as required. A) Upto 35 sq.mm.	280.000	metre	24.00	6720.00	INR Six Thousand Seven Hundred & Twenty Only	6720.00
34	Providing & Fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/recessed/submain wiring/cable etc. as required.	8.000	metre	36.00	288.00	INR Two Hundred & Eighty Eight Only	288.00
35	SITC of minimum 1.5 HP non clog type raw sewage transfer pump(cutter pump) to transfer raw sewage with minimum Discharge of 5 m3/hr at 10 meter head from underground septic tank to site i/c foundation/support arrangement,protection, necessary E & M -civil arrangement (rain protection enclosure for electrical system if required, cabling arrangement etc. complete)all including , providing necessary G.I./UPVC/CPVC/flexible piping arrangement ,interlinking,necessary valves, pressure gauges,inlet/outlet arrangement, including all necessary accessories with flange,SS bolts and nuts,gasket,Water tight power supply connection,earthing connection, etc. complete job as required as per site condition for satisfactory work condition as per approved make of AAI & as directed by EIC.	2.000	Job	70000.00	140000.00	INR One Lakh Forty Thousand Only	140000.00

36	Supply, installation, testing and commissioning of centrifugal, monoblock, Treated water pump minimum 1 HP , to transfer water from treated water tank with minimum Discharge of 5 m3/hr at 10 meter head,Cast Iron Impeller,Cast Iron Motorbody,concrete foundation/supporting arrangement ,necessary outdoor enclosure for rain protection,necessary E & M -civil arrangement (rain protection enclosure for electrical system if required, cabling arrangement etc. complete ,providing individual UPVC suctionlines,interlinking and common delivery line upto 1mtr with UPVC piping,UPVC butter fly valves(forbothsuction&discharge),UPVC non return valves,presure gauges with isolation etc. as required as per site condition including all necessary accessories etc. complete as required as per approved make of AAI & as directed by EIC.	2.000	Job	37000.00	74000.00	INR Seventy Four Thousand Only	74000.00
37	SH III : CAMC of STP plant 10 KLD after expiry of DLP of 01 year CAMC for 1st year after DLP	1.000	Job	90000.00	78606.00	INR Seventy Eight Thousand Six Hundred & Six Only	90000.00
38	CAMC for 2nd year after DLP	1.000	Job	100000.00	81630.00	INR Eighty One Thousand Six Hundred & Thirty Only	100000.00
39	CAMC for 3rd year after DLP	1.000	Job	110000.00	83919.00	INR Eighty Three Thousand Nine Hundred & Nineteen Only	110000.00
40	CAMC for 4th year after DLP	1.000	Job	115000.00	81995.00	INR Eighty One Thousand Nine Hundred & Ninety Five Only	115000.00
41	CAMC for 5th year after DLP	1.000	Job	120000.00	79956.00	INR Seventy Nine Thousand Nine Hundred & Fifty Six Only	120000.00
Total in Figures					3128498.90	INR Thirty One Lakh Twenty Eight Thousand Four Hundred & Ninety Eight and Paise Ninety	3257392.90
Quoted Rate in Words		INR Thirty One Lakh Twenty Eight Thousand Four Hundred & Ninety Eight and Paise Ninety Only					

Signature Not Verified

Digitally signed by Preeti Beniwal
Date: 2023.06.27 17:46:05 IST
Location: eProcurement System for
Central PSUs

Beeth
21/02/23