



रजिस्टर्ड ए.डी. दवारा/By Regd. A.D.

सं.सं. भाविप्रा/भोपाल/वि.नि./प्रभारी(अभि.-वि.)/का.आ.-23/2022-23 | 1979(1-9)
Ref. No: AAI/BPL/APD/ In-Charge(E-E)/WO-23/2022-23

दिनांक: 22.02.2023
Date: 22.02.2023

सेवा में,

मेसर्स पॉशडेकोर, लोढ़ा एस्टेट,
मित्तल इंडस्ट्रियल एस्टेट नंबर 5 के पीछे,
मरोल नाका अंधेरी ईस्ट,
मुंबई - 400059 (महाराष्ट्र)
ई-मेल: nitin@poshdecor.com

M/s POSHDECOR, Lodha Estate,
Behind Mittal Industrial Estate No.5,
Marol Naka Andheri East,
Mumbai - 400059 (Maharashtra)
E-mail: nitin@poshdecor.com

विषय : “राजा भोज विमानतल, भोपाल पर एनआईटीबी के प्रबुद्ध आंतरिक साइनेजेस का प्रावधान ।”
Subject: “Provision of Illuminated Internal Signages of NITB at R.B. Airport, Bhopal”

संदर्भ : 1) दिनांक 13.02.2023 को खोली गई आपकी निविदा
Ref.: 1) Your tender opened on dated 13.02.2023

महोदय/Dear Sir,

- 1- उल्लेखित कार्य हेतु आपकी ई-निविदा आपके द्वारा उद्धृत कुल **रु. 38,13,150/-** (रु. अड़तीस लाख तेरह हजार एक सौ पचास मात्र) की नियत मद दर पर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से एतद् द्वारा स्वीकृत की जाती है, जो कि ई-निविदा की अनुमानित लागत **रु. 51,58,917/-** (रु. इक्यावन लाख अठ्ठावन हजार नौ सौ सतरह मात्र) से **26.09 % कम** है ।

Your E-Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 38,13,150.00 (Rupees Thirty Eight Lakh Thirteen Thousand One Hundred Fifty only)** which is **26.09% Below** the estimated cost put to E-Tender of **Rs. 51,58,917.00 (Rupees Fifty One Lakh Fifty Eight Thousand Nine Hundred Seventeen Only)**.

- 2- विमानतल निदेशक / प्रभारी (अभि.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, राजा भोज विमानतल, भोपाल इस कार्य के इंजीनियरिंग प्रभारी होंगे। आपसे निवेदन है कि आप संविदा करार पर हस्ताक्षर करने एवं उसे पूरा करने हेतु **20.03.2023** तक विमानतल निदेशक / प्रभारी (अभि.-विद्युत), भारतीय विमानपत्तन प्राधिकरण, भोपाल विमानपत्तन के कार्यालय में उपस्थित हो । संविदा करार **रु 500/-** (पाँच सौ रुपये) के न्यायिकेतर (नॉन - ज्युडिशियल) स्टांप पेपर पर बनाया जायगा तथा स्टांप पेपर की लागत आपके द्वारा वहन की जाएगी ।

Airport Director / In-Charge (Engg.-Elect.), Airports Authority of India, Raja Bhoj Airport, Bhopal shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Airport Director / In-Charge (Engg.-Elect.), Airports Authority of India, Raja Bhoj Airport, Bhopal by **20.03.2023** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs. 500/- (Rupees Five Hundred only)** and the cost of the stamp paper shall be borne by you.

- 3- कृपया इस पत्र के जारी होने के 10 दिनों के अंदर प्रतिभूति जमा के रूप में **रु. 3,81,315/-** (रु. तीन लाख इक्यासी हजार तीन सौ पंद्रह मात्र) की राशि इस कार्यालय में जमा करा दें अन्यथा करारनामों की संविदा की सामान्य शर्त के पृष्ठ संख्या - 15 पर दी गई शर्त 1ए के अनुसार उक्त राशि आपके बिल से काट ली जाएगी ।

Please deposit **Rs. 3,81,315/- (Rupees Three Lakh Eighty One Thousand Three Hundred Fifteen Only)** towards Security Deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted as per condition of Clause 1A on page 15 of the contract document.

13

- 4- आपसे अनुरोध है कि आप ठेका श्रमिक (विनियम एवं उन्मूलन) अधिनियम 1970 के उपबंधों का अनुपालन करें। साथ ही ठेका श्रमिक (विनियम एवं उन्मूलन) केन्द्रीय नियमावली 1971 एवं केन्द्रीय एवं राज्य सरकारों के न्यूनतम वेतन तथा उससे संबंधित अन्य नियमों का पालन करें।
You are requested to comply with the provisions of contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) Central rules 1971 and minimum wages Act and rules thereof Central and State Governments.
- 5- आपको सहायक महाप्रबंधक (अभि.-वि.), भारतीय विमानपत्तन प्राधिकरण, राजा भोज विमानतल, भोपाल से तत्काल संपर्क करने का भी निर्देश दिया जाता है। आपको कार्यस्थल (साइट) सौंपने का कार्य उनके द्वारा किया जाएगा।
You are also directed to contact Asstt. Gen. Manager (Engg.-Elect.), AAI, Bhopal Airport immediately who will arrange to hand over the site to you.
- 6- कृपया नोट करे की कार्य पूरा करने के लिए आपको **03 (तीन) माह** का समय प्रदान किया जाता है। यह समय इस पत्र के जारी करने की तिथि के 10वे दिन से माना जाएगा।
Please note that the time allowed for carrying out the work shall be **03 (Three) Months** to complete the work. The same shall be reckoned from 10th day from date of issue of this letter.
- 7- इस ठेके से संबंधित किसी भी प्रकार के पत्र व्यवहार के लिए विमानतल निदेशक / प्रभारी (अभि.-विद्युत), भा.वि.प्रा., राजा भोज विमानतल भोपाल - 462036 को संबोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the Airport Director / In-Charge (Engg.-Elect.), Airports Authority of India, R. B. Airport, Bhopal - 462036.
- 8- कृपया इस पत्र की प्राप्ति की सूचना दें तथा इसके साथ अनुलग्न अनुप्रति पर हस्ताक्षर करके टोकन के प्रतिग्रहण के रूप में अधोहस्ताक्षरी को वापस भेज दें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9- यदि कोई विसंगति पाई जाती है तो अंग्रेजी भाषा ही मान्य होंगी।
In case any discrepancy is found, then English version will be taken as correct.

भवदीय / Yours Faithfully



(रामजी अवस्थी / Ramjee Awasthi)

विमानतल निदेशक / प्रभारी (अभि.-विद्युत)

Airport Director / In-Charge (Engg.-Elect.)

भा.वि.प्रा., राजा भोज विमानतल, भोपाल - 462036

AAI, Raja Bhoj Airport, Bhopal - 462036.

कृते तथा ओर से, अध्यक्ष,

For and on behalf of Chairman,

भारतीय विमानपत्तन प्राधिकरण.

Airports Authority of India.

N.O.O. / मूल प्रतिलिपि पर नहीं**Copy to/ प्रतिलिपि प्रेषित :-**

1. संयुक्त महाप्रबंधक (सतर्कता), भा.वि.प्रा
पश्चिमी क्षेत्र, सी.एस.आई. एयरपोर्ट, मुंबई-99. (निविदा प्रपत्र के शेड्यूल 'A' की कॉपी सहित)
Jt. General Manager (Vigilance) AAI.
Western Region, C.S.I. Airport, Mumbai-99 (Along with copy of Schedule 'A' of tender document)
2. आयकर आयुक्त
आयकर कार्यालय, होशंगाबाद रोड,
मैदा मिल के सामने, भोपाल।
Commissioner of Income Tax,
Income Tax office, Hoshangabad Road, Opposite Maida Mill, Bhopal.

आंतरिक/ INTERNAL

1. महाप्रबंधक (अभि- विद्युत), भा.वि.प्रा, दुमना विमानतल, जबलपुर - 482005 जानकारी हेतु ।
General Manager (Engg.-Elect.), AAI, Dumna Airport, Jabalpur - 482005 for information please
2. सहायक महाप्रबंधक (वित्त), भा.वि.प्रा, राजा भोज विमानतल, भोपाल-462036 जानकारी हेतु ।
Asstt. Gen. Manager (Finance), AAI, R.B. Airport, Bhopal - 462036 for information please
3. सहायक महाप्रबंधक (अभि- विद्युत), भा.वि.प्रा, राजा भोज विमानतल, भोपाल-462036 कार्यस्थल सौंपने एवं
उचित कार्यवाही हेतु ।
Asstt. Gen. Manager (Engg.-Elect.), AAI, R.B. Airport, Bhopal - 462036 To handover the site and
necessary action.
4. प्रबंधक (अभि- विद्युत), भा.वि.प्रा, राजा भोज विमानतल, भोपाल-462036 ठेका करारानुसार कार्य
निष्पादन हेतु ।
Manager (Engg.-Elect.), AAI, R.B. Airport, Bhopal - 462036 To Supervise the work as per
contract agreement.
5. करार प्रति/Agreement Copy.
6. कार्य फाईल/Works File.



विमानतल निदेशक / प्रभारी (अभि.-विद्युत)
Airport Director / In-Charge (Engg.-Elect.)

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AGM(E-E), AAI, R.B. Airport, Bhopal

Name of Work: Provision of Illuminated Internal Signages of NITB at R.B. Airport, Bhopal.

Contract No: AAI/BPL/ENGG(E)/NIT-18/2022-23

Name of the
Bidder/
Bidding
Firm /
Company :

POSHDECOR

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1.00	Entry/Exit Announcer Drg. No. - Refer design drawing 1.6bS, 1.6bG Providing and fixing Non-illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in- Charge. All exterior signs should be manufactured considering harsh outdoor conditions, weatherproofing techniques and materials shall be used. Sign Portal : Type B: 50mm deep portal has to be fabricated from 3 mm thick Yellow Aluminium Composit Panel with 0.25 mm PVDF, exterior grade with manufacturers warranty and test certificate from principle OEM from ALUDECOR / ALUCOBOND /EUROBOND or equivalent make, The internal structural frame to be made from 50 X 25 x 2 mm aluminium box section. Sign Letters : Providing and fixing Primary channel letters 50mm thk and Secondary profile cut letters 10mm thk, 3D cut letters in black glossy acrylic. All the letters would be made in profile to achieve true right angle. All mounting would be done in true plumb and using templet, keeping the alignment of the letters in one level	2.00	Job	90000.00	180000.00	INR One Lakh Eighty Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
2.00	2.1 a - Ceiling Hung Directional Sign Refer design drawing 2.1aS, 2.1aG Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge Sign face Sign face shall be made in 5mm thick 040 white acrylic (as specified) having graphics pasted in Plotter cut Block out vinyl. The Plotter cut block out vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in- Charge. Sign Frame : Providing and fixing sign frame 50mm wide Powder coated, colour RAL 9006 aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system on one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance. Suspender : Providing and fixing Stainless steel 35 x 35mm Hollow sections (assuming typical length of 1 meter) mounted on slabs/beams/walls. Lighting : All internal illumination shall be using LED strip edge Lights of approved make with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by the contractor at the site					
2.01	Message - 1	20.00	Job	30000.00	600000.00	INR Six Lakh Only
2.02	Message - 2	9.00	Job	39000.00	351000.00	INR Three Lakh Fifty One Thousand Only
2.03	Message - 3	1.00	Job	45000.00	45000.00	INR Forty Five Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
3.00	2.1b-3 Floor mounted directional sign - Single Refer design drawing 2.1b-3S, 2.1b-3G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in- Charge Sign face Sign face shall be made in 5mm thick 040 white acrylic (as specified) having graphics pasted in Plotter cut Block out vinyl. The Plotter cut block out vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in- Charge. Sign Frame: Providing and fixing sign frame 50mm wide Powder coated, colour RAL 9006 aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system on one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance. Sign Structure All structural members in SS square post 100 x 100 X 3mm, brush finished. base plate embedded below the floor finish and provided with a floor trim ring. All hardware used for fixing of sign shall be Stainless steel. Post including SS base Plate and Gussets in 6mm thick SS Plate as per drawing with holes to fix it on holding down bolts anchored in concrete slab. The post shall closed with a 3 mm thick SS plate as specified and approved by the Engineer-In-charge. Cost to include all activities and temporary props used for a perfect vertical in plumb installation, etc. required for fixing the sign in an internal location. Tension Rod: Providing and fixing tension rod in brush finished S.S. with the turn buckle system. Tension rod shall be fixed to the sign structure and the sign frame with S.S. gusset plates					
3.01	Lighting: All internal illumination shall be using LED strip edge Lights of approved make with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by the contractor at the site. Foundation: The item cost includes cutting and opening the floor finish at location, and making good the location to match the original finish after fixing and installation of sign Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete as per drawing.					
3.02	Message - 1	4.00	Job	105000.00	420000.00	INR Four Lakh Twenty Thousand Only

7

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
3.03	Message - 3	2.00	Job	120000.00	240000.00	INR Two Lakh Forty Thousand Only
3.04	Message - 5	2.00	Job	135000.00	270000.00	INR Two Lakh Seventy Thousand Only
4.00	2.2a - Wall Mounted Facility Announcer Drg. No. - Refer design drawing 2.2a-S, 2.2a-G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge Sign face Sign face shall be made in 5mm thick 040 white acrylic (as specified) having graphics pasted in Plotter cut Block out vinyl. The Plotter cut block out vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in- Charge. Sign Frame: Providing and fixing sign frame 50mm wide Powder coated, colour RAL 9006 aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system on one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance. Lighting: All internal illumination shall be using LED strip edge Lights of approved make with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by the contractor at the site. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete as per drawing.	15.00	Job	15900.00	238500.00	INR Two Lakh Thirty Eight Thousand Five Hundred Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
5.00	2.2d-1 Counter mounted facility Announcer Drg. No. Refer design drawing 2.2d-1G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in- Charge Sign face Sign face shall be made in 5mm thick 040 white acrylic (as specified) having graphics pasted in Plotter cut Block out vinyl. The Plotter cut block out vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in- Charge. Sign Frame: Providing and fixing sign frame 70mm wide Powder coated, colour RAL 9006 aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system on one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance. Sign Structure : All structural members in SS square post 100 x 100 x 3 mm, brush finished. base plate embedded below the floor finish and provided with a floor trim ring. All hardware used for fixing of sign shall be Stainless steel. Post including SS base Plate and Gussets in 6mm thick SS Plate as per drawing with holes to fix it on holding down bolts anchored in concrete slab. The post shall closed with a 3 mm thick SS plate as specified and approved by the Engineer-In-charge. Cost to include all activities and temporary props used for a perfect vertical in plumb installation, etc. required for fixing the sign in an internal location.					
5.01	Lighting: All internal illumination shall be using LED strip edge Lights of approved make with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by the contractor at the site.	4.00	Job	51000.00	204000.00	INR Two Lakh Four Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
6.00	Boarding Gates - Wall mounted / Ceiling Hung 2.2g-2 Boarding Gates - Wall mounted / Ceiling Hung Refer design drawing 2.2g-2, 2.2g-2-G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge Sign face Sign face shall be made in 5mm thick 040 white acrylic (as specified) having graphics pasted in Plotter cut Block out vinyl. The Plotter cut block out vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in- Charge. Sign Frame: Providing and fixing sign frame 70mm wide Powder coated, colour RAL 9006 aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system on one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance. Lighting: All internal illumination shall be using LED strip edge Lights of approved make with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by the contractor at the site.	10.00	Job	30000.00	300000.00	INR Three Lakh Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
7.00	Belt No. Sign 2.2h - Belt No. sign Refer design drawing 2.2h-S, 2.2h-G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in- Charge Sign Box: Providing and fixing sign box with laser cut Bent Fabrication in 5mm thick 040 acrylic with pantone yellow C Vinyl pasted over acrylic. Block out vinyl for text Pantone Black 6C. Complete box excluding bottom side is lighted with internal LED lighting. Acrylic fabrication shall have transparent structural supports for obstruction free lighting. Box to be directly mounted on the sign structure. Bottom panel: Bottom MS Panel powder coated in colour to match Vinyl Black of Pantone Black 6C. Sign Structure: Type 2 All structural members in SS square post 75 x 75 x 2.5 mm (assuming typical length of 2.7 meter), brush finished. base plate fixed to existing floor. All hardware used for fixing of sign shall be Stainless steel Post including SS base Plate and Gussets in 6mm thick SS Plate as per drawing with holes to fix it on holding down bolts anchored in concrete slab. The post shall have closed with a 3 mm thick SS plate as specified and approved by the Engineer-In- charge. Cost to include all activities and temporary props used for a perfect vertical in plumb installation, etc required for fixing the sign in an internal location. Lighting: All internal illumination shall be using LED strip Lights from of approved make with electronic controllers, having even spread and overlaps to avoid banding and dark spots and adhering to the LUX levels mentioned in the performance specification. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by the contractor at the site. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete as per drawing.	3.00	Job	33000.00	99000.00	INR Ninety Nine Thousand Only
8.00	Baggage Screening Box 2.2j-2- Baggage Screening Box Drg. No. -Refer design drawing 2.2j-2S, 2.2j-2G Providing and fixing non illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in- Charge Sign face: Providing and fixing Plotter cut Block out vinyl Pantone Black 6C, vinyl for text Cyan Pantone 311C and printed vinyl media for airline logos as per graphics, pasted over 3 mm aluminium sheet. Sign Structure: The sign mounting frame made up of 25 x 25 x 1.29 mm MS Square section. Accessories: Providing and fixing all accessories such as thimbles, end connectors, nut-inserts, screws, rivets, bolts, washers, nuts, etc. complete as per drawing	3.00	Job	12000.00	36000.00	INR Thirty Six Thousand Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
9.00	2.4 - Utility Signs 2.4a - Washroom / Drinking Water / Baby care Drg. No. -Refer design drawing 2.4a-S, 2.4a-G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge Sign face Sign face shall be made in 5mm thick 040 white acrylic (as specified) having graphics pasted in Plotter cut Block out vinyl. The Plotter cut block out vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in- Charge. Sign Frame: Providing and fixing sign frame 50mm wide Powder coated, colour RAL 9006 aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system on one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance. Lighting: All internal illumination shall be using LED strip edge Lights of approved make with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by the contractor at the site.	35.00	Job	12000.00	420000.00	INR Four Lakh Twenty Thousand Only
10.00	2.4b - Service Areas Drg. No. -Refer design drawing 2.4b-G Providing and fixing non-illuminated signs including all operations from fabrication to installation all complete as per drawings,technical specifications, signage schedule and to the satisfaction of the Engineer-in- Charge. Sign face : Digitally printed Graphics on vinyl pasted on 3mm thick black acrylic mounted on walls/claddings/ paneling's using VHB Tape	25.00	Job	510.00	12750.00	INR Twelve Thousand Seven Hundred & Fifty Only

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
11.00	2.4c – Lift No Sign Drg. No. -Refer design drawing 2.4c-S, 2.4c-G Providing and fixing illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in-Charge Sign face Sign face shall be made in 5mm thick 040 white acrylic (as specified) having graphics pasted in Plotter cut Block out vinyl. The Plotter cut block out vinyl shall match the specified colour (colour Pantone Black 6C) and vinyl for text Pantone yellow C or Cyan 311C as per graphics and of specified make duly approved by the Engineer-in- Charge. Sign Frame: Type - 2 Providing and fixing sign frame 50mm wide Powder coated, colour RAL 9006 aluminium extrusion with inbuilt frame to receive the sign face. The sign face shall be fixed to sign frame with 3M brand dual lock system on one side and 3M double side tape from the other side. The panel should be made easily openable for maintenance. Lighting: All internal illumination shall be using LED strip edge Lights of approved make with electronic controllers, having even spread and overlaps to avoid banding and dark spots. Cost to include all internal connections and Wiring, terminating and connecting the incoming cable laid by the contractor at the site.	36.00	Job	9600.00	345600.00	INR Three Lakh Forty Five Thousand Six Hundred Only
12.00	2.5 - Statutory Signs Drg. No. -Refer design drawing 2.5G-01, 2.5G-02 Providing and fixing Non-illuminated signs including all operations from fabrication to installation all complete as per drawings, technical specifications, signage schedule and to the satisfaction of the Engineer-in- Charge. Sign Face: Digitally printed Graphics on vinyl pasted on 3mm thick black acrylic mounted on walls/claddings/ paneling using VHB Tape					
12.01	Poster Size A1	2.00	Job	1500.00	3000.00	INR Three Thousand Only
12.02	Poster Size A4	4.00	Job	900.00	3600.00	INR Three Thousand Six Hundred Only

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER # BASIC RATE In Figures To be entered by the Bidder (Without GST) Rs. P	NUMBER # TOTAL AMOUNT in Rs. P	TEXT # TOTAL AMOUNT In Words
1	2	4	5	13	53	55
13.00	Emergency Signs - Photoluminescent Refer design drawing 2.6b-G Providing and fixing all Photoluminescent signs in the dedicated fire escape passages of the airports as per locations given in sign schedules, made of inkjet printing using artworks provided and with photoluminescent material as per technical specifications. Inkjetprinting shall be done on self-adhesive vinyl and pasted on 2mm thick powder coated white (RAL 9016) aluminium plate and fixed at location using screws. as per specification and using provided artwork including all operations from procuring the correct materials and made to sizes as specified and approved by the Engineer-in- charge. including all installation activities like marking, alignment and fixing with screws into the wall/cladding/face to the satisfaction of the Engineer-in- Charge					
13.01	Emergency Signs Photoluminiscent - Fire Equipment Sign (2.6b-1)	15.00	Job	1080.00	16200.00	INR Sixteen Thousand Two Hundred Only
13.02	At Lift (2.6b-4)	11.00	Job	1500.00	16500.00	INR Sixteen Thousand Five Hundred Only
13.03	Emergency escape direction sign (Exit) (2.6b-5)	10.00	Meter	1200.00	12000.00	INR Twelve Thousand Only
Total in Figures					3813150.00	INR Thirty Eight Lakh Thirteen Thousand One Hundred & Fifty Only
Quoted Rate in Words		INR Thirty Eight Lakh Thirteen Thousand One Hundred & Fifty Only				

Signature Not Verified

Digitally signed by Dadar Singh
 Date: 2023.04.27 10:34:56 IST
 Location: eProcurement System for Central
 PSUs

APD / In-Charge (Engg-E)
 AAI, R. B. Airport, Bhopal