



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
डिब्रूगढ़ हवाई अड्डा, डिब्रूगढ़
DIBRUGARH AIRPORT, DIBRUGARH

सं.भा.वि.प्रा./डिब/अभि.-सिविल/मेन्त/ W0-11/विशेष मरम्मत /२२-२३/

दिनांक: 24/02/2023

Ref.No.AAI/DIB/Engg-Civil/Maint/W0-11/ Special Repairs/22-23 Dated: 24/02/2023

To,
M/s Amtung Enterprise,
Gohpur Tinali,
Itanagar, Arunachal Pradesh,
Papum Pare District, Arunachal Pradesh
Pin-791113.

विषय: डिब्रूगढ़ हवाई अड्डे पर टर्मिनल बिल्डिंग और सिटी साइड के फेस लिफ्टिंग के लिए विशेष मरम्मत।
Name of Work: Special Repairs for face lifting of terminal Building and City Side at
Dibrugarh Airport.

संदर्भ: निविदा क्रमांक - 2023_AAI_14884_1 (कार्य की वित्तीय ई-बोली 20.02.2023 को खोली गई)
Ref.: Tender ID No.2023_AAI_14884_1 (Financial E-Bid for the work opened on
20.02.2023)

महोदय/Sir,

1. उपर्युक्त कार्य हेतु आपकी ई निविदा के सम्बन्ध में, आपके द्वारा उद्धरित राशि कुल ₹ 60,81,930.00 (साठ लाख इक्यासी हजार नौ सौ तीस रुपये मात्र) गुड्स एंड सर्विस टैक्स के बिना ,जो कि निविदा की प्राक्कलित मूल्य ₹ 64,10,552.00 से 5.13% नीचे है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rate quoted by you totaling to **Rs.60,81,930.00 (Sixty Lakhs Eighty One Thousand Nine Hundred Thirty Only) excluding GST** which is **5.13% (Five point One Three Percent)** below the estimate cost put to tender **₹64,10,552.00.**

2. संयुक्त महाप्रबंधक (इंजीनियरिंग.-सिविल.), डिब्रूगढ़ विमानपत्तन उपरोक्त कार्य के प्रभारी अभियंता होंगे। अतः आपसे अनुरोध किया जाता है की दिनांक: 21.03.2023 तक संयुक्त महाप्रबंधक (इंजीनियरिंग.-सिविल.), भा.वि.प्रा., डिब्रूगढ़ के कार्यालय में आकर अनुबंध पर हस्ताक्षर करने और समझौता पूरा करें। अनुबंध को रुपये 100/- (केवल एक सौ रुपये के गैर-न्यायिक स्टांप पेपर पर निष्पादित किया जाएगा।) -/100 एक सौ रुपये मात्र (और स्टांप पेपर की कीमत आपको वहन करनी होगी।

Jt. GM (Engg-Civil) AAI, Dibrugarh Airport, Dibrugarh, shall be the Engineer-In-Charge of the work. You are requested to attend the office of Jt. GM (Engg-Civil), AAI, Dibrugarh Airport by **21.03.2023** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

(Signature)
25/2/23
1 | Page

3. कृपया इस पत्र के जारी होने के 10 दिनों के अन्दर प्रतिभूति जमा के रूप में **₹ 6,08,193.00 (छह लाख आठ हजार एक सौ तिरानवे रुपये मात्र)** की राशि इस कार्यालय में जमा करा दें अन्यथा संविदा की सामान्य शर्तों के खंड 1 A पृष्ठ संख्या जी.सी.सी 1 7 पर खंड A1 कि शर्त के अनुसार घटाया जाएगा।

Please deposit **Rs.6,08,193.00(Rupees Six Lakhs Eight Thousand one Hundred Ninety Three Only)** towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per GCC Clause 1A on page 17 of the contract document.

4. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की शर्तों) के प्रावधान का पालन करें।) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि खंड 19 पृष्ठ संख्या 50 पर में निर्दिष्ट है और संविदा की सामान्य शर्तों के पेज नं 89 और केंद्र और राज्य सरकार के नियम।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) central rules 1971, Child labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other Construction workers welfare cess Act 1996 as specified in clause 19 on page no. 50 and page no. 89 of GCC of tender and rules of Central and State Govt.

5. आपको यह भी निर्देश दिया जाता है कि आप **सहायक महाप्रबंधक(अभि.-सिविल)-II, भा.वि.प्रा., डिब्रूगढ़** से अविलम्ब संपर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact **AGM(Engg-Civil)-II, AAI, Dibrugarh Airport, Dibrugarh** immediately who will arrange to hand over the work to you.

6. कृपया ध्यान दें कि कार्य करने के लिए नियत समय **2 (दो)** महीने होगा जिसकी गणना इस पत्र के जारी होने के 10 वें दिन से की जाएगी।


Please note that the time allowed for carrying out the work shall be **2 (Two) months** and same shall be reckoned from the 10th day after issue of this letter.

7. इस अनुबंध से सम्बंधित किसी भी प्रकार के पत्राचार संयुक्त महाप्रबंधक (इंजीनियरिंग.-सिविल.) भारतीय विमानपत्तन प्राधिकरण, डिब्रूगढ़ विमानपत्तन, डिब्रूगढ़ -786012 को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Jt. GM(Engg-Civil), Airports Authority of India, Dibrugarh Airport - 786012.

8. कृपया इस पत्र के प्राप्ति की सूचना दें तथा इसके साथ संलग्न इस पत्र की प्रतिलिपि पर विधिवत हस्ताक्षर करने के उपरांत स्वीकृति के प्रमाण स्वरूप इसे अधोहस्ताक्षरी को वापस भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.


25/7/23


9. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण मान्य होगा।

In case of any discrepancy is found then English version will be taken as correct.

धन्यवाद / Thanking you,

संलग्न: Item Rate SOQ. (Page-01 to 03)

भवदीय/Yours Sincerely,



ब्रिज मोहन कौल (Brij Mohan Kaul)

संयुक्त महाप्रबंधक (इंजीनियरिंग.-सिविल)/ Joint GM (Engg.– Civil)

कृते तथा की ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI

भा.वि.प्रा. डिब्रूगढ़ विमानपत्तन / AAI, Dibrugarh Airport

[Validate](#)[Print](#)[Help](#)

Tender Inviting Authority: Bonny Bastian, AGM(Engg-Civil)-II, AAI, Dibrugarh Airport

Name of Work: Special Repairs for face lifting of terminal building and City Side at Dibrugarh Airport

Contract No: 2023_AAI_141884_1

Item Rate Boq

Name of the Bidder/ Bidding Firm / Company :

M/s Amtung Enterprise

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2 Providing and laying wanderfloor "SAFETY/TRACTION" Series Anti Skid Vinyl Flooring of 1.5 mm thickness or equivalent suited for heavy traffic with extra grip for walking/movements having performance characteristics within permissible limits to relevant specifications as per instruction and Direction of Engineer-in-charge. (Sample to be got approved from EIC before Execution of item)	3	4	5	6	7
1	Providing and laying wanderfloor "SAFETY/TRACTION" Series Anti Skid Vinyl Flooring of 1.5 mm thickness or equivalent suited for heavy traffic with extra grip for walking/movements having performance characteristics within permissible limits to relevant specifications as per instruction and Direction of Engineer-in-charge. (Sample to be got approved from EIC before Execution of item)	581.00	sqm	800.00	464800.00	INR Four Lakh Sixty Four Thousand Eight Hundred Only
2	Providing and fixing Double Glazing Unit Glass of Series SS COOL LITE ST120 of Saint Goban of Approved make or Equivalent conforming to relevant specifications as per Instruction and Direction of Engineer-in-charge	29.00	sqm	6000.00	174000.00	INR One Lakh Seventy Four Thousand Only
3	Providing and fixing frosted Architectural Glass Film (plain / designer) of 3M DINOC series or equivalent of 50 micron thickness over the existing glass panes at all height as per direction and satisfaction of Engineering-In-charge. (Sample for colour and architectural design to be got approved from EIC before Execution of item)	105.00	sqm	900.00	94500.00	INR Ninety Four Thousand Five Hundred Only
4	Providing and fixing Anti Glare sun Control Film (plain / designer) of 3M Prestige series or equivalent of 50 micron thickness conforming to relevant technical specification over the existing glass panes at all height as per direction and satisfaction of Engineering-In-charge.	261.00	sqm	1180.00	307980.00	INR Three Lakh Seven Thousand Nine Hundred & Eighty Only
5	Job contract for providing backhoe loader (JCB) i/c diesel, Driver and helper with on hourly basis for cleaning wild growth, levelling of ground etc. inside operational area including fuel, hydraulic oil, operator etc. complete.	15.00	Per Job	1900.00	28500.00	INR Twenty Eight Thousand Five Hundred Only
6	Job contract for providing Tipper i/c diesel, Driver and helper with on hourly basis inside Non operational/ operational area including fuel, hydraulic oil, operator etc. complete.	15.00	Per Job	1600.00	24000.00	INR Twenty Four Thousand Only
7	Job contract for deploying unskilled labour on daily basis for miscellaneous jobs viz cleaning of surroundings, minor demolishing/repair, any urgent work etc. with required tools and plants and supervision. (minimum wages as per rate published by Chief Labour Commissioner (C) should be paid and necessary documentary evidence should be maintained by the contractor.	100.00	Per Job	750.00	75000.00	INR Seventy Five Thousand Only
8	Job contract for deploying Semi-skilled labour on daily basis for miscellaneous jobs viz cleaning of surroundings, minor demolishing/repair, any urgent work etc. with required tools and plants and supervision. (minimum wages as per rate published by Chief Labour Commissioner (C) should be paid and necessary documentary evidence should be maintained by the contractor.	25.00	Per Job	830.00	20750.00	INR Twenty Thousand Seven Hundred & Fifty Only
9	Job contract for deploying skilled labour on daily basis for miscellaneous jobs viz cleaning of surroundings, minor demolishing/repair, any urgent work etc. with required tools and plants and supervision. (minimum wages as per rate published by Chief Labour Commissioner (C) should be paid and necessary documentary evidence should be maintained by the contractor.	15.00	Per Job	900.00	13500.00	INR Thirteen Thousand Five Hundred Only
10	Providing and fixing stainless steel 316 Anti Skid Concentric circles with plain bevel edge tactile flooring studs of size 35mm dia reduced to 25 mm X 4.5 mm with stem 6 mm X 12 mm for guidance of visually impaired divyang Jan with proper drilling and applying suitable adhesive in drilled holes in existing floor as per direction and satisfaction of Engineer-in-charge.	2016.00	each	175.00	352800.00	INR Three Lakh Fifty Two Thousand Eight Hundred Only

11	Providing and fixing stainless steel 316 Anti Skid linear grooves with plain bevel edge tactile flooring directional strip of size 280mm X 35mm X 4.5mm with stem 6mm X 12mm for guidance of visually impaired divyang Jan with proper drilling and applying suitable adhesive in drilled holes in existing floor as per direction and satisfaction of Engineer-in-charge.	2,934.00	each	376.00	1100250.00	INR Eleven Lakh Two Hundred & Fifty Only
12	Providing and fixing precast RCC chair bench with back rest seating bench of three seater capacity (plain / colourful) of as per direction and satisfaction of Engineer-in-charge. Dimension: 1500 mm x 450 mm x 1000 mm (length x seating height x total height x width)	16.00	each	6800.00	108800.00	INR One Lakh Eight Thousand Eight Hundred Only
13	Filling weather proof silicon sealant of approved make in joints of Glazing as per Direction and Satisfaction of Engineer-in-charge. Each bottle of capacity 260-350 ml	134.00	each	300.00	40200.00	INR Forty Thousand Two Hundred Only
14	Providing Rectangular FRP Planter of Size 0.900 m x 0.600 x 0.30 m with local design and colour as per Direction and Satisfaction of Engineer-in-charge.	10.00	each	4100.00	41000.00	INR Forty One Thousand Only
15	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	50.00	Sqm	100.00	5000.00	INR Five Thousand Only
16	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (One or more coat applied @ 0.90 ltr/10 sqm).	200.00	Sqm	100.00	20000.00	INR Twenty Thousand Only
17	Artistic painting of Logos , letters, themes, scenarios etc. on exterior wall with premium acrylic exterior paint with silicon additives of all shades. Two more coats of paint to be applied with approved colour combinations to obtain themes , G20 Logos etc. approved by the Engineer -In-Charge. The cost shall include all materials, scaffoldings, labour etc.	150.00	Sqm	800.00	120000.00	INR One Lakh Twenty Thousand Only
18	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete , i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc ., of required size , on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer -in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	415.00	Kg	690.00	286350.00	INR Two Lakh Eighty Six Thousand Three Hundred & Fifty Only
19	Providing and laying Ceramic glazed floor tiles of size 300X300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White , Ivory, Grey, Flame Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry pointing the joints with white cement and matching pigment etc. complete.	100.00	sqm	1140.00	114000.00	INR One Lakh Fourteen Thousand Only
20	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete , including disposal of rubbish to the dumping ground , all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	100.00	sqm	400.00	40000.00	INR Forty Thousand Only
21	Providing and laying flamed finish Granite stone flooring in required design and patterns , in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	200.00	sqm	3480.00	696000.00	INR Six Lakh Ninety Six Thousand Only
22	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead For thickness of tiles 10 mm to 25 mm	300.00	sqm	300.00	90000.00	INR Ninety Thousand Only
23	Disposal of building rubbish / malha / similar unserviceable, dismantled or waste materials by mechanical means , including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer -in-charge, beyond 50 m initial lead , for all loads including all lifts involved.	100.00	cum	500.00	50000.00	INR Fifty Thousand Only
24	Providing and laying in Metal Ceiling System of 600X600 mm module which includes repair of ceiling tile system if required , replacing of existing metal ceiling tiles with new metal ceiling tiles of 600 mm x 600 mm of Armstrong or equivalent make , of texture, design and colour as approved and as per Direction of Engineer-in-charge. The existing ceiling tiles shall be placed and stored in a place as per Direction of Engineer-in-charge.	1,000.00	each	580.00	580000.00	INR Five Lakh Eighty Thousand Only

INR 251143

25	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	550.00	Sqm	890.00	489500.00	INR Four Lakh Eighty Nine Thousand Five Hundred Only
26	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not be more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer -in-charge (length of finished kerb edging shall be measured for payment) (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	12.00	Cum	9000.00	108000.00	INR One Lakh Eight Thousand Only
27	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	50.00	cum	5800.00	290000.00	INR Two Lakh Ninety Thousand Only
28	Providing and applying 2.5 mm thick road marking strips (retroreflective) of specified shade / colour using hot thermoplastic material by fully / semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications.	300.00	sqm	300.00	90000.00	INR Ninety Thousand Only
29	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work	500.00	sqm	450.00	225000.00	INR Two Lakh Twenty Five Thousand Only
30	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	200.00	kg	120.00	24000.00	INR Twenty Four Thousand Only
31	Manufacturing, supplying and fixing retro reflective overhead signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeing conforming to type - III of ASTM -D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC: 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with their resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat The rate includes the cost of rounding off the corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge (Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment Overhead Informatory road signage	10.00	sqm	800.00	8000.00	INR Eight Thousand Only
Total in Figures				800.00	6081930.00	INR Sixty Lakh Eighty One Thousand Nine Hundred & Thirty Only
Quoted Rate in Words		INR Sixty Lakh Eighty One Thousand Nine Hundred & Thirty Only				


 23/12/23