

BOQ Summary Details

Tender Title: Associate electrical works for operationalization of new terminal building SH Relocation of fire pump room.
Tender ID: 2023_AAI_142635_1

Sheet Name	Sl.No	Bidder Name	Amount	Bid Rank
BoQ1	1	Voltas Ltd	8333333.00	L1
	2	Sterling and Wilson Pvt. Ltd	8848766.00	L2

[Signature]
24/04/2023
ACME-C

[Signature]
H. Khan

[Signature]
Am (Fin)

Contract No: 2023_AAI_142635_1

L1 Amount	L1 Vendor
1453436.00	Voltas Ltd

1.00	Supplying, installation, testing and commissioning of Electric driven Main Fire Pump suitable for automatic operation and consisting of following, complete in all respects, as required : (a) Horizontal type, multistage, centrifugal, split casing pump of cast iron body & bronze impeller with stainless steel shaft, mechanical seal conforming to IS 1520. (b) Suitable HP Squirrel cage induction motor, TEFC, synchronous speed 1500 RPM, suitable for operation on 415 volts, 3 phase 50 Hz, AC supply with IP 55 protection for enclosure, horizontal foot mounted type with Class-'F' insulation, conforming to IS-325. (c) M.S. fabricated Common base plate, coupling, coupling guard, foundation bolts etc. as required. (d) Suitable cement concrete foundation duly plastered with anti vibration pads. 2850 lpm at 70 m Head to ensure a minimum pressure of 3.5 kg/sq.cm. at highest and farthest outlet. (The pump shall be capable of giving a discharge of not less than 150% of the rated discharge at a head of not less than 65% of the rated head and Motors for Main fire pumps shall be at least equivalent to the horse power required to drive the pump at 150% of its rated discharge and shall be designed for continuous full load duty.)	2.00	Set
------	--	------	-----

~~Handwritten signature~~

[Handwritten signature]

1-27-74
 E. J. Kelly
 [Signature]

2.00	Supplying, installation, testing and commissioning of diesel engine driven main fire pump suitable for automatic operation and consisting of following, complete in all respects, as required : (a) Horizontal type, multistage, centrifugal pump of cast iron body and bronze impeller with stainless steel shaft, mechanical seal conforming to IS 1520. (b) Suitable HP, 1500 RPM water cooled with radiator, diesel engine conforming to relevant IS standard complete with auto starting mechanism, 12/24 volts electric starting equipment, diesel tank, exhaust pipe extended upto 10 m outside pump house duly insulated with 50 mm thick glass wool with 1.0 mm thick aluminium sheet cladding, residential silencer, instruments and protection as per standard specification, stop solenoid for auto stop in the event of fault with audio indications, painted with post office red colour etc. as required. (c) M.S fabricated, common base plate, coupling, coupling guard, foundation bolts etc. as required. (d) Suitable cement concrete foundation duly plastered and with anti vibration pads. 2850 lpm at 70 m Head to ensure a minimum pressure of 3.5 kg/sq cm. at highest and farthest outlet. (The motor shall be designed at least 20% greater than the maximum HP required to drive the pump at its duty point. It shall also be capable of driving the pump at 150% of the rated discharge)	1.00 Set
3.00	Supplying, installation, testing and commissioning of electric driven pressurisation pump suitable for automatic operation and consisting of following, complete in all respects, as required : (Jockey Pump) (a) Horizontal type, multistage, centrifugal pump of cast iron body and bronze impeller with stainless steel shaft, mechanical seal conforming to IS 1520. (b) Suitable HP squirrel cage induction motor TEFC type suitable for operation on 415 volts, 3 phase 50 Hz AC supply with IP 55 class of protection for enclosure, horizontal foot mounted type with Class-'F' insulation, conforming to IS : 325. (c) M.S fabricated Common base plate, coupling, coupling guard, foundation bolts etc. as required. (d) Suitable cement concrete foundation duly plastered and with anti vibration pads. 180 lpm at 70 m Head (HP for pump shall designed considering item no. 01 and 02 above)	2.00 Set
4.00	Fabrication, supply, installation testing & commissioning of Electrical control panel DETAILED DESCRIPTION AS PER SOQ SL. NO. 4 OF TENDER DOCUMENT	1.00 Set

1006430.00	1006430.00	1093780.00	1093780.00	1006430.00	Volta Ltd
159092.00	318184.00	196502.00	393004.00	318184.00	Volta Ltd
1071893.00	1071893.00	1037364.00	1037364.00	1037364.00	Sterling and Wilson Pvt. Ltd

Handwritten signature and initials in blue ink.

Handwritten signature in blue ink.

Handwritten signature and text in blue ink, including the word 'Approved'.

5.00	Providing, laying, testing & commissioning of 'C' class heavy duty MS pipe conforming to IS 3589/IS 1239 including Welding, fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame and painting with two or more coats of synthetic enamel paint of required shade complete as required :		
5.01	50 mm dia	30.00 Mtr	
5.02	80 mm dia	30.00 Mtr	
5.03	150 mm dia	110.00 Mtr	
5.04	200 mm dia (wall thickness 6.3 mm)	25.00 Mtr	
6.00	Providing laying, testing & commissioning of 'C' class heavy duty MS Pipe conforming to IS 1239/3589 i/c fittings like elbows, tees, flanges, tapers, nuts bolts, gaskets etc. in/on ground including welding, excavation (if in ground) & providing cement concrete blocks as supports, anticorrosive treatment with coaltar/asphalt tape (if in ground) as per IS 10221, painting, refilling the trench (if in ground) etc. of following sizes complete as required. 150 mm. dia	180.00 Mtr	
7.00	Supplying, fixing, testing & commissioning of double flanged sluice valve of rating PN 1.6 with non rising spindle, bronze/gun metal seat, ISI marked complete with nuts, bolts, washers, gaskets and conforming to IS 780 of following sizes as required :		
7.01	80 mm dia	4.00 Set	
7.02	150 mm dia	7.00 Set	
7.03	200 mm dia	2.00 Set	
8.00	Supplying, fixing, testing and commissioning of butterfly valve of PN 1.6 rating with bronze/gunmetal seat duly ISI marked complete with nuts, bolts, washers, gaskets conforming to IS 13095 of following sizes as required :		
8.01	50 mm dia	1.00 Set	
8.02	80 mm dia	2.00 Set	
9.00	Providing, installation, testing and commissioning of non-return valve of following sizes conforming to IS: 5312 complete with rubber gasket, GI bolts, nuts, washers etc.as required :		


 24/02/23
 Trench-5

1294.00	38820.00	1453.00	43590.00
1987.00	59610.00	1977.00	59310.00
3928.00	432080.00	3995.00	439450.00
6215.00	155375.00	5918.00	147950.00
4289.00	772020.00	5023.00	904140.00
17035.00	68140.00	28374.00	113496.00
25014.00	175098.00	49390.00	345730.00
55114.00	110228.00	76306.00	152612.00
4511.00	4511.00	4797.00	4797.00
5321.00	10642.00	5917.00	11834.00


 24/02/23

38820.00	Voltas Ltd
59310.00	Sterling and Wilson Pvt. Ltd
432080.00	Voltas Ltd
147950.00	Sterling and Wilson Pvt. Ltd
772020.00	Voltas Ltd

68140.00	Voltas Ltd
175098.00	Voltas Ltd
110228.00	Voltas Ltd

4511.00	Voltas Ltd
10642.00	Voltas Ltd


 24/02/23

9.01	80 mm dia	2.00	Set
9.02	150 mm dia	3.00	Set
10.00	Providing, installation, testing and commissioning of stainless steel Y-strainer fabricated out of 1.6 mm thick stainless steel, Grade 304, sheet with 3 mm dia holes with stainless steel flange.		
10.01	80 mm dia	2.00	Each
10.02	150 mm dia	3.00	Each
10.03	200 mm dia	2.00	Each
11.00	Supplying and fixing air vessel made of 250 mm dia, 8mm thick MS sheet, 1200 mm in height with air release valve on top and flanged connection to riser, drain arrangement with 25 mm dia gun metal wheel valve with required accessories, pressure gauge and painting with synthetic enamel paint of approved shade as required.	1.00	Set
12.00	Providing & fixing of pressure switch in M.S. pipe line including connection etc. as required.	5.00	Each
13.00	Providing & fixing pressure gauge of range 0-14kg/cm ² or more in following sizes M.S. pipe including connection etc as required.	7.00	Each
14.00	Providing, fixing, testing & commissioning of installation control valve of cast iron body, brass/bronze working parts comprising of water motor alarm, bronze seat clapper, clapper arm and hydraulically driven mechanical gong bell to sound continuous alarm when the wet riser/sprinkler system activates, pressure gauges, emergency releases, strainer, pressure switch, cock valve complete with drain valve and bypass, test control box, ball valves, MS pipe of required size, flanges, orifice plate, gasket etc of following sizes as required : 150 mm dia	2.00	Set

9549.00	19098.00	5370.00	10740.00
24511.00	73533.00	13023.00	39069.00
8523.00	17046.00	10450.00	20900.00
20261.00	60783.00	16373.00	49119.00
40562.00	81124.00	25770.00	51540.00
59713.00	59713.00	47089.00	47089.00
2140.00	10700.00	6239.00	31195.00
4234.00	29638.00	4164.00	29148.00
129107.00	258214.00	72595.00	145190.00


10740.00	Sterling and Wilson Pvt. Ltd
39069.00	Sterling and Wilson Pvt. Ltd
17046.00	Voltas Ltd
49119.00	Sterling and Wilson Pvt. Ltd
51540.00	Sterling and Wilson Pvt. Ltd
47089.00	Sterling and Wilson Pvt. Ltd
10700.00	Voltas Ltd
29148.00	Sterling and Wilson Pvt. Ltd
145190.00	Sterling and Wilson Pvt. Ltd

Signature
24/02/2023
Finance


Signature

Signature
24/02/2023

15.00	Providing, Fixing, reinforced neoprene rubber vibration eliminators/expansion joints (to provide relief from stresses at pipe flanges) suitable for upto 16 kg/cm ² pressure, as per specification of the manufacturers complete as required and as specified.			
15.01	150 mm dia	6.00	Each	
15.02	80 mm dia	4.00	Each	
16.00	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 8 way, Double door	1.00	Each	
17.00	Supplying and fixing following rating, double pole, (single phase and neutral), 240V, residual current circuit breaker (RCCB), having a sensitivity current 30mA in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 A	1.00	Each	
18.00	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	6.00	Each	
19.00	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. Group C	10.00	Point	
20.00	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	80.00	Mtr	
21.00	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	40.00	Mtr	


 24/10/2025
 Hrm (C-C)

12589.00	75534.00	16373.00	98238.00	
8794.00	35176.00	7755.00	31020.00	
7101.00	7101.00	9350.00	9350.00	
4057.00	4057.00	4891.00	4891.00	
546.00	3276.00	1366.00	8196.00	
1144.00	11440.00	7213.00	72130.00	
693.00	55440.00	546.00	43680.00	
693.00	27720.00	546.00	21840.00	


 Hrm (Fin)

75534.00	Voltas Ltd
31020.00	Sterling and Wilson Pvt. Ltd
7101.00	Voltas Ltd
4057.00	Voltas Ltd
3276.00	Voltas Ltd
11440.00	Voltas Ltd
43680.00	Sterling and Wilson Pvt. Ltd
21840.00	Sterling and Wilson Pvt. Ltd

22.00	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	6.00	Each
23.00	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	2.00	Each
24.00	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required.	30.00	Mtr
25.00	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	50.00	Mtr
26.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 90 mm dia (OD-90 mm & ID-76 mm nominal)	150.00	Mtr
27.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/DWC HDPE pipe as required. Above 95 sq. mm and upto 185 sq. mm	150.00	Mtr
28.00	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required.		
28.01	Upto 35 sq. mm (clamped with 1mm thick saddle)	60.00	Mtr
28.02	Above 35 sq. mm and upto 95 sq. mm (clamped with 25x3mm MS flat clamp)	60.00	Mtr
28.03	Above 95 sq. mm and upto 185 sq. mm (clamped with 25/40x3mm MS flat clamp)	80.00	Mtr
29.00	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq. mm (clamped with 1mm thick saddle)	60.00	Mtr

(Signature)
22/01/2022

1144.00	6864.00	1603.00	9618.00
15249.00	30498.00	14872.00	29744.00
1176.00	35280.00	270.00	8100.00
229.00	11450.00	270.00	13500.00
1143.00	171450.00	600.00	90000.00
195.00	29250.00	164.00	24600.00
143.00	8580.00	98.00	5880.00
183.00	10980.00	124.00	7440.00
224.00	17920.00	190.00	15200.00
143.00	8580.00	98.00	5880.00

(Signature)
22/01/2022

6864.00	Voltas Ltd
29744.00	Sterling and Wilson Pvt. Ltd
8100.00	Sterling and Wilson Pvt. Ltd
11450.00	Voltas Ltd
90000.00	Sterling and Wilson Pvt. Ltd
24600.00	Sterling and Wilson Pvt. Ltd

5880.00	Sterling and Wilson Pvt. Ltd
7440.00	Sterling and Wilson Pvt. Ltd
15200.00	Sterling and Wilson Pvt. Ltd
5880.00	Sterling and Wilson Pvt. Ltd

(Signature)
22/01/2022

30.00	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.		
30.01	3½ X 95 sq. mm (45mm)	4.00	Each
30.02	3½ X 150 sq. mm (50mm)	2.00	Each
30.03	4 X 16 sq. mm (28mm)	4.00	Each
31.00	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray (Galvanisation thickness not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. 225 mm width X 50 mm depth X 1.6 mm thickness	60.00	Mtr
32.00	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray "bends" (galvanisation not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. 225 mm width X 50 mm depth X 1.6 mm thickness	15.00	Each
33.00	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray "Tee" (galvanisation not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. 225 mm width X 50 mm depth X 1.6 mm thickness	6.00	Each
34.00	Supplying and installing following size of perforated Hot Dipped Galvanised Iron cable tray "Cross member" (galvanisation not less than 50 microns) with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.I. suspenders including G.I. bolts & nuts, etc. as required. 225 mm width X 50 mm depth X 1.6 mm thickness	6.00	Each

Handwritten signature and date: 27/04/2019


2398.00	9592.00	1920.00	7680.00
2532.00	5064.00	2657.00	5314.00
1479.00	5916.00	1110.00	4440.00
1318.00	79080.00	1497.00	89820.00
2998.00	44970.00	1886.00	28290.00
3929.00	23574.00	1886.00	11316.00
3663.00	21978.00	2471.00	14826.00

Handwritten signature and date: 27/04/2019

7680.00	Sterling and Wilson Pvt. Ltd
5064.00	Voltas Ltd
4440.00	Sterling and Wilson Pvt. Ltd
79080.00	Voltas Ltd
28290.00	Sterling and Wilson Pvt. Ltd
11316.00	Sterling and Wilson Pvt. Ltd
14826.00	Sterling and Wilson Pvt. Ltd

Handwritten signature and date: 27/04/2019

35.00	Providing, laying, testing & commissioning of 'B' class heavy duty G.I. pipe conforming to IS 1239 including welding, fittings like elbows, tees, flanges, tapers, nuts, bolts, gaskets etc. and fixing the pipe on the wall/ceiling with suitable clamp/support frame and painting with two or more coats of synthetic enamel paint of required shade complete as required : 100 mm	80.00 Mtr	
36.00	Supply of PVC/XLPE insulated and PVC sheathed / XLPE of 1.1 KV grade following type armoured power cable conforming to IS 7098 part-I complete as required.		
36.01	4 Core x 6 sqmm. copper conductor	100.00 Mtr	
36.02	4 Core x 16 sqmm. Aluminum conductor	70.00 Mtr	
36.03	3.5 Core x 95 sqmm. Aluminum conductor	70.00 Mtr	
36.04	3.5 Core x 150 sqmm. Aluminum conductor	250.00 Mtr	
37.00	Supply and fixing of 450mm sweep metal blade exhaust fan suitable for operation on 230 V, 50 Hz, Single phase, A.C supply in the existing opening including connections, testing, commissioning etc. as required	8.00 Each	
38.00	Supply and fixing of 600mm sweep metal blade metal body industrial wall fan suitable for 240V, 1-ph 50HZ AC supply on wall including connections, testing, commissioning etc. complete as required.	2.00 Each	
39.00	Supply installation testing commissioning of 4 ft long 36W Surface mounting LED batten 6500K, efficacy >100 lumen/watt, power factor ≥0.95, IP20, CRI ≥80, burning hours 50000 hours, 85% driver efficiency, THDs10% with 05 years warranty certificate from OEM, made out of CRCA / extruded aluminum/PDC aluminum, mounting clamps, fixing arrangement, LEDs driver, complying with LM 80 & LM 79 etc. complete as required.	6.00 Each	

9/10/2023

 (C-2) 10/10/23

2021.00	161680.00	2568.00	205440.00
491.00	49100.00	483.00	48300.00
250.00	17500.00	228.00	15960.00
792.00	55440.00	735.00	51450.00
1289.00	322250.00	1059.00	264750.00
8794.00	70352.00	8140.00	65120.00
14086.00	28172.00	15609.00	31218.00
3987.00	23922.00	1783.00	10698.00


 10/10/23

161680.00	Voltas Ltd
-----------	------------

48300.00	Sterling and Wilson Pvt. Ltd
15960.00	Sterling and Wilson Pvt. Ltd
51450.00	Sterling and Wilson Pvt. Ltd
264750.00	Sterling and Wilson Pvt. Ltd
65120.00	Sterling and Wilson Pvt. Ltd
28172.00	Voltas Ltd
10698.00	Sterling and Wilson Pvt. Ltd


 10/10/23

40.00	Supply, installation, testing and commissioning of 80W LED street light 5700K, efficacy >110 lumen/watt, power factor ≥0.95, IP65, CRI ≥70, burning hours 50000 hours, 85% driver efficiency, THD ≤10% with 05 years warranty certificate from OEM, made out of CRCA / extruded aluminum/ PDC aluminum, heat sink, mounting clamps, fixing arrangement, LEDs driver, surge protection system, complying with LM 80 & LM 79 etc. complete as required.	16.00	Each
41.00	Supply and fixing wall mounting type GI metal bracket for streetlight including clamps, nuts, bolts, screws, making holes on wall etc. complete as required at suitable locations as directed by Engineer-In-Charge.	16.00	Each
42.00	Supplying, installation, testing and commissioning of electric driven positive suction pump consisting of following complete in all respects, as required: (a) Horizontal type, multistage, centrifugal pump of cast iron body and bronze impeller with stainless steel shaft, mechanical seal (b) Suitable HP squirrel cage induction motor TEFC type suitable for operation on 415 volts, 3 phase 50 Hz AC supply with IP 55 class of protection for enclosure, horizontal foot mounted type with Class-F insulation (c) M.S fabricated Common base plate, coupling, coupling guard, foundation bolts etc. as required. (d) Suitable cement concrete foundation duly plastered and with anti vibration pads (e) Rain shed with enclosure for outdoor use (f) interconnection with suction and discharge pipe line with reducer, flanges, gasket, nuts, bolts etc. Range: 30m-45m head range and 17-10 lps capacity	2.00	Each
43.00	Supply installation testing commissioning of star-delta starter suitable for up to 12.5 HP pump-motor set including drilling on wall, screws, nuts, bolts, connection with proper lugs etc. and ensuring successful operation of the pump motor set associated with the starter complete as required.	2.00	Each
44.00	Supply installation testing commissioning of 2HP 1-ph 230V 50Hz dewatering submersible pump including connection, discharge pipe line of minimum 6 mtr long of suitable size etc. complete as required. Make: KSB, Model: AMAPORTER503 SE or equivalent.	2.00	Each
45.00	Excavation of hard rock including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 metres.	5.00	Cum
46.00	Excavation of soft soil including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50 metres.	5.00	Cum

Handwritten signature and date: 21/07/2023

8563.00	137008.00	7704.00	123264.00
1412.00	22592.00	1604.00	25664.00
112610.00	225220.00	120554.00	241108.00
24051.00	48102.00	31314.00	62628.00
65482.00	130964.00	43383.00	86766.00
1698.00	8490.00	1980.00	9900.00
1091.00	5455.00	2420.00	12100.00

Handwritten signature and date: 21/07/2023

123264.00	Sterling and Wilson Pvt. Ltd
22592.00	Voltas Ltd
225220.00	Voltas Ltd
48102.00	Voltas Ltd
86766.00	Sterling and Wilson Pvt. Ltd
8490.00	Voltas Ltd
5455.00	Voltas Ltd

Handwritten signature and date: 21/07/2023

Handwritten notes in the top left corner, including "8848766.00" and "8333333.00".

8848766.00

8333333.00

Handwritten signature "Hodan" with "Am(Fin)" written below it.

Handwritten signature "Hodan" with "Am(Fin)" written below it.

Handwritten notes in the middle left corner, including "8848766.00" and "8333333.00".

Total in Figures

Lowest Amount Quoted BY: Voltas Ltd(8333333.00)

Handwritten signature "Hodan" with "Am(Fin)" written below it.