



भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India



संख्या: एएआई/एजीटी/इंजी(इ)/अवार्ड-09/2022-23

दिनांक/ Date: 28/03/2023

No.: AAI/AGT/ENGG(E)/AWARD-09/2022-23 /38-43

सेवा में / To,

मेसर्स/M/s Aditya Techno Products Pvt. Ltd.
Corp. Office-Flat No. 102 (Ground Floor),
Plot No. 123, Sector-6, Vaishali,
Gaziabad, U.P-201010

कार्य का नाम/Name of Work: एमबीबी हवाई अड्डे, अगरतला में आईएलएस प्रणाली और एटीएस भवन के लिए बिजली आपूर्ति में वृद्धि का कार्य / Augmentation of power supply for ILS system and ATS building at MBB Airport, Agartala.

संदर्भ /Ref : Tender ID No./टेंडर आई डी संख्या- 2023_AAI_142673_1

महोदय/Dear Sir,

उपर उल्लिखित कार्य हेतु आपका टेंडर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकार किया जाता है, आपके द्वारा मद मूल्यों पर कोटेड राशि कुल रु. 1,17,60,705/- (रु. एक करोड़ सत्रह लाख साठ हजार सात सौ पांच मात्र) (जीएसटी को छोड़कर), जो कि टेंडर की अनुमान/उचित राशी रु. 1,46,85,309/- से 19.92% प्रतिशत नीचे है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to **Rs. 1,17,60,705/-** (Rupees One Crore Seventeen lakh Sixty Thousand Seven Hundred and Five only) (excluding GST), which is 19.92% below the Estimated/Justified cost put to tender of **Rs. 1,46,85,309/-**.

सहायक महाप्रबंधक (अभि-विद्युत), भा.वि.प्रा, एमबीबी हवाई अड्डा, अगरतला इस कार्य के प्रभारी-अभियंता होंगे। आपसे निवेदन है कि करारनामे पर हस्ताक्षर करने के लिए दिनांक 12-04-2023 तक एमबीबी हवाई अड्डा, अगरतला के कार्यालय में उपस्थित हों। ठेके का करारनामा रु. 100/- (रु. एक सौ) मात्र के नॉनज्यूडीशियल स्टैम्प पेपर पर निष्पादित किया जाएगा तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Asst. General Manager (Engg-E), AAI, MBB Airport, Agartala shall be the Engineer-In-Charge of the work. You are requested to attend the office of the Asst. General Manager (Engg-E), AAI, MBB Airport, Agartala by **12-04-2023** to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs.100/-** (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

Contd... P/2



P-2

आपके टेंडर के साथ प्राप्त धरोदर राशी रु. 2,91,764/- (रुपये दो लाख इक्यानवे हजार सात सौ चौंसठ मात्र) ठेके के दस्तावेज से पृष्ठ 16 पर दी गई शर्त 1(A) के अनुसार जमानत राशी परिवर्तित कर दी गई है। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर जमानत राशी की बकाया रु. 8,84,307/- (रुपये आठ लाख चौंसती हजार तीन सौ सात मात्र) अदा की जाए अन्यथा निविदा दस्तावेज के कंडीशन 1(A) पेज संख्या 16 के अनुसार उक्त राशी उनके रनिंग बिल से कटौती की जाएगी। जमानत राशी अनुबंध दस्तावेज के एससीसी खंड 31 (ई) पृष्ठ -152 के अनुसार जारी किया जाएगा।

The earnest money amount of **Rs. 2,91,764 /-** (Rupees Two Lakh Ninety-one Thousand Seven Hundred and Sixty-four only) received along with your tender will be treated and converted as part of security deposit as per clause 1(A) on page 16 of tender contract document. Please deposit **Rs. 8,84,307/-** (Rupees Eight Lakh Eighty-four Thousand Three Hundred and Seven only) towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from your running bill as per condition 1(A) on page 16 of the contract document. Security deposit shall be released as per SCC clause 31 (e) page -152 of contract document.

आपसे निवेदन है कि अनुबंध श्रमिक (विनियमन तथा उन्मूलन) अधिनियम 1970, अनुबंध श्रमिक (विनियमन तथा उन्मूलन) केंद्रीय नियम 1971, केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधानों का अनुपालन अवश्य करें।

You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation & abolition) Central rules 1971 and minimum wages Act & rules thereof central and state Governments.

आपको निर्देश दिया जाता है कि आप तुरंत प्रबंधक (अभि-विद्युत), भा.वि.प्रा, एमबीबी हवाईअड्डा, अगरतला से सम्पर्क करें वह आपको साइट सौंपने की व्यवस्था करेंगे।

You are also directed to contact Manager (Engg-E), AAI, MBB Airport, Agartala, immediately who will arrange to hand over the site to you.

कृपया नोट कर लें कि काम करने का अनुमत समय 06 (छह) महीना है जो कि कार्य आदेश के जारी करने के दस (10) वें दिन से गिना जाएगा।

Please note that the time allowed for carrying out the work is **06 (Six) months**, which shall be reckoned from 10th day of issue of this order.

इस ठेके के संबंध में आगे का कोई भी पत्राचार प्रभारी-अभियंता को किया जाएगा।

Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-charge.

Contd... P/3



P-3


कृपया पावती भेजें और स्वीकृति प्रतीक के तौर पर संलग्नित पत्र की हस्ताक्षरित प्रति इस कार्यालय को अवश्य भेजें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

भवदीय/ Yours faithfully,

संलग्न/Encl: Bill of Quantities

Page-03



समर कुमार विश्वास/Samar Kumar Biswas)

सहायक महाप्रबंधक (अभि-विद्युत)/A.G.M.(Engg-E),
कृते तथा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से।

For and on behalf of Chairman,
Airports Authority of India.

BILL OF QUANTITIES

Name of Work: Augmentation of power supply for ILS system and ATS building at MBB Airport, Agartala.

Item No.	Items of Work	Quantity	Unit	Rate (Rs)	Amount (Rs)
1.00	Supply of following sizes XLPE insulated and PVC sheathed aluminium conductor armoured power cable of 1.1KV grade confirming to IS 7098, Part-I 1988 with up to date amendments and confirming to technical specifications. (a) 3.5c x 240 Sq.mm	6900.00	Mtr.	1102.00	7603800.00
2.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size in the existing RCC/ HUME/ METAL/HDPE pipe as required. (a) Above 185 sq. mm and upto 400 sq. mm	6500.00	Mtr.	55.00	357500.00
3.00	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size in the existing masonry open duct as required. (a) Above 185 sq. mm and upto 400 sq. mm	30.00	Mtr.	90.00	2700.00
4.00	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required. (a) Above 185 sq. mm and upto 400 sq. mm (clamped with 40x3mm MS flat clamp)	140.00	Mtr.	114.00	15960.00
5.00	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1 kV grade as required. (a) 3.5c x 240 sq. mm (62mm)	14.00	Each	1850.00	25900.00
6.00	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1 kV grade as required. (a) 3.5c x 240 sq. mm	13.00	Set	2865.00	37245.00
7.00	Providing, laying and fixing following dia G.I. pipe (medium class) in ground/concrete/road crossing complete with all types of accessories including trenching (minimum 60 cm deep) and re-filling/making good the same with soil/concrete etc. as required. (a) 80mm dia.	178.00	Mtr.	850.00	151300.00


Item No.	Items of Work	Quantity	Unit	Rate (Rs)	Amount (Rs)
8.00	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc..direct in ground/concreate/all kinds of soil (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. (a) 120 mm dia (OD-120 mm & ID-103 mm nominal)	6000.00	Mtr.	205.00	1230000.00
9.00	Earthing with G.I. earth plate 600 mm x 600 mm x 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required.	6.00	Each	5795.00	34770.00
10.00	Providing and fixing 25 mm x 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and refilling etc. as required.	30.00	Mtr.	673.00	20190.00
11.00	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	10.00	Mtr.	184.00	1840.00
12.00	Supply and laying of PN6 class high density polyethylene (HDPE) plain pipe of 160mm dia confirming to IS:4984 (1995) with latest amendment, complete with all types of accessories like couplers,bends etc, across the Runway / Taxiway/ Apron at a minimum depth of 1.2 Mtr or as per site requirement by Horizontal Directional Drilling (HDD) method.	705.00	Mtr.	1500.00	1057500.00
13.00	Excavation of soil, providing soiling and 100mm thick PCC flooring at bottom and construction of brick massonary manhole of inner size [1500 mm(L) x 1200 mm(W) x 1000 mm(D)] with 250 mm wall thickness including plaster of inner surface and providing reomval type RCC sectionalized top slab of minimum 150 mm thick as per site requirement and direction of Engineer-in-charge.	10.00	Job	20100.00	201000.00

Item No.	Items of Work	Quantity	Unit	Rate (Rs)	Amount (Rs)
14.00	Design, fabrication, supply, installation, testing and commissioning of weather, vermin proof, powder- coated, fully compartmentalized outdoor type feeder pillar panel {minimum IP 65 protection)with lifting hooks, fabricated with 2mm thick CRCA sheet with hinged double door with gasket, detachable gland plates for cable chamber, 2 earthing studs, bottom type cable entry provision having locking arrangement in front, chemically treated through at-least seven-tank process consisting of the following switchgears: a) Incomer:- 250A, 4 pole, 36kA MCCBs (Ics = 100% of Icu) : 1 Nos. b) Outgoing :-250A, 4 pole, 36kA MCCBs (Ics = 100% of Icu) : 1 Nos, 63A, 4 pole, 25kA MCCBs (Ics = 100% of Icu) : 2 Nos c) Bus-bar: 300A, 3Ø, 4 wire Aluminum. e) Indication Lamp: LED indication lamps with back-up fuse for 3 phase indications of incoming supply & ON/OFF indication for all outgoing and incomer. f) Aluminum earth bar of suitable size - 1 Set.	3.00	Job	312000.00	936000.00
15.00	Modification in existing panel by providing & fixing of 250 A MCCB, Indication lamp, connector, lugs, roatatry handle,aluminium busbar and other accessories etc complete as required in the existing blank compartment of L.T panel & other associated works as per site condition.	2.00	Job	42500.00	85000.00

Total Rs.

1,17,60,705.00

**(In words: Rupees One Crore Seventeen lakh Sixty Thousand Seven Hundred and Five only)
Excluding GST**


(Samar Kumar Biswas)
 Asstt.G.M. (Engg.-Elect)
 AAI, MBB Airport, Agartala