

सं.स. : भाविप्रा/वारा/अभि./वेहिकल्स पार्किंग/डब्लू-80/305-15/1987-97 दिनांक: 22.03.2023
Ref No.: AAI/VNS/ENGG/ Vehicles Parking / W-80/ Date: 22.03.2023

सेवा में,

मेसर्स राहुल कन्स्ट्रक्शन्स
401, टावर डी-1, के.एल.जे. प्लेटिनम प्लस
सेक्टर-77, फरिदाबाद-121004

M/s Rahul Constructions,
Flat No. 401, Tower D-1, KLJ Platinum
Plus, Sector-77, Faridabad-121004

विषय : एलबीएसआई हवाईअड्डे वाराणसी पर शासन, राजनीतिक वाहन, स्टाफ वाहनों के लिए पार्किंग क्षेत्र का विकास और कार पार्किंग में क्षतिग्रस्त फुटपाथ टाइलों को बदलना।

Development of parking area for Governance, political vehicle, staff vehicles and replacement of damaged footpath tiles in car parking at LBSI Airport Varanasi.
(Tender ID : 2023_AAI_144875_1)

संदर्भ : ई-निविदा खुलने की तिथि : 15.03.2023

प्रिय महोदय/Dear Sir,

- 1) उपरोक्त कार्य की, कुल निविदा रकम रुपये 68,99,999.00 (रुपया अड़सठ लाख निन्याबे हजार नौ सौ निन्याबे मात्र) (जीएसटी रहित) की मद दर निविदा, जो कि कार्य की अनुमानित लागत रुपये 107.70 लाख (जीएसटी रहित) से 35.93% (पैंतीय दशमलव नौ तीन प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the net tender amount Rs 68,99,999.00 (Rupees Sixty Eight Lakhs Ninety Nine Thousand Nine Hundred Ninety Nine only) (excluding GST) which is 35.93% (Thirty Five point Ninety Three percent) below to the estimated cost put to tender of Rs. 107.70 lakhs (excluding GST).

- 2) सहा0 महाप्रबन्धक (अभि0-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे तथा सहा0 प्रबन्धक (अभि0-सि0), भा. वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी उनके प्राधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि दिनांक 01.04.2023 तक सहा0 महाप्रबन्धक (अभि0-सिविल) के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपये के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

The AGM(Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work and Asstt. Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be our authorised representative. You are requested to attend the office of the AGM(Engg-Civil) by 01.04.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.

- 3) धरोहर राशि रुपये 2,15,400.00 (रुपया दो लाख पन्द्रह हजार चार सौ मात्र) संविदा प्रपत्र के अनुच्छेद 1ए पेज 16 के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपये 4,74,600.00 (रुपया चार लाख चौहत्तर हजार छः सौ मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

01/

शेष पृष्ठ 2 पर....



The earnest money amount of Rs. 2,15,400.00 (Rupees Two Lakhs Fifteen Thousand Four Hundred only) received along with your tender will be treated and converted as a part of security deposit. Please deposit Rs. 4,74,600.00 (Rupees Four Lakhs Seventy Four Thousand Six Hundred only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition GCC 1A on page 16 of the contract document.

- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से सहा0 प्रबन्धक (अभि0-सि0), भा. वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।
You are also directed to contact the Asstt. Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi, immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 03(तीन) महीने हैं जो कि दिनांक 01.04.2023 से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be 03 (Three) months and the same shall be reckoned from 01.04.2023
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः सहा0 महाप्रबन्धक (अभि-सिविल), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी-221006, को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the AGM (Engg-Civil), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006
- 8) कृपया इस पत्र की पावती भेजें एवं पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल प्रष्ठ 06) (सिविल एवं विद्युत कार्य) रु. 68,99,999.00) संलग्न है।
Schedule 'A' (total page 06) (Civil & Elect. works Rs. 68,99,999.00) of the work is enclosed.

उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।
In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

भवदीय

संलग्नक- यथोपरि
Encl:- As above

स.म.प्र.(अभि.-सिविल),
A GM (Engg-Civil)

अध्यक्ष, भा0वि0प्रा0 के लिए व उनकी तरफ से
For and on behalf of the Chairman, AAI



प्रतिलिपि:

मूल प्रति पर नहीं (NOO)

अ. बाहरी-

1. उपमहाप्रबन्धक (अभि)-उ0क्षे0, भाविप्रा, नई दिल्ली-110037 : सूचनार्थ
2. सहायक श्रम आयुक्त (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ
3. श्रम प्रवर्तन अधिकारी (सी), 189-ए/4ए, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज : सूचनार्थ

ब. आंतरिक-

- | | | |
|--|---|------------------------|
| 1. निदेशक विमानपत्तन | : | सूचनार्थ |
| 2. प्रभारी (वित्त) | : | -तदैव- |
| 3. सं.म.प्र. (अभि-विद्युत) | : | -तदैव- |
| 4. श्री आशीष कुमार गुप्ता, सहा0 प्रबन्धक (अभि-सिविल) | : | आवश्यक कार्यवाही हेतु। |
| 5. कार्यदेश फाईल | : | |
| 6. अनुबन्ध | : | |

7: MIS KH8

विनोद कुमार पाण्डे
9 22-03-2023

स.म.प्र.(अभि.-सिविल),

सहायक महाप्रबन्धक (अभि.-सिविल)
Asstt General Manager (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

O/C

ing Authority: Airports Authority of India

Work: Development of parking area for Governance, political vehicle, staff vehicles and replacement of damaged footpath tiles in car parking at LBSI Airport Varanasi.

Contract No: 2023_AAI_144875_1

Name of the Bidder/ Bidding Firm / Company :	RAHUL CONSTRUCTIONS						
PRICE SCHEDULE							
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	7	8	10
1.00	Civil Works						
1.01	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	Item1	2822.00	cum	44.00	124168.00	INR One Lakh Twenty Four Thousand One Hundred & Sixty Eight Only
1.02	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	Item2	2567.00	cum	49.00	125783.00	INR One Lakh Twenty Five Thousand Seven Hundred & Eighty Three Only
1.03	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres.	Item3	850.00	Sqm	95.00	80750.00	INR Eighty Thousand Seven Hundred & Fifty Only
1.04	Consolidation of sub grade with power road roller of 8 to 12 tonne capacity dressing to camber and consolidating with road roller including making good the undulations etc.	Item4	3667.00	Sqm	1.00	3667.00	INR Three Thousand Six Hundred & Sixty Seven Only


	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.05	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge : With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	Item5	678.00	Cum	1740.50	1180059.00	INR Eleven Lakh Eighty Thousand & Fifty Nine Only
1.06	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	Item6	678.00	Cum	1666.00	1129548.00	INR Eleven Lakh Twenty Nine Thousand Five Hundred & Forty Eight Only
1.07	Carriage of materials by mechanical transport including loading,unloading and stacking of Earth for a lead upto 1 km	Item7	2567.00	Cum	44.00	112948.00	INR One Lakh Twelve Thousand Nine Hundred & Forty Eight
1.08	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 1)450 mm dia RCC pipes.	Item8	90.00	meter	1888.00	169920.00	INR One Lakh Sixty Nine Thousand Nine Hundred & Twenty Only
1.09	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1)1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	Item9	71.00	cum	4949.00	351379.00	INR Three Lakh Fifty One Thousand Three Hundred & Seventy Nine Only
1.10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:4 (1 cement : 4 coarse sand)	Item10	10.00	cum	5555.00	55550.00	INR Fifty Five Thousand Five Hundred & Fifty Only
1.11	15 mm cement plaster on rough side of single or half brick wall of mix:1:4 (1 cement: 4 coarse sand)	Item11	75.00	sqm	249.00	18675.00	INR Eighteen Thousand Six Hundred & Seventy Five Only
1.12	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator,filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.80 mm thick C.C. paver block of M-30 grade with approved color design and pattern	Item12	4516.88	sqm	611.00	2759810.63	INR Twenty Seven Lakh Fifty Nine Thousand Eight Hundred & Ten and Paise Sixty Two Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1.13	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not be more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	Item13	26.00	cum	6500.00	169000.00	INR One Lakh Sixty Nine Thousand Only
1.14	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Dark shade pigment using ordinary cement	Item14	313.00	Sqm	555.00	173715.00	INR One Lakh Seventy Three Thousand Seven Hundred & Fifteen Only
1.15	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	Item15	25.00	cum	777.00	19425.00	INR Nineteen Thousand Four Hundred & Twenty Five Only
1.16	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm	Item16	250.00	Sqm	33.00	8250.00	INR Eight Thousand Two Hundred & Fifty Only
1.17	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Fume Red, Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	Item17	90.00	Sqm	777.00	69930.00	INR Sixty Nine Thousand Nine Hundred & Thirty Only
1.18	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Item18	10.00	cum	149.00	1490.00	INR One Thousand Four Hundred & Ninety Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2.00	Electrical works :						
2.01	Supply of LED flood light of 200 Watt with high pressure die cast Aluminium / standard alloy housing and LEDs of approved make pasted on diecast housing and high efficiency PMMA diffuser, Driver installed on cast aluminium housing and prewired upto the terminal block. It has a system lumen luminaire efficacy of not less than 110 lm/W, CCT 5700 k, suitable for outdoor applications complete make Bajaj model GLEAM F 220 L WH SY PC SD V2 or as per technical specifications.	Item19	8.00	Each	7250.00	58000.00	INR Fifty Eight Thousand Only
2.02	Supply of LED street light of 100 Watt with pressure die cast housing/ standard alloy housing and toughened glass individual LEDs with secondary lens approved make . It has a system lumen luminaire efficacy of not less than 110 lm/W, CCT 5700 k, suitable for outdoor applications complete make Bajaj model Model : ZELA P 120 L WH PO TG SD or as per technical specifications.	Item20	16.00	Each	4100.00	65600.00	INR Sixty Five Thousand Six Hundred Only
2.03	Supply of 07 mtrs. high GI OCTAGONAL continuously tapered galvanised street light pole (bottom size 130 mm min. & top size 70 mm min.) with double arm GI bracket (length of bracket shall be based on design) for installation of LED Flood light luminaire (100 Watt) suitable for wind velocity as per IS 875 (but not less than 50 m/sec.), fabricated out of 3 mm MS plate in single section, suitable for installation on a precast foundation with supply of minimum 4 nos. of foundation bolt & anchor plate, rigid flange plate (200x200x12mm min.) welded with the base of pole for fixing on foundation bolts complete as reqd. for structural stability as specified, weather proof and vandal resistant door flush with the exterior surface containing a terminal plate of 5 mm thick backlite sheet with 32 Amp heavy duty connector for loop in loop out cable terminations suitable for upto two numbers 4 core 25 Sq.mm cables & 2A DP MCB for each fixture connections, earthing bolts for continuous earth connection including 3core 4 sqmm copper flexible cable from connector to led fitting ,complete as required & as specified.	Item21	4.00	Each	7100.00	28400.00	INR Twenty Eight Thousand Four Hundred Only
2.04	Supply of 07 mtrs. high GI OCTAGONAL continuously tapered galvanised street light pole (bottom size 130 mm min. & top size 70 mm min.) with single arm GI bracket (length of bracket shall be based on design) for installation of LED Flood light luminaire (100 Watt) suitable for wind velocity as per IS 875 (but not less than 50 m/sec.), fabricated out of 3 mm MS plate in single section, suitable for installation on a precast foundation with supply of minimum 4 nos. of foundation bolt & anchor plate, rigid flange plate (200x200x12mm min.) welded with the base of pole for fixing on foundation bolts complete as reqd. for structural stability as specified, weather proof and vandal resistant door flush with the exterior surface containing a terminal plate of 5 mm thick backlite sheet with 32 Amp heavy duty connector for loop in loop out cable terminations suitable for upto two numbers 4 core 25 Sq.mm cables & 2A DP MCB for each fixture connections, earthing bolts for continuous earth connection including 3core 4 sqmm copper flexible cable from connector to led fitting ,complete as required & as specified.	Item22	8.00	Each	6500.00	52000.00	INR Fifty Two Thousand Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	Words
2.05	Supply of 9 mtrs. Long OCTAGONAL galvanised street light pole with circular (GI bracket 1000 mm dia or as per OEM,s) of for installation of 04 number LED luminaire suitable., fabricated out of Min. 3 mm sheet, in single section, suitable for installation on a precast foundation with supply of 4 nos. of foundation bolts complete as reqd. for structural stability as specified, weather proof and vandal resistance door of height not less than 300 mm flush with the exterior surface containing a terminal plate of backlite sheet with 3 way, 32 Amp connector & insulated caps for loop in loop out cable terminations , 3 core, 6 Sq.mm cables 3 run & 10A, DP MCB-03 number for each fixture connections, earthing bolts for continuous earth connections complete as required & as specified :	Item23	1.00	Each	18421.37	18421.37	INR Eighteen Thousand Four Hundred & Twenty One and Paise Thirty Seven Only
2.06	Erection of 07/09 Mtr.high G.I.OCTAGONAL & bracket with all accessories in reinforced cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling including positioning of template & foundation bolts (supplied with pole to match with pole base plate) & providing and fixing of DWVC HDPE pipe of size 50 mm dia (2 pieces of min. 0.75 m length) in the foundation for loop-in-loop-out of the cable to the pole including LED fitting installation complete as required and as specified	Item24	13.00	Each	3450.00	44850.00	INR Forty Four Thousand Eight Hundred & Fifty Only
2.07	Supply of XLPE insulated, PVC innersheathed, armoured aluminium cable, 1100 V as per IS 7098 (Part 1) 1988 with upto date amendments of following sizes: a) 4C x 16 sq. mm	Item25	300.00	Meter	105.00	31500.00	INR Thirty One Thousand Five Hundred Only
2.08	Supply of following sizes HDPE Pipe suitable to lay in underground as per IS:4984/95 duly ISI marked, i) 32 mm outer dia PE80, PN10	Item26	250.00	Meter	25.00	6250.00	INR Six Thousand Two Hundred & Fifty Only
2.09	Laying of following size HDPE /GI pipe in the soil / ground up to depth of approx 0.75 meter including covering with excavation and refilling the trench, consolidation and making good the surface etc. complete as required. a) Upto 32 mm dia	Item27	250.00	Meter	50.00	12500.00	INR Twelve Thousand Five Hundred Only
2.10	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1KV of size upto 35 sq. mm in the existing HDPE/RCC/ HUME/ METAL pipe etc complete as required.	Item28	300.00	Meter	15.00	4500.00	INR Four Thousand Five Hundred Only
2.11	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	Item29	4.00	Each	3700.00	14800.00	INR Fourteen Thousand Eight Hundred Only
2.12	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. A) 4 X 16 sq. mm (28mm)	Item30	2.00	Set	180.00	360.00	INR Three Hundred & Sixty Only

	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2.13	Providing & fixing of 6 SWG GI wire on surface or in the recess for loop earth.	Item31	250.00	Mtr	35.00	8750.00	INR Eight Thousand Seven Hundred & Fifty Only
Total in Figures						6899999.00	INR Sixty Eight Lakh Ninety Nine Thousand Nine Hundred & Ninety Eight and Paise One Hundred Only
Quoted Rate in Words		INR Sixty Eight Lakh Ninety Nine Thousand Nine Hundred & Ninety Eight and Paise One Hundred Only					


 22-03-2023
 Agm 6-2
 सहायक महाप्रबन्धक (अभि.-सिविल)
 Asstt. General Manager (Engg.-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi