



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
औरंगाबाद हवाईअड्डा AURANGABAD AIRPORTS

संदर्भ सं: भाविप्रा/औबाद/अभि-सिविल/W-117/2023/398-407

दिनांक : 26.04.2023

सेवा में,
मेसर्स माल इन्फ्रास्ट्रक्चर,
'रामदेव', सी- 5/11, टाउन सेंटर,
बैंक ऑफ महाराष्ट्र क्षेत्रीय कार्यालय ऑफीस
के पीछे, सिडको, औरंगाबाद — 431 003
ईमेल - mallinfrastructure@rediffmail.com

To,
M/s. Mall infrastructure,
"Ramdev", C-5/11,
Town Center,
Behind Bank of Maharashtra Regional office,
CIDCO, Aurangabad – 431 003
Email : mallinfrastructure@rediffmail.com

कार्य का नाम : औरंगाबाद हवाई अड्डे पर नए डी.व्ही.ओ.आर. इमारत का निर्माण कार्य।
Name of work : Construction of New DVOR building at Aurangabad Airport.

संदर्भ : दिनांक 15.03.2023 को खोली गयी आपकी ई-निविदा सं. 2023_AAI_146091_1
Ref. : (i) Your e-tender no. 2023_AAI_146091_1 opened on Dt. 15.03.2023
(ii) Negotiation held on date 16.03.2023 and your offer vide letter dated 21.03.2023

महोदय / Dear Sir,

- उपर उल्लेखित कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण कि ओर से आपके द्वारा बताए गये मद मुल्यों पर 0.65% की छूट सहित रु 85,53,239/- (रु. पचासी लाख तिरपन हजार दो सौ उनतालीस मात्र) को सभी करों को शामिल करके परंतु जी. एस. टी विरहित स्वीकृत की जाती है जोकी कार्य की अनुमानित लागत रुपये 81,21,885/- से 5.31% उपर है।
- Your e-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the Item Rates including rebate of 0.65% quoted by you totaling to Rs. 85,53,239/- (Rupees Eighty Five Lakhs Fifty Three Thousand Two Hundred Thirty Nine Only) inclusive of all taxes but excluding of GST which is 5.31% above the estimate cost put to tender Rs. 81,21,885/-.
- सहा. महाप्रबंधक अभियांत्रिकी (सिविल), औरंगाबाद हवाईअड्डा कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप करारनामे पर हस्ताक्षर करने के लिये दिनांक 06.05.2023 को या पहले तक सहा. महाप्रबंधक अभियांत्रिकी (सिविल), भाविप्रा., औरंगाबाद हवाईअड्डा के कार्यालय में उपस्थित हो तथा करारनामे को पुरा करें। ठेके का करारनामा रुपये 100/- के नोनजुडिशियल स्टेम्प पर निष्पादित किया जायेगा तथा स्टेम्प पेपर का खर्चा आपके द्वारा उठाया जायेगा।
- Asstt. General Manager Engg (Civil), AAI, Aurangabad Airport shall be Engineer-in-charge of the work. You are requested to attend the office of sign the contract agreement at the office of the Asstt. General Manager Engg (Civil), AAI, Aurangabad Airport on or before 06.05.2023 to sign and complete the agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of the stamp paper shall be borne by you.

26/04/2023

राजेश वाणी / RAJESH WANI
सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण Airports Authority of India
औरंगाबाद विमानक्षेत्र Aurangabad Airport

WAW H201191 1111 1111

3. आपकी निविदा के साथ प्राप्त धरोहर राशि ऑन लाईन रु. 1,62,500/- (रु. एक लाख बासठ हजार पाँच सौ मात्र) ठेके के दस्तावेज से पृष्ठ 16 पर दि गई खण्ड 1 ए के अनुसार जमानत राशि में परिवर्तित कर दी गई है। कृपया इस पत्र के जारी होने की तिथी से 15 दिनों के भीतर जमानत राशि की बकाया रु. 6,92,824/- (रु. छह लाख बानवे हजार आठ सौ चौबीस रुपये मात्र) जमा कराना है। असफल होने पर आपके चालु बिल से काट लिया जायेगा।
3. The earnest money amount of Rs. 1,62,500/- (Rupees One Lakh Sixty Two Thousand Five Hundred Only) received online along with your tender has been converted as part of security deposit as per clause-1 (A) on page 16 of tender document. Please deposit Rs. 6,92,824/- (Rupees Six Lakhs Ninety Two Thousand Eight Hundred Twenty Four Only) towards Security deposit within 15 days from the date of issue of this letter, failing which the same will be deducted from your running bill as per clause-1 (A) on page 16 of the tender document.
4. आपसे निवेदन है कि आप केन्द्रीय और राज्य सरकारों के 1970 अधिनियम अनुबन्ध श्रम नियम तथा 1971 के केन्द्रीय नियम नियमन तथा उन्मूलन एवं केंद्र तथा राज्य सरकारों के न्यूनतम वेतन अधिनियमों और नियमों के प्रावधानों का अनुपालन करें।
4. You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation and abolition) Central rules 1971 and Minimum Wages Act & rules thereof Central and State Governments.
5. आप वस्तु एवं सेवा कर (जी.एस.टी.) के तहत पंजीकृत हैं। आपके निविदा मद दर में किसी भी कर, टैक्स, फिस और शुल्क शामिल है, जिसके तहत कोई भी नियम जीएसटी विरहित बोली प्रस्तुत करने की अंतिम तिथि के अनुसार लागू और आप जीएसटी प्रावधान के अनुरूप है। जी.एस.टी प्रावधानों का अनुपालन और किसी भी इनपुट क्रेडिट की रूकावट के मामले में, आप भाविप्रा को क्षतिपूर्ति करने के लिए जिम्मेदार होंगे।
5. You are registered under Goods & Service Tax (GST). Your tendered item rate is inclusive of any taxes duties, cess, fee and charges levied under any statute but excluding GST as applicable on the last date of bid submission and has given undertaking that you are compliant of GST provision. In case of non-compliance of GST provisions and blockage of any input credit, you shall be responsible to indemnify AAI.
6. आपको निर्देश दिया जाता है कि आप तुरंत सहा. प्रबंधक (अभि-सिविल), भा.वि.प्रा., औरंगाबाद हवाईअड्डा, औरंगाबाद से मिले वह आपको साईट सौंपने की व्यवस्था करेंगे।
6. You are also directed to contact Asstt. Manager (Engg-Civil), AAI, Aurangabad Airport, Aurangabad immediately who will arrange to hand over the site to you.
7. कृपया नोट करें कि काम करने का अनुमत समय 06 (छह) माह है जो इस पत्र के जारी होने के दसवें दिन 06.05.2023 से शुरू होगा।
7. Please note that the time allowed for carrying out the work is 06 (Six) months and shall be reckoned from the tenth day i.e. 06.05.2023 after issue of this letter.

26/04/2023.

राजेश वाणी / RAJESH WANI

सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Engg.-Civil)

8. हिंदी और अंग्रेजी के बीच विसंगति के मामले में अंग्रेजी संस्करण का पालन किया जाएगा।
8. In case of discrepancy between hindi and english, english version will be followed.
9. इस ठेके के संबंध में आगे कोई भी पत्राचार सहा. महाप्रबंधक अभियांत्रिकी (सिविल), भाविप्रा., औरंगाबाद हवाईअड्डा, औरंगाबाद - 431 007 के पते पर किया जाए।
9. Any further correspondence in connection with the contract should normally be addressed to the Asstt. General Manager Engg. (Civil), AAI, Aurangabad Airport, Aurangabad - 431 007.
10. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।
10. All letters referred above shall form part of contract.
11. अनुरक्षण अवधि के दौरान क्षति, दोषों के लिए ठेकेदार ठेके के दस्तावेज से खण्ड 17 पृष्ठ 47 व 48 पर दी गई अवधि के लिए जिम्मेदार होगा।
11. Contractor shall be liable for damages, defects during maintenance period as mentioned in clause 17 on page 47 and 48 of the contract document.
12. कृपया पावती भेजे।
12. Please acknowledge the receipt.

संलग्न : (07) सात शेड्यूल की प्रती

भवदीय,


26/04/2023

राजेश वाणी (RAJESH WANI) (राजेश वाणी)
सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण Airport Authority of India
औरंगाबाद विमानक्षेत्र Aurangabad Airport सहा. महाप्रबंधक (अभियांत्रिकी-सिविल)
भाविप्रा, औरंगाबाद हवाईअड्डा

प्रतिलिपी :

1. महाप्रबंधक (अभि-प.क्षे.), भा. वि. प्रा., क्षेत्रीय मुख्यालय, क्षे. का. निदेशक का कार्यालय, न्यु एअरपोर्ट कॉलोनी, पारसी वाडा, मुंबई - 400 099
2. सतर्कता अधिकारी, भा. वि. प्रा., क्षेत्रीय मुख्यालय, क्षे. का. निदेशक का कार्यालय, न्यु एअरपोर्ट कॉलोनी, पारसी वाडा, मुंबई - 400 099
3. विमानपत्तन निदेशक, भाविप्रा, औरंगाबाद हवाईअड्डा, औरंगाबाद।
4. उप. महाप्रबंधक (अभि-सिविल) प.क्षे., भा. वि. प्रा., क्षेत्रीय मुख्यालय, क्षे. का. निदेशक का कार्यालय, न्यु एअरपोर्ट कॉलोनी, पारसी वाडा, मुंबई - 400 099
5. व. प्रबंधक (वित्त और लेखा), भाविप्रा, औरंगाबाद हवाईअड्डा।
6. सहा. प्रबंधक (अभि-सिविल) भाविप्रा, औरंगाबाद हवाईअड्डा।
7. श्रमप्रवर्तन अधिकारी (केन्द्रीय), 57 ए, रेल्वे लाईन, गुम्डेल नगर, सोलापुर - 413 001 (कार्य आरंभ की सूचना प्रोफार्मा VI-B संलग्न किया है)
8. सहायक भविष्य निधि आयुक्त, कर्मचारी भविष्य निधि संगठन, श्रम मंत्रालय, भारत सरकार, उप क्षेत्रीय कार्यालय, प्लॉट सं. 2, टाउन सेंटर, सिडको, औरंगाबाद - 431 003.
9. करारनामा प्रत।


ज्ञानकारी हेतु।

FORM VI - B

Notice of Commencement/Completion of Contract work.

1. Name of the principal employer and address Sh. R. S. Wani, Asstt. General Manager Engg (C), Airports Authority of India, Aurangabad Airport, Aurangabad – 431 007.
2. Number and date of Certificate of Registration RLCP (8) / 2007 Regn. Dated 29.05.2007

I hereby intimate that the contract work “Construction of New DVOR building at Aurangabad Airport” given to M/s. Mall infrastructure, “Ramdev”, C-5/11, Town Center, Bank of Maharashtra Regional office, CIDCO, Aurangabad – 431 003” is awarded on 26.04.2023 and will be commenced from 06.05.2023.


26/04/2023

Signature of the principle employer
राजेश वाणी / RAJESH WANI
सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण Airports Authority of India
औरंगाबाद विमानक्षेत्र Aurangabad Airport

To,
The Labour Enforcement Officer (Central),
Ministry of Labour, Govt. of India,
57-A, Railway lines,
Gumdel Nagar,
Solapur – 413 001

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Asst. General Manager (Engg-Civil) Airports Authority of India, Aurangabad Airport

Name of Work: Construction of New DVOR building at Aurangabad Airport

Contract No: 2023_AAI_146091_1

Name of the Bidder/ Bidding Firm / Company : Mall Infrastructure

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P (Excluding GST)	TOTAL AMOUNT Without Taxes in Rs. P (Excluding GST)	TOTAL AMOUNT In Words (Excluding GST)
1	2	4	5	13	53	55
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth within airport premises including all leads and lift up to 1.5m, as directed by Engineer-in-Charge: All kinds of soil	1019.00	sqm	120.00	122280.00	INR One Lakh Twenty Two Thousand Two Hundred & Eighty Only
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead within airport premises including all leads and lift up to 1.5m, as directed by Engineer-in-charge. All kinds of soil	657.00	cum	180.00	118260.00	INR One Lakh Eighteen Thousand Two Hundred & Sixty Only
3	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within airport premises including all leads and lifts : All kinds of soil. Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	200.00	metre	320.00	64000.00	INR Sixty Four Thousand Only
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, within airport premises including all leads and lifts	271.00	cum	150.00	40650.00	INR Forty Thousand Six Hundred & Fifty Only
5	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials. All kinds of soil	171.00	cum	70.00	11970.00	INR Eleven Thousand Nine Hundred & Seventy Only
6	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	36.00	cum	3200.00	115200.00	INR One Lakh Fifteen Thousand Two Hundred Only
7	Clearing grass and removal of the rubbish within Airport premises outside the periphery of the area cleared.	13267.00	sqm	30.00	398010.00	INR Three Lakh Ninety Eight Thousand & Ten Only
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	23.00	cum	5200.00	119600.00	INR One Lakh Nineteen Thousand Six Hundred Only
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	173.00	cum	4200.00	726600.00	INR Seven Lakh Twenty Six Thousand Six Hundred Only
10	Providing and laying damp-proof course 50mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand(zone-III) : 4 graded stone aggregate 20mm nominal size).	18.00	sqm	350.00	6300.00	INR Six Thousand Three Hundred Only
11	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	50.00	cum	5700.00	285000.00	INR Two Lakh Eighty Five Thousand Only
12	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	9.00	cum	6500.00	58500.00	INR Fifty Eight Thousand Five Hundred Only
13	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	17.00	cum	7000.00	119000.00	INR One Lakh Nineteen Thousand Only
14	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Foundations, footings, bases of columns, etc. for mass concrete	246.00	sqm	450.00	110700.00	INR One Lakh Ten Thousand Seven Hundred Only
15	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Suspended floors, roofs, landings, balconies and access platform.	72.00	sqm	550.00	39600.00	INR Thirty Nine Thousand Six Hundred Only
16	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Lintels, beams, plinth beams, girders, bressumers and cantilevers	138.00	sqm	550.00	75900.00	INR Seventy Five Thousand Nine Hundred Only
17	Centering and shuttering including strutting, propping etc. and removal of form for d) Columns, Pillars, Piers, Abutments, Posts and Struts	157.00	sqm	500.00	78500.00	INR Seventy Eight Thousand Five Hundred Only

26/04/2023

राजेश वाणी / RAJESH WANI

सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Engg.-Civil)
 भारतीय विमानपत्तन प्राधिकरण Airports Authority of India
 औरंगाबाद विमानक्षेत्र Aurangabad Airport

18	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Edges of slabs and breaks in floors and walls Above 20 cm wide	10.00	sqm	500.00	5000.00	INR Five Thousand Only
19	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	4646.00	kg	85.00	394910.00	INR Three Lakh Ninety Four Thousand Nine Hundred & Ten Only
20	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	2541.00	kg	88.00	223608.00	INR Two Lakh Twenty Three Thousand Six Hundred & Eight Only
21	Add for plaster drip course/ groove in plastered surface or moulding to R.C.C. projections.	36.00	metre	350.00	12600.00	INR Twelve Thousand Six Hundred Only
22	Brick work with common burnt clay F.P.S. (non modular) / Fly ash bricks of class designation 5.0 in foundation and plinth in -Cement mortar 1:4 (1 cement : 4 coarse sand)	23.00	cum	7700.00	177100.00	INR One Lakh Seventy Seven Thousand One Hundred Only
23	Half brick masonry with common burnt clay F.P.S. (non modular) / Fly ash bricks of class designation 5.0 in superstructure above plinth level up to floor V level Cement mortar 1:4 (1 cement :4 coarse sand).	11.10	sqm	850.00	9435.00	INR Nine Thousand Four Hundred & Thirty Five Only
24	Extra for providing and placing in position 2 Nos 6mm dia. M.S. bars at every third course of half brick masonry.	11.10	sqm	500.00	5550.00	INR Five Thousand Five Hundred & Fifty Only
25	Brick work with common burnt clay F.P.S. (non modular)/ Fly ash bricks of class designation 5.0 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	36.03	cum	7800.00	281034.00	INR Two Lakh Eighty One Thousand & Thirty Four Only
26	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite stone slab of all colour and texture except black, Cherry/Ruby red Area of slab over 0.50 sqm	20.00	sqm	4000.00	80000.00	INR Eighty Thousand Only
27	Extra for fixing marble /granite stone, over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive, including cleaning etc. complete.	32.00	metre	1000.00	32000.00	INR Thirty Two Thousand Only
28	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	37.00	sqm	1300.00	48100.00	INR Forty Eight Thousand One Hundred Only
29	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	7.00	sqm	8500.00	59500.00	INR Fifty Nine Thousand Five Hundred Only
30	Extra for Providing and fixing flush doors with decorative veneering instead of non decorative ISI marked flush door shutters conforming to IS: 2202 (Part I) - On one side only	7.00	sqm	2000.00	14000.00	INR Fourteen Thousand Only
31	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer of make Hardwyn or approved equivalent (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	8.00	each	2000.00	16000.00	INR Sixteen Thousand Only
32	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 300x16 mm	24.00	each	500.00	12000.00	INR Twelve Thousand Only
33	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 300x10 mm	16.00	each	350.00	5600.00	INR Five Thousand Six Hundred Only
34	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm	16.00	each	300.00	4800.00	INR Four Thousand Eight Hundred Only
35	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	16.00	Each	450.00	7200.00	INR Seven Thousand Two Hundred Only
36	Providing and fixing on wall fire retardant EGSB grade Medium Density Fiber (M.D.F.) Board conforming to IS 12406-1988 such as NUWUD or equivalent, Pre-laminated one side decorative lamination and other side balancing lamination, with all necessary fixing arrangement and framework and screws etc. complete. 12 mm thick.	72.00	sqm	2000.00	144000.00	INR One Lakh Forty Four Thousand Only
37	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1059.00	kg	120.00	127080.00	INR One Lakh Twenty Seven Thousand & Eighty Only
38	Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 1.60 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 1.60 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strikeplate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge: a) Profile B : Fixing with adjustable lugs with split end tail to each jamb	22.00	m	5500.00	121000.00	INR One Lakh Twenty One Thousand Only
39	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	824.00	kg	150.00	123600.00	INR One Lakh Twenty Three Thousand Six Hundred Only

26/04/2023

राजेश वाणी / RAJESH WANI

सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Engg.-Civil)

भारतीय विमानपत्तन प्राधिकरण Airports Authority of India

औरंगाबाद विमानक्षेत्र Aurangabad Airport

40	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	18.00	sqm	1200.00	21600.00	INR Twenty One Thousand Six Hundred Only
41	Providing and laying antiskid vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	57.00	sqm	1400.00	79800.00	INR Seventy Nine Thousand Eight Hundred Only
42	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement & matching pigments etc. complete.a) Size of Tile 600x600 mm	30.00	sqm	1400.00	42000.00	INR Forty Two Thousand Only
43	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : a) In 75x75 mm deep chase	67.00	metre	800.00	53600.00	INR Fifty Three Thousand Six Hundred Only
44	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.a)110 mm diameter	50.00	metre	450.00	22500.00	INR Twenty Two Thousand Five Hundred Only
45	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. a) Bend 87.5° i) 110 mm bend	20.00	each	450.00	9000.00	INR Nine Thousand Only
46	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length,including cutting brick work and fixing in cement mortar 1:4 (1 cement: 4 coarse sand) and making good the wall etc. complete. a)110 mm	10.00	each	100.00	1000.00	INR One Thousand Only
47	Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200 x 600 mm panel to form grids of 600 x 600 mm and wall angle of size 24 x 24 x 0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge - 12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm,made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part I and laminated with white 0.16mm thick fire retardant PVC film on the face side and 12micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit.	56.00	sqm	2000.00	112000.00	INR One Lakh Twelve Thousand Only
48	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:6 (1 cement : 6 fine sand)	457.00	sqm	400.00	182800.00	INR One Lakh Eighty Two Thousand Eight Hundred Only
49	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	199.00	sqm	450.00	89550.00	INR Eighty Nine Thousand Five Hundred & Fifty Only
50	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work	335.00	sqm	130.00	43550.00	INR Forty Three Thousand Five Hundred & Fifty Only
51	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	366.00	sqm	90.00	32940.00	INR Thirty Two Thousand Nine Hundred & Forty Only
52	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 Kg/ 10 sqm)	199.00	sqm	220.00	43780.00	INR Forty Three Thousand Seven Hundred & Eighty Only
53	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : a)Two or more coats on new work	104.00	sqm	180.00	18720.00	INR Eighteen Thousand Seven Hundred & Twenty Only
54	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	366.00	sqm	70.00	25620.00	INR Twenty Five Thousand Six Hundred & Twenty Only
55	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead within airport premises including all leads and lifts.	1421.00	sqm	30.00	42630.00	INR Forty Two Thousand Six Hundred & Thirty Only
56	Supplying and filling with good quality mureom including watering, ramming, consolidating and dressing complete	318.00	cum	800.00	254400.00	INR Two Lakh Fifty Four Thousand Four Hundred Only
57	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	182.00	cum	4800.00	873600.00	INR Eight Lakh Seventy Three Thousand Six Hundred Only
58	Providing and fixing in position pre-moulded joint filler in expansion joints.	4244.00	er cm width	10.00	42440.00	INR Forty Two Thousand Four Hundred & Forty Only

26/04/2023

राजेश वाणी / RAJESH WANI

सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (E&C-Civil)

भारतीय विमानपत्तन प्राधिकरण Airports Authority of India

औरंगाबाद विमानक्षेत्र Aurangabad Airport

59	Providing and laying factory made chamfered edge Cement Concrete paver blocks in foot path, park & lawns driveway or light & traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of coarse sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, all complete as per manufacturer's specifications & direction of Engineer-in- Charge. 60mm thick Cement concrete paver block of M-35 grade with approved colour, design & pattern.	154.00	sqm	850.00	130900.00	INR One Lakh Thirty Thousand Nine Hundred Only
60	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : a) W.C. pan with ISI marked white solid plastic seat and lid	1.00	Each	15000.00	15000.00	INR Fifteen Thousand Only
61	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern.	1.00	Each	10500.00	10500.00	INR Ten Thousand Five Hundred Only
62	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap	1.00	Each	7000.00	7000.00	INR Seven Thousand Only
63	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink with drain board 510x1040 mm bowl depth 250 mm	1.00	Each	12500.00	12500.00	INR Twelve Thousand Five Hundred Only
64	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	5.00	Each	1800.00	9000.00	INR Nine Thousand Only
65	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge.	2.00	Each	1500.00	3000.00	INR Three Thousand Only
66	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 40 mm dia	5.00	each	100.00	500.00	INR Five Hundred Only
67	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : Rectangular shape 453x357 mm	1.00	each	1500.00	1500.00	INR One Thousand Five Hundred Only
68	Providing and fixing toilet paper holder : C.P. brass	1.00	each	750.00	750.00	INR Seven Hundred & Fifty Only
69	Providing and fixing soil, waste and vent pipes : 75 mm diameter : Hubless centrifugally cast (spun) iron pipes epoxy coated inside & outside IS:15905	20.00	metre	750.00	15000.00	INR Fifteen Thousand Only
70	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 15 mm nominal outer dia Pipes	25.00	metre	190.00	4750.00	INR Four Thousand Seven Hundred & Fifty Only
71	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 25 mm nominal outer dia Pipes	25.00	metre	420.00	10500.00	INR Ten Thousand Five Hundred Only
72	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 40 mm nominal outer dia Pipes	25.00	metre	870.00	21750.00	INR Twenty One Thousand Seven Hundred & Fifty Only
73	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 25 mm nominal dia Pipes	375.00	metre	400.00	150000.00	INR One Lakh Fifty Thousand Only
74	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 40 mm nominal dia Pipes	50.00	metre	700.00	35000.00	INR Thirty Five Thousand Only
75	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 50 mm nominal dia Pipes	50.00	metre	800.00	40000.00	INR Forty Thousand Only
76	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 50 mm dia nominal bore	550.00	metre	625.00	343750.00	INR Three Lakh Forty Three Thousand Seven Hundred & Fifty Only
77	Providing and fixing brass bib cock of approved quality. 15 mm nominal bore	3.00	each	1250.00	3750.00	INR Three Thousand Seven Hundred & Fifty Only
78	Providing and fixing brass stop cock of approved quality 15 mm nominal bore	2.00	each	650.00	1300.00	INR One Thousand Three Hundred Only
79	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore.	2.00	each	1500.00	3000.00	INR Three Thousand Only

26/04/2023

राजेश वाणी / RAJESH WANI

सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Enngg.-Civil)

भारतीय विमानपत्तन प्राधिकरण Airports Authority of India

औरंगाबाद विमानक्षेत्र Aurangabad Airport

80	Painting G.I. pipes and fittings with synthetic enamel white paint with two coats over a ready mixed priming coat, both of approved quality for new work : 50 mm diameter pipe	650.00	metre	200.00	130000.00	INR One Lakh Thirty Thousand Only
81	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1000.00	per litre	14.00	14000.00	INR Fourteen Thousand Only
82	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	20.00	each	650.00	13000.00	INR Thirteen Thousand Only
83	Providing and fixing PTMT grating of approved quality and colour. Rectangular type with openable circular lid 150 mm nominal size square 100 mm diameter of the inner hinged round grating.	5.00	each	550.00	2750.00	INR Two Thousand Seven Hundred & Fifty Only
84	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	3.00	each	600.00	1800.00	INR One Thousand Eight Hundred Only
85	Cutting holes up to 30x30 cm in walls including making good the same: With common burnt clay F.P.S. (non modular) bricks	20.00	each	750.00	15000.00	INR Fifteen Thousand Only
86	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete - 150 mm dia. R.C.C. pipe	200.00	metre	600.00	120000.00	INR One Lakh Twenty Thousand Only
87	Providing orange colour safety foot rest of minimum 6 mm thick plastic encapsulated as per IS : 10910, on 12 mm dia steel bar conforming to IS: 1786, having minimum cross section as 23 mmx25 mm and over all minimum length 263 mm and width as 165 mm with minimum 112 mm space between protruded legs having 2 mm tread on top surface by ribbing or chequering besides necessary and adequate anchoring projections on tail length on 138 mm as per standard drawing and suitable to with stand the bend test and chemical resistance test as per specifications and having manufacture's permanent identification mark to be visible even after fixing, including fixing in manholes with 30x20x15 cm cement concrete block 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) complete as per design.	24.00	each	600.00	14400.00	INR Fourteen Thousand Four Hundred Only
88	Constructing soak pit 1.20x1.20x1.20 m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	1.00	each	16000.00	16000.00	INR Sixteen Thousand Only
89	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : b) For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	294.00	kg	550.00	161700.00	INR One Lakh Sixty One Thousand Seven Hundred Only
90	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : b) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	121.00	kg	550.00	66550.00	INR Sixty Six Thousand Five Hundred & Fifty Only
91	Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side	61.00	sqm	1500.00	91500.00	INR Ninety One Thousand Five Hundred Only
92	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber /neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	19.00	sqm	950.00	18050.00	INR Eighteen Thousand & Fifty Only
93	Providing and fixing aluminium round shape handle of outer dia 100 mm with SS screws etc. complete as per direction of Engineer-in-charge Polyester powder coated minimum thickness 50 micron aluminium	16.00	each	300.00	4800.00	INR Four Thousand Eight Hundred Only

26/04/2023

राजेश वाणी / RAJESH WANI
 सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Engrg.-Civil)
 भारतीय विमानपत्तन प्राधिकरण Airports Authority of India
 औरंगाबाद विमानक्षेत्र Aurangabad Airport

94	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement : 4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. All above operations to be done in order and as directed and specified by the Engineer-in-Charge : i) With average thickness of 120 mm and minimum thickness at khurra as 65 mm.	74.00	sqm	2000.00	148000.00	INR One Lakh Forty Eight Thousand Only
95	Welding anchor bolt with main bar of counter poise column by electric welding machine including transportation of welding machine at site and cost of welding rods etc. complete	1.00	Job	20000.00	20000.00	INR Twenty Thousand Only
96	Providing and fixing SWR PVC pipes including all necessary PVC fittings and accessories. This includes jointing of pipes & fittings with solvent complete as per direction of Engineer in Charge: 110 mm dia	150.00	metre	350.00	52500.00	INR Fifty Two Thousand Five Hundred Only
97	Providing, Placing and Fixing at Site Septic Tank of diameter 600 m and depth 2.5 metre with all necessary fittings, fixtures and arrangements complete as per direction of Engineer In-charge	1.00	each	18982.00	18982.00	INR Eighteen Thousand Nine Hundred & Eighty Two Only
98	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers, end caps etc. conforming to IS 14390 (Part II) complete with fitting cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc, complete as required. 160 mm dia (OD-160 mm and ID-135 mm nominal)	375.00	metre	500.00	187500.00	INR One Lakh Eighty Seven Thousand Five Hundred Only
99	Supplying and laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers, end caps etc. conforming to IS 14390 (Part II) complete with fitting cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc, complete as required. 200 mm dia (OD-200 mm and ID-175 mm nominal)	75.00	metre	700.00	52500.00	INR Fifty Two Thousand Five Hundred Only
100	Structural consultancy charges for preparation of detailed structural design, drawing & bar bending schedule including soil investigation on the basis of relevant latest IS code and sound engineering practices & the same to be vetted by Prof./HOD of any Govt. recognised college & AICTE accredited Engineering college including site visit whenever required during execution of work.	1.00	Job	255000.00	255000.00	INR Two Lakh Fifty Five Thousand Only
Total in Figures					8609199.00	INR Eighty Six Lakh Nine Thousand One Hundred & Ninety Nine Only
Quoted Rate in Words		INR Eighty Six Lakh Nine Thousand One Hundred & Ninety Nine Only				

26/04/2023

राजेश वाणी / RAJESH WANI

सहा. महाप्रबंधक (अभि-सिविल) Asst. Gen. Manger (Enigg.-Civil)

भारतीय विमानपत्तन प्राधिकरण Airports Authority of India

औरंगाबाद विमानक्षेत्र Aurangabad Airport

Date: 21/03/2023

To,
Asstt. General Manager (Engg-Civil)
Aurangabad Airport

Subject: Negotiation meeting for the work of Construction of New DVOR at
Aurangabad Airport Tender ID : 2023_AAI_146091_1 opened on
15.03.2023 regarding


Dear Sir,

As per subject matter we are the L1 Bidder of above said work, As per your
mail on 20th march 2023 for revised quote amount, we are offering 0.65 % rebate
on Bill Value.

Thanking in anticipation ..

Respect's

Mall Infrastructure


20/04/2023
राजेश वाणी / RAJESH WANI
सहा. महाप्रबंधक (अधि-सिविल) Asst. Gen. Manger (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण Airports Authority of India
औरंगाबाद विमानक्षेत्र Aurangabad Airport