

Ref: AAI/CHQ/Engg.(C)-NER/Agartala/Re-Carpeting RWY/2023-24/254-272 SPEED POST Date 23.05.2023

मैसर्स शिवा बिल्डटेक प्राइवेट लिमिटेड

केबिन नंबर: 354, डी-288-89/10,

लक्ष्मी नगर, वाधवा कॉम्प्लेक्स,

विकास मार्ग, नई दिल्ली-110092

मोबाइल : 9811087846, 9811084231

ई-मेल : shivabuildtech@gmail.com

M/s Shiva Buildtech Pvt. Ltd.

Cabin No: 354, D-288-89/10,

Laxmi Nagar, Wadhwa Complex,

Vikas Marg, New Delhi - 110092

(M) : 9811087846, 9811084231

E-mail: shivabuildtech@gmail.com

Name of work : Re-Carpeting of Runway, Taxiways, Grading of Operational Area, Development of Drainage System And Associated Works (Civil & Electrical) at M.B.B. Airport, Agartala. (Tender ID: 2023_AAI_147392_1)

Ref: Your e-tender dated : 27.03.2023

महोदय,

Dear Sir,

1. उपरोक्त कार्य के लिए आपकी ई-निविदा एतद्वारा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से आपके द्वारा उद्धृत मद दरों पर स्वीकृत की जाती है जो कुल राशि रु. 68,27,82,676.00 (रुपये अड़सठ करोड़ सत्ताईस लाख बयासी हजार छः सौ छिहत्तर मात्र) जीएसटी को छोड़कर जो कि निविदा में रखी गई अनुमानित लागत 76,48,15,000.00 रुपये से 10.73 % कम है।

Your e-tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the item rates amount quoted by you total amounting to Rs. 68,27,82,676.00 (Rupees Sixty Eight Crore Twenty Seven Lakh Eighty Two Thousand Six Hundred and Seventy Six Only) excluding GST which is 10.73% below the estimated cost put to tender of Rs. 76,48,15,000.00

2. संयुक्त महाप्रबंधक/उप महाप्रबंधक (अभि.- सिविल) भा.वि.प्रा., एम. बी. बी. हवाई अड्डा, अगरतला कार्य के प्रभारी अभियंता होंगे। आपसे अनुरोध है कार्य प्रारम्भ करने की निर्धारित तिथि से 15 दिवस के अन्दर अनुबंध समझौते पर हस्ताक्षर करने और पूरा करने के लिए उप महाप्रबंधक (अभि.- सिविल) भारतीय विमानपत्तन प्राधिकरण, एनएटीएस कॉम्प्लेक्स, आईजीआई एयरपोर्ट, टर्मिनल-2 के पास, नई दिल्ली - 110037 के कार्यालय में उपस्थित हों। संविदा करार 100/- (एक सौ रुपये मात्र) के मूल्य के गैर-न्यायिक स्टाम्प पेपर पर निष्पादित किया जाएगा तथा स्टॉप पेपर की कीमत आपको वहन करनी होगी।

Jt. GM/DGM (Engg.-Civil), AAI, M.B.B. Airport, Agartala shall be the Engineer-in-Charge of to work. You are requested to attend the office of the DGM (Engg.-Civil), Airports Authority of India, NATS Complex, IGI Airport, Near Terminal-2, New Delhi-110037 within 15 days from the stipulated date of start of the work to sign and complete the Contract Agreement. The Contract Agreement shall be executed on a non-judicial stamp paper of value of Rs. 100/ (Rupees one hundred only) and the cost of the stamp paper shall be borne by you.

For Shiva Buildtech Pvt. Ltd.

Director

0003

उप-महाप्रबंधक (अभि.-सिविल) उत्तरी पूर्वी क्षेत्र, नि.पु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

[A large diagonal line is drawn across the page, likely indicating a cancellation or a placeholder for a signature.]

[Handwritten signature]

उप-महाप्रबंधक (अभि-सिविल), उत्तरी पूर्वी क्षेत्र, नि.मु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

उप-महाप्रबंधक (अभि-सिविल), उत्तरी पूर्वी क्षेत्र, नि.मु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

3. कृपया प्रतिभूति जमा राशि 3,41,39,134.00 रुपये (रुपये तीन करोड़ इकतालीस लाख उनतालीस हजार एक सौ चौतीस मात्र) इस पत्र के जारी होने की तारीख से 10 दिनों के भीतर जमा करें। ऐसा न करने पर, दस्तावेज के जी. सी. सी. की पृष्ठ संख्या 16 पर शर्त खंड 1 ए के अनुसार उसकी कटौती की जाएगी।

Please deposit Rs. 3,41,39,134.00 (Rupees Three Crore Forty One Lakh Thirty Nine Thousand One Hundred Thirty Four only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no. 1A at page no.16 of GCC of Contract document.

4. अनुबंध दस्तावेज के खंड 14 जी. सी. सी. के पृष्ठ संख्या 10 एवं जी. सी. सी. के पृष्ठ संख्या 131 पर अनुसूची 'ई' की शर्त के अनुसार, स्वीकृति पत्र जारी होने के 30 दिनों के भीतर, आप भा.वि.प्रा. को 2,04,83,481.00 रुपये (रुपये दो करोड़ चार लाख तिरासी हजार चार सौ इक्यासी मात्र) राशि की एक कार्य निष्पादन गारंटी अनुबंध दस्तावेज के जीसीसी-109 पर परिशिष्ट-XI में संलग्न प्रोफार्मा के अनुसार बैंक गारंटी के रूप में प्रस्तुत करेंगे।

Within 30 days of issue of acceptance letter, you shall submit to AAI, a Performance Guarantee as per condition of clause 14 at page-10 of GCC & SCHEDULE 'E' on Page no. 131 of GCC of Contract document for an amount of Rs. 2,04,83,481.00 (Rupees Two Crore Four Lakh Eighty Three Thousand Four Hundred Eighty One only) in the form of Bank Guarantee as per proforma appended at APPENDIX-XI on GCC-109 of Contract document.

5. आपसे अनुरोध है कि ठेका श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की शर्तें) अधिनियम 1996, भवन एवं अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि निविदा के जीसीसी के पृष्ठ संख्या 49 पर खंड -19 में निर्दिष्ट है और संशोधन सहित केंद्र और राज्य सरकारों के नियमों के प्रावधान) का अनुपालन करें।

You are requested to comply with the provision of contract labour (Regulation & abolition) Act of 1970 and contract labour (Regulation & Abolition) Central Rules 1971, Child Labour (Prohibition & Regulation) Act 1986, Construction Workers (Regulation of Employment and Condition of Service) Act 1996, Building and other construction Workers Welfare Cess Act 1996 as specified in Clause-19 on page No. 49 of GCC of tender and rules of Central and State Governments including amendments.

6. आपको निर्देश दिया जाता है कि आप संयुक्त महाप्रबंधक / उप महाप्रबंधक (अभि.- सिविल) भा.वि.प्रा., एम. बी. बी. हवाई अड्डा, अगरतला, से तुरंत संपर्क करें जो कि आपको कार्य स्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact the Office of Jt. GM / DGM (Engg.-Civil), AAI, M.B.B. Airport, Agartala, immediately who will arrange to hand over the site to you.

7. कृपया ध्यान दें कि कार्य करने के लिए अनुमत समय 15 महीने (बारिश के लिए माने गए 03 (तीन) महीने सहित) होगा और इसकी गणना इस पत्र के जारी होने के 10वें दिन से की जाएगी।

Please note that the time allowed for carrying out the work shall be 15 months (including 03 (Three) months considered for rains) and same shall be reckoned from the 10th day after issue of this letter.

For Shiva Buildtech Pvt. Ltd.

0004

उप-महाप्रबंधक (अभि.-सिविल) उत्तरी पूर्वी क्षेत्र, नि.गु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India
नई दिल्ली/New Delhi

[Faint, illegible text from the reverse side of the page, visible through the paper.]


उप-महाप्रबंधक (अभि-सिविल) उत्तरी पूर्वी क्षेत्र, नि.मु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India
नई दिल्ली / New Delhi

उप-महाप्रबंधक (अभि-सिविल) उत्तरी पूर्वी क्षेत्र, नि.मु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण/Airports Authority of India
नई दिल्ली / New Delhi

8. ई-निविदा प्रक्रिया के दौरान उठाए गए सभी शुद्धिपत्र, प्रश्न, स्पष्टीकरण आदि और ऊपर उल्लिखित पत्रों सहित उनके उत्तर भी समझौते का हिस्सा होंगे।

All corrigendum, queries, clarifications etc. raised during e-tendering process and replies thereof including the letters referred above shall also form part of the Agreement.

9. अनुबंध के संबंध में किसी भी अन्य पत्राचार को सामान्य रूप से प्रभारी अभियंता यानी संयुक्त महाप्रबंधक / उप महाप्रबंधक (अभि.-सिविल) भा.वि.प्रा., एम. बी. बी. हवाई अड्डा, अगरतला को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the Engineer In-Charge i.e., Jt. GM / DGM (Engg.-Civil), AAI, M.B.B. Airport, Agartala.


10. कृपया रसीद की पावती दें और इसके साथ संलग्न इस पत्र की डुप्लीकेट प्रति को स्वीकृति के प्रतीक के रूप में अधोहस्ताक्षरी को विधिवत हस्ताक्षर करने के बाद लौटा दें।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after duly signing it to the undersigned as a token of acceptance.

11. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही माना जाएगा।

In case any discrepancy is found than English version will be treated as correct.

Yours faithfully


(आर. के. ब्रमिनिया)

उप-महाप्रबंधक (अभि.-सिविल) / निर्मित मुख्यालय, उत्तर पूर्वी क्षेत्र
Dy. General Manager (Engg.-Civil) / CHQ, NER
एनएटीएस कॉम्प्लेक्स, आईजीआई एयरपोर्ट, नई दिल्ली - 110037

NATS Complex, IGI Airport, New Delhi-110037
For and on behalf of the Chairman,
AIRPORTS AUTHORITY OF INDIA

Distribution List:-

External:-

1. सहायक श्रम आयुक्त, अगरतला
Asst. Labour Commissioner, Agartala
2. क्षेत्रीय भविष्य निधि आयुक्त, अगरतला
Regional Provident Fund Commissioner,
Agartala
3. व्यावसायिक कर आयुक्त, अगरतला
Commercial Tax Commissioner, Agartala
4. अतिरिक्त आयकर आयुक्त, अगरतला
Additional Commissioner of Income tax, Agartala

ये 04 (1 से 4) प्रतियां संयुक्त महाप्रबंधक (अभि.-सिविल), एम. बी. बी. हवाई अड्डा, अगरतला, को संबंधित कार्यालयों में भेजने की व्यवस्था करने के अनुरोध के साथ अग्रेषित की जा रही हैं।

These 04 (1 to 4) copies are being forwarded to Jt. GM (Engg.-Civil), M.B.B. Airport, Agartala, with the request to arrange the delivery of the same to the respective offices.

For Shiva Builders Pvt. Ltd.

उप-महाप्रबंधक (अभि-सिविल) उत्तरी पूर्वी क्षेत्र, नि.पु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi



उप-महाप्रबंधक (अभि-सिविल) उत्तरी पूर्वी क्षेत्र, नि.पु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

उप-महाप्रबंधक (अभि-सिविल) उत्तरी पूर्वी क्षेत्र, नि.पु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

Internal:

1. निजी सचिव, अध्यक्ष, एएआई, नि.मु., नई दिल्ली।
P.S. to Chairman, AAI, CHQ, New Delhi.
2. निजी सचिव, सदस्य (योजना) नि.मु., नई दिल्ली।
P.S. to Member (Planning), AAI, CHQ, New Delhi.
3. कार्यकारी निदेशक (अभि.) पू. क्षे. एवं उ. पू. क्षे. (नि.मु.), एएआई, नई दिल्ली।
ED ENGG-ER & NER (CHQ), AAI, New Delhi.
4. कार्यकारी (एफ एंड ए) निदेशक एएआई, नि.मु., नई दिल्ली।
E.D. (F&A), AAI, CHQ, New Delhi.
5. कार्यकारी निदेशक (योजना) एएआई, नि.मु., नई दिल्ली।
E.D. (Planning), AAI, CHQ, New Delhi.
6. कार्यकारी निदेशक (वास्तु.) एएआई, नि.मु., नई दिल्ली।
E.D. (Arch.), AAI, CHQ, New Delhi.
7. कार्यकारी निदेशक (पीएमक्यूए) एएआई, नि.मु., नई दिल्ली।
E.D. (PMQA), AAI, CHQ, New Delhi.
8. क्षेत्रीय कार्यकारी निदेशक, एएआई, क्षेत्रीय मुख्यालय, उ.पू.क्षे., गुवाहाटी।
RED, AAI, RHQ, NER, Guwahati.
9. महाप्रबंधक (एफ एंड ए) - उ.पू.क्षे., एएआई, क्षेत्रीय मुख्यालय, एलजीबीआई एयरपोर्ट गुवाहाटी।
G.M. (F&A)-NER, AAI, RHQ, LGBI Airport Guwahati.
10. महाप्रबंधक (अभि.-सिविल), - उ.पू.क्षे., नि.मु., एनएटीएस कॉम्प्लेक्स, नई दिल्ली।
GM (Engg-Civil)-NER (CHQ), AAI, NATS Complex, New Delhi
11. महाप्रबंधक (अभि.-विद्युत), - पू. क्षे. एवं उ. पू. क्षे. (नि.मु.), एएआई, नई दिल्ली।
GM (Engg-Elect)-ER & NER (CHQ), AAI, New Delhi
12. एयरपोर्ट निदेशक, एम. बी. बी. हवाई अड्डा, अगरतला।
APD, AAI, M.B.B. Airport, Agartala.
13. संयुक्त महाप्रबंधक (अभि.-सिविल), एम. बी. बी. हवाई अड्डा, अगरतला।
Jt. GM (Engg.- Civil), M.B.B. Airport, Agartala.

रविन्द्र कुमार
23/05/23
(आर. के. ब्रमनिया)

(R. K. Bramniya)

उप-महाप्रबंधक (अभि.-सिविल)/ निगमित मुख्यालय, उत्तर पूर्वी क्षेत्र

Dy. General Manager (Engg.-Civil) / CHQ, NER

एनएटीएस कॉम्प्लेक्स, आईजीआई एयरपोर्ट, नई दिल्ली -110037

NATS Complex, IGI Airport, New Delhi-110037

For and on behalf of the Chairman,
AIRPORTS AUTHORITY OF INDIA

For Shiva Buildtech Pvt. Ltd.

Director

उप-महाप्रबंधक (अभि.-सिविल), उत्तरी पूर्वी क्षेत्र, नि.मु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

0006



[A large, faint, diagonal line is drawn across the page, likely a placeholder for a signature or stamp.]

[Handwritten signature]

उप-महाप्रबंधक (अभि-सिविल), उत्तरी पूर्वी क्षेत्र, नि.पु.
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

उप-महाप्रबंधक (अभि-सिविल) क्षेत्र-उत्तर-पूर्व
Dy. General Manager (Engg.-Civil), NER-CHQ.
भारतीय विमानपत्तन प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

Validate Print Help

Item Rate BoQ

Tender Inviting Authority: Airports Authority of India

Name of Work: Re-carpeting of Runway, taxiways, Grading of Operational Area and associated works (Civil & Electrical) at M.B.B Airport, Agartala

Contract No: 2023_AAI_147392_1

Name of the Bidder/ Bidding Firm / Company :		M/s Shiva Buildtech Pvt. Ltd .				
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	2510.00	Cum	97.00	243470.00	INR Two Lakh Forty Three Thousand Four Hundred & Seventy Only
2	Supply and filling selected earth obtained from approved external sources (excluding rock) including royalty in layers not exceeding 20 cm in depth breaking clods, watering and consolidation of each layer by roller and rolling every third and top most layer with power roller of minimum 8 tonnes and dressing up in embankments or roads plinth filling or filling of ground depressions including of all leads and lifts to meet requirement of table 300 - 2 of Morth (refer Morth specification section - 305)	35165.00	Cum	196.00	6892340.00	INR Sixty Eight Lakh Ninety Two Thousand Three Hundred & Forty Only
3	Excavation of soil using hydraulic excavator of 0.90cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and disposed of the excavated earth, transporting to the embankment location including loading and unloading with all lifts and leads within airport premises excluding the survey work as per direction of Engineer-in-charge (ref. MORTH Specification section-301)	458835.00	Cum	97.00	44506995.00	INR Four Crore Forty Five Lakh Six Thousand Nine Hundred & Ninety Five Only
4	Construction of embankment with available excavated earth deposited at site from other locations with spreading, neatly leveling/ grading and compacting layer by layer to achieve the desired levels and compactions to meet the requirement of table 300-2 of MORTH specification etc. complete in all respects excluding the survey work as per direction of Engineer-in-Charge.(ref. MORTH Specification section-305)	455515.00	Cum	97.00	44184955.00	INR Four Crore Forty One Lakh Eighty Four Thousand Nine Hundred & Fifty Five Only

स-सहायक (अभि-सिनि) उत्तरी पूर्वी क्षेत्र, नि.पु.
 Dy. General Manager (Engg.-Civil), NER-CHO.
 भारतीय विमानपत्तन प्राधिकरण/ Airports Authority of India
 नई दिल्ली/ New Delhi

12/09

श्री शिवा बिल्डटेक प्रा. लि.
 Director

5	Carrying out Topographical and contour surveying, traversing, contouring & coordinating all permanent and semi-permanent feature by Total station survey instrument and Auto Level as required including mobilization and demobilization of the survey team after completion of survey work at Airport premises of operational area and newly acquired in different plots as per direction of the Engineer in-charge. The following steps shall be taken up: i) Carrying out site survey and taking reduced level 3m x 3m grid. ii) Submission of sets of contour map in suitable scale and size with marking import ants (3 (three) nos. coloured hard copies & 1(one) soft copy. iii) Submission of level sheet in Excel format (Hard copy & soft copy) with quantity calculation for cutting & filling earth as per the gradient which shall be decided by the Engineer in charge. iv) The requisite all survey works for execution of earthwork, quantity work out for Running/Final Bill shall also be included in the scope of survey work.	480.00	Acres	5200.00	2496000.00	INR Twenty Four Lakh Ninety Six Thousand Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering (a) All work up to plinth level (i) 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	1090.00	Cum	7200.00	7848000.00	INR Seventy Eight Lakh Forty Eight Thousand Only
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering (a) All work up to plinth level (i) 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 40 mm nominal size)	105.00	Cum	7900.00	829500.00	INR Eight Lakh Twenty Nine Thousand Five Hundred Only
8	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced Cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. (a) All works upto plinth level (i) Concrete of M25 grade with minimum cement content of 330 kg /cum	3350.00	Cum	8890.00	29781500.00	INR Two Crore Ninety Seven Lakh Eighty One Thousand Five Hundred Only
9	Add for using extra cement in the items of design mix over and above the specified cement content therein.	2033.00	Quintal	970.00	1972010.00	INR Nineteen Lakh Seventy Two Thousand & Ten Only
10	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	3485.00	Sqm	279.00	972315.00	INR Nine Lakh Seventy Two Thousand Three Hundred & Fifteen
11	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	30505.00	Sqm	475.00	14489875.00	INR One Crore Forty Four Lakh Eighty Nine Thousand Eight
12	Centering and shuttering including strutting, propping etc. and removal of form for : Suspended floors, roofs, landings, balconies and access platform	2260.00	Sqm	520.00	1175200.00	INR Eleven Lakh Seventy Five Thousand Two Hundred Only
13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. (a) Thermo-Mechanically Treated bars.	468400.00	Kg	88.00	41219200.00	INR Four Crore Twelve Lakh Nineteen Thousand Two Hundred
14	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: (a) Cement mortar 1:4 (1 cement : 4 sand)	14.00	Cum	8800.00	123200.00	INR One Lakh Twenty Three Thousand Two Hundred Only
15	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	160280.00	Kg	169.00	27087320.00	INR Two Crore Seventy Lakh Eighty Seven Thousand Three Hundred & Twenty Only

For Shiva Buildtech Pvt. Ltd.

Director

0008

सुप-मैनेजर (अभि-सिनि), सली पूर क्षेत्र, निम्न.
Dy. General Manager (Engg.-Civil), NER-CHO.
सुपरी विमानतः प्राधिकरण / Airports Authority of India
नई दिल्ली / New Delhi

16	Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & painted to be paid separately)	74400.00	Kg	142.00	10564800.00	INR One Crore Five Lakh Sixty Four Thousand Eight Hundred Only
17	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : (a) Two or more coats on new work	9995.00	Sqm	160.00	1599200.00	INR Fifteen Lakh Ninety Nine Thousand Two Hundred Only
18	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced Cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. (a) All works upto plinth level (i) Concrete of M35 grade with minimum cement content of 370 kg /cum	2505.00	Cum	9520.00	23847600.00	INR Two Crore Thirty Eight Lakh Forty Seven Thousand Six Hundred Only
19	Providing and submitting the preliminary drawings, carrying out structural design, preparation of detailed structural drawing and developing working architectural drawing. This item also includes carrying out necessary soil investigation works. In which the design to be done for the proposed work. The structural design and drawings shall be got vetted by IIT/NIT/Govt. Engineering colleges. The design and drawing so submitted shall be got approved by Engineer in charge before execution of work. After approval of structural design and drawing by AAI 5 (Five) set of "Good for Construction" design and drawing showing all relevant details shall be submitted duly signed by the consultant. Consultant shall also submit any other details required relevant to the scope and completion of work. (a) For all RCC Structures	1.00	Job	1200000.00	1200000.00	INR Twelve Lakh Only
20	Supply and Stacking at site					
20.01	(a) 90mm to 45mm size stone aggregate	420.00	Cum	4840.00	2032800.00	INR Twenty Lakh Thirty Two
20.02	(b) 63mm to 45 mm size stone aggregate.	316.00	Cum	5200.00	1643200.00	INR Sixteen Lakh Forty Three
20.03	(c) Stone screening 13.2 mm nominal size.	146.00	Cum	5650.00	824900.00	INR Eight Lakh Twenty Four
20.04	(d) Moorum	53.00	Cum	3600.00	190800.00	INR One Lakh Ninety Thousand
21	Laying, spreading and compacting stone aggregate of specified size to WBM specifications including spreading in uniform thickness, hand picking rolling with 3 wheeled road/ vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/ binding material to fill up interstices of coarse aggregate watering and compacting to the required density.	563.00	Cum	700.00	394100.00	INR Three Lakh Ninety Four Thousand One Hundred Only
22	Providing and applying tack coat using bitumen emulsion (Rapid setting) complying with IS:8887, spraying the bitumen with mechanically operated spray unit at the rate specified below, cleaning and preparing the existing pavement surface as per specifications complete in all respects as per direction of Engineer-In-Charge. If the actual quantity of bitumen varies from the quantity specified, necessary cost adjustment for deviation in the quantity of bitumen shall be done as per rate in actual supply voucher from nearest refinery at the time of execution. The rate of bitumen exclusive of GST shall only be considered for payment. (a) 0.20 Kg/Sqm on existing bituminous surface	419600.00	Sqm	14.00	5874400.00	INR Fifty Eight Lakh Seventy Four Thousand Four Hundred Only

For Shiva Buildtech Pvt. Ltd.

Director

0005

नई दिल्ली / New Delhi

राष्ट्रीय विमानपत्तन प्राधिकरण / Airports Authority of India

Dy. General Manager (Engg.-Civil), NER-CHQ.

उप-सहस्रायक (अग्नि-सिद्धि) उत्तरी पूर्वी क्षेत्र, न.पु.

0010

23	Providing and laying of Hot Mix Dense Bituminous Macadam (DBM) using crushed stone aggregate of quality, size and grading as specified and Cement filler as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in- Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 shall be taken as 110 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% Cement by weight of aggregates as filler material.	7510.00	Cum	14200.00	106642000.00	INR Ten Crore Sixty Six Lakh Forty Two Thousand Only
24	Providing and laying of Hot Mix Semi Dense Asphaltic Concrete (SDAC) using crushed stone aggregate of quality, size and grading as specified and Cement filler as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in- Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 content shall be taken as 120 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% Cement by weight of aggregates as filler material.	9445.00	Cum	15000.00	141675000.00	INR Fourteen Crore Sixteen Lakh Seventy Five Thousand Only
25	Providing and laying of Hot Mix Dense Asphaltic Concrete (DAC) using crushed stone aggregate of quality, size and grading as specified and Cement filler as specified and Viscosity Grade Bitumen (supplied in bulk) in proportions as per job mix formula and laid to specified levels, grade and camber as per specification, drawings and as directed by the Engineer-in- Charge including compacting with 8-10 tonne, preferably vibratory road roller of adequate capacity to achieve the specified values of compaction, strength, surface accuracy complete [for tendering purpose VG bitumen of grade VG-30 content shall be taken as 135 kg/m3 of mix supplied in bulk produced by Govt. Refineries and 2% Cement by weight of aggregates as filler material	6800.00	Cum	15700.00	106760000.00	INR Ten Crore Sixty Seven Lakh Sixty Thousand Only
26	Painting runway/taxi track/apron marking including lettering with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of ail dirt, scales, oil, grease and other foreign mater;al etc. and lining out complete. (a)Two or more coats	8530.00	Sqm	295.00	2516350.00	INR Twenty Five Lakh Sixteen Thousand Three Hundred & Fifty Only
27	Painting runway/taxi track/apron marking including lettering with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of ail dirt, scales, oil, grease and other foreign mater;al etc. and lining out complete. (a)One or more coats	9945.00	Sqm	340.00	3381300.00	INR Thirty Three Lakh Eighty One Thousand Three Hundred Only
28	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. (a) In Cement Mortar	580.00	Cum	700.00	406000.00	INR Four Lakh Six Thousand Only
29	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (a) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	3813.00	Cum	1240.00	4728120.00	INR Forty Seven Lakh Twenty Eight Thousand One Hundred & Twenty Only
30	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (a) Nominal concrete 1:4:8 or richer mix (i/c equivalent design mix).	3813.00	Cum	1150.00	4384950.00	INR Forty Three Lakh Eighty Four Thousand Nine Hundred & Fifty Only
31	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 1 kilometre, as per direction of Engineer-in-charge.	499.00	Cum	970.00	484030.00	INR Four Lakh Eighty Four Thousand &Thirty Only
32	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 sand) including testing of joints etc. complete (a) 900 mm dia RCC pipes.	45.00	Metre	8800.00	396000.00	INR Three Lakh Ninety Six Thousand Only

33	Carriage of material by mechanical transport including Loading, unloading upto 4.00km (a) Lime, moorum, building rubbish.	3813.00	Cum	196.00	747348.00	INR Seven Lakh Forty Seven Thousand Three Hundred & Forty
34	Supply of C.I. Isolating Transformer housing box, water light round type, metal container of outside size 330 mm, height 450 mm made of 10 mm thick cast iron moulding all round, except the top surface, which is 15 mm thick, cast iron moulding suitable to receive a light fitting base plate on the top and underground housing associated with transformer power cable and having 2nos both side 50mm dia clear hole centre (each 180 degree apart) at 75 mm above bottom surface suitable to receive 02 nos 50 mm diameter HDPE pipe and check nut as required. The box should have two SS earth bolt of M 10 x 40 tapped inside near the holes (4" away from the hole centre) and having a drain hole at the bottom suitably tapped to receive 15 mm diameter, 'B' class GI pipe and having clear opening of 220 mm at the top surface and 6 Nos. M 10 tapped hole at the hole centre 260 mm to receive fitting base plate and bolts complete with neoprime rubber gasket for the top covers as required as per the drawing & specifications.	72.00	Each	34000.00	2448000.00	INR Twenty Four Lakh Forty Eight Thousand Only
35	Supply of C.I. Collar suitable for mounting installing on the existing transformer housing box, made out of water tight round type metal container of outside size 330 mm diameter and upto 175mm height (as per site requirement), 10 mm thick all round except on the top surface which is 15 mm thick and a clear opening of 220 mm diameter at the top as well as bottom having 6 Nos. x M-10 tapped hole along the circumferential centre of 260 mm diameter top/bottom plate to receive bolts as required as per the drawing & specifications. total 12nos of SS bolts shall be provided to fix the collar and light fixture. the housing box should have 2 nos. clear hole (01 nos in each opposite side) of 50mm dia suitable to receive 50 mm dia HDPE pipe and check nuts as required. The housing box should be complete with neoprime rubber gasket for the top covers, painting with Anti-corrosive primers and paint inside and outside etc. as per drawing and specification complete as required.	240.00	Each	18000.00	4320000.00	INR Forty Three Lakh Twenty Thousand Only
36	Supply of 1 x 16 Sq. mm 5 KV grade single core, multistranded annealed plain copper conductor, underground, unscreened, unarmoured XLPE insulated and PVC outer sheathed, anti-rodent and anti-termite treated Airfield Lighting Cable generally conforming to IS 7098 Part II with up to date amendments etc. complete as required.	27000.00	Metre	225.00	6075000.00	INR Sixty Lakh Seventy Five Thousand Only
37	Supply of 5 KV grade, 16 sq. mm size plug and receptacle of type I class "B" connector suitable for field attachment with 5 KV grade of PVC/XLPE insulated PVC sheathed single core copper conductor Airfield Lighting cable conforming to the relevant IS specification etc. complete as required.	350.00	Each	1150.00	402500.00	INR Four Lakh Two Thousand Five Hundred Only
38	Supply of 50 mm size HDPE pipe including all accessories such as couplers, end cap etc in accordance with IS- 4984 - 1995 as amended up to date (PE80, PN10) complete as required.	27700.00	Metre	225.00	6232500.00	INR Sixty Two Lakh Thirty Two Thousand Five Hundred Only
39	Supply of Secondary lead cable of size 2 x 4 sq.mm PVC insulated PVC sheathed anti termite & anti rodent stranded copper conductor airfield lighting cable of 1.1 KV grade. Confirming to IS 1554 part II with up to date amendments as required for following length along with 1.1KV grade Plug and receptacles moulded plug at one end and receptacles at the other end etc complete as required.					
39.01	a) 1 Mtrs	235.00	Each	630.00	148050.00	INR One Lakh Forty Eight Thousand
39.02	b) 15 Mtrs	12.00	Each	3600.00	43200.00	INR Forty Three Thousand Two
39.03	c) 20 Mtrs	7.00	Each	5200.00	36400.00	INR Thirty Six Thousand Four
39.04	d) 30 Mtrs	8.00	Each	6300.00	50400.00	INR Fifty Thousand Four Hundred
40	Supply of Secondary lead cable of size 2 x 4 sq.mm PVC insulated PVC sheathed anti termite & anti rodent stranded copper conductor airfield lighting cable of 1.1 KV grade. Confirming to IS 1554 part II with up to date amendments as required.	150.00	Metre	180.00	27000.00	INR Twenty Seven Thousand Only

41	Supply of 1.1KV Plug and receptacle suitable for secondary lead of size 2 x 4 sq.mm PVC insulated PVC sheathed anti termite & anti rodent stranded copper conductor airfield lighting cable.	44.00	Set	4300.00	189200.00	INR One Lakh Eighty Nine Thousand Two Hundred Only
42	Supply of following type 5 KV grade 50Hz series type Isolating Transformers, encapsulated in polyester resin finally moulded in neoprene type rubber with primary & secondary connections and ready to install etc. complete as required.					
42.01	a) 200W 20A/6.6Amp 5KV Grade Isolating Transformer	25.00	Each	45000.00	1125000.00	INR Eleven Lakh Twenty Five
42.02	b) 15W, 20/6.6 Amps 5 KV grade Isolating Transformer	120.00	Each	21400.00	2568000.00	INR Twenty Five Lakh Sixty Eight
43	Supply of Inset type bidirectional fittings suitable for high intensity THRESHOLD/END light fitting for aviation visual aids requirements meeting ICAO standards complete with shallow base and matching body of the fitting, inner body and outer cover made of die cast aluminium complete with 3 x 105 Watts, 6.6 Amps pre focused reflector halogen lamp of 6.6 amps current with connected heat resistant accessories, prism assembly, optical assembly, "O" ring seal, pressure relief test plug, hardware, green/red prism / lenses and all standard accessories and ready for site installation complete as required.	44.00	Each	4300.00	189200.00	INR One Lakh Eighty Nine Thousand Two Hundred Only
44	Supply of Inset type bidirectional fittings suitable for high intensity RUNWAY EDGE light fitting for aviation visual aids requirements meeting ICAO standards complete with shallow base and matching body of the fitting, inner body and outer cover made of die cast aluminium complete with 2 x 105 Watts, 6.6 Amps pre focused reflector halogen lamp of 6.6 amps current with connected heat resistant accessories, prism assembly, optical assembly, "O" ring seal, pressure relief test plug, hardware, Yellow/white/green/red prism / lenses and all standard accessories and ready for site installation complete as required.					
44.01	a) White/White	5.00	Each	1600.00	8000.00	INR Eight Thousand Only
44.02	b) White/Yellow	22.00	Each	1980.00	43560.00	INR Forty Three Thousand Five
45	Supply of Bi-Directional Elevated Type high intensity Runway Edge Light Fittings in compliance with ICAO: Annex 14-Volume I & FAA: L-862 AC150/5345-46 suitable for use with 200W 6.6A halogen lamp complete with all accessories including lamp and clear or Yellow/White spreader lens and CI base plate.	15.00	Each	3600.00	54000.00	INR Fifty Four Thousand Only
46	Cutting groove of size 300 mm wide and 150 mm deep (or as required) with saw cut machine, refilling and finishing the surface with coarse sand and bitumen or cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 10 mm dia nominal), etc complete as reqd.	25.00	CUM	5200.00	130000.00	INR One Lakh Thirty Thousand Only
47	Laying of 50mm dia HDPE pipe as per IS specification complete with fitting and cutting, jointing with coupler, bend etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	24000.00	metre	106.00	2544000.00	INR Twenty Five Lakh Forty Four Thousand Only
48	Laying of one number 5 KV grade single core, PVC/XLPE insulated and PVC sheathed stranded copper conductor underground airfield lighting cable in the existing RCC/ HUME/ METAL/HDPE pipe complete as required.	24000.00	metre	25.00	600000.00	INR Six Lakh Only
49	Laying of 50mm dia HDPE pipe as per IS specification complete with fitting and cutting, jointing with coupler, bend etc. in the existing trench/ runway surface complete as required.	3400.00	metre	52.00	176800.00	INR One Lakh Seventy Six Thousand Eight Hundred Only
50	Making field connections by crimping upto 16 Sq.mm plug and receptacle with the existing 6 / 16 Sq.mm single core PVC/XLPE insulated copper conductor cable including filling the gap with water sealant material, applying PVC insulation tape of approved/reputed make etc complete as required.	340.00	Each	295.00	100300.00	INR One Lakh Three Hundred Only

0012

व्य-प्रमुख (प्रति-निर्देश) उत्तरी पूर्वी क्षेत्र, वि.प्र.
 Dy. General Manager (Engg.-Civil), NER-CHQ.
 भारतीय विमानतंत्र प्राधिकरण / Airports Authority of India
 नई दिल्ली / New Delhi

51	Installation of transformer housing boxes (Item No.1) with a base concrete of 1:2:4 of size 800 mm X 600 mm with 100mm thick at bottom and all around concrete of 1 : 2 : 4, 150 mm thick, top sloped with 1:2:4 cement concrete including fixing 2nos. 50mm dia HDPE pipe and providing and fixing of 15mm diameter B class GI pipe with check nuts for drainage of water, smoothening the top surface with cement, including excavation of hard surface/ bituminous concrete at the runway shoulder etc. complete as required.	72.00	Each	4300.00	309600.00	INR Three Lakh Nine Thousand Six Hundred Only
52	Installation of transformer housing box Collar (Item No.2) with a base concrete of 1:2:4 of size 600 mm diameter and 175mm height and all around concrete of 1 : 2 : 4, 150 mm thick, top sloped with 1:2:4 cement concrete including fixing 2nos. 50mm diameter HDPE pipe with check nuts for series AFL cable, smoothening the top surface with cement, including excavation of hard surface/ bituminous concrete at the runway shoulder etc. complete as required.	240.00	Each	3900.00	936000.00	INR Nine Lakh Thirty Six Thousand Only
53	Dismantling of Bi-directional/unidirectional, ELEVATED type of RUNWAY EDGE LIGHT/ TURNING PAD LIGHT/ THRESHOLD LIGHT/WING BAR LIGHT and its supporting pipe fitting etc. from the base plate, isolating transformers from transformer housing box after opening the base plate and M10 size SS/MS hardware etc., and stacking in AAI store.	305.00	Each	340.00	103700.00	INR One Lakh Three Thousand Seven Hundred Only
54	Dismantling of INSET type of RUNWAY EDGE LIGHT fitting etc., from the Runway surface including disconnection and removing its secondary lead of length up to 60 meters from the runway surface after properly removing the compound, making good the damages and stacking in AAI store.	27.00	Each	4300.00	116100.00	INR One Lakh Sixteen Thousand One Hundred Only
55	Re-Installation of Bi-directional/unidirectional, ELEVATED type of RUNWAY EDGE LIGHT/ TURNING PAD LIGHT/ WING BAR LIGHT etc., complete fittings on the existing base plate, installation of isolation transformer, interconnection, testing, commissioning including thoroughly cleaning the fixtures and its accessories, before installation i/c providing extension support pipe of cast aluminum/aluminum of 65 mm diameter size to raise the height of elevated Approach light to match with the new central runway surface etc. as required.	269.00	Each	1600.00	430400.00	INR Four Lakh Thirty Thousand Four Hundred Only
56	Re-installation of Bi-directional/unidirectional, INSET type of RUNWAY EDGE/THRESHOLD light fittings , installation of isolating transformer, interconnection, testing, commissioning including thoroughly cleaning the fixtures and its accessories before installation laying of secondary lead in length up to 50 mtrs. including core/groove cutting of the hard standing and fixing the fitting using quick setting sealant compound etc. complete as required.	72.00	Each	5200.00	374400.00	INR Three Lakh Seventy Four Thousand Four Hundred Only
57	Earthing with G.I pipe of 4.5 meters long x 40 mm diameter i/c accessories and providing masonry enclosures with cover plate having locking arrangement, watering pipes etc., including charcoal or coke and salt complete as required.	25.00	Each	6300.00	157500.00	INR One Lakh Fifty Seven Thousand Five Hundred Only
58	Providing and fixing 6 SWG GI wire along with cable for loop earthing as required.	27000.00	Metre	36.00	972000.00	INR Nine Lakh Seventy Two
59	Supply and laying for Earth connection from earth electrode with 6 SWG GI wire in 15 mm diameter G.I pipe (Class-B) etc., as required.	100.00	Metre	430.00	43000.00	INR Forty Three Thousand Only
60	Supply of 160mm size HDPE pipe including all accessories such as couplers, end cap etc in accordance with IS- 4984 - 1995 as amended upto date (PE80, PN10) complete as required.	1344.00	Metre	1980.00	2661120.00	INR Twenty Six Lakh Sixty One Thousand One Hundred & Twenty
61	Making horizontal boring with all terrain horizontal directional drilling, digging machine at a depth of minimum 1.2 meter or as per site condition and Civil Aviation Requirement (CAR) and laying of 160 mm size of HDPE pipe.	1344.00	Metre	1800.00	2419200.00	INR Twenty Four Lakh Nineteen Thousand Two Hundred Only
62	Laying of cable size upto 11 kV, 120 sqmm. in the existing horizontal bore HDPE pipe	1344.00	Metre	97.00	130368.00	INR One Lakh Thirty Thousand
63	Construction of Chamber for having clear size of 600mmX600mmX1000mm deep including excavation, 1:4:8 cement concrete bed, 1:2:4 reinforcement cement concret for cover slab with 10mm steel bars, plastering, Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 complete for crossing of Runway cable.	30.00	Each	11500.00	345000.00	INR Three Lakh Forty Five Thousand Only

For Shiva Buildtech Pvt. Ltd.

Director

CO13

स-सहायक (अभि-निर्देश) उत्तरी पूर्वी क्षेत्र, नि.उ.
 Dy. General Manager (Engg.-Civil), NER-CHQ.
 भारतीय विमानतंत्र प्राधिकरण / Airports Authority of India
 नई दिल्ली / New Delhi

64	Supply of 1 x 6 Sq. mm 5 KV grade single core, multistranded annealed plain copper conductor, underground, unscreened, unarmoured XLPE insulated and PVC outer sheathed, anti-rodent and anti-termite treated Airfield Lighting Cable generally conforming to IS 7098 Part II with up to date amendments etc. complete as required.	2500.00	Metre	90.00	225000.00	INR Two Lakh Twenty Five Thousand Only
65	Supply of 5 KV grade, 6 sq. mm size plug and receptacle of type I class "B" connector suitable for field attachment with 5 KV grade of PVC/XLPE insulated PVC sheathed single core copper conductor Airfield Lighting cable conforming to the relevant IS specification etc. complete as required.	40.00	Each	1150.00	46000.00	INR Forty Six Thousand Only
66	Supply of following type 5 KV grade 50Hz series type Isolating Transformers, encapsulated in polyester resin finally moulded in neoprene type rubber with primary & secondary connections and ready to install etc. complete as required. a) 200W 6.6A/6.6Amp 5KV Grade Isolating Transformer	40.00	Each	45000.00	1800000.00	INR Eighteen Lakh Only
67	Supply and Installation of suitable size MS Junction Box of Size 300(L)X300(H)X200mm(W) with provision for 2 nos cable entry/exit, alongwith 2 nos 5 KV grade fuse base with copper Link for incoming & outgoing cable (upto 1 x 16 Sqmm) with copper lugs. The base of the box to be fixed with 2feet 40mm GI pipe complete as required as per the site condition.	10.00	Set	2500.00	25000.00	INR Twenty Five Thousand Only
68	Supply of elevated type LED fitting suitable for taxiway, apron edge light for operation at 20/6.6 Amp series supply, complete with omnidirectional blue lens (Glass), lens clamping mechanism, breakable coupling, gasket, 2-pin lead, base plate with 06 nos. M 10 stainless steel bolts and other accessories including LED with an integrated encapsulated electronic converter of power consumption approx 7 watt, complete fitting conforming to latest ICAO requirement.	120.00	Each	520.00	62400.00	INR Sixty Two Thousand Four Hundred Only
Total in Figures					682782676.00	INR Sixty Eight Crore Twenty Seven Lakh Eighty Two Thousand Six Hundred & Seventy
Quoted Rate in Words		INR Sixty Eight Crore Twenty Seven Lakh Eighty Two Thousand Six Hundred & Seventy Six Only				

For Shiva Buildtech Pvt. Ltd.

0014

उप-प्रमुख (अभि-निर्देश) उत्तरी पूर्वी क्षेत्र, वि.पु.
Dy. General Manager (Engg.-Civil), NER-CHO.
भारतीय विमानतट प्राधिकरण/Airports Authority of India
नई दिल्ली/New Delhi

(सु)