

JUSTIFICATION STATEMENT

Name of work : Construction of temporary Barrack for APSP staff at Vijayawada Airport

S.No	Description	Unit	Qty	Justified Rate	Justified Amount	DSR 2021
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. A) All kinds of soil.	Cum	139.86	386.34	54,033.51	2.8.1
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	139.86	206.00	28,811.16	2.25
3	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked materials. All kinds of soil	Cum	19.04	84.70	1,612.69	2.26.1
4	Supplying and filling in plinth with River sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	38.19	1604.90	61,291.13	2.27
5	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m.	Sqm	18526.00	22.80	422,392.80	2.28.1
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	Cum	43.81	4829.10	211,562.87	4.1.10
7	Centering and shuttering including strutting, propping etc. and removal of form for all heights : a) Foundations, footings, bases of columns, etc. for mass concrete.	Sqm	47.52	268.80	12,773.38	5.9.1
8	Centering and shuttering including strutting, propping etc. and removal of form for all heights : A) Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	26.90	537.00	14,445.30	5.9.5
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. a) Thermo-Mechanically Treated bars.	Kgs	2086.00	100.60	209,851.60	5.22.6
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. a) Thermo-Mechanically Treated bars.	Kgs	481.60	100.60	48,448.96	5.22A.6
11	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	14.90	8,379.50	124,854.55	5.1.2

[Signature]
10/04/2023
Aqm

[Signature]
10/04/2023
Aqm 4 Justification statement

[Signature]
10/04/2023

JUSTIFICATION STATEMENT

Name of work : Construction of temporary Barrack for APSP staff at Vijayawada Airport

S.No	Description	Unit	Qty	Justified Rate	Justified Amount	DSR 2021
12	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	3.44	9723.00	33,447.12	5.2.2
13	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 5 average compressive strength in super structure above plinth level up to floor V level in : A)Cement mortar 1:6 (1 cement : 6 Coarse sand)	Cum	34.77	8388.22	291,658.41	6.34.2
14	Providing and fixing factory made uPVC white colour casement/casement cum fixed glazed windows comprising of uPVC multi-chambered frame, sash and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), uPVC extruded glazing beads of appropriate dimension, EPDM gasket, stainless steel (SS 304 grade) friction hinges, zinc alloy (white powder coated) casement handles, G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessar stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Note: For uPVC frame, sash and mullion extruded profiles minus 5% tolerancein dimension i.e. in depth & width of profile shall be acceptable Casement window double panels with top fixed with S.S. friction hinges (350 x 19 x 1.9 mm) made of (small series) frame 47 x 50 mm, sash 47 x 68 mm & mullion 47 x 68 mm all having wall thickness of 1.9 ± 0.2 mm and single glazing bead of appropriate dimension. (Area of window upto 2.50 sqm).	Sqm	18.75	6403.90	120,073.13	9.147A.3

[Signature]
10/04/2023

[Signature]
10/04/2023
Justification statement

[Signature]
10/04/2023

JUSTIFICATION STATEMENT

Name of work : Construction of temporary Barrack for APSP staff at Vijayawada Airport

S.No	Description	Unit	Qty	Justified Rate	Justified Amount	DSR 2021
15	Providing and fixing factory made uPVC white colour casement/casement cum fixed glazed windows comprising of uPVC multi-chambered frame, sash and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), uPVC extruded glazing beads of appropriate dimension, EPDM gasket, stainless steel (SS 304 grade) friction hinges, zinc alloy (white powder coated) casement handles, G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessar stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Note: For uPVC frame, sash and mullion extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Casement cum fixed panel window having both end single casement panel, middle fixed panels and at top completely fixed ventilator with S.S friction hinges (350 x 19 x 1.9) made of (big series) frame 67 x 60 mm , sash 67 x 80 mm & mullion 67 x 80 mm all having wall thickness of 2.3 ± 0.2 mm and single glazing bead/double glazing bead of appropriate dimension. (Area of window above 3.00 sqm upto 5.00 sqm).	Sqm	18.75	7143.50	133,940.63	9.147A.6

[Signature]
10/04/2023

[Signature]
10/04/2023

[Signature]
10/04/2023

JUSTIFICATION STATEMENT

Name of work : Construction of temporary Barrack for APSP staff at Vijayawada Airport

S.No	Description	Unit	Qty	Justified Rate	Justified Amount	DSR 2021
16	Providing and fixing factory made uPVC white colour casement/ Casement cum fixed glazed door comprising of uPVC multi-chambered frame,sash and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), uPVC extruded glazing beads of appropriate dimension, EPDM gasket, zinc alloy (white powder coated) 3D hinges and one handle on each side of panels along with zinc plated mild steel multi point locking having transmission gear, cylinder with keeps and one side key, G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws, etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Note: For uPVC frame, sash and mullion extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Casement door with top hung ventilator with 3D and S.S. friction hinges (400 x 19 x 1.9 mm) made of (big series) frame 67 x 64 mm, sash 67 x 110 mm & mullion 67 x 80 mm all having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension.(Area of door upto 2.50 sqm)	Sqm	5.04	9180.80	46,271.23	9.147C.2
17	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kgs	602.88	110.00	66,316.80	10.2
18	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	Kgs	4007.25	155.60	623,528.10	10.16.1

H. Lakshmi
10/04/2023
Agm

Amul
10/04/2023
Agm

[Signature]
10/04/2023

Justification statement

JUSTIFICATION STATEMENT

Name of work : Construction of temporary Barrack for APSP staff at Vijayawada Airport

S.No	Description	Unit	Qty	Justified Rate	Justified Amount	DSR 2021
19	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete	Kgs	120.00	105.30	12,636.00	10.19
20	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on bOHT side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	165.00	711.30	117,364.50	12.50
21	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. 12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part I and laminated with white 0.16mm thick fire retardant PVC film on the face side and 12micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit.	Sqm	127.71	1454.70	185,779.74	12.52.3
22	12 mm cement plaster of mix : A)1:6 (1 cement: 6 fine sand)	Sqm	146.28	241.70	35,355.88	13.1.2

[Signature]
10/04/2023
Aa m c

[Signature]
10/04/2023
Aa m c

Justification statement

[Signature]
10/04/2023

JUSTIFICATION STATEMENT

Name of work : Construction of temporary Barrack for APSP staff at Vijayawada Airport

S.No	Description	Unit	Qty	Justified Rate	Justified Amount	DSR 2021
23	15 mm cement plaster of mix : A)1:6 (1 cement: 6 fine sand)	Sqm	165.18	279.00	46,085.22	13.2.2
24	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Sqm	165.18	117.00	19,326.06	13.46.1
25	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	Sqm	100.00	120.00	12,000.00	13.61.1
26	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	146.28	124.00	18,138.72	13.60.1
27	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	Sqm	127.71	547.23	69,886.74	11.3.1
28	Cement plaster skirting up to 30 cm height, with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement. 18 mm thick	Sqm	9.75	473.07	4,612.43	11.6.1
29	Providing and laying factory made chamfered edge Cement Concrete paver blocks In foot path, park & lawns driveway or light & traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of course sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, all complete as per manufacturer's specifications & direction of Engineerin- Charge. 60mm thick Cement concrete paver block of M-35 grade with approved colour, design & pattern.	Sqm	100.00	670.00	67,000.00	16.91.1
			895.00		3,093,498.66	

Total Justified Cost Civil works : 3,093,498.66
Total Justified Cost Electrical works : 429,300.00
3,522,798.66


10/04/2023
Manager (E-Civil)


10/04/2023
Asst. General Manager (E-Civil)


10/04/2023
Jt. General Manager (E-Civil)

AIRPORTS AUTHORITY OF INDIA
VIJAYAWADA INTERNATIONAL AIRPORT
JUSTIFICATION STATEMENT


Name of work: Construction of Temporary Barrack for APSP Staff at Vijayawada Airport
S.H: Electrical Work

Item No.	Description of Item	Qty	Unit	Rate (Rs. (Ex.GST))	Amount (Rs.) (Ex. GST)	Remark
1	Supply of 4 Core x 25 Sq.mm, XLPE insulated and PVC sheathed armoured aluminium conductor power cable of 1.1 KV grade conforming to IS 7098 (Part-1) with upto date ammendments etc., complete as required.	100	Mtr	321.00	32100.00	MR
2	Supplying and making end termination with brass double compression gland and aluminium lugs for 4C x 25 Sq.mm of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	2	Set	865.00	1730.00	MR
3	Supplying and laying of OD 40 mm dia., HDPE, PE63, PN-6 Pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 4984, complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. Note: Only required quantity of HDPE Pipe to be supplied and laid at site. If any balance pipe is available after laying and same shall be taken back by agency. Payment will be made as actual utilization at site. Nothing will be paid extra.	80	Mtr	193.00	15440.00	MR
4	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL/DWC/HDPE pipe as required. Upto 35 sq. mm	80	Mtr	30.00	2400.00	MR
5	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq. mm (clamped with 1mm thick saddle)	10	Mtr	47.00	470.00	MR
6	Supplying and fixing of 8 way (4 + 24), Double door surface / recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) as required	1	Each	12183.00	12183.00	MR
7	Supplying and fixing of 63A, four pole, 415 V, miniature circuit breaker in the existing MCB DB complete with connections, testing and commissioning etc. as required.	1	Each	2047.00	2047.00	MR
8	Supplying and fixing of 63A, 300mA, Four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current 300 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.	1	Each	3389.00	3389.00	MR
9	Supplying and fixing 6 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required Single pole	24	Each	249.00	5976.00	MR
10	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	2	Each	6274.00	12548.00	MR

[Signature]
10/4/23
MURUGAN

[Signature]
SMR-E)
10-04-2023


Item No.	Description of Item	Qty	Unit	Rate (Rs. (Ex.GST))	Amount (Rs.) (Ex. GST)	Remark
11	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required.	60	Mtr	42.00	2520.00	MR
12	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	20	Mtr	59.00	1180.00	MR
13	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group B	20	Point	1154.00	23080.00	MR
14	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed PVC conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. Group B	10	Point	688.00	6880.00	MR
15	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	150	Mtr	262.00	39300.00	MR
16	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed medium class PVC conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	100	Mtr	325.00	32500.00	MR
17	Supplying and fixing following size / modules, GI box of 1.2mm Thick alongwith modular base & cover plate for modular switches in recess etc. as required.					
17.1	4 Module (125mmX75mm)	10	Each	534.00	5340.00	MR
17.2	6 Module (200mmX75mm)	4	Each	572.00	2288.00	MR
17.3	8 /9 Module (125mmX125mm)	12	Each	683.00	8196.00	MR
18	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
18.1	5/6 A switch	14	Each	108.00	1512.00	MR
18.2	15/16 A switch	16	Each	179.00	2864.00	MR
18.3	3 pin 5/6 A socket outlet	14	Each	153.00	2142.00	MR
18.4	6 pin 15/16 A socket outlet	16	Each	245.00	3920.00	MR
19	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required	10	Each	451.00	4510.00	MR
20	Supply of 36W, recessed mounted, beautifully designed full glow high efficiency LED 2'X2' luminaries with CRCA steel sheet housing with high transitive diffuser with comfortable experience through its classic design and glare free soft illumination including electronic driver with operating voltage range (120 - 270V AC) and with colour temperature 5700K range. LED having with minimum 70% lumen maintenance. System consumption should be 36W full glow fixture with minimum lumen package of 3600 lumens	15	Each	3877.00	58155.00	MR



 10/12/23
 10-04-2023
 (MIE-15)

Item No.	Description of Item	Qty	Unit	Rate (Rs. (Ex.GST))	Amount (Rs.) (Ex. GST)	Remark
21	Supply of 20W, 4 feet, Energy efficient, surface mounting, batten type LED luminaries with aluminium housing and integrated electronic driver with operating voltage range (120 - 270V AC) with colour temperature 5700K range. LED having minimum 20,000 burning hours with minimum 70% lumen maintained, system consumption should be less than 20W and especially designed for commercial use etc., complete as required.	34	Each	820.00	27880.00	MR
22	Supply of LED Street light fitting with wattage of 45W with high power LEDs, system efficacy not less than 110 lumen/watt, suitable optics for uniform light distribution, integral control driver with minimum 3kV surge suppressor, fitting made up of high pressure die-cast aluminium housing with suitable thermal management arrangement, toughened glass with IP 65 protection, suitable to operate on single phase AC supply, inline with technical specifications etc., complete as required.	16	Each	3728.00	59648.00	MR
23	Supply of 1200mm Sweep, High speed, 230 m3/min air delivery, ceiling fan complete with fan blades, top and bottom canopy with all accessories suitable for operation on 230V AC supply etc., as required.	15	Each	3056.00	45840.00	MR
24	Supply and fixing of wrinkle free bend, 40mm dia., 1.5 Meter length, Medium class GI Pipe with all arrangement for fixing of pipe on wall surface / GI Pole suitable for installation of LED Street light fitting. Job include fabrication, pipe cutting, bending, welding etc. complete as per site requirement.	6	Job	701.00	4206.00	MR
25	Installation testing commissioning of all type of LED luminaries, ceiling fans, exhaust fans, wall fans etc., including all necessary accessories / clamp / washers / metal chain on recess / surface / wall bracket / Wall mounted of height up to 5 mtrs etc., as required.	40	Each	100.00	4000.00	MR
26	Supplying and fixing extra down rod for ceiling fan of 100 cm length G.I. pipe, 15 mm dia, heavy gauge including, clamps, nuts, bolts, weldings, painting, etc. as required. (Note : Item execute as on need requirement)	10	Job	271.00	2710.00	MR
27	Supplying and fixing Cable End Box (Loose Wire Box) suitable for following triple pole and neutral, sheet steel, MCB distribution board, 415 Volts, on surface/ recess, complete with testing and commissioning etc.as required For 8 way, Double door TPN MCBDB	2	Each	1173.00	2346.00	MR
Total (A) Rs.					429,300.00	

(Rupees Four Lacs Twenty Nine Thousand and Three Hundred Only)

Jr. Executive (Engg-E)
AAI, Vijayawada Airport


Manager (Engg-E)
AAI, Vijayawada Airport


Senior Manager (Engg-E) 10-04-23
AAI, Vijayawada Airport


Joint General Manager (Engg-E)
AAI, Vijayawada Airport