



सं. संख्या : भाविप्रा/कोल्हापूर/(अभि-वी)/जी.एल.एफ/2023-24/ 02/290 दिनांक: 16.05.2023

सेवा में,
 में, टेक्नो इलेक्ट्रिकल्स
 इलेक्ट्रिकल इंजीनियर अंड कांटेक्टर्स,
 2/65, उदय पार्क सोसाइटी, रिफाइनरी रोड, गोरवा,
 वडोदरा -16।

To,
 M/s. Techno Electricals
 Electrical Engineers & Contractors,
 2/65, Uday Park Society, Refinery Road,
 Gorwa, Vadodara -16.

Name of work: "Extension of Runway with Blast pad, RESA, Taxiway Apron, GSE Area, Isolation Bay, New Domestic Terminal Building and Miscellaneous works at Kolhapur Airport."

Sh: Shifting of GLF system for existing CCR to New CCR, connection to the new ATC Tower -Associated Electrical works.

संदर्भ/Ref.: 1) आपका ई-टेंडर आय डी: 2023_AAI_150227_1, वित्तीय बीड दिनांक: 27.04.2023 को खोला गया |

Your e-tender ID 2023_AAI_150227_1, Financial Bid Opened on 27.04.2023.

महोदय/ Dear Sir,

- ऊपर उल्लेखित कार्य हेतु आपका टेंडर अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपके द्वारा बताए गए मद मूल्यों पर आपकी टेंडर राशि जीएसटी रहित कुल रु.1,50,17,738.00 (रुपये एक करोड़ पचास लाख सत्रह हजार सात सौ अड़तीस मात्र) है जो कि टेंडर की अनुमानित लागत राशि रु. 2,13,14,149 से 29.54% नीचे है |
- Your tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you Excluding GST totaling to **Rs. 1,50,17,738.00 (Rupees One Crore Fifty Lakh Seventeen Thousand Seven Hundred and Thirty-Eight Only)** which is 29.54% below the estimated cost put to tender of **Rs. 2,13,14,149.00**
- उप महाप्रबंधक, अभि (विद्युत), भा वि प्रा, कोल्हापूर हवाई अड्डा कार्य के प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप आपकी ओर से एक विश्वसनीय प्रतिनिधि नियुक्ति करें जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 25.05.2023 तक सहायक महाप्रबंधक, अभि(विद्युत), कोल्हापूर एयरपोर्ट के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु. 100/- गैर न्यायिक स्टैम्प पेपर पर निष्पादित किया जाएगा तथा पेपर का खर्च आपके द्वारा उठाया जायगा |
- Dy. General Manager (Engg-E), AAI, Kolhapur Airport shall be the Engineer-In-Charge of the work. You are requested to depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend the office of the Asst. General Manager (Engg-E), AAI, Kolhapur Airport by 25.05.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs. 100/- (Rupees One hundred only)** and the cost of the stamp paper shall be borne by you.

Contd....P/2

बिद्युत रॉय / Bidyut Roy

सहा. महाप्रबंधक (अभि.विद्युत)

Asst. Gen. Manager (Engg-E)

भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
 A. A. I. Kolhapur Airport, Kolhapur

3. आपके टेंडर के साथ प्राप्त धरोदर राशि रु. 4,26,283.00 (रुपये चार लाख छब्बीस हजार दो सौ तिरासी मात्र) ठेके के दस्तावेज़ के GCC: 16 पर दी गई शर्त 1 (ए) के अनुसार जमानत राशि में परिवर्तित कर दी गई है। कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर जमानत राशि की बकाया राशि रु. 15,01,773.00 (रु. पंद्रह लाख एक हजार सात सौ तिहत्तर मात्र) यह कार्य आदेश जारी होने की तिथि से 10 दिनों के भीतर अदा की जाए अन्यथा ठेके के दस्तावेज़ के GCC: 16 पर दी गई शर्त 1(ए) के अनुसार उक्त राशि रनिंग बिल से कटौती की जाएगी।
3. The earnest money amount of Rs. 4,26,283.00 (Rupees Four Lakh Twenty Six Thousand Two Hundred and Eighty Three Only) received along with your tender will be treated and converted as part of security deposit as per clause 1(A) on page GCC-16 of tender document. Please deposit Rs. 15,01,773.00 (Rupees Fifteen Lakh One Thousand Seven Hundred and Seventy Three Only) towards security deposit within 10 days from the date of issue of this letter, failing which the same shall be deducted from your running bill as per condition 1(A) on GCC: page 16 of the contract document.
4. आपसे निवेदन है कि आप केंद्रीय और राज्य सरकारों 1970 के अधिनियम अनुबंध श्रम नियम तथा 1971 के केंद्रीय नियम (नियमन तथा उन्मूलन) एवं केंद्र तथा राज्य सरकार के न्यूनतम वेतन अधिनियम और नियमों के प्रावधान का अनुपालन करें।
4. You are requested to comply with the provisions of contract labour (Regulation and abolition) Act of 1970 and contract labour (Regulation & abolition) Central rules 1971 and minimum wages Act & rules thereof central and state Governments.
5. आपको निर्देश दिया जाता है कि आप तुरंत सहा. महाप्रबंधक (अभि-विद्युत), भाविप्रा, कोल्हापूर हवाईअड्डा से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे।
5. You are also directed to Contact Asst. General Manager (Engg-E), AAI, Kolhapur Airport immediately who will arrange to hand over the site to you.
6. कृपया नोट कर लें कि काम पूर्ण करने का अवधि दो (02) माह है जोकि इस पत्र के जारी करने के बाद दसवे दिन से गिना जायगा।
6. Please note that the time allowed for carrying out the work is **Two (2) Months**, which shall be reckoned from the tenth day after the date of issue of this letter.
7. इस ठेके के संबंध में आगे का कोई भी पत्राचार उप. महाप्रबंधक (अभि-विद्युत), भाविप्रा, कोल्हापूर हवाईअड्डा के पते पर किया जाए।
7. Any further correspondence in connection with the contract should normally be addressed to the Dy. General Manager (Engg-E), AAI, Kolhapur Airport.
8. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।
8. All the letters referred above shall form part of the contract.
9. पत्र को स्वीकार करने के पश्चात नकल प्रति पर हस्ताक्षर करके टोकन के रूप में पुनः भेज दें।
9. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.

Bidyut Roy 16-5-23
बिद्युत रॉय / Bidyut Roy

सहा. महाप्रबंधक (अभि.विद्युत)

Asst. Gen. Manager (Engg-E)

भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
A. A. I. Kolhapur Airport, Kolhapur

Contd...P/3

- 10 यदि अँग्रेजी और हिन्दी पाठ मे कोई अंतर पाया जाता है तो अँग्रेजी विवरण सही माना जाएगा।
10. If there is any discrepancy between English and Hindi then meaning derived in English will be given precedence.

धन्यवाद / Thanking You,

भवदीय / Yours faithfully,

Bidyut Roy
16.5.23

सहा. महाप्रबंधक (अभि-विद्युत)/ Asst. General Manager (Engg-E),
कृते तथा ओर से, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण,
For and on behalf of Chairman,
Airports Authority of India.

संलग्न/Encl: Schedule of Quantity

बिद्युत रॉय / Bidyut Roy
सहा. महाप्रबंधक (अभि.विद्युत)
Asst. Gen. Manager (Engg-E)
भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
A. A. I. Kolhapur Airport, Kolhapur

Name of Work: Extension of Runway with Blast pad, RESA, Taxiway apron, GSE Area, Isolation Bay, New Domestic Terminal Building and miscellaneous works at Kolhapur Airport.
SH : Shifting of GLF system for existing CCR to New CCR room, connection to the new ATC Tower - Associated Electrical works.


PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST	TOTAL AMOUNT In Words(Excluding GST)
1	2	4	5	12	13	53	55
1	Supply of 2.5 sq.mm 61 core armoured 650/ 1100V grade copper control cable XLPE insulated as per IS 7098 (Part-I) with ammendments up to date for Remote control panel etc complete as required.	2400	Meter	INR	1620.00	3888000.00	INR Thirty Eight Lakh Eighty Eight Thousand Only
2	Supply of 2.5 sq.mm 10 core armoured 650/ 1100V grade copper control cable XLPE insulated as per IS 7098 (Part-I) with ammendments up to date for Remote control panel etc complete as required.	600	Meter	INR	300.00	180000.00	INR One Lakh Eighty Thousand Only
3	Supply of 6 sqmm. PVC insulated & PVC Sheathed Stranded copper conductor single core airfield lighting cable of 5KV grade confirming to IS 1554 Part-II with upto date amendement s as required and conforming to particuar specifications.	14640	Meter	INR	100.00	1464000.00	INR Fourteen Lakh Sixty Four Thousand Only
4	Supply of 16 sqmm. PVC insulated & PVC Sheathed Stranded copper conductor single core airfield lighting cable of 5KV grade confirming to IS 1554 Part-II with upto date amendement s as required and conforming to particuar specifications.	14400	Meter	INR	190.00	2736000.00	INR Twenty Seven Lakh Thirty Six Thousand Only
5	Supply of 2 x 4 sq.mm size secondary lead made out of multi stranded copper conductor, EPR insulated PCP sheathed, treated 600V grade cable as specified in particular specification and as required.	400	Meter	INR	160.00	64000.00	INR Sixty Four Thousand Only
6	Supply of following sizes of XLPE insulated PVC sheathed, Aluminium conductor armoured power cable of 1.1 KV grade conforming to IS 7098 (Part 2) amended upto date : a) 3.5 X 25Sq.mm Aluminium conductor cable	2700	Meter	INR	139.00	375300.00	INR Three Lakh Seventy Five Thousand Three Hundred Only
7	Supply of following sizes of XLPE insulated PVC sheathed, Aluminium conductor armoured power cable of 1.1 KV grade conforming to IS 7098 (Part 2) amended upto date : a) 3.5 X 95Sq.mm Aluminium conductor cable	200	Meter	INR	410.00	82000.00	INR Eighty Two Thousand Only
8	Supply of following sizes of XLPE insulated PVC sheathed, Aluminium conductor armoured power cable of 1.1 KV grade conforming to IS 7098 (Part 2) amended upto date : a) 4C X 6Sq.mm Aluminium conductor cable	300	Meter	INR	90.00	27000.00	INR Twenty Seven Thousand Only
9	Supplying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete as required. 63 mm Dia	17420	Meter	INR	63.00	1097460.00	INR Ten Lakh Ninety Seven Thousand Four Hundred & Sixty Only

16.5.23
बिद्युत राय / Bidyut Roy
सहा. महाप्रबंधक (अभि.विद्युत)
Asst. Gen. Manager (Engg-E)
भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST	TOTAL AMOUNT In Words(Excluding GST)
1	2	4	5	12	13	53	55
10	Supplying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete as required. 100 mm Dia	4000	Meter	INR	125.00	500000.00	INR Five Lakh Only
11	Laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (80 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63 mm dia	17420	Meter	INR	95.00	1654900.00	INR Sixteen Lakh Fifty Four Thousand Nine Hundred Only
12	Laying of following size DWC HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc. direct in ground (80 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 100 mm dia	4000	Meter	INR	95.00	380000.00	INR Three Lakh Eighty Thousand Only
13	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipes as required. Upto 35 sq. mm	31740	Meter	INR	19.00	603060.00	INR Six Lakh Three Thousand & Sixty Only
14	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipes as required. Above 35 sq. mm and up to 95 sq. mm	200	Meter	INR	35.00	7000.00	INR Seven Thousand Only
15	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing RCC/ HUME/ METAL pipe as required. (for control cable of 61 core) Above 95 sq. mm and up to 185 sq. mm	4000	Meter	INR	60.00	240000.00	INR Two Lakh Forty Thousand Only
16	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required Upto 35 sq. mm (clamped with 1mm thick saddle)	300	Meter	INR	30.00	9000.00	INR Nine Thousand Only
17	Kerfs cutting with machine in runway / taxiway of bituminous surface of suitable depth and width for secondary cable, laying of cable, and refilling the same with cement mortar and finishing with sealant material etc complete as required.	400	Meter	INR	450.00	180000.00	INR One Lakh Eighty Thousand Only
18	Earthing with G.I. earth pipe 4.5 meter long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/coke and salt as required.	17	Job	INR	8000.00	136000.00	INR One Lakh Thirty Six Thousand Only

बिद्युत रॉय / Bidyut Roy
 सहा. महाप्रबंधक (अभि. विद्युत)
 Asst. Gen. Manager (Engg-E)
 भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
 Kolhapur

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST	TOTAL AMOUNT In Words(Excluding GST)
1	2	4	5	12	13	53	55
19	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing cable as required	17420	Meter	INR	27.00	470340.00	INR Four Lakh Seventy Thousand Three Hundred & Forty Only
20	Supply of 5 KV, Cu grade plug and receptacle of type I class "B" connector suitable for field attachment with 5 KV grade PVC insulated PVC sheathed single core 6 Sq.mm copper conductor cable conforming to the relevant IS specification etc. complete as required	60	Nos	INR	450.00	27000.00	INR Twenty Seven Thousand Only
21	Supply of 5 KV, Cu grade plug and receptacle of type I class "B" connector suitable for field attachment with 5 KV grade PVC insulated PVC sheathed single core 16 Sq.mm copper conductor cable conforming to the relevant IS specification etc. complete as	50	Nos	INR	450.00	22500.00	INR Twenty Two Thousand Five Hundred Only
22	Supply of 600 V grade plug and receptacle of type II, class 'B' connector and suitable field attachment with EPR insulated, PCP sheathed, two core copper conductor secondary cable 4 sq.mm as required.	20	Nos	INR	550.00	11000.00	INR Eleven Thousand Only
23	Making field connections by crimping 6 Sq.mm or 16Sq.mm plug and receptacle with existing single core PVC copper conductor PVC insulated, PVC sheathed cable/XLPE cable including filling the gap with water sealing compound, applying HT insulation tape, over which PVC tape etc. as required	130	Job	INR	100.00	13000.00	INR Thirteen Thousand Only
24	Supplying and making cable route marker with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) of size 60 cm X 60 cm at the bottom and 50 cm X 50 cm at the top with a thickness of 10cm including inscription duly engraved as required.	231	Job	INR	350.00	80850.00	INR Eighty Thousand Eight Hundred & Fifty Only
25	Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.	80	Job	INR	450.00	36000.00	INR Thirty Six Thousand Only
26	Supply installation of FRP fully weather protected outdoor feeder box (IP65) having a cable entry of minimum 35 Sq. mm with TPN 40A 25 KVA MCCB as required. (for WDI LDI cable joint)	2	Job	INR	10000.00	20000.00	INR Twenty Thousand Only
27	Supply of 15 Watts 6.6/6.6 Amps 5KV grade 50 Hz series type isolating transformer conforming to relevant IS, encapsulated in polyster resin finally moulded with neoprene type rubber with primary & secondary connections as specified in particular specifications complete as required.	15	Nos	INR	3000.00	45000.00	INR Forty Five Thousand Only



 बिद्युत रॉय / Bidyut Roy
 सहा. महाप्रबंधक (अभि.विद्युत)
 Asst. Gen. Manager (Engg-E)
 भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
 A. A. I. Kolhapur Airport, Kolhapur

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST	TOTAL AMOUNT In Words(Excluding GST)
1	2	4	5	12	13	53	55
28	Supply of cast iron isolating Transformer housing box, water tight round type, metal container of outside size 330 mm dia, height 450 mm made of 10 mm thick cast iron moulding all round, except the top surface, which is 15 mm thick, cast iron moulding suitable to receive a light fitting base plate on the top and underground housing associated with transformer, power cable and having two holes opposite as per site requirement at the periphery, centre 75 mm above bottom surface suitable to receive 50 mm dia HDPE/medium class G.I pipe and one no of suitable hole to receive 15mm B class G.I pipe for loop earthing as required as required. The box should have two SS earh bolts of M10x40 mm tapped inside near the hole (4" away from hole centre) and having drain hole at the bottom suitably tapped to receive 15mm dia GI pipe and having clear opening of 220 mm at the top surface and 06 Nos. M10 tapped hole having centre to centre distance of 260mm alongwith bolts as required as per the drawings. Double Hole CI Housing Box	12	Nos	INR	5400.00	64800.00	INR Sixty Four Thousand Eight Hundred Only
29	Installation of Transformer Housing Box with a base concrete of 1:3:6 of size 630x630x100mm thick all round concrete of 1:2:4, 150mm thick, the top sloppedd with 1:2:4 cement concrete including providing and fixing 250mm long 15mm dia. "B" class GI pipe with check nut for drainage of water including excavation of side shoulder and refilling etc. complete as required.	12	Job	INR	3000.00	36000.00	INR. Thirty Six Thousand Only
30	Supply of FAA and ICAO complied inset type Omni directional 8" dia, medium intensity LED Taxi light complete with vulcanised plug for connection to isolating transformer, lamp holder assembly, blue prism with stopper & gaskets, O-ring, washers, brass cable gland assembly, upper and lower cover etc and all other accessories complete as required complying with relevant FAA and ICAO standards.	6	Nos	INR	40000.00	240000.00	INR Two Lakh Forty Thousand Only
31	Supply of FAA and ICAO complied LED lamp& Driver assembly for Inset fitting taxi way light fitting complete as required.	2	Nos	INR	14000.00	28000.00	INR Twenty Eight Thousand Only
32	Inset fitting spares Prismatic Blue lens	2	Nos	INR	8500.00	17000.00	INR Seventeen Thousand Only
33	Installation testing commissioning of Remote control pannel Cum display unit at control tower suitable for remote operation of constant current regulators and comprise of the following including interconnections etc. With terminal block etc. complete as required.	1	Job	INR	15000.00	15000.00	INR Fifteen Thousand Only

Bidyut Roy
16.5.23

विद्युत रॉय / Bidyut Roy
सहा. महाप्रबंधक (अभि.विद्युत)
Asst. Gen. Manager (Engg-E)
भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
A. A. I. Kolhapur Airport, Kolhapur

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST	TOTAL AMOUNT In Words(Excluding GST)
1	2	4	5	12	13	53	55
34	Installation testing and commissioning of Crash siren (Horizontal Double mounting carbon brush less AC motor) along with wiring (Supply and Laying) with 2.5Sq.mm X 3 C FRLS copper cable on existing cable tray or Wall along with fixing of 10A DP MCB in industrial MCB Box including termination with proper lugs and installation of push siren button . suitable for operation at 240V 50 hz AC supply and audible range range should of 3 Km.	1	Job	INR	5000.00	5000.00	INR Five Thousand Only
35	Installation testing commissioning of Rotating beacon on top ATC tower with suitable civil foundation as per OEM specifications along with wiring (Supply and Laying) with 2.5Sq.mm X 3 C FRLS copper cable on existing cable tray or Wall along with fixing of 10A DP MCB in industrial MCB Box including termination with proper lugs etc as per specifications complete as required.	1	Job	INR	6528.00	6528.00	INR Six Thousand Five Hundred & Twenty Eight Only
36	Dismantalling, Shifting and re-installation of the following capacity microprocessor based CCR along with transportation from old power house to CCR room of new power house including securing and fixing with proper nut and bolts input and output cable connections , providing connection and required connector and other sundry items testing and comissioning etc. complete (reistallation at New CCR room includes required fabrication work like cutting of MS Chequered plate, making suitable frame with MS angle/ channel as required for installing CCR) as required. 4 kw	8	Job	INR	10000.00	80000.00	INR Eighty Thousand Only
37	Dismantalling, Shifting and re-installation of the following capacity microprocessor based CCR along with transportation from old power house to CCR room of new power house including securing and fixing with proper nut and bolts input and output cable connections , providing connection and required connector and other sundry items testing and comissioning etc. complete (reistallation at New CCR room includes required fabrication work like cutting of MS Chequered plate, making suitable frame with MS angle/ channel as required for installing CCR) as required. 7.5 kw	5	Job	INR	10000.00	50000.00	INR Fifty Thousand Only
38	Dismantalling, Shifting and re-installation of the following capacity microprocessor based CCR along with transportation from old power house to CCR room of new power house including securing and fixing with proper nut and bolts input and output cable connections , providing connection and required connector and other sundry items testing and comissioning etc. complete (reistallation at New CCR room includes required fabrication work like cutting of MS Chequered plate, making suitable frame with MS angle/ channel as required for installing CCR) as required. 20 Kw	3	Job	INR	10000.00	30000.00	INR Thirty Thousand Only


 बिद्युत रॉय / Bidyut Roy
 सहा. महाप्रबंधक (अभि.विद्युत)
 Asst. Gen. Manager (Engg-E)
 भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE(Excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Excluding GST	TOTAL AMOUNT In Words(Excluding GST)
1	2	4	5	12	13	53	55
39	Installation, Testing and Commissioning of inset fitting with core cutting, aligning and setting i/c providing sealing material and installation of Isolating Transformers, Crimping / Jointing of Plug receptacles, laying of secondary lead in existing GI pipe in groove i/c cutting and sealing of groove and other accessories required for commissioning i/c supply of all materials except fixture, secondary lead, plug and receptacles and isolating transformer etc. as required.	6	Job	INR	6000.00	36000.00	INR Thirty Six Thousand Only
40	Excavation of the cable trenches in hard rock not exceeding 1.5 metres in width, and lift upto 1.5 metres, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 metres.	50	CUM	INR	1200.00	60000.00	INR Sixty Thousand Only
Total in Figures						15017738.00	INR One Crore Fifty Lakh Seventeen Thousand Seven Hundred & Thirty Eight
Quoted Rate in Words		INR One Crore Fifty Lakh Seventeen Thousand Seven Hundred & Thirty Eight Only					

Bidyut Roy
16.5.23

बिद्युत रॉय / Bidyut Roy
सहा. महाप्रबंधक (अभि.विद्युत)
Asst. Gen. Manager (Engg-E)
भा. वि. प्रा. कोल्हापूर हवाई अड्डा, कोल्हापूर
A. A. I. Kolhapur Airport, Kolhapur