



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
बिरसी हवाई अड्डा, गोंदिया
BIRSI AIRPORT, GONDIA

WORK ORDER / कार्यादेश

संदर्भ सं. : भाविप्रा/गोंदिया/अभि-सि./2023/AMC(COLONY)/का.आ./ 152-161 दिनांक: 02/06/2023
Ref. No.: AAI/GONDIA/ENGG(C)/2023/AMC(COLONY)/WO/ Date : 02/06/2023

स्पीड पोस्ट / Speed Post

सेवा में/To,

मेसर्स विशाल चैनलाल मंडिया,
भटेरा रोड, बालाघाट अस्पताल के सामने,
बालाघाट (म.प्र.)- 481001

M/s. Vishal Chainlal Mandiya,
Bhatera Road, Infront of Balaghat Hospital,
Balaghat (M.P.) - 481001
Email : vishalmandiya1309@gmail.com

कार्य का नाम :- बिरसी हवाई अड्डा, गोंदिया पर भाविप्रा आवासीय कालोनी के वर्ष (2023-2024) के लिये सिविल कार्यों का वार्षिक अनुरक्षण अनुबंध ।

Name of work :- Annual maintenance contract of Civil works for AAI Residential Colony at Birsi Airport, Gondia (2023-24).

संदर्भ:- आपकी निविदा दिनांक 26/05/2023

Ref.- Your tender opened on 26/05/2023

महोदय/Sir,

- 1) उपर उल्लेखित कार्य हेतु आपकी ई-निविदा को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है, आपने डी.एस.आर. 2021 और अतिरिक्त विविध आइटम के प्रतिशत दर पर 58.01% (प्रतिशत) कोट किया है (जी.एस.टी. छोड़कर) जोकि डी.एस.आर. 2021 और अतिरिक्त विविध आइटम के अनुमानित प्रतिशत दर से 41.99% (प्रतिशत) नीचे है । इस कार्य की अनुमानित लागत राशि रु. 16,00,000/- (रुपये सोलह लाख, मात्र) (जी.एस.टी. छोड़कर) है ।
 - Your e-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the percentage rate quoted by you is 58.01% over the DSR 2021 and Additional Miscellaneous Items (excluding GST) which is 41.99% below the estimated percentage rate over DSR 2021 and Additional Miscellaneous Items. The total estimated cost for the work is Rs. 16,00,000/- (Rupees Sixteen Lakhs, Only) (excluding GST).
- 2) वरिष्ठ प्रबंधक (अभि- सि.), भाविप्रा, बिरसी हवाई अड्डा, गोंदिया इस कार्य के इंजीनियर-इन-चार्ज होंगे। आपसे निवेदन है कि आप दिनांक 26/06/2023 तक वरिष्ठ प्रबंधक (अभि-सि.), भाविप्रा, बिरसी हवाई अड्डा, गोंदिया के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करें। ठेके का करारनामा रु. 100/- के नोनज्युडिशियल स्टैम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा उठाया जाएगा ।
 - Sr. Manager (Engg-Civil), AAI, Birsi Airport, Gondia shall be Engineer-in-Charge of the work. You are requested to attend the office of Sr. Manager (Engg-Civil), AAI, Birsi Airport, Gondia by 26/06/2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One Hundred, only) and the cost of the stamp paper shall be borne by you.

 02/06/2023

जारी / Contd.....2

बिरसी, हवाई अड्डा, गोंदिया (महाराष्ट्र) - 441 601
Birsi Airport, Gondia (Maharashtra) - 441 601

एस.के.सिंह/S.K.Singh
व.प्र.(अभि-सिविल)/Sr. Manager (Engg.Civil)
भा.वि.प्रा./A.A.I.
बिरसी विमानपत्तन गोंदिया/Birsi Airport Gondia 441601



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
बिरसी हवाई अड्डा, गोंदिया
BIRSI AIRPORT, GONDIA

// 2 //

- 3) कृपया इस पत्र के जारी होने की तिथि से 10 दिनों के भीतर जमानत राशि रु. 1,60,000/- (रुपये एक लाख साठ हजार, मात्र) जमा करवायें, अन्यथा ठेके के दस्तावेज पृष्ठ Page 16 of GCC पर दी गई खण्ड 1 A के अनुसार वसूल किया जायेगा ।
- Please deposit Rs. 1,60,000/- (Rupees One Lakh Sixty Thousand, Only) towards security deposit within 10 days from the date of issue of this letter failing which, the same will be deducted as per condition of Clause no.1 A on Page 16 of GCC of the contract document.
- 4) आपसे अनुरोध है कि 1970 के श्रम अनुबंध (विनियमन और उन्मूलन) एवं 1971 के केंद्रीय नियम श्रम अनुबंध (विनियमन और उन्मूलन), 1986 के बाल श्रम (निषेध और विनियमन), 1996 के निर्माण श्रमिक (रोजगार और सेवा की शर्त का विनियमन), 1996 के बिल्डिंग एवं संविदा की सामान्य शर्त खण्ड 19 पृष्ठ क्रमांक 49 में निर्दिष्ट अन्य निर्माण श्रमिक कल्याण सेस अधिनियम एवं केन्द्रीय और राज्य सरकारों के नियमों का अनुपालन करें ।
- You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act of 1970 and Contract Labour (Regulation and Abolition) Central Rules 1971 and Minimum wages act and rules thereof of Central and State Government.
- 5) आपको निर्देश दिया जाता है कि आप तुरंत वरि.प्रबंधक (अभि-सि.), भाविप्रा, बिरसी हवाई अड्डा, गोंदिया से मिलें, वही आपको साइट सौंपने की व्यवस्था करेंगे ।
- You are also directed to contact Sr. Manager (Engg-Civil), AAI, Birsi Airport, Gondia immediately who will arrange to hand over the site to you.
- 6) कृपया नोट कर लें कि काम करने का अनुमत समय 12 (बारह) महीने हैं जोकि इस पत्र के जारी करने के दसवे दिन से गिना जाएगा ।
- Please note that the time allowed for carrying out the work shall be 12 (Twelve) months and same shall be reckoned from the 10th day after the date of issue of this letter.
- 7) उपरोक्त सदभित सभी पत्र इस ठेके का भाग होंगे ।
- The letters under reference shall be part of agreement.
- 8) इस ठेके के संबंध में आगे कोई भी पत्राचार सामान्यतः इंजीनियर-इन-चार्ज को संबोधित किया जाएगा।
- Any further correspondence in connection with the contract should normally be addressed to the Engineer-in-Charge.
- 9) कृपया इस पत्र को पावती भेजे ।
- Please acknowledge the receipt.
- 10) यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा ।
- In case any discrepancy is found then English version will be taken as correct.

भवदीय / Yours Faithfully,

 02/06/2023

वरिष्ठ प्रबंधक (अभि-सिविल),
Sr. Manager (Engg-Civil)

कृते अध्यक्ष भारतीय विमानपत्तन प्राधिकरण
For and on behalf of the Chairman AAI
बिरसी हवाई अड्डा, गोंदिया/ Birsi Airport, Gondia

संलग्नक / Encl. : 08 (आठ) पृष्ठ ।

Schedule of Quantities – 08 pages.

" SCHEDULE A - (Schedule of Quantity) "

Name of Work :- Annual Maintenance Contract of Civil Works for AAI Residential Colony at Birsai Airport, Gondia (2023-24).

Sr. No.	Description of Items	Unit	Rate
(I)	Schedule "A" (Part-I & II) (as per DSR - 2021 with upto date correction slip) All the sub-head of DSR 2021 from SL.No. 1 to 26 from page no. 1 to 591	DSR-2021 Units	DSR 2021 Schedule Rates
(II)	Schedule "A" (Part-III) Add. Misc. Items/Non-DSR Items (Rate derived at par with DSR - 2021)	Unit	Rate at par with DSR-2021
1	Machanized Water Storage Tank Cleaning (RCC overhead or underground) by High Pressure Pump 80-120 bar with stain cutter gun, Sludge Removal by sludge suction unit, Vacuum Cleaning, use of Anti Bacterial Agent and Last Ultra Violet radiation in tank all above work including of all taxes as instructed by Engineer-in-Charge.	Per litre	0.30
2	Machanized Water Storage Tank Cleaning (Plastic Tank) by High Pressure Pump 80-120 bar with stain cutter gun, Sludge Removal by sludge suction unit, Vacuum Cleaning, use of Anti Bacterial Agent and Last Ultra Violet radiation in tank all above work including of all taxes as instructed by Engineer-in-Charge. 50 upto 500 litre.	Per Tank	345.06
3	Machanized Water Storage Tank Cleaning (Plastic Tank) by High Pressure Pump 80-120 bar with stain cutter gun, Sludge Removal by sludge suction unit, Vacuum Cleaning, use of Anti Bacterial Agent and Last Ultra Violet radiation in tank all above work including of all taxes as instructed by Engineer-in-Charge. From 501 upto 3000 litre.	Per Tank	656.19
4	Supplying Un-Skilled labour for day to day maintenance jobs, (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time, the contractor shall be responsible to supervise the work assigned to labours and has to supply tools and plant as per requirement. (No variation on schedule of rates quoted will be applicable on this item).	Per Day	729.08
5	Supplying Semi-Skilled labour for day to day maintenance jobs, (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time, the contractor shall be responsible to supervise the work assigned to labours and has to supply tools and plant as per requirement. (No variation on schedule of rates quoted will be applicable on this item).	Per Day	751.64
6	Supplying Skilled labour for day to day maintenance jobs, (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time, the contractor shall be responsible to supervise the work assigned to labours and has to supply tools and plant as per requirement. (No variation on schedule of rates quoted will be applicable on this item). Carpenter/Mason/Plumber/Welder/Sewerman	Per Day	787.16

एस.के.सिंह/S.K.Singh

व.प्र. (अभि.-सिविल)/Sr. Manager (Engg.Civil)

आ.वि.आ. /A.A.I.

बिरसाई विमानतळ, गोंदिया /Birsai Airport Gondia-441601

sq 1

Sr. No.	Description of Items	Unit	Rate
7	Providing & Supplying Carpenter (Semi-skilled) on daily basis for day to day maintenance work. (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time, the contractor shall be responsible to supervise the work assigned to labours and has to supply tools & plant and uniform as per requirement. (The rates are inclusive of 02 sets uniform, shoes & shocks). (No variation on schedule of rates quoted will be applicable on this item).	Per Month	20,065.27
8	Providing & Supplying Plumber (Semi-skilled) on daily basis for day to day maintenance work. (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time, the contractor shall be responsible to supervise the work assigned to labours and has to supply tools & plant and uniform as per requirement. (The rates are inclusive of 02 sets uniform, shoes & shocks). (No variation on schedule of rates quoted will be applicable on this item).	Per Month	20,065.27
9	Providing & Supplying Sewerman (Semi-skilled) on daily basis for day to day maintenance work. (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time, the contractor shall be responsible to supervise the work assigned to labours and has to supply tools & plant and uniform as per requirement. (The rates are inclusive of 02 sets uniform, shoes & shocks). (No variation on schedule of rates quoted will be applicable on this item).	Per Month	20,065.27
10	Providing & Supplying Helper (Un-skilled) on daily basis for day to day maintenance work. (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time, the contractor shall be responsible to supervise the work assigned to labours and has to supply tools & plant and uniform as per requirement. (The rates are inclusive of 02 sets uniform, shoes & shocks). (No variation on schedule of rates quoted will be applicable on this item).	Per Month	19,478.74
11	Providing & Supplying Computer Data Entry Operators/ Clerical work (Skilled) for Engineering Office for typing / entering data in word / excel for preparing estimate, billing, miscellaneous works as per direction of EIC/ associated officer in engineering on daily basis for day to day office work. (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time). (The rates are inclusive of 02 sets uniform, shoes & shocks). (No variation on schedule of rates quoted will be applicable on this item).	Per Month	20,988.84
12	Providing & supplying office assistant (Un-skilled) on daily basis for day to day office work. (The contractor is bound to make payment as per minimum fair wages prevailing as notified by ministry of labour and employment of State / Central Govt. which is circulated by labour commissioner time to time. (The rates are inclusive of 02 sets uniform, shoes & shocks). (No variation on schedule of rates quoted will be applicable on this item).	Per Month	19,478.74
13	Cartage of malba, grass, etc from inside/outside of AAI premises to outside/inside of AAI premises by mechanical means including loading and unloading complete as directed by the Engineer-in-charge. Measuring Truck/Tractor capacity upto 3 cum.	Per Trip	1,353.79
14	Testing of potable water as per BIS from local water supply authority (i/c supplying of water sample to the laboratory) and providing the sample test report to Engineer-in-charge. General water analysis (standard tests)	Per Sample	3,168.79

एस.के.सिंह/S.K.Singh

व.प्र. (अभि. -सिविल)/Sr. Manager (Engg.Civil)

भा.वि.प्र./A.A.I.

SOQ.2

बिस्मिल्लाह गोरिया/Bismita Goria-441601

Sr. No.	Description of Items	Unit	Rate
15	Providing & supplying of G.I. fittings of all size from (15 mm to 50 mm dia) including dismantling old one and replacing with new one (Tees, Elbows, Collars etc.) as direction of Engineer-in-charge.	Each	89.92
16	Dismantling chain link fencing and stacking the same within 50 mtrs lead.	Sqm	49.06
17	Brick work with bricks of class designation 3.5 in foundation and plinth in: Cement mortar 1:6 (1 Cement : 6 coarse sand)	Cum	4,476.95
18	Brick work with F.P.S. bricks of class designation 3.5 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement: 6 coarse sand)	Cum	5,755.03
19	Half brick masonry with bricks of class designation 3.5 in foundations and plinth in : Cement mortar 1:4 (1 Cement : 4 coarse sand)	Sqm	5,761.02
20	Half brick masonry with F.P.S. bricks of class designation 3.5 in superstructure above plinth level upto floor V level : Cement mortar 1 : 4 (1 cement : 4 coarse sand)	Sqm	716.78
21	Providing & fixing cudappa stone slab minimum 30mm (Avg.) thick for kitchen and other platform on walls etc. complete to the satisfaction of Engineer-in-charge.	Sqm	758.36
22	Supply of JCB on hire basis including Diesel lubricant, driver etc. complete at site as per the direction of Engineer-in-charge.	Hrs.	1,320.76
23	Supplying & Stacking plastic sand bags by filling sand in new bags & stacking them properly at specified location complete to the satisfaction of Engineer-in-charge.	Per Bag	75.30
24	Supplying & Stacking plastic sand bags by filling available sand in new bags & stacking them properly at specified location complete to the satisfaction of Engineer-in-charge.	Per Bag	41.28
25	Providing and fixing water meter of Kranti make or equivalent in G.I. pipe line including cutting & threading the pipe & making long screws etc. complete as per direction & to the satisfaction of Engineer-in-charge. 15mm dia nominal bore.	Each	1,540.34
26	Providing 6 mm thick table top glass with all edges polished, half rounded corner as per required size complete to the satisfaction of Engineer-in-charge.	Sqm	1,384.05
27	Providing 8 mm thick table top glass with all edges polished, half rounded corner as per required size complete to the satisfaction of Engineer-in-charge.	Sqm	2,005.79
28	Fixing G.I. chain link fabric fencing of required width available in mesh size made of G.I. wire of dia. 3mm to 4 mm including strengthening with 2mm dia. wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. (GI chain link fabric fencing to be supplied by AAI free of cost)	Sqm	145.93

एस.के.सिंह/S.K.Singh
 व.प्र. (अभि-सिविल)/Sr. Manager (Engg.Civil)
 भा.वि.भा./A.A.I.
 दिल्ली विमानतट, गोरिया/Birsi Airport Gorreria-441601

Sr. No.	Description of Items	Unit	Rate
29	Supply of ball valve (brass) of approved quality complete : High or low pressure with plastic floats: 15 mm nominal bore	Each	343.53
30	Supply of ball valve (brass) of approved quality complete : High or low pressure with plastic floats: 20 mm nominal bore	Each	563.66
31	Supply of ball valve (brass) of approved quality complete : High or low pressure with plastic floats: 25 mm nominal bore	Each	629.70
32	Supply of PVC ball valve excluding brass fittings of approved quality complete : High or low pressure with plastic floats:	Each	277.49
33	Supply of C.P. Brass Health Faucet of approved make as per direction of Engineer-in-Charge. 15mm dia nominal bore	Each	838.82
34	Supply of C.P. Brass Health Faucet excluding pipe of approved make as per direction of Engineer-in-Charge. 15mm dia nominal bore	Each	629.70
35	Chequered precast cement concrete tiles 22 mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). (Tiles to be supplied by AAI free of cost). Dark shade pigment using ordinary Cement	Sqm	509.81
36	Supplying and providing welder with welding machine and other accessories/ equipments required for welding to M.S. frames, grills, iron gates etc. complete as per direction/ satisfaction of Engineer-in-charge.	Per Day	2,283.83
37	Cleaning of Roof, terrace, chhajja, etc of buildings i/c of all Khurras & rain water pipe in these area as per direction of Engineer-in-charge and disposal of rubbish to out side of the building area. (Only cleaned area will be measured)	Sqm	5.48
38	Providing & supply of commercial plywood 8mm thick to make panelling, office racks etc complete as per direction of Engineer-in-charge.	Sqm	822.49
39	Providing & supply of commercial plywood 12mm thick to make paneling, office racks, boards etc. complete as per direction of Engineer-In-Charge.	Sqm	810.27
40	Providing & supply of commercial plywood 18mm thick to make paneling, office racks, boards etc. complete as per direction of Engineer-In-Charge.	Sqm	942.77
41	Providing and fixing 22 inch G.I. make Cover Over Head PVC tank at roof and complete with locking arrangement as per direction of Engineer-in-charge .	Each	501.45

एस.क.सिंह/S.K.Singh

व.प्र. (अभि-सिक्कि)/Sr. Manager (Engg.Civil)

भा.वि.आ./A.A.I.

बिराही विमानतल, गोरिया/Birsi Airport Gondia-441604

Sr. No.	Description of Items	Unit	Rate
42	Providing and fixing 19 inch G.I. make Cover Over Head PVC tank at roof and complete with locking arrangement as per direction of Engineer-in-charge.	Each	433.65
43	Providing and fixing 16 inch G.I. make Cover Over Head PVC tank at roof and complete with locking arrangement as per direction of Engineer-in-charge.	Each	300.48
44	Providing and fixing mirror (0.9m x 0.75m) of superior glass of required shape and size with plastic moulded frame of any shade with 6mm thick hard board backing.	Each	2,696.57
45	Deduct for taking away of C.P. brass/Brass bib cock, stop cock, long nose bib cock, angle valve, ball valve, close hole basin mixer, C.P. waste in basin/ sink etc and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg.	236.09
46	Deduct for taking away of SCI pipe fitting, centrifugal cast (spun)/sand cast iron pipes and fittings, C.I. flushing cistern, G.I. pipes and fittings, steel doors, window, ventilators, grill, round or square bars etc. and the like item received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg.	16.95
47	Deduct for taking away of PVC connections, PVC flushing cistern with fittings, PVC over head tank, PVC bib cock, stop cock, ball valve, loft tank etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg.	12.11
48	Deduct for taking away of aluminium butt hinges, sliding door bolts, tower bolts, pull boly lock, handle, door stopper, casement stay, tee channels, plates etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Kg.	30.26
49	Deduct for taking away of plastic/M.S bucket etc. and the like received from dismantling. The material so received shall be the property of contractor after dismantling duly weighed/ measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	Each	22.01
50	Providing & fixing of venetian blind with necessary fittings as per direction of Engineer-In-Charge.	Sqm	2,113.23
51	Providing & fixing of roller blind with necessary fittings as per direction of Engineer-In-Charge.	Sqm	3,222.67
52	Providing & fixing spreader for sensor urinal complete as per direction and satisfaction of Engineer-in-charge.	Each	752.84
53	Repairing and refixing of door/window shutter including removal of shutter from chowkhat, cutting wherever required and fixing of butt hinges on other side of frame of shutter wherever required.	Each	467.79

एस.क. सिंह/S.K.Singh

व.प्र. (अभि. -सिविल)/Sr. Manager (Engg.Civil)

आ.वि.आ./A.A.I.

विस्तार विभाग/गोरिया/Birsi Airport Condo 44

Sr. No.	Description of Items	Unit	Rate
68	Providing and supply of 50 mm diameter uPVC pipes (Sch-40) including all fittings eg. Bends, junctions, elbow, f-tee, m-tee, offsets, access pieces etc. jointing with solvent cement complete in all respect as per direction of Engineer-in-charge.	Mtr	357.71
69	Providing & supply of 40mm dia uPVC SWR pipe including all fittings eg. Bends, junctions, elbow, f-tee, m-tee, offsets, access pieces etc. jointing with solvent cement complete in all respect as per direction of Engineer-in-charge.	Mtr	257.55
70	Providing & supply of 50mm dia uPVC SWR pipe including all fittings eg. Bends, junctions, elbow, f-tee, m-tee, offsets, access pieces etc. jointing with solvent cement complete in all respect as per direction of Engineer-in-charge.	Mtr	257.55
71	Providing & supply of 75mm dia uPVC SWR pipe including all fittings eg. Bends, junctions, elbow, f-tee, m-tee, offsets, access pieces etc. jointing with solvent cement complete in all respect as per direction of Engineer-in-charge.	Mtr	400.63
72	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) with all fittings and fixtures complete. 10 litre capacity - White	Each	1,057.74
73	Providing & supply of Hose Nipple G.I. fittings of all size from (15 mm to 50 mm dia x 100mm length) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	68.48
74	Providing & supply of X-Nipple G.I. fittings of all size from (15 mm to 50 mm dia x 100mm length) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	73.98
75	Providing & supply of X-Nipple G.I. fittings of all size from (15 mm to 50 mm dia x 150mm length) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	81.68
76	Providing & supply of X-Nipple G.I. fittings of all size from (15 mm to 50 mm dia x 200mm length) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	90.48
77	Providing & supply of X-Nipple G.I. fittings of all size from (15 mm to 50 mm dia x 250mm length) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	189.31
78	Providing & supply of Nipple G.I. fittings of all size from (15 mm to 50 mm dia x 100mm length) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	49.76
79	Providing & supply of Nipple G.I. fittings of all size from (15 mm to 50 mm dia x 150mm length) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	57.47
80	Providing & supply of Nipple G.I. fittings of all size from (15 mm to 50 mm dia x 200mm length) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	66.27
81	Providing and supplying plotting stones of 2 feet height for marking and other as per the instructions of EIC.	Each	51.04
82	Providing & supply of MT & FT G.I. fittings of all size (15 mm to 50 mm dia) including dismantling old one and replacing with new one as per direction of Engineer-in-charge.	Each	30.82
	Please quote your percentage rate of above items i.e. for Part-I & II (DSR-2021) + Part-III (Add. Misc. Items), by considering the base rate as 100, as indicated in Important Note mentioned below.		

Sr. No.	Description of Item	Quantity
1	Schedule "A" (Part-I & II) all the sub-head of DSR - 2021 from sr. no. 01 to 26 from page no. 01 to 591 & (Part-III) Add. Misc. Items/Non-DSR Items 01 to 82	1.00


एस.के. सिंह / S.K. Singh
 व.प्र. (अभि.-सिविल) / Sr. Manager (Engg. Civil)
 भा. वि. मा. / A.A.I.
 बि. सी. विमानतल, गोरिया / Birsai Airport Gondia-491001

Sr. No.	Description of Items	Unit	Rate
IMPORTANT NOTE:			
A) GUIDELINES FOR QUOTING THE % RATE BY THE BIDDER:-			
1. Bidder is required to quote only one value for percentage which will be applicable to Schedule "A"			
2. Bidder shall quote rate only in % (percentage) wherein 100 is taken as base value for Schedule "A"			
3. The percentage rate shall be quoted only in digits without applying any sign of (+) or (-)			
4. Following are some examples for quoting the % rate by the bidder:-			
a) If bidder wants to quote 5% below the Schedule "A" rates, then the bidder has to quote 5% in Envelope-II/Price bid with (-) sign. (Since 100 is base value of Schedule "A" and as bidder wants to quote 5% below the Schedule "A" means value 5 is subtracted from base value 100 and percentage quote becomes 100-5=95)			
b) If bidder wants to quote 4% above the Schedule "A" rates, then the bidder has to quote 4% in Envelope-II/Price bid with (+) sign. (Since 100 is base value of Schedule "A" as a bidder wants to quote 4% above the Schedule "A" means value 4 is added in base value 100 and percentage quote becomes 100 + 4 = 104)			
B) The payment of Items shall be regulated as below :-			
(a) Schedule of rates as per DSR 2021 and Additional Miscellaneous items			
Rate of item as per schedule = X			
Rate to be considered for payment = $(X/1.1405) \times (100 \div \text{Quoted percentage Rate})$			
100			
NOTE :- The aforesaid payment of items i.e. (B) shall not be applicable for manpower supply items i.e. for item nos. 04 to 12			



एस.के. सिंह / S.K. Singh

व.प्र. (अभि.-सिविल)/Sr. Manager (Engg. Civil)

भा.वि.भा./A.A.I.

बिराही विमानतल, गोरिया/Birsi Airport Goria