



भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA

By Speed Post/E-Mail

सं०सं० : भा.वि.प्रा./वी.एन.एस./अभि.(सि.)/वी.आ.पी.लाउन्ज-रिनोवेसन/डब्लू-81/

दिनांक: 12.06.2023

Ref. No.: AAI/VNS/ENGG(C)/VIP Lounge-Renovation/W-81/788-99/4296-4307

Date: 12.06.2023

सेवा में,

मेसर्स एस. के. कन्स्ट्रक्शन
ग्राम : बरेमा, पोस्ट : रामेश्वर,
वाराणसी-221405

To,

M/s S. K. Construction,
Village : Barema, Post : Rameshwar,
Varanasi-221405

विषय: लाल बहादुर शास्त्री अन्तर्राष्ट्रीय हवाईअड्डा वाराणसी पर नये टर्मिनल भवन में वी.आई.पी. लाउन्ज एवं टी-12 टॉयलेट ब्लॉक का नवीनीकरण।

Renovation of VIP Lounge, T-12 Toilet block in New Terminal Building at LBSI Airport, Varanasi.

(Tender ID : 2023_AAI_153081_1)

संदर्भ: ई-निविदा खुलने की तिथि : 30.05.2023

प्रिय महोदय, Dear Sir

- 1) उपरोक्त कार्य की कुल निविदा रकम रु. 55,90,550.24 (रुपया पचपन लाख नब्बे हजार पाँच सौ पचास एवं चौबीस पैसे मात्र) (जीएसटी रहित) की मद दर निविदा, जो कि कार्य की अनुमानित लागत रु. 76.47 लाख (जीएसटी रहित) से 24.74% (चौबीस दशमलव सात चार प्रतिशत) कम है, आपके द्वारा निविदा प्रपत्र की अनुसूची 'अ' में दर्शायी गयी मद दरों पर भरी गई है, अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत की जाती है।

Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India at the net tender amount Rs. 55,90,550.24 (Rupees Fifty Five Lakh Ninety Thousand Five Hundred Fifty and Twenty Four Paise Only) (Excluding GST) which is 24.74% (Twenty Four Point Seven Four Percent) below to the estimated cost put to tender of Rs. 76.47 lakh (Excluding GST).

- 2) सहायक महाप्रबन्धक (अभि०-सि०), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तरराष्ट्रीय विमानपत्तन, वाराणसी इस कार्य के कार्य प्रभारी अभियन्ता होंगे तथा प्रबन्धक (अभि०-सि०), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तर्राष्ट्रीय विमानपत्तन, वाराणसी उनके प्राधिकृत प्रतिनिधि होंगे। आपसे अनुरोध है कि दिनांक 07.07.2023 तक अधोहस्ताक्षरी के कार्यालय में उपस्थित होकर संविदा अनुबन्ध को हस्ताक्षरित कर पूर्ण करें। अनुबन्ध 100/- रुपए के गैर न्यायिक स्टाम्प पेपर पर सम्पादित किया जाएगा, स्टाम्प पेपर की कीमत आपके द्वारा वहन की जाएगी।

The AGM (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be the Engineer-in-charge of the work and Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi shall be our authorised representative. You are requested to attend the office of the undersigned by 07.07.2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- and the cost of stamp paper shall be borne by you.

- 3) धरोहर राशि रुपया 1,52,940.00 (एक लाख बावन हजार नौ सौ चालीस मात्र) संविदा प्रपत्र के अनुच्छेद 1ए पेज 16 के अनुसार प्रतिभूति निक्षेप राशि का हिस्सा मानकर उसमें बदल दिया जाएगा। कृपया शेष प्रतिभूति निक्षेप राशि रुपया 4,06,115.00 (रुपया चार लाख छः हजार एक सौ पन्द्रह मात्र) इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त के अनुसार चालू लेखा बिलों से की जाएगी।

The earnest money amount of Rs. 1,52,940.00 (Rupees One Lakh Fifty Two Thousand Nine Hundred forty only) received along with your tender will be treated and converted as a part of security deposit. Please deposit Rs. 4,06,115.00 (Rupees Four Lakh Six Thousand One Hundred fifteen only), towards balance security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted from the Running Account Bills as per condition GCC 1A on page 16 of the contract document.

M/s S.K. Construction

Sky

Proprietor

सहायक महाप्रबन्धक (अभि०-सि०)
Asstt. General Manager (Enng.-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India



- 4) आपसे अनुरोध है कि संविदा श्रमिक प्रावधान (विनिमय एवं उन्मूलन) एक्ट 1970, श्रमिक प्रावधान (विनिमय एवं उन्मूलन)-केन्द्रीय नियम 1971, न्यूनतम मजदूरी अधिनियम एवं इस सम्बन्ध में केन्द्र/राज्य सरकार के नियमों का पालन करना सुनिश्चित करें।
You are requested to comply with the provisions of Contract Labour (Regulation & Abolition) Act of 1970 and Contract Labour (Regulation & Abolition) Central rules 1971 and Minimum Wages Act & Rules thereof Central and State Governments with upto date amendments.
- 5) आपको निर्देशित किया जाता है कि आप तुरन्त प्रभाव से प्रबन्धक (अभि0-सि0), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तरराष्ट्रीय विमानपत्तन, वाराणसी से सम्पर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।
You are also directed to contact the Manager (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi, immediately who will arrange to hand over the site to you.
- 6) कृपया ध्यान दें कि कार्य पूर्ण करने की अवधि 06 (छ) महीने है जो कि 22.06.2023 से प्रभावी मानी जाएगी।
Please note that time allowed for carrying out the work shall be 06 (Six) Months and the same shall be reckoned from the 22.06.2023.
- 7) संविदा के सन्दर्भ में किसी भी प्रकार का पत्राचार सामान्यतः सहायक महाप्रबन्धक (अभि0-सि0), भा.वि.प्रा., लाल बहादुर शास्त्री अन्तरराष्ट्रीय विमानपत्तन, वाराणसी-221006 को सम्बोधित करें।
Any further correspondence in connection with the contract should normally be addressed to the AGM (E-C), AAI, Lal Bahadur Shastri International Airport, Varanasi-221006.
- 8) कृपया इस पत्र की पावती भेजें या पत्र कि अनुलिपि जो कि संलग्न है को हस्ताक्षरित कर अधोहस्ताक्षरी को स्वीकृत चिन्ह के रूप में वापस करें।
Please acknowledge the receipt or return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
- 9) विषयक कार्य से संबंधित अनुसूची-अ, (कुल पृष्ठ 21) (सिविल एवं विद्युत कार्यो रु. 55,90,550.24) संलग्न है।
Schedule 'A' (total pages 21) (Civil & Electrical works Rs. 55,90,550.24) of the work is enclosed.
- उपरोक्त के हिन्दी पाठ में कोई अन्तर या द्विधार्थकता होने की स्थिति में अंग्रेजी पाठ मान्य होगा।
In case of difference or ambiguity in Hindi and English version, the English version will prevail.

धन्यवाद।

संलग्नक : यथोपरि

Encl.: As above

भवदीय

M/s S.K. Construction

Sky

Proprietor

सहायक महाप्रबन्धक (अभि0-सिविल)

Asstt. General Manager (E-C)

अध्यक्ष, भा0वि0प्रा0 के लिए व उनकी तरफ से

For and on behalf of the Chairman, AAI

सहायक महाप्रबन्धक (अभि.-सिविल)

Asstt. General Manager (Engg.-Civil)

भारतीय विमानपत्तन प्राधिकरण

Airports Authority of India



प्रतिलिपि:

मूल प्रति पर नहीं (NOO)

(1) आन्तरिक / Internal:

- | | | | |
|---|---|---|---|
| 1 | निदेशक विमानपत्तन, ला0ब0शा0अं0 विमानपत्तन, वाराणसी /
Airport Director, LBSI Airport, Varanasi | : | सूचनार्थ /
For kind information |
| 2 | संयुक्त महाप्रबन्धक (अभि0-वि0) ला0ब0शा0अं0 विमानपत्तन, वाराणसी /
JGM (E-E), LBSI Airport, Varanasi | : | तदैव / -do- |
| 3 | उप महाप्रबन्धक (वित्त) ला0ब0शा0अं0 विमानपत्तन, वाराणसी /
DGM (Finance), LBSI Airport, Varanasi | : | तदैव / -do- |
| 4 | सहा0 महाप्रबन्धक (अभि0-सि0), ला0ब0शा0अं0 विमानपत्तन, वाराणसी /
AGM (E-C), LBSI Airport, Varanasi | : | तदैव / -do- |
| 5 | प्रबन्धक (अभि0-सि0), ला0ब0शा0अं0 विमानपत्तन, वाराणसी /
Manager (E-C), LBSI Airport, Varanasi | : | आवश्यक कार्यवाही हेतु /
For necessary action |
| 6 | अनुबन्ध प्रति / Agreement copy | | |
| 7 | फाइल प्रति / File copy | | |

(2) बाहरी / External: सूचनार्थ / For kind information:

1. DGM (Engg), RHQ, NR, AAI, Operational Office, Gurgaon Road, New Delhi
उप महाप्रबन्धक (अभि0-सि0), क्षेत्र0, उ0क्षेत्र0, भाविप्रा0, आपरेशनल आफिसेस, गुडगाँव रोड, नई दिल्ली
2. Asstt. Labour Commissioner (C), 189-A/4, Alopi Bagh, Post- Daraganj, Allahabad
सहायक श्रम आयुक्त (सी), 189-ए/4, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज
3. Labour Enforcement Officer (C), 189-A/4, Alopi Bagh, Post- Daraganj, Allahabad
श्रम प्रवर्तन अधिकारी (सी), 189-ए/4, अलोपी बाग, पोस्ट-दारागंज, प्रयागराज
4. Regional Provident Fund Commissioner-II, Sub Regional office, Bhavishya Nidhi Bhawan,
Ashok Vihar, Phase-I, Panch Kosi Road, Pahariya, Varanasi-221007, Phone No.: 0542-2585738
क्षेत्रीय भविष्य निधि आयुक्त-II उप क्षेत्रीय कार्यालय, भविष्य निधि भवन, अशोक विहार, चरण-I, पंचकोशी
रोड, पहड़िया-वाराणसी-221007, फोन नं0 : 0542-2585738

12/06/23

सहायक महाप्रबन्धक (अभि0-सिविल)
Asstt. General Manager (E-C)

M/s S.K. Construction

S K

Proprietor

सहायक महाप्रबन्धक (अभि.-सिविल)
Asstt. General Manager (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Validate Print Help

Item Rate BQ

Tender Inviting Authority: Airports Authority of India

Name of Work: Renovation of VIP Lounge, T-12 Toilet block in New Terminal Building at LBSI Airport, Varanasi

Contract No: 2023_AAI_153081_1

Name of the Bidder/ Bidding Firm / Company :	M/S S K CONSTRUCTION PROP SURENDRA KUMAR YADAV R/O BAREMA POST RAMESHWAR VARANASI						
PRICE SCHEDULE							
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
	2	3	4	5	7	8	10
1.01	Civil Works						
1.01	Demolishing cement concrete including disposal of material within 50 metres lead: 1:3:6 or richer mix	Item1	28.23	cum	450.00	12703.50	INR Twelve Thousand Seven Hundred & Three and Paise Fifty
1.02	Demolishing R.C.C. work manually/by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer in charge.	Item2	0.75	cum	900.00	675.00	INR Six Hundred & Seventy Five Only
1.03	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer in charge a) In cement mortar	Item3	2.25	cum	250.00	562.50	INR Five Hundred & Sixty Two and Paise Fifty Only
1.04	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead: Of area 3 sq. metres and below a)	Item4	7.00	each	200.00	1400.00	INR One Thousand Four Hundred Only
1.05	Dismantling stone slab/tiles flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	Item5	316.71	sqm	15.00	4750.65	INR Four Thousand Seven Hundred & Fifty and Paise Sixty Five
1.06	Dismantling steel work manually/by mechanical means in built up sections without dismembering, Refabricating and refixing same as per site requirement as per direction of Engineer-in-charge.	Item6	200.00	kg	2.00	400.00	INR Four Hundred Only
1.07	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 metres lead : Thickness above 10 mm up to 25 mm	Item7	205.49	sqm	25.00	5137.25	INR Five Thousand One Hundred & Thirty Seven and Paise Twenty Five Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.08	Dismantling C.I. pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes & lead at site within 50 metre lead as per direction of Engineer-in-charge: a) Up to 150 mm diameter metre	Item8	120.00	mtr	50.00	6000.00	INR Six Thousand Only
1.09	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	Item9	9.00	each	300.00	2700.00	INR Two Thousand Seven Hundred Only
1.10	Dismantling of Sanitary fixtures & fittings including WC, Urinals, Wash Basins etc. including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	Item10	23.00	each	50.00	1150.00	INR One Thousand One Hundred & Fifty Only
1.11	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing, false ceiling and toilet cubicles including disposal of unserviceable surplus material and stacking of serviceable material within 50 meters lead as directed by Engineer-in-charge.	Item11	186.68	sqm	15.00	2800.20	INR Two Thousand Eight Hundred and Paise Twenty Only
1.12	Dismantling G.I. pipes (internal work) including chasing wall after taking out the pipes, manually/ by mechanical means and making wall good with 1:3:6 concrete including stacking of pipes lead as per direction and satisfaction of Engineer-in-charge : 15 mm to 75 mm nominal bore	Item12	200.00	mtr	20.00	4000.00	INR Four Thousand Only
1.13	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground as sujested by EIC.	Item13	98.33	sqm	20.00	1966.60	INR One Thousand Nine Hundred & Sixty Six and Paise Sixty
1.14	Dismantling of toilet fixtures of type including stacking of useful materials at store and disposal of unserviceable material to dumping ground as shown by EIC all complete.	Item14	27.00	each	50.00	1350.00	INR One Thousand Three Hundred & Fifty Only
1.15	Dismantling or taking out fixed mirror in toilet including disposal of unserviceable surplus material and stacking of serviceable material at suitable place as direction and satisfaction by Engineer-in-charge.	Item15	7.74	sqm	50.00	387.00	INR Three Hundred & Eighty Seven Only
1.16	Centering and shuttering including strutting, propping etc. and removal of form for all heights : a) Lintels, beams, plinth beams, girders, bressumers and cantilevers	Item16	19.50	sqm	310.00	6045.00	INR Six Thousand & Forty Five Only
1.17	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.a) Thermo-Mechanically Treated bars of grade Fe-500D or more.	Item17	348.47	Kg	82.00	28574.54	INR Twenty Eight Thousand Five Hundred & Seventy Four and Paise Fifty
1.18	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-II) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Item18	2.24	cum	7100.00	15904.00	INR Fifteen Thousand Nine Hundred & Four Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1.19	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:3 (1 cement :3 coarse sand)	Item19	112.00	sqm	760.00	85120.00	INR Eighty Five Thousand One Hundred & Twenty Only
1.20	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1.2.4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	Item20	18.77	cum	5850.00	109804.50	INR One Lakh Nine Thousand Eight Hundred & Four and Paise Fifty Only
1.21	Extra for providing and placing 2 nos. 6 mm dia M.S. bars at every third course of half brick masonry.	Item21	94.50	sqm	50.00	4725.00	INR Four Thousand Seven Hundred & Twenty Five Only
1.22	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade. Area of slab upto 0.50 sqm	Item22	10.40	sqm	3280.00	34112.00	INR Thirty Four Thousand One Hundred & Twelve Only
1.23	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. b) 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Item23	7.77	sqm	2150.00	16705.50	INR Sixteen Thousand Seven Hundred & Five and Paise Fifty Only
1.24	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters. (Overall area of shutter to be measured over item no. 21)	Item24	7.56	sqm	450.00	3402.00	INR Three Thousand Four Hundred & Two Only
1.25	Supplying and installation of 12 mm thick frameless toughened glass door of Dorma-Germany / Linco-Australia / Geze-Germany or approved equivalent. Glass to be ordered double layer high density super fine toughened glass of any required size. Glass to be toughened by special chemical to strengthened by double impact, all edge to be machine polished and sides also to be toughened. The work also includes cutting of floor (15mm strip of size 15mm X 15mm) for floor spring this would hold the glass at bottom. The work includes cost of all cut outs/holes The doors to be hung on Dorma heavy floor spring BTS 84 - DORMA / FS 004 - Linco / TS 500 EN3 of Geze or approved equivalent . The patch fittings consisting of all required patch fittings for doors with side and upper panels, upper and bottom patches, floor lock with cylinder and strike plate and pull handle of size 350mmX22mm complete as per direction of Engineer-in-charge. Single Leaf Door Shutter (size 1.2 m X 2.1 m)	Item25	1.00	sqm	12500.00	12500.00	INR Twelve Thousand Five Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.26	Providing & fixing Stainless Steel tower bolts of OZONE TBS-10"/6" SS 304 grade or approved equivalent of grade 304 heavy duty with necessary Stainless Steel screws, etc. complete as per directions of Engineer-in- Chargea) 250 x 25 mm	Item26	6.00	each	800.00	4800.00	INR Four Thousand Eight Hundred Only
1.27	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position all complete	Item27	500.00	Kg	88.00	44000.00	INR Forty Four Thousand Only
1.28 M/s S.K. Construction	Providing and fixing 12-15 mm thick moulded Acrylic solid surface counter/ slab tops of Dupont/Samsung Staron/Avonite or approved equivalent for kitchen platforms , vanity counters,window sills, facias and similar location of required size of approved shade, colour and texture fixed over 12 mm thick base ply with seamless joints through thermoforming process including all fixing, sticking, moulding, bending, use of flexible ply (if required) as per requirements of the approved drawings etc. and as per the directions of the Engineer in charge complete at all levels.Solid surface of approved shade & company	Item28	17.40	sqm	12500.00	217500.00	INR Two Lakh Seventeen Thousand Four Hundred & Ninety Nine and Paise One Hundred Only
1.29	Providing and laying in floors anti skid homogenous vitrified tiles with water absorption less than 0.08% and conforming to IS:15622 of approved Belgium Grey NITCO/Marbonite -Ash Grey/Porselano – Dew Grey JOHNSON/ Fresco Azul RAK CERAMICS brand/ manufacturer, of size 600 x 600mm x 9.6 to 10mm and 600 x 300 x 9.6 to 10mm in combination as per approved drawing without warpage of approved make and colour shades laid on 20 mm bed of cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints of thickness 3 mm with solid epoxy grout of PIDILITE / LATICRETE / BAL ENDURA / FERROUS CRETE or approved equivalent of desired shade etc. complete and as per pattern specified in approved drawings and specifications complete as per directions of Engineer-in-charge.	Item29	108.83	sqm	980.00	106653.40	INR One Lakh Six Thousand Six Hundred & Fifty Three and Paise Forty Only
1.30	38 mm thick wood block flooring of first class teak wood laid over 25 mm thick leveling layer of cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 10 mm nominal size) to be paid separately, coated with a thin layer of hot bitumen penetration 80/25 (blown type) @ 2.45 kg per sqm, including fixing blocks in position after dipping in hot bitumen (blown type) up to half depth, planed, levelled smooth and finished complete.	Item30	88.35	sqm	7250.00	640537.50	INR Six Lakh Forty Thousand Five Hundred & Thirty Seven and Paise Fifty Only
1.31	Providing and fixing expansion hold fasteners on C.C. /R.C.C./Brick masonry surface backing including drilling necessary holes and the cost of bolt etc complete.(a) Fastener with threaded dia 10 mm	Item31	100.00	each	22.00	2200.00	INR Two Thousand Two Hundred Only
1.32	Providing and fixing pre-polished mirror finished homogenous vitrified tile with water absorption less than 0.08% and conforming to IS:15622 of approved brand/manufacturer in skirting risers of steps and dado on wall over 12mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm including pointing in white cement mixed with pigment to match the shade complete as per directions of Engineer-In-Charge.a) 600x300x9.6 to 10mm thick	Item32	351.38	sqm	1100.00	386518.00	INR Three Lakh Eighty Six Thousand Five Hundred & Eighteen Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.33	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/ partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm Interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :a) 12.5 mm thick tapered edge gypsum moisture resistant board	Item33	186.68	sqm	990.00	184813.20	INR One Lakh Eighty Four Thousand Eight Hundred & Thirteen and Paise Twenty Only
1.34	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :(a) Two or more coats on new work	Item34	200.00	sqm	90.00	18000.00	INR Eighteen Thousand Only
1.35	Wall & Ceiling painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :(a) Two or more coats on new work	Item35	186.68	sqm	95.00	17734.60	INR Seventeen Thousand Seven Hundred & Thirty Four
1.36	Providing and fixing plain lining with necessary screws/nuts & bolts/ nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete as per direction of Engineer-incharge (Frame work shall be paid for separately). 12mm thick commercial ply conforming to IS : 1328 BWR type	Item36	112.80	sqm	850.00	95880.00	INR Ninety Five Thousand Eight Hundred & Eighty Only

M/s S.K. Construction

वायुमार्ग महानगर (एन-मिनि)
 Asst. General Manager (Eng. Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airports Authority of India
 राय बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.37	Providing & fixing in position 4mm thk. Aluminium composite panels in external face, column/wall cladding and canopy ceiling of approved make conforming to ASTM standard /specifications comprising polyethylene core sandwiched between two skins of 0.50mm thick special alloyed aluminium sheet to have overall thickness of 4mm with exterior coating of PVDF Paint. Fixing of surface cladding to masonry/ concrete faces/steel structure as called for, including appropriate and adequate framework of aluminium tubular sections 50x25x3mm and 25x38x3mm to fix the composite panel to the frame, straight/slope and curvilinear profile and shapes including all accessories and all incidental work. The cladding shall be done in accordance with the drawings, fixed to sides and faces of columns /piers, to sills and soffits of window opening, returned over coping, to R.C.C/ structural steel system, etc, to line and level. The joints shall be properly sealed with approved Silicon sealant to make the joints watertight and weather proof including, fixing over aluminium frame using mechanical fasteners such as Aluminium cleats and Stainless Steel fasteners. Specially designed frame work with vertical and horizontal members of extruded aluminium section which shall be made of alloy 6063 T6, as approved by the Engineer-in-charge (as per drawing enclosed)The work shall be complete as per specification and directions of Engineer-in -Charge.	Item37	45.00	sqm	4250.00	191250.00	INR One Lakh Ninety One Thousand Two Hundred & Fifty Only
1.38	Providing & fixing of white vitreous China wall mounting cascade type water closet American standard Acacia E double vortex WC 2/4.2 L 3119 WT/ Proguard (sc.seat&cover).KHOLER Vitreous 99994IN-0, ROCA The GAP RS346477460 & RE801472464, JAQUAR O PS-WHT-15951 with CP bolts, nuts, CI chair hanging arrangements, bakelite seat & cover with CP hinges & rubber buffers, CP brass screw, washer with all accessories with WC connector with Rubber Lip / Buffer and side gap filled with silicon sealant wherever required with flush valve American standard /Grohe WC 38987000,Kohler 7702IN-P-NA, Jaquar JCS-WHT-2400 Flushing cistern GD 2 & 38732000 Skate Cosmopolitan Wall plate/Kholer 8857IN-M-MS1 ROCA RE890195001 Jaquar JCP-CHR-392415 approved including brass / SS screws and washer complete including cutting, making good the walls, floors, slab wherever required as per direction of Engineer-Incharge.	Item38	8.00	each	9950.00	79600.00	INR Seventy Nine Thousand Six Hundred Only
1.39	Providing & fixing sensor based automatic battery operated electronic wash basin sensor tap of chrome finished American standard model no FFAS8506-D00500BF0 - 24500,KHOLER 48957IN-ND-CP AUCLEN, ROCA RT5A5609CON, JAQUAR 3NR-CHR-51011 AQ UISENSE (or approved equivalent) with solenoid valve at inlet, Doppler based sensor, control box complete with all flexible pipes & accessories as per direction of Engineer-Incharge.	Item39	10.00	each	8900.00	89000.00	INR Eighty Nine Thousand Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.40	Providing & fixing of white vitreous china under counter wash basin 550x450 American standard Active model no 600 mm WVP-0440.000.04, KHOLER 2215IN-0 LADENA, 2240X-0 VINTAGE, ROCA RS327871461, JAQUAR FNS-WHT-40701 with CP brass waste assembly, CP cast brass bottle trap with extension piece (Jaquar ALD-CHR-769L300X190 / Grohe A-8107-D1Y / Kohler 7314IN-CP, Roca RF9066A1 or approved equivalent), 450 mm long CP copper connections pipes (Jaquar Cat No. 803B or approved equivalent), wall flanges and rubber adapters for waste connection complete including CI/MS brackets duly painted, nuts, washers, cutting and making good the walls floors wherever required as per direction of Engineer-Incharge.	Item40	8.00	each	5000.00	40000.00	INR Forty Thousand Only
1.41	Providing & fixing Off white vitreous china flat back urinal with automatic flushing systems American Standard CP-6507.322.04(Concept 1.9 L Urinal HE2, KHOLER 16321T-M-0 PATIO TOUCHLESS, ROCA RS35945E000 EURET or approved equivalent) comprising of all plumbing, electronic and electrical items. CP brass flush pipe with CP brass elbow, CP brass spreader, CP wall flange, infrared photo cells, eyes electrically operated solenoid valve, step down transformer / equipment and any other item required to provide satisfactory functioning including necessary wall cutting / chasing and making good, as required for urinal flushing complete as mentioned above as per direction of Engineer-Incharge.	Item41	8.00	each	16800.00	134400.00	INR One Lakh Thirty Four Thousand Four Hundred Only
1.42	Providing & fixing C.P. hand spray with lever control (health faucet) American Standard TP 406, KHOLER 12925IN-CP, ROCA RF9060A1, JAQUAR ALD-CHR-573 or approved equivalent) and flexible hose 1 m long connection with C.P. holder for hand spray complete in all respects as per direction of Engineer-Incharge.	Item42	12.00	each	1650.00	19800.00	INR Nineteen Thousand Eight Hundred Only
1.43	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. a) 15 mm dia nominal bore	Item43	4.00	each	450.00	1800.00	INR One Thousand Eight Hundred Only
1.44	Providing & fixing 15 mm dia C.P. brass angle valve American Standard FLR 5053N A-4400, KHOLER 80155IN-4-CP CUFF, ROCA RF525159700, JAQUAR AQT-CHR-3057 with C.P. brass wall flange with any other items complete including cutting and making good the walls wherever required as per direction of Engineer-Incharge.	Item44	25.00	each	600.00	15000.00	INR Fifteen Thousand Only
1.45	Providing and fixing plasticised PVC connection pipe with brass unions :45 cm length 15 mm nominal bore	Item45	10.00	each	40.00	400.00	INR Four Hundred Only
1.46	Providing & fixing stainless steel jumbo roll toilet tissue dispenser (Bobrick cat no. B2890 or approved equivalent) with stainless steel roller complete with accessories, including cutting and making good the walls and floors wherever required as per direction of Engineer-Incharge.	Item46	12.00	each	6500.00	78000.00	INR Seventy Eight Thousand Only

सहायक महाप्रबन्धक (अभि.-सिविल)
 Asstt General Manager (Engg.-Civil)
 भारतीय विमानपत्तन प्राधिकरण
 Airport Authority of India
 लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
 Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.47	Providing & fixing recessed liquid soap dispenser (Bobrick cat no. B-822 or approved equivalent) as per direction of Engineer-In-charge.	Item47	10.00	each	4500.00	45000.00	INR Forty Five Thousand Only
1.48	Providing & fixing of 760 mm long stainless steel grab bar (Bobrick code B-5806.99x30 /) or approved equivalent) including screw, rawl plugs making wall good, complete as per directions of Engineer-In-charge.	Item48	1.00	each	4250.00	4250.00	INR Four Thousand Two Hundred & Fifty Only
1.49	Providing & fixing of 1065 mm long stainless steel grab bar (Bobrick code B-5806.99 x42/) or approved equivalent) including screw, rawl plugs making wall good, complete as per directions of Engineer-In-charge..	Item49	1.00	each	4500.00	4500.00	INR Four Thousand Five Hundred Only
1.50	Providing & fixing recessed paper towel dispenser and waste receptable (Bobrick cat no. B-3944)or approved equivalent) as per direction of Engineer-In-charge.	Item50	4.00	each	45800.00	183200.00	INR One Lakh Eighty Three Thousand Two Hundred Only
1.51	Providing & fixing of modular toilet cubicles (Titan Standard 12 mm series of Merino/ sturdo classique of greenlam industries or approved equivalent) consisting of high pressure 12 mm thick compact laminate board as per IS 2046 (Indian Standards) and as per fire retardant BS-476/97 standards with phenolic core panels for partitions of intermediate divider, doors and pilasters(. The cubicle shall have dimensions of 1500 mm depth x 900 mm width x 2050 mm height with a door size of minimum head rail on top of panels and panels shall be fixed on the floor with a clearance of maximum 150 mm using stainless steel satin finish adjustable legs screwed to the floor included stainless steel (SS) lock set, SS door knob, SS gravity self closing hinge, SS coat hook with door stopper, SS U channel, SS head rail, SS adjustable foot, SS tabular holder, SS head rail wall bracket, SS head rail corner connection and SS noise reducing tape, etc.(all SS accessories shall be of Grade 304) as per direction of Engineer-In-charge.Note:- The quantity shall be calculated on basis of surface area of compact laminate board.	Item51	20.50	sqm	7250.00	148625.00	INR One Lakh Forty Eight Thousand Six Hundred & Twenty Five Only
1.52	Providing & fixing Urinal Modesty Panels having standard dimension of 1200 mm Height x 450 -500 mm Width and 12 mm thickness (SS Series of Merino Industries /sturdo classique of greenlam industries or approved equivalent) Panel starts 500-600 mm above ground level, complete with compact Laminate Board: 12 mm thick Compact Laminate (Titan Series of Merino Industries or approved equivalent) made as per IS 2046 (Indian Standard) and as per fire retardant BS-476/97 standard and should be heat, bacteria, water, chemical, scratch and impact resistant 12 mm thick solid compact laminate panels as per approved texture/shade. The product should have Green Guard Certificate. Including all accessories as per approval and direction of Engineer-in-Charge Modesty panels will be fixed with right angle bracket which will be provided in stainless steel grade-304. (a) Right Angle Bracket b) Screws & Wall Plugs. Hardware & Fixing : All screws will of 304 Grade in stainless steel with satin finish & panel will be supported by right angle brackets & will be used to hold the panels with a clearance height upto 500-600 mm. The work includes all accessories, machineries, tools etc., complete as per direction of Engineer-in-charge.	Item52	7.00	each	4280.00	29960.00	INR Twenty Nine Thousand Nine Hundred & Sixty Only

5 Key

Asslt. General Manager (Civil)
भारतीय विमानपत्तन निगम
Airports Authority of India
लाल बहादुर शास्त्री अंतर्राष्ट्रीय विमानतट
Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.59	Providing and fixing 3 layer PP-R (Poly propylene random copolymer) pipes SDR 7.4 U V stabilized and anti - microbial fusion welded, having thermal stability for hot and cold water supply including all PP-R plain and brass threaded polypropylene random fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes testing of joints complete as per direction of Engineer-In-charge. Concealed work including cutting chases and making good the walls etc. a) PN -16 Pipe, 32 mm outer diameter	Item59	60.00	mtr	390.00	23400.00	INR Twenty Three Thousand Four Hundred Only
1.60	Providing, fixing, joints and testing in position the following UPVC Pipe confirming to IS:4985 of 6kg sqcm for sanitary and sewage system cut to required length pipe to be laid below level in trenches up to required depth, including excavation in all kind of soil (hard rock) dewatering, refilling, watering, ramming and removing the surplus excavated material and putting 100 m sand all-round and making good the same. 50 mm OD	Item60	100.00	mtr	215.00	21500.00	INR Twenty One Thousand Five Hundred Only
1.61	Providing, fixing, joints and testing in position the following UPVC Pipe confirming to IS:4985 of 6kg sqcm for sanitary and sewage system cut to required length pipe to be laid below level in trenches up to required depth, including excavation in all kind of soil (hard rock) dewatering, refilling, watering, ramming and removing the surplus excavated material and putting 100 m sand all-round and making good the same. 75 mm OD	Item61	40.00	mtr	465.00	18600.00	INR Eighteen Thousand Six Hundred Only
1.62	Providing, fixing, joints and testing in position the following UPVC Pipe confirming to IS:4985 of 6kg sqcm for sanitary and sewage system cut to required length pipe to be laid below level in trenches up to required depth, including excavation in all kind of soil (hard rock) dewatering, refilling, watering, ramming and removing the surplus excavated material and putting 100 m sand all-round and making good the same. 110 mm OD	Item62	104.00	mtr	545.00	56680.00	INR Fifty Six Thousand Six Hundred & Eighty Only
1.63	Providing and fixing 3M Frosted Sparkle Graphic Film over the designated locations with wet applications at all floors in any design and pattern complete as per the direction and satisfaction of Engineer-in- charge. (No deductions shall be made for the blank areas in the pattern. only film area will be measured)	Item63	5.04	sqm	1100.00	5544.00	INR Five Thousand Five Hundred & Forty Four Only
1.64	Providing and fixing beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Item64	6.48	sqm	1260.00	8164.80	INR Eight Thousand One Hundred & Sixty Four and Paise Eighty Only
1.65	Providing and fixing 100 mm stainless steel grating for Floor trap.	Item65	6.00	each	150.00	900.00	INR Nine Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.76	Providing and application of texture paint on wall/ columns with acrylic resins in water dispersion and special metallic and pearly components make the highly flexible in terms of the variety of decorative effects that can be achieved with special texture paint of OIKOS – Italy Multidecor series, /Pidilite / Acro or approved equivalent as per approved colour and pattern as per direction of Engineer-In -Charge. The works include application of one coat of primer, two coat of low VOC Emulsion using tinted roller and brush (as per manufacturer's specification and approval of E-I-C), and one coat of metallic pearl special texture paint applied with recommended tool for application as per selected finish(as per manufacturer's specification and approval of E-I-C) , including cost and conveyance of all material , labour , sundries, tools and machinery etc. including the base preparation with POP/ Putty etc. all complete as per approved pattern and color as per direction of Engineer-In-Charge.	Item76	26.61	sqm	650.00	17296.50	INR Seventeen Thousand Two Hundred & Ninety Six and Paise Fifty Only
1.77	Providing and fixing 20x2mm thick stainless steel T section strip (golden clour) in wall lining with structural steel adhivise etc, all complete as per direction of the Engineer in-charge.	Item77	200.00	mtr	725.00	145000.00	INR One Lakh Forty Five Thousand Only
1.78	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete : 2nd class teak wood 50x12 mm	Item78	300.00	mtr	165.00	49500.00	INR Forty Nine Thousand Five Hundred Only
1.79	Providing and fixing SS 304 grade Gutterman channel of size 100x30 mm with Top Grating of load class Human load . Steel tray (drip tray) of standard design with necessary fabrication, hanger and support under the horizontal suspended soil / waste header. Tray shall be installed in slope with drain connection at end. The installation shall be to the satisfaction / approval of Engineer-in-charge. The installation shall be to the satisfaction / approval of Engineer-in-charge.	Item79	9.00	mtr	3200.00	28800.00	INR Twenty Eight Thousand Eight Hundred Only
1.80	Providing & fixing lavatory wash basin for handicapped toilet American Standard WP-1530.001.04 & CL0741S-6DACT, KHOLER 20812IN-1-0 STRUKTURA, ROCA RS327230000 Access or approved equivalent) and CP cast Brass bottle trap with extension piece (Jaquar ALD-CHR-769L300X190 / Grohe A-8107-D1Y / Kohler 7314IN-CP, Roca RF9066A1 or approved equivalent) for handicap toilet complete with brackets, tracks, waste pipes and other accessories complete as required as per direction of Engineer-Incharge.	Item80	1.00	Each	20000.00	20000.00	INR Twenty Thousand Only
1.81	Providing & fixing Sink Cock for Pantry /Kitchen KHOLER PULLDOWN KITCHEN FAUCET K-562-SD-VS) with extension piece (Jaquar ,Grohe P or approved equivalent), 450 mm long CP copper connections pipes (Jaquar Cat No. 803B or approved equivalent), wherever required as per direction of Engineer-Incharge.	Item81	1.00	Each	8000.00	8000.00	INR Eight Thousand Only

5 K Proprietor

Asst. General Manager
Airports Authority of India
Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.82	Providing & fixing Sink for Pantry /Kitchen sink with drain board CERA- B4712502 or approved equivalent) with Pantry Sink & CP brass waste assembly, CP cast Brass bottle trap with extension piece (Jaquar ALD-CHR-769L300X190 / Grohe A-8107-D1Y / Kohler 7314IN-CP, Roca RF9066A1 or approved equivalent), wall flanges and rubber adapters for waste connection complete wherever required as per direction of Engineer-Incharge.	Item82	1.00	Each	12600.00	12600.00	INR Twelve Thousand Six Hundred Only
1.83	Providing & fixing of white wash basin for VIP Lounge washroom, KHOLER Vitreous 19034IN- XBV-0 Escalade vanity top 100cm w/gov, s White "6910.1000"with CP brass waste assembly, CP cast brass bottle trap with extension piece (Jaquar Cat No. 769B / Grohe cat no. 26920 / Kohler cat no. K-16407IN-CP or approved equivalent), 450 mm long CP copper connections pipes (Jaquar Cat No. 803B or approved equivalent), wall flanges and rubber adapters for waste connection complete including CI/MS brackets duly painted, nuts, washers, cutting and making good the walls floors wherever required as per direction of Engineer-Incharge.	Item83	1.00	Each	42000.00	42000.00	INR Forty Two Thousand Only
1.84	Supplying and installation of 12 mm thick frameless toughened glass door of Dorma-Germany / Linnox-Australia / Geze-Germany or approved equivalent. Glass to be ordered double layer high density super fine toughened glass of any required size. Glass to be toughened by special chemical to strengthened by double impact, all edge to be machine polished and sides also to be toughened. The work also includes cutting of floor (15mm strip of size 15mm X 15mm) for floor spring this would hold the glass at bottom. The work includes cost of all cut outs/holes The doors to be hung on Dorma heavy floor spring BTS 84 - DORMA / FS 004 - Linnox / TS 500 EN3 of Geze or approved equivalent. The patch fittings consisting of all required patch fittings for doors with side and upper panels, upper and bottom patches, floor lock with cylinder and strike plate and pull handle of size 350mmX22mm complete as per direction of Engineer-In-Charge. a) Double Leaf Door Shutter(2.0 m X 2.4 m)	Item84	4.20	Sqm	6850.00	28770.00	INR Twenty Eight Thousand Seven Hundred & Seventy Only
1.85	Providing and fixing of stainless steel 304 grade of Dorma-dpl make (code no. 54.4400.02.200)/Reynears-USA or approved equivalent round pipe handles of size 300 x 19 mm dia. with necessary screws etc. complete.	Item85	4.00	pair	2500.00	10000.00	INR Ten Thousand Only
1.86	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	Item86	8.00	Each	150.00	1200.00	INR One Thousand Two Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1.87	Design, Supply, fabrication, and installation of IMP - Metal, Plain & imposed stainless steel sheet SS 316L in N3D- 06 Gold (Austeneid emposed Pattern) 316 Superior grade finish of Naman Steel or approved equivalent make with 1.5mm as shown In drawing with 90 degree rightangle sharp V grooving bending without radius and as per approval including marine ply thick 19mm thick framework as per vendor design. Metal to be cladded on 19mm marine plywood with appropriate make silicone Mc coy produced soudal construction FC Silicone Sizes and spacing to be designed by bidder wit neat and clean appearance. No where screws should be visible. Metal panel shall be completed in all aspects as shown in drawing including all other necessary related works as specified and as directed by Engineer in Charge. Necessary cutout to be provided as specified. same shall be cleaned and handed over to the client.	Item87	27.60	Sqm	6250.00	172500.00	INR One Lakh Seventy Two Thousand Five Hundred Only
1.88	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Item88	100.00	cum	250.00	25000.00	INR Twenty Five Thousand Only
1.89	Carriage of material By Mechanical Transport (Tractor with trolly) including loading, unloading and stacking of serviceable material at designated locations/Store and disposal of unserviceable material as per direction of EIC.	Item89	10.00	trip	1200.00	12000.00	INR Twelve Thousand Only
1.90	Providing architectural/engineering consultancy with detailed 3-D concept design for the renovation of 1 VIP lounge and 1 toilet as per the items selected in estimate and preparataion of architectural/structural design drawings of selected 3-D concept design. Design should be based on latest BIS codes and standard engineering practice. The design shall be prepared by qualified and registered architectural/engineering consultant, approved by Engineer-in-charge, all complete as per existing drawings of VIP lounge and toilet. The agency shall be solely responsible for the adequacy and structural safety of the proposed structure. After approval of 3-D concept design, architectural/engineering drawing 3 (three) set of good for construction design & drawing showing all relevant details shall be submitted duly signed by consultant and after completion of work as build drawing (U3 sets) to be submitted.	Item90	1.00	Job	110000.00	110000.00	INR One Lakh Ten Thousand Only

5-V-4 (Proprietor)

सहायक महाप्रबन्धक (अभि-संवित्त)
Asstt General Manager (Engg.-Civil)
भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2.00	Electrical works :						
2.01	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	Item91	29.00	Point	1250.00	36250.00	INR Thirty Six Thousand Two Hundred & Fifty Only
2.02	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	Item92	40.00	Point	800.00	32000.00	INR Thirty Two Thousand Only
2.03	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required. (a)(2 X 2.5 sq. mm +1 X 2.5 sq. mm earth wire)	Item93	215.00	Meter	280.00	60200.00	INR Sixty Thousand Two Hundred Only
2.04	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess , including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	Item94	2.00	Each	450.00	900.00	INR Nine Hundred Only
2.05	Wiring for light/ power plug with 2X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 1 No 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	Item95	150.00	Metre	350.00	52500.00	INR Fifty Two Thousand Five Hundred Only
2.06	Supplying and fixing following size/modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required. 3 Module (100mmx75mm)	Item96	8.00	Each	225.00	1800.00	INR One Thousand Eight Hundred Only
2.07	Supplying and fixing following size /modules, GI box along with modulat base & Cover plate for modular switches in recess etc. as required. 6 Module	Item97	13.00	Each	290.00	3770.00	INR Three Thousand Seven Hundred & Seventy Only
	Supplying and fixing following modular switch/socket on the existing modular plate & switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 5/6 A switch	Item98	19.00	Each	110.00	2090.00	INR Two Thousand & Ninety Only
	Supplying and fixing following modular switch/socket on the existing modular plate & switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 15/16 A switch	Item99	8.00	Each	100.00	800.00	INR Eight Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2.10	Supplying and fixing following modular switch/socket on the existing modular plate & switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 3 pin 5/6 A socket outlet.	Item100	19.00	Each	80.00	1520.00	INR One Thousand Five Hundred & Twenty Only
2.11	Supplying and fixing following modular switch/socket on the existing modular plate & switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. 6 pin 15/16 A socket outlet.	Item101	8.00	Each	140.00	1120.00	INR One Thousand One Hundred & Twenty Only
2.12	Supplying and fixing following size/modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required. 2 Module (75mmx75mm)	Item102	5.00	Each	200.00	1000.00	INR One Thousand Only
2.13	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (Telephone socket outlet(RJ-11))	Item103	3.00	Each	100.00	300.00	INR Three Hundred Only
2.14	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (TV antenna socket outlet)	Item104	1.00	Each	200.00	200.00	INR Two Hundred Only
2.15	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required. (Conduit 25 mm)	Item105	80.00	Meter	200.00	16000.00	INR Sixteen Thousand Only
2.16	Supplying and drawing co-axial TV cable RG-6 grade, 0.7 mm solid copper conductor PE insulated, shielded with fine tinned copper braid and protected with PVC sheath in the existing surface/ recessed steel/ PVC conduit as required.	Item106	100.00	Meter	35.00	3500.00	INR Three Thousand Five Hundred Only
	Supplying and fixing of following ways surface/recess mounting, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415V, on surface/recess, complete with tinned copper bus bar, neutral bus bar, earth bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator) 6 way (4+18), PPI DB, Double door	Item107	1.00	Meter	11500.00	11500.00	INR Eleven Thousand Five Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2.18	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way, Double door	Item108	1.00	Each	1600.00	1600.00	INR One Thousand Six Hundred Only
2.19	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 12 way, Double door	Item109	1.00	Each	1800.00	1800.00	INR One Thousand Eight Hundred Only
2.20	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.(Single pole MCB 6-32 Amp)	Item110	20.00	Each	165.00	3300.00	INR Three Thousand Three Hundred Only
2.21	Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required.	Item111	4.00	Each	25.00	100.00	INR One Hundred Only
2.22	Supplying and fixing following rating, double pole, (single phase and neutral), 240 volts, Miniature circuit breaker (MCB), in the existing MCB DB complete with connections, testing and commissioning etc. as required.	Item112	2.00	Each	600.00	1200.00	INR One Thousand Two Hundred Only
2.23	Supplying and fixing following rating, double pole, (single phase and neutral), 240 volts, miniature current circuit breaker (MCB), in the existing MCB DB complete with connections, testing and commissioning etc. as required (40 amps)	Item113	3.00	Each	850.00	2550.00	INR Two Thousand Five Hundred & Fifty Only
2.24	Supplying and fixing Cable End Box (Loose Wire Box) suitable for following triple pole and neutral, sheet steel, MCB distribution board, 415 Volts, on surface /recess, complete with testing and commissioning etc. as required. For 6 way, Double door TPN MCBDB	Item114	1.00	Each	1200.00	1200.00	INR One Thousand Two Hundred Only
	Supplying and fixing Cable End Box (Loose Wire Box) suitable for following single pole and neutral, sheet steel, MCB distribution board, 240 Volts, on surface /recess, complete with testing and commissioning etc. as required. For 12 way, Double door SPN MCBDB	Item115	2.00	Each	650.00	1300.00	INR One Thousand Three Hundred Only
	Supplying and fixing following rating, four pole, 415 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63A	Item116	1.00	Each	750.00	750.00	INR Seven Hundred & Fifty Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2.27	Supply of recessed mounted LED circular downlighter of rated capacity of 15W to 20 W, with minimum lumen output 95 lumens per Watt, pre die- cast aluminium housing, integrated driver and suitable to operate on 230-240V, 50Hz AC supply complete as per technical specification etc as required.(Make : Philips (LuxSpace Pro) Model: DN590B M LED20S -6500 PSU WH WD or equivalent.)	Item117	50.00	Each	2650.00	132500.00	INR One Lakh Thirty Two Thousand Five Hundred Only
2.28	Supply of approx 4 feet length recessed LED luminaire of rated capacity 14 W to 20 W, minimum lumen output 95 lumens/Watt, with pre-wired luminaire, aluminium extruded linear lighting luminaires, internal wiring, integral electronic control driver complete etc. as required.(Make : Philips (PureLine Slim) Model: RC780X LED22S-6500 PSU W5L113 OD WH) or equivalent.)	Item118	44.00	Each	4500.00	198000.00	INR One Lakh Ninety Eight Thousand Only
2.29	Supply of LED flexible type Strip Light complete with drivers etc. complete as required. (Make : Philips, SkyCove LED Strip : LED Strip SKYCove 5M WW with driver or equivalent)	Item119	30.00	Mtr.	250.00	7500.00	INR Seven Thousand Five Hundred Only
2.30	Supplying , installation , testing and commissioning of Passive Infrared(PIR) technology based occupancy sensor having high performance , non regulated programmable type , suitable for connected load upto 10Amp , for mounting height up to 2.8 mtr and for 5 m diameter coverage area along with necessary fixing arrangements i/c programming at site etc. complete as required.	Item120	7.00	Each	3500.00	24500.00	INR Twenty Four Thousand Five Hundred Only
2.31	Installation, testing and commissioning of pre-wired, LED Recess/ surface Mounted, 15-20W LED fitting etc of item no-26 above fixtures with all accessories including nut bolt washer and hanging/fixing arrangements if required directly on existing in False ceiling / surface/ including connection as per site requirement.	Item121	50.00	Each	260.00	13000.00	INR Thirteen Thousand Only
2.32	Installation, testing and commissioning of pre-wired, 14-20 watt LED Slash LED Recess/ surface Mounted, LED light etc of item no-27 above fixtures with all accessories including nut bolt washer and hanging/fixing arrangements if required directly on existing in False ceiling / wall / surface including connection as per site requirement.	Item122	44.00	Each	300.00	13200.00	INR Thirteen Thousand Two Hundred Only
2.33	Installation, testing and commissioning of pre-wired, LED strip on Recess/ surface etc of item no-28 above fixtures with all accessories including wiring, hanging/fixing arrangements if required directly on existing in False ceiling / wall / surface including connection as per site requirement.	Item123	30.00	Each	260.00	7800.00	INR Seven Thousand Eight Hundred Only
2.34	Supplying and fixing modular type call bell/ buzzer with LED indication, suitable for single phase, 230 volts, complete as required.	Item124	2.00	Each	600.00	1200.00	INR One Thousand Two Hundred Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2.35	Supply of following sizes of Power Cables, multi stranded conductor, XLPE Insulated, cores laid up, PVC tape / Extruded Inner sheathed , Armour, FRLS at outer sheathed, 1100V grade as per IS 7098(Part 1) 1988 (a) 4 CORE 10 sq.mm. CU Ar. XLPE cable)	Item125	25.00	Meter	600.00	15000.00	INR Fifteen Thousand Only
2.36	Supply of following sizes of Power Cables, multi stranded conductor, XLPE Insulated, cores laid up, PVC tape / Extruded Inner sheathed , Armour, FRLS at outer sheathed, 1100V grade as per IS 7098(Part 1) 1988 (a) 3 CORE 6 sq.mm. CU Ar. XLPE cable	Item126	65.00	Meter	250.00	16250.00	INR Sixteen Thousand Two Hundred & Fifty Only
2.37	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size on cable tray as required. Upto 35 sq. mm (clamped with 0.55mm thick saddle)	Item127	45.00	Meter	30.00	1350.00	INR One Thousand Three Hundred & Fifty Only
2.38	Laying and fixing of one number PVC insulated and PVC sheathed power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq mm (clamped with 0.55mm thick saddle)	Item128	45.00	Meter	38.00	1710.00	INR One Thousand Seven Hundred & Ten Only
2.39	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required. (a) 4 C X 10 sq. mm)	Item129	2.00	Each	220.00	440.00	INR Four Hundred & Forty Only
2.40	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required (a) 3 C X 6 sq. mm	Item130	2.00	Each	150.00	300.00	INR Three Hundred Only
2.41	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	Item131	30.00	Each	50.00	1500.00	INR One Thousand Five Hundred Only
2.42	Supply & fixing of Heavy duty, Wall mounted, fully Automatic Hand Dryers suitable to operate on single phase, 230V, 50Hz AC supply having Stainless steel body, motor speed upto 2500 RPM, noise level upto 70dB, etc.	Item132	4.00	Each	12500.00	50000.00	INR Fifty Thousand Only

Sl. No.	Item Description	Item Code / Make	Quantity	Units	RATE (excluding GST) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
2.50	Supply of 2 pair telephone cable having of 0.5 mm high conductivity, solid annealed bare copper with high density polyethylene insulation, paired, polyester and sheathed with high Oxygen Index, fire retardant, PVC compound, grey outer sheath.	Item140	50.00	Mtr	15.00	750.00	INR Seven Hundred & Fifty Only
2.51	Supply of CAT6 , unarmored , 4 Pair unshielded twisted pair (UTP) LAN (Computer) cable.	Item141	50.00	Mtr	30.00	1500.00	INR One Thousand Five Hundred Only
2.52	Laying /drawing of telephone(2p) / data cable (4p) in existing 25 mm Metal/PVC conduit /casing capping complete as required.	Item142	100.00	Mtr	20.00	2000.00	INR Two Thousand Only
Total in Figures						5590550.24	INR Fifty Five Lakh Ninety Thousand Five Hundred & Fifty and Paise Twenty Four Only
Quoted Rate in Figures				Select		0.0000	Zero Only
Quoted Rate in Words		INR Fifty Five Lakh Ninety Thousand Five Hundred & Fifty and Paise Twenty Four Only					

12/06/23
AGM C (Civil)

अजय सिंह
AJAY SINGH
सहा. महाप्रबन्धक (अभि-सिविल)
Asst. General Manager (Engg.-C)
आरविन्द्रा, लांबवशा अंतरराष्ट्रीय हवाई अड्डा, वाराणसी
A.A.I., L.B.S. International Airport, Varanasi

Signature Not Verified

Digitally signed by VINOD KUMAR PANDEY
Date: ... IST
Location: eProcurement System for Central PSUs

M/s S.K. Construction

Proprietor
लाल बहादुर शास्त्री हवाई अड्डा, वाराणसी
Lal Bahadur Shastri Airport, Varanasi

सहायक महाप्रबन्धक (अभि-सिविल)
Asst. General Manager (Engg.-C/I)
आरविन्द्रा विमानपत्तन प्राधिकरण
Airports Authority of India