

भारतीय विमानपत्तन प्राधिकरण
AIRPORTS AUTHORITY OF INDIA
डिब्रूगढ़ हवाई अड्डा, डिब्रूगढ़
DIBRUGARH AIRPORT, DIBRUGARH

सं.भा.वि.प्रा./डिब/अभि.-सिविल/मेन्त/ W0-05/सुरक्षा दीवार का निर्माण /२३-२४/
Ref.No.AAI/DIB/Engg-Civil/Maint/W0-05/Const of Security wall /23-24

816-31

दिनांक: 23.06.2023

Dated: 23.06.2023

To,
M/s Zeliezhu & Sons,
House No-207, Ground Floor,
Hengerabari Main Road near Hengerabari L.P. School,
Guwahati, Assam-781036

विषय: डिब्रूगढ़ हवाई अड्डे पर रनवे का विस्तार (बैलेंस कार्य), आइसोलेशन बे और अन्य संबद्ध कार्य आदि
(एसएच: डिब्रूगढ़ हवाई अड्डे पर रनवे विस्तार के लिए रक्षा से प्राप्त भूमि में सुरक्षा परिसर की दीवार का निर्माण)।

Name of Work: Extension of Runway (Balance Work), Isolation Bay and other allied works etc. at Dibrugarh Airport (SH: Construction of Security Compound wall in the land acquired from defense for runway extension at Dibrugarh Airport)

संदर्भ: निविदा क्रमांक - 2023_AAI_154284_1 (कार्य की वित्तीय ई-बोली 12.06.2023 को खोली गई)

Ref.: Tender ID No. 2023_AAI_154284_1 (Financial E-Bid for the work opened on 12.06.2023)

महोदय/Sir,

- उपर्युक्त कार्य हेतु आपकी ई निविदा के सम्बन्ध में, आपके द्वारा उद्धरित राशि कुल **₹.1,27,48,825.00** (एक करोड़ सत्ताईस लाख अड़तालीस हजार आठ सौ पच्चीस रुपये मात्र) गुड्स एंड सर्विस टैक्स के बिना, जो कि निविदा की प्राक्कलित मूल्य **₹. 1,65,29,100.00** से **22.87%** नीचे है, को अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से स्वीकृत किया जाता है।

Your E-tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India, at the item rate quoted by you totaling to **Rs.1,27,48,825.00 (One Crore Twenty Seven Lakhs Forty Eight Thousand Eight Hundred Twenty Five Rupees Only) excluding GST** which is **22.87% (Twenty Two point Eight Seven Percent)** below the estimate cost put to tender **₹ 1,65,29,100.00**.

- वरिष्ठ प्रबंधक** (इंजीनियरिंग.-सिविल.), डिब्रूगढ़ विमानपत्तन उपरोक्त कार्य के प्रभारी अभियंता होंगे। अतः आपसे अनुरोध किया जाता है की दिनांक: 18.07.2023 तक **वरिष्ठ प्रबंधक** (इंजीनियरिंग.-सिविल.), भा.वि.प्रा., डिब्रूगढ़ के कार्यालय में आकर अनुबंध पर हस्ताक्षर करने और समझौता पूरा करें। अनुबंध को रुपये 100/- (केवल एक सौ रुपये के गैर-न्यायिक स्टॉप पेपर पर निष्पादित किया जाएगा।) -/100 एक सौ रुपये मात्र (और स्टाम्प पेपर की कीमत आपको वहन करनी होगी।)

Senior Manager (Engg-Civil) AAI, Dibrugarh Airport, Dibrugarh, shall be the Engineer-In-Charge of the work. You are requested to attend the office of **Senior Manager (Engg-Civil)**, AAI, Dibrugarh Airport by 18.07.2023 to sign and complete the contract agreement. The

S. Sagar
23/6/2023
SM(E-C)

contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100/- (Rupees One hundred only) and the cost of the stamp paper shall be borne by you.

2. कृपया इस पत्र के जारी होने के 10 दिनों के अन्दर प्रतिभूति जमा के रूप में **₹ 12,74,882.50 (रुपये बारह लाख चौहत्तर हजार आठ सौ बयासी दशमलव पांच शून्य मात्र)** की राशि इस कार्यालय में जमा करा दें अन्यथा संविदा की सामान्य शर्तों के खंड 1A पृष्ठ संख्या जीसी.सी. 16 पर खंड 1A कि शर्त के अनुसार घटाया जाएगा।

Please deposit **Rs 12,74,882.50 (Rupees Twelve Lakhs Seventy Four Thousand Eight hundred Eighty Two Point Five Zero Only)** towards security deposit within 10 days from the date of issue of this letter, failing which, the same will be deducted from your running bills as per GCC Clause 1A on page 17 of the contract document.

3. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और ठेका श्रम (विनियमन और उन्मूलन) केंद्रीय नियम 1971, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण श्रमिक (रोजगार का विनियमन और सेवा की शर्तों) के प्रावधान का पालन करें।) अधिनियम 1996, भवन और अन्य निर्माण श्रमिक कल्याण उपकर अधिनियम 1996 जैसा कि खंड 19 पृष्ठ संख्या 50 पर में निर्दिष्ट है और संविदा की सामान्य शर्तों के पेज नं 89 और केंद्र और राज्य सरकार के नियम।

You are requested to comply with the provision of Contract Labour (Regulation and Abolition) Act 1970 and Contract Labour (Regulation and Abolition) central rules 1971, Child labour (Prohibition & Regulation) Act 1986, Construction workers (Regulation of Employment and Conditions of Service) Act 1996, Building and other Construction workers welfare cess Act 1996 as specified in clause 19 on page no. 50 and page no. 89 of GCC of tender and rules of Central and State Govt.

4. आपको यह भी निर्देश दिया जाता है कि आप **वरिष्ठ प्रबंधक (अभि.-सिविल), भा.वि.प्रा., डिब्रूगढ़** से अविलम्ब संपर्क करें जो आपको कार्यस्थल सौंपने की व्यवस्था करेंगे।

You are also directed to contact **Senior Manager, AAI, Dibrugarh Airport, Dibrugarh** immediately who will arrange to hand over the work to you.

5. कृपया ध्यान दें कि कार्य करने के लिए अनुमत समय **05 (पांच)** माह होगा जिसमें वर्षा ऋतु के 02 महीने शामिल हैं और इसे इस पत्र के जारी होने के 10 वें दिन या साइट को सौंपने की वास्तविक तिथि जो भी पहले हो, से माना जाएगा

Please note that the time allowed for carrying out the work shall be **05 (Five) Months** including 02 months considered for rain season and same shall be reckoned from the 10th day after issue of this letter or the actual date of handing over the site whichever is earlier.

6. इस अनुबंध से सम्बंधित किसी भी प्रकार के पत्राचार **वरिष्ठ प्रबंधक (इंजीनियरिंग.-सिविल.) भारतीय विमानपत्तन प्राधिकरण, डिब्रूगढ़ विमानपत्तन, डिब्रूगढ़ - 786012** को संबोधित किया जाना चाहिए।

Any further correspondence in connection with the contract should normally be addressed to the **Senior Manager (Engg-Civil), Airports Authority of India, Dibrugarh Airport - 786012.**

S. Sagar
23/6/23
SM(E-C)

7. कृपया इस पत्र के प्राप्ति की सूचना दें तथा इसके साथ संलग्न इस पत्र की प्रतिलिपि पर विधिवत हस्ताक्षर करने के उपरांत स्वीकृति के प्रमाण स्वरूप इसे अधोहस्ताक्षरी को वापस भेजे।

Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.


8. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण मान्य होगा।

In case of any discrepancy is found then English version will be taken as correct.

धन्यवाद / Thanking you,

संलग्न: Item Rate SOQ. (Page-01 to 03)

भवदीय/Yours Sincerely,



सतपाल सागर (Satpal Sagar)

वरिष्ठ प्रबंधक (इंजीनियरिंग.-सिविल)/ Senior Manager (Engg.– Civil)

कृते तथा की ओर से अध्यक्ष, भा.वि.प्रा. / For and on behalf of Chairman, AAI

भा.वि.प्रा. डिब्रूगढ़ विमानपत्तन / AAI, Dibrugarh Airport

Tender Inviting Authority: Bonny Bastian, DGM(Engg-Civil), AAI, Dibrugarh Airport

Name of Work: Extension of Runway (Balance Work), Isolation Bay and other allied works etc at Dibrugarh Airport, (SH: Construction of Security Compound wall in the land acquired from defense for runway extension at Dibrugarh Airport.)

Contract No: 2022-AA-154294_1

Name of the Bidder/ Bidding Firm / Company :	ZELIEZHU AND SONS
--	-------------------

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words	TEXT #
1	1	3	4	5	6	7	
1	Dismantling the foundation after excavation, dismembering each element carefully and taking out and stacking all parts carefully numbered and bundled for a lead up to 2 Km, existing colour coated weld mesh fencing in defence area of height 2.6 with additional 1.00 m Concertina coils and 6 nos runner wires over hanging demarketing defence area erected by Military engineers at site. The existing fencing consists of colour coated poles placed approximately 2.50 m centre to centre filled with specialised colour coated weld mesh with nut and bolt arrangements. The work includes dismembering each component like concertina runner wire, concertina coil, weld mesh and poles and stacking properly to re-erect at location shown by the Defence. The cost shall include all activities for excavation required, dismantling the concrete on which the poles are fixed, transportation and orderly stacking etc complete as per the direction of engineer in charge.	510.00	metre			INR Five Lakh Eighty Nine Thousand & Fifty Only	
2	Fixing and re erecting weld mesh fencing obtained under item No.1 at approved location in coordination with defence authorities in the same pattern it was originally available including excavation for foundation of poles, required welding /modification for available poles, adding additional members if required, additional nuts and bolts as per site requirements, cost of cement concrete mix 1:1.5:3 (1 cement 1.5 coursed sand 3 stone aggregate 20 mm nominal size), etc complete as per the direction of engineer in charge.	510.00	metre	1155.00	589050.00	INR Fifteen Lakh Seven Thousand & Fifty Only	
3	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material upto a lead of 1 km, as per direction of Engineer-in-charge.	12.00	Cum	2955.00	1507050.00	INR Three Thousand Five Hundred & Forty Only	
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil	2479.00	cum	295.00	3540.00	INR Three Lakh Fifty Nine Thousand Four Hundred & Fifty Five Only	
				145.00	359455.00		

880905
23/6/23
SWE-C

5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	1387.00	cum				INR One Lakh Thirty One Thousand Seven Hundred & Sixty Five Only
6	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials All kinds of soil	413.00	cum		95.00	131765.00	INR Twenty Two Thousand Seven Hundred & Fifteen Only
7	Providing and filling, Boulders or river shingles of size ranging from 150 mm to 225 mm in layers not exceeding 25 cm in foundations upto plinth including filling voids / gaps with sand or graded river pebbles, watering and compacting with earth rammers or suitable compactors of sufficient capacity to achieve required density to the required thickness for improving the foundation soil all complete as per direction and satisfaction of Engineer (Note: - Please read the Technical specifications of the item on before quoting). -in-charge	690.00	cum		55.00	22715.00	INR Eight Lakh Sixty Five Thousand Nine Hundred & Fifty Only
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand (zone-II)) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	138.00	cum		1255.00	865950.00	INR Five Lakh Eighty Seven Thousand One Hundred & Ninety Only
9	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	521.00	sqm		4255.00	587190.00	INR One Lakh Seventy Four Thousand Five Hundred & Thirty Five Only
10	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, bressumers and cantilevers	1098.00	sqm		335.00	174535.00	INR Three Lakh Fifty Six Thousand Eight Hundred & Fifty Only
11	Centering and shuttering including strutting, propping etc. and removal of form for : Columns, Pillars, Piers, Abutments, Posts and Struts	983.00	sqm		325.00	356850.00	INR Two Lakh Ninety Nine Thousand Eight Hundred & Fifteen Only
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars Grade of steel: Fe 500	18793.00	Kg		305.00	299815.00	INR Fifteen Lakh Ninety Seven Thousand Four Hundred & Five Only
13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete Above plinth level upto Thermo-Mechanically Treated bars Grade of steel: Fe 500	6312.00	Kg		85.00	1597405.00	INR Five Lakh Thirty Six Thousand Five Hundred & Twenty Only
14	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III)) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	309.00	cum		85.00	536520.00	INR Nineteen Lakh Sixty Three Thousand Six Hundred & Ninety Five Only
15	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III)) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	14.00	cum		6355.00	1963695.00	INR Eighty Eight Thousand Nine Hundred & Seventy Only
					6355.00	88970.00	

880925
23/6/23
SM(E-C)

16	Reinforced cement concrete work in beams , suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level , excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand/zone-II) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	29.00	cum				INR One Lakh Eighty Four Thousand Two Hundred & Ninety Five Only
17	Brick work with common burnt clay F .P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in : Cement mortar 1:6 (1 cement : 6 coarse sand) /AAC Block	76.00	cum		6355.00	184295.00	INR Four Lakh Sixty Thousand One Hundred & Eighty Only
18	Brick work with non modular fly ash bricks conforming to IS :12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in Cement mortar 1:6 (1 cement : 6 Coarse sand)	242.00	cum		6055.00	460180.00	INR Seventeen Lakh Twenty Four Thousand Two Hundred & Fifty Only
19	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1415.00	Kg		7125.00	1724250.00	INR Two Lakh Nineteen Thousand Three Hundred & Twenty Five Only
20	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	1052.00	Sqm		155.00	219325.00	INR One Lakh Ninety Four Thousand Six Hundred & Twenty Only
21	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand),	1052.00	Sqm		185.00	194620.00	INR One Lakh Sixty Three Thousand & Sixty Only
22	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	574.00	Sqm		155.00	163060.00	INR Seventy One Thousand Seven Hundred & Fifty Only
23	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 lit/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	1029.00	Sqm		125.00	71750.00	INR Two Lakh Ten Thousand Nine Hundred & Forty Five Only
24	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	49.00	Sqm		205.00	210945.00	INR Ten Thousand & Forty Five Only
25	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre operable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G .I. barbed wire tied to angle iron , all complete as per direction of Engineer -in-charge, with reinforced barbed tape (R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	510.00	metre		205.00	10045.00	INR Four Lakh Twenty Five Thousand Eight Hundred & Fifty Only
Total in Figures					835.00	425850.00	INR One Crore Twenty Seven Lakh Forty Eight Thousand Eight Hundred & Twenty Five Only
Quoted Rate in Words		INR One Crore Twenty Seven Lakh Forty Eight Thousand Eight Hundred & Twenty Five Only					


 22/11/2023
 SH(E-C)