

भाविप्रा/कोल्हापुर/उप.म.(अभि-सि)/डब्ल्यू-03/2023-24/96
AAI/Kolhapur/Dy.GM (Engg-C)/W-03/2023-24/96

दिनांक: 20/07/2023
Date: 20/07/2023

सेवा मे,
मेसर्स पारिख कश्यप इंदुलाल,
801, रामेश्वर अपार्टमेंट,
जलाराम-1, गली नं. 2/3,
यूनिवर्सिटी रोड, राजकोट - 360 007.

To,
M/s. Parikh Kashyap Indulal,
801, Rameshwar Apartment,
Jalaram -1, Street No. 2/3,
University Road, Rajkot - 360 007.

कार्य का नाम : - कोल्हापुर हवाई अड्डे का विकास। उपशीर्ष: एनटीबी में प्रावधान जैसे चेक इन काउंटर, एस.एस. बोलाईस, मे आई हेल्प डेस्क, आंतरिक विभाजन, सन कंट्रोल फिल्म, रिफ्लेक्टिव फिल्म, सुगम्य भारत अभियान के अनुसार दिव्यांग लोगों के लिए सुविधाओं का प्रावधान, एसीपी क्लैडिंग, एसएस रेलिंग आदि।

Name of Work: Development of Kolhapur Airport. SH - Provision in NTB viz Check in Counters, S.S Bollards, May I help desk, Internal Partition, Sun Control Film, Reflective Film, Provision of Facilities for Differently Abled People as per Accessible India Campaign, ACP Cladding, SS Railing etc.

संदर्भ:- दिनांक 22/06/2023 को खोला गया आपका ई-टेंडर 2023_AAI_154740_1 (वित्तीय लिफाफा)।

Ref: Your e-tender no. 2023_AAI_154740_1 (financial bid) opened on 22/06/2023.

महोदय/Sir,

- उपरोक्त कार्य हेतु आपकी ई-निविदा अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण की ओर से, आपके द्वारा उद्धृत मद दर पर कुल रु. 2,44,97,167/- (रु. दो करोड़ चवालीस लाख सत्तानवे हजार एक सौ सड़सठ, मात्र) (GST के बगैर) पर स्वीकृत की जाती है जो की निविदा में रखी गयी अनुमानित लागत रु. 3,11,00,000/- (रु. तीन करोड़ ग्यारह लाख, मात्र) से 21.23 % नीचे है।

Your E-Tender for the work mentioned above is hereby accepted on behalf of the Chairman, Airports Authority of India at the item rates quoted by you totaling to Rs. 2,44,97,167/- (Rs. Two Crore Forty-Four Lakhs Ninety-Seven Thousand One hundred & Sixty-Seven, only) (Excluding GST) which is 21.23% below the estimated cost put to tender of Rs. 3,11,00,000/- (Rs. Three Crore Eleven Lakhs, only).

- उप महाप्रबंधक (इंजी-सिविल), भारतीय विमानपत्तन प्राधिकरण, कोल्हापुर विमानक्षेत्र, कोल्हापुर कार्य प्रभारी अभियंता होंगे। आपसे निवेदन है कि आप स्वयं या आपकी ओर से एक विश्वसनीय प्रतिनिधि प्रतिनियुक्त करे जो करारनामे पर हस्ताक्षर करने के लिए अधिकृत हो तथा वह दिनांक 18/08/2023 तक संयुक्त महाप्रबंधक (इंजी-सिविल), भाविप्रा, कोल्हापुर विमानक्षेत्र के कार्यालय में उपस्थित हो तथा करारनामे को पूरा करे। ठेके का करारनामा रु. 300/- (रु. तीन सौ मात्र) के नोन-ज्यूडिशियल स्टेम्प पेपर पर निष्पादित किया जाएगा, तथा पेपर का खर्च आपके द्वारा वहन किया जाएगा।

Deputy General Manager (Engg- Civil), Airports Authority of India, Kolhapur Airport, Kolhapur shall be the Engineer-in-charge of the work. You are requested to attend or depute your accredited representative, empowered to sign the contract agreement on your behalf, to attend


20/07/2023

the office of the Dy. General Manager (Engg- Civil), AAI, Kolhapur Airport by **18/08/2023** to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value **Rs. 300/- (Rs. Three Hundred only)** and the cost of the stamp paper shall be borne by you.

2. इस निविदा के साथ मांगी गयी अग्रिम धन राशि **रु. 6,22,000.00/- (रु. छह लाख बाईस हजार, मात्र)** थी जो की आपके मूल खाते मे प्राप्त हो जावेगी। कृपया, प्रतिभूति निक्षेप राशि **रु. 24,49,717.00/- (रु. चौबीस लाख उनतालीस हजार सात सौ सत्रह, मात्र)** इस पत्र के निर्गत दिनांक से दस दिनों के भीतर जमा करें अन्यथा उक्त धनराशि की कटौती संविदा प्रपत्र की उक्त संदर्भित शर्त 1A पृष्ठ क्रमांक GCC-16 के अनुसार की जाएगी।

The earnest money deposit of **Rs. 6,22,000.00 (Rs. Six Lakh Twenty-Two Thousand, Only)** will be refunded back to your original account. Please deposit **Rs. 24,49,717.00/- (Rupees Twenty-Four Lakh Forty-Nine Thousand Seven Hundred & Seventeen only)**, towards security deposit within 10 days from the date of issue of this letter, failing which the same will be deducted as per condition of GCC Clause no. 1A at page 16 of GCC of tender document.

3. आपसे अनुरोध है कि अनुबंध श्रम (विनियमन और उन्मूलन) अधिनियम 1970 और अनुबंध श्रम (विनियमन और उन्मूलन) 1971 केंद्रीय नियमों के प्रावधान का पालन करे, बाल श्रम (निषेध और विनियमन) अधिनियम 1986, निर्माण कार्यकर्ता (रोजगार का विनियमन और सेवा की शर्त) अधिनियम 1996, बिल्डिंग और अन्य निर्माण कार्यकर्ता कल्याण सेस अधिनियम 1996 जैसा कि निविदा के जीसीसी के खंड 19 पृष्ठ 49 और केंद्रीय तथा राज्य सरकार के नियमों में निर्दिष्ट है।

You are requested to comply with the provision of Contract labour (Regulation and Abolition) Act 1970 and Contract labour (Regulation and Abolition) Central rules 1971 Child labour (Prohibition and Regulation) Act 1986, Construction workers (Regulation of Employment and Condition of service) Act 1996, Building and other construction workers welfare cess act 1996 as specified in clause 19 page 49 of GCC of tender & minimum wage act and rules of Central and state government.

4. आपको निर्देश दिया जाता है कि आप तुरंत **वरिष्ठ प्रबंधक (इंजी-सिविल)**, भाविप्रा, कोल्हापुर विमानक्षेत्र से मिले वह आपको साइट सौंपने की व्यवस्था करेंगे। कृपया नोट कर ले कि काम करने का अनुमत समय **04 (चार) महीना** है जोकि दिनांक 31/07/2023 से गिना जायेगा।

You are also directed to contact **Senior Manager (Engg-Civil)**, AAI, Kolhapur Airport immediately who will arrange to hand over site to you. Please note that, the time allowed for carrying out the work is **04 (Four) Months** which shall be reckoned from the date 31/07/2023.

5. इस ठेके के संबंध में आगे की कोई भी पत्राचार **उप महाप्रबंधक (इंजी-सिविल)**, भाविप्रा, कोल्हापुर विमानक्षेत्र, कोल्हापुर 416004 के पते पर किया जाए।

Any further correspondence in connection with the contract should normally be addressed to the **Deputy General Manager (Engg-Civil)**, AAI, Kolhapur Airport, Kolhapur -416004.

6. उपरोक्त संदर्भित सभी पत्र इस ठेके का भाग होंगे।

All the letters referred above shall from part of contract.


7. उपरोक्त कार्य के लिए त्रुटि दायित्व की अवधि 12 (बारह) महीने होगी।

The defects liability period for the above-mentioned work is 12 (Twelve) months.

 20/08/23

8. यदि ठेकेदार को किसी भी सुरक्षा नियम का उल्लंघन करते हुए पाया जाता है, तो वह ब्लैक लिस्टेड हो जाएगा और अन्य कानूनी कार्यवाही के लिए जिम्मेदार होगा।
If Contractor is found violate any of Security Regulations, he shall be Black listed and will be responsible subjected to other Legal Proceedings.
9. स्वीकृति के प्रतीक के रूप में अधिसूचना में हस्ताक्षर करने के बाद कृपया इस पावती को स्वीकार करें और इस पत्र की नकल प्रतिलिपि वापस करें।
Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a token of acceptance.
10. यदि कोई विसंगति पाई जाती है तो अंग्रेजी संस्करण को सही रूप में लिया जाएगा।
In case any discrepancy is found then English version will be taken as correct.

भवदीय /Yours faithfully



उप महाप्रबंधक (अभि-सिविल),

भाविप्रा, कोल्हापुर हवाईअड्डा, कोल्हापुर
कृते अध्यक्ष, भारतीय विमानपत्तन प्राधिकरण
Deputy General Manager (Engg.-Civil),
AAI, Kolhapur Airport, Kolhapur
For & on behalf of Chairman, AAI

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: <AGM (Engg.-Civil), AAI, Kolhapur Airport>

Name of Work: <"Development of Kolhapur Airport.

SH: - Provision in NTB viz Check in Counters, S.S Bollards, May I help desk, Internal Partition, Sun Control Film/Reflective Film, Provision of Facilities for Differently Abled People as per Accessible India Campaign, ACP Cladding, SS Railing etc.">


Contract No: <0231- 2677706, 2023_AAI_154740_1>

Name of the Bidder/ Bidding Firm / Company :	Parikh Kashyap Indulal
--	------------------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8	10
1	Providing and fixing ISI mark Commercial plywood of approved brand like kitply, greenply or equivalent with necessary screws, nails and nuts wherever necessary etc. complete as per direction of Engineer-in-charge. a) 19 mm thick commercial plywood	item1	248.000	Sqm		1900.00	471200.00	INR Four Lakh Seventy One Thousand Two Hundred Only
2	Providing and fixing ISI mark Commercial plywood of approved brand like kitply, greenply or equivalent with necessary screws, nails and nuts wherever necessary etc. complete as per direction of Engineer-in-charge. a) 6mm thick commercial plywood	item2	7.000	Sqm		925.00	6475.00	INR Six Thousand Four Hundred & Seventy Five Only
3	Providing and fixing 12mm thick solid acrylic polymer LG HAUSYS S028/ G101 or equivalent of approved colour with necessary adhesive, screws, nails and nuts etc. wherever necessary including bending in desired shape if required as per drawing complete as per direction of Engineer-in-charge.	item3	85.000	Sqm		15400.00	1309000.00	INR Thirteen Lakh Nine Thousand Only
4	Providing & Fixing decorative high pressure laminated sheet of plain /wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality. a) 1.0 mm thick	item4	211.000	Sqm		1100.00	232100.00	INR Two Lakh Thirty Two Thousand One Hundred Only
5	Providing and fixing IS : 12817 marked stainless steel butt hinges with stainless steel screws etc. complete : a) 100X58X1.90 mm	item5	56.000	Each		250.00	14000.00	INR Fourteen Thousand Only
6	Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete. a)125 mm	item6	28.000	Each		150.00	4200.00	INR Four Thousand Two Hundred Only
7	Providing edge moulding to 18 mm thick marble/granite stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc complete as per design approved by Engineer-in-Charge. a) Granite stone	item7	89.000	Mtrs		350.00	31150.00	INR Thirty One Thousand One Hundred & Fifty Only
8	Providing and fixing 18mm thick granite of any colour machine cut machine polished of required size, fixed on table top with suitable adhesive as per direction of Engineer-in-charge and finished.	item8	21.000	Sqm		3350.00	70350.00	INR Seventy Thousand Three Hundred & Fifty Only
9	Providing and fixing special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc. complete. a) 50 mm	item9	36.000	Each		750.00	27000.00	INR Twenty Seven Thousand Only



20/11/2023

10	Providing and fixing powder coated telescopic drawer channels 300 mm long with necessary screws etc. complete as per directions of Engineer- in-charge. a) one set	item10	32.000	one Set	750.00	24000.00	INR Twenty Four Thousand Only
11	Providing and fixing of Stainless Steel Bollard made of SS: 304 grade having 1000mm projected height & 150mm dia with 2.77mm thickness having truncated top at 45 degree as per drawing. The base plate shall be of 250 mm dia 8 mm thick of stainless steel: 304 grades, cover with stainless steel plate of 1.5 mm thick flushing with ground. The upper part (truncated portion) of Bollard shall be covered with 3mm thick SS: 304 grade sheet. The complete Bollard should be fixed with minimum 03 nos. 100mm height & 10mm dia fasteners for fixing at ground as shown in drawing including, welding, polishing, buffing complete with necessary holes etc. The bollard should have 3 Nos. of reflective band strip of size 50 mm wide all around with micro prismatic retro-reflective sheeting grade type VIII as per ASTM-D-4956-07, pasted on the Bollard for better visibility at night including demolishing existing granite /concrete and restoring the same, all complete as per direction of Engineer-In-Charge.	item11	60.000	Each	7500.00	450000.00	INR Four Lakh Fifty Thousand Only
12	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	item12	1263.000	kg	630.00	795690.00	INR Seven Lakh Ninety Five Thousand Six Hundred & Ninety Only
13	Providing and fixing in position tactile directional strips as per the approved lay out made of stainless steel material of grade SS 316 having antiskid linear grooves with plain bevel edges. The dimensions of the strip should be 280mm x 35mm x 4.5mm and dimensions of the stem should be 6mm x 12mm (with groove in the centre) having 3 no stem and the centre to centre distance between the stem of one strip should be 120mm. The tactile strip must be installed along the direction of travel with correct spacing between each unit @ 4 tactile strips within a spacing of 300mm x 300mm. For installation of the strips, the floor needs to be drilled for about 12mm depth without breaking the floor and after cleaning the floor epoxy grout need to be injected and the tactile strips should be placed over the holes complete as per the particular specification and directions of EIC.	item13	4000.000	each piece	340.00	1360000.00	INR Thirteen Lakh Sixty Thousand Only
14	Providing and fixing in position tactile warning studs as per the approved layout made of stainless steel material of grade SS 316 having antiskid concentric circles with plain bevel edges. The dimensions of the studs should be 35mm reduced to 25mm x 4.5mm and dimensions of the stem should be 6mm x 12mm (with groove in the centre) having 1 no. stem. The tactile stud must be installed with correct spacing between each unit @36 tactile studs within a spacing of 300mm x 300mm. For installation of studs the floor need to be drilled for about 12 mm depth without damaging/breaking the floor and after cleaning the floor epoxy grout needs to be injected and the tactile stud should be placed in the holes complete as per the particular specification and direction of EIC.	item14	17000.000	each piece	70.00	1190000.00	INR Eleven Lakh Ninety Thousand Only
15	Providing and Fixing Reflective Film of 3M India Ltd./Lumar/Garware/Avery Dennison or equivalent as per the manufacture Specification on glass including cleaning of glass etc. complete as per direction of engineer in charge.	item15	170.000	sqm	625.00	106250.00	INR One Lakh Six Thousand Two Hundred & Fifty Only
16	Providing and Fixing Opaque /Frosted Film of 3M India Ltd./Lumar/Garware/Avery Dennison or equivalent as per the manufacture Specification on glass including cleaning of glass etc. complete as per direction of engineer in charge.	item16	467.000	sqm	550.00	256850.00	INR Two Lakh Fifty Six Thousand Eight Hundred & Fifty Only
17	Providing and fixing safety film of make 3M India Ltd./Lumar/Garware/Avery Dennison or equivalent as per the manufacture, Specification, 7/8 mil safety film on glass panels inside of structural glazing after cleaning of the glass surface with cleaning agent at all floors/levels/height. The rate shall include all taxes, transportation, labour, material, T & P and scaffolding, etc. complete as per direction of Engineer-In-Charge. The length and breadth of finished exposed surface shall be measured in sqm for payment. (NOTE:- The agency should submit warranty for adhesion, strength, appearance and solar reflective properties from manufacturer of safety film for 5 years).	item17	1754.000	sqm	1700.00	2981800.00	INR Twenty Nine Lakh Eighty One Thousand Eight Hundred Only
18	Providing and Fixing Decorative Film 3M India Ltd./Lumar/Garware/Avery Dennison or equivalent as per the manufacture Specification on glass including cleaning etc. complete as per direction of engineer in charge	item18	273.320	sqm	1100.00	300652.00	INR Three Lakh Six Hundred & Fifty Two Only
19	Providing and Fixing Non-Reflective Film of 3M India Ltd./Lumar/Garware/Avery Dennison or equivalent as per the manufacture Specification on glass including cleaning of glass etc. complete as per direction of engineer in charge.	item19	30.000	sqm	600.00	18000.00	INR Eighteen Thousand Only

[Signature]
20/8/2023

20	Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building, for all heights and all levels etc. including: (a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design. (b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. (c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316. Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium items The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete, as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of groove) shall be measured in sqm. up to two decimal places.	item20	1965.000	sqm		3750.00	7368750.00	INR Seventy Three Lakh Sixty Eight Thousand Seven Hundred & Fifty Only
21	Providing and supplying aluminium extruded tubular and other aluminium sections as per the architectural drawings and approved shop drawings, the aluminium quality as per grade 6063 T5 or T6 as per BS 1474, including super durable powder coating of 60-80 microns conforming to AAMA 2604 of required colour and shade as approved by the Engineer-in-Charge. (The item includes cost of material such as cleats, sleeves, screws etc. necessary for fabrication of extruded aluminium frame work. Nothing extra shall be paid on this account). The weight of aluminium extruded section shall be taken for purpose of payment.	item21	10550.000	kg		420.00	4431000.00	INR Forty Four Lakh Thirty One Thousand Only
22	Providing and fixing 12 mm thick frameless toughened glass partition /door shutter of approved brand and manufacture with edge polishing, including patch fittings, hinges, fixing arrangement and making necessary holes etc. all complete as per direction of Engineer in charge (Door handle, lock, stopper, pivot, door closer and aluminium frame if any etc. to be paid separately)	item22	291.000	sqm		3300.00	960300.00	INR Nine Lakh Sixty Thousand Three Hundred Only
23	Providing and fixing vertical blinds of approved make as per manufacturer's specification and size complete in all respect as per direction of Engineer-in-charge. a) 100mm wide pelmets	item23	260.000	sqm		1350.00	351000.00	INR Three Lakh Fifty One Thousand Only
24	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth for all leads and lifts within AAI premises, as directed by Engineer-in-charge. a) All kinds of soil	item24	20.000	cum		200.00	4000.00	INR Four Thousand Only
25	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. a) Ordinary rock	item25	16.000	cum		700.00	11200.00	INR Eleven Thousand Two Hundred Only
26	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	item26	24.000	cum		125.00	3000.00	INR Three Thousand Only
27	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: a) 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	item27	4.000	cum		6000.00	24000.00	INR Twenty Four Thousand Only

[Signature]
 20/12/2023

28	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	item28	4.000	cum	4000.00	16000.00	INR Sixteen Thousand Only
29	Centering and shuttering including strutting, propping etc. and removal of form for all heights : a) Foundations, footings, bases of columns, etc. for mass concrete	item29	120.000	sqm	600.00	72000.00	INR Seventy Two Thousand Only
30	Centering and shuttering including strutting, propping etc. and removal of form for all heights : a) Columns, Pillars, Piers, Abutments, Posts and Struts	item30	72.000	sqm	600.00	43200.00	INR Forty Three Thousand Two Hundred Only
31	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. a) Thermo-Mechanically Treated bars of grade Fe-500D or more	item31	2500.000	kg	95.00	237500.00	INR Two Lakh Thirty Seven Thousand Five Hundred Only
32	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. a) Thermo-Mechanically Treated bars of grade Fe-500D or more	item32	1000.000	kg	95.00	95000.00	INR Ninety Five Thousand Only
33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. All works upto plinth level a) Concrete of M25 grade with minimum cement content of 330 kg /cum Note : -The Mix Design is available with AAI Kolhapur Airport and the same will be provided to the contractor for the work. Contractor has to prepare a trial mix with the design provided by AAI and get the results verified before execution of work. All the material to be used for execution shall be tested and matched with mix design provided by AAI before execution of work. The extra cement as per design will be payable to the contractor under relevant item.	item33	20.000	cum	6500.00	130000.00	INR One Lakh Thirty Thousand Only
34	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. a) In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	item34	9100.000	kg	115.00	1046500.00	INR Ten Lakh Forty Six Thousand Five Hundred Only
35	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : a) Two or more coats on new work.	item35	500.000	sqm	110.00	55000.00	INR Fifty Five Thousand Only
Total in Figures						24497167.00	INR Two Crore Forty Four Lakh Ninety Seven Thousand One Hundred & Sixty Seven Only
Quoted Rate in Words			INR Two Crore Forty Four Lakh Ninety Seven Thousand One Hundred & Sixty Seven Only				

[Handwritten Signature]
20/10/23

Signature Not Verified

Digitally signed by SIDHARTHA NAMDEO BHASME
Date: 2023.10.07 18:51:25 IST
Location: eProcurement System for Central PSUs

