



भारतीय विमानपत्तन प्राधिकरण
Airports Authority of India
VIJAYAWADA AIRPORT, VIJAYAWADA -521 102

Lr. No. AAI/VIJ/ENGG(E-C)/DGM(E-C)/Renovation of Toilets/2023/886 Dt: 25/09/2023.

To,

Speed Post

M/S. SHAIK UMAR MUJIB,
Main Canal Road, 14-1-8/1,
Basiveddypeta,
Nidadavole - 534301,
West Godavari District,
Andhra Pradesh.

Name of work : Renovation of Toilets in Domestic Terminal at Vijayawada Airport.

Ref: (Tender ID no: 2023_AAI_ 154977)

Sir,

1. Your tender for the work mentioned above is hereby accepted on behalf of Chairman, Airports Authority of India, at the item rates quoted by you totaling to Rs. **33,54,693.26/-** (Rupees Thirty-Three lakhs Fifty-Four Thousand Six Hundred and Ninety-Three and Paise Twenty-Six only) excluding GST, which is **18.81%** below the estimated cost put of tender of Rs 41,31,708/-.
2. Dy. General Manager Engg-(C), AAI, Vijayawada Airport, Vijayawada, shall be the Engineer-in-charge of the work. You are requested to attend the office of Dy. General Manager (E-C), AAI, Vijayawada Airport by 10/10/2023 to sign and complete the contract agreement. The contract agreement shall be executed on a non-judicial stamp paper of value Rs. 100.00 (Rupees One Hundred Only) and the cost of the stamp paper shall be borne by you.
3. Please deposit Rs. 3,35,469/- (Rupees Three lakhs Thirty-five thousand four hundred Sixty nine only) towards Security Deposit within 15 days from the date of issue of this letter, failing which, the same will be deducted as per Clause-1A at page GCC-16 of Contract Agreement.
4. You are requested to comply with the provision of Contract Labor (Regulation and Abolition) Act 1970 and Contract Labor (Regulation and Abolition) Central rules 1971, Child labor (Prohibition and Regulation) Act 1986, Construction Worker (Regulation of employment and condition of service) Act 1996, Building and other construction works welfare Cess Act 1996 as specified in Clause 19 on page no GCC-49 and minimum wages Act 1948 and Employees Provident Fund and Misc. Provision Act 1952 and ESI Act 1948 as specified in Clause 20 & Clause 20(A) on Page No GCC-55 & 56 and rules there of Central and State Governments.


[Handwritten signature]
28/09/2023
DGM (E-C)

उप महाप्रबंधक (अभि-सिविल)
Dy. General Manager (Engg-Civil)
भा.वि.प्रा. विजयवाडा
AAI, VIJAYAWADA

5. You are Directed to contact **Asst. General Manager Engg(C)**, AAI, Vijayawada Airport, immediately who will arrange to hand over the site to you.
6. Please note that time allowed for carrying out the work shall be **04 (Four) months** and same shall be reckoned from the 10th day from the date of issue of this letter.
7. Any further correspondence in connection with the contract should normally be addressed to the Engineer-In-charge.
8. Please acknowledge the receipt and return the duplicate copy of this letter enclosed herewith after signing it to the undersigned as a taken of acceptance.

Yours faithfully,

Encl:
Item Rate BOQ


25/09/2023
Dy. General Manager Engg(C),
For and on behalf of Chairman,
Airports Authority of India,
Vijayawada Airport.
उप महाप्रबन्धक (अभि-सिविल)
Dy. General Manager (Engg-Civil)
भा.वि.प्रा, विजयवाडा हवाई अड्डा
AAI, Vijayawada Airport-52110

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: AGM(E-C)

Name of Work: Renovation of toilets in Domestic Terminal at Vijayawada Airport

Contract No: 2023_AAI_154977

Name of the Bidder/ Bidding Firm / Company :		Shaik Umar Mujib					
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	12	13	53	55
1	Rennovation of toilets						
1.01	Dismantling tile work in floors, wall and roofs laid in cement mortar including stacking material within 50 metres lead. a) For thickness of tiles 10 mm to 25 mm.	103.77	Sqm	INR	450.00	46696.50	INR Forty Six Thousand Six Hundred & Ninety Six and Paise Fifty Only
1.02	12 mm cement plaster of mix : a) 1:6 (1 cement: 6 coarse sand)	50.00	Sqm	INR	261.00	13050.00	INR Thirteen Thousand & Fifty Only
1.03	Providing and fixing wash basin long body Pillar cock automatic sensor based of Hindware code: F240003/ Jaquar make Code: (SNR-CHR-51011N) with required fittings complete as directed by Engineer-in-charge.	22.00	Each	INR	10000.00	220000.00	INR Two Lakh Twenty Thousand Only
1.04	Providing and fixing S.S. body automatic liquid soap dispenser of Jaquar make Code: (SDR-BLC-DJ0160AS) or Hindware including cutting and making good the walls, wherever required complete as directed by Engineer-in-charge.	22.00	Each	INR	9000.00	198000.00	INR One Lakh Ninety Eight Thousand Only
1.05	Providing & Fixing of 15 mm dia angle valve of make Jaquar make Code: (AQT-CHR-3053) / Hindware CODE: F850030 with C.P. brass wall flange with any other items complete including unplasticised PVC connection pipe with brass unions of 45cm length & 15mm nominal bore complete in all respect.	22.00	Each	INR	899.00	19778.00	INR Nineteen Thousand Seven Hundred & Seventy Eight Only
1.06	Providing and fixing toilet paper holder of Jaquar make Code: (ACN-CHR-1153S) / Hindware CODE: F880003including cutting and making good the walls, wherever required complete as directed by Engineer-in-charge.	24.00	Each	INR	1550.00	37200.00	INR Thirty Seven Thousand Two Hundred Only

Amul
25/09/2023

उप महाप्रबंधक (अभि-सिविल)
Dy.General Manager (Engg-Civil)

भा.वि.प्रा, विजयवाडा हवाई अड्डा
AAI, Vijayawada Airport-521102

1.07	Providing and fixing beveled edge 5 mm thick Clear mirror of superior glass (of approved quality,size, shade & colour etc.) fixed on 12 mm thick water proof plywood of (Saint Gobain / Modiguard) make to complete fixing on the wall with frame backing or studs with nails and screws and required adhesive at all levels as directed by Engineer-in-charge. (Sample of Mirror shall be got approved from Engineer-in-Charge).	23.63	Sqm	INR	1700.00	40171.00	INR Forty Thousand One Hundred & Seventy One Only
1.08	Providing and fixing 5mm thick toughened lacquered glass (Saint Gobain / Modiguard) of appropriate size and design complete fixed on the wall as directed by Engineer-in-charge. (Sample of glass shall be got approved from Engineer-in-Charge).	15.00	Sqm	INR	2200.00	33000.00	INR Thirty Three Thousand Only
1.09	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved	50.00	Cum	INR	1500.00	75000.00	INR Seventy Five Thousand Only
1.1	Providing wall paper decorative including fixing on walls etc. complete as per direction of Engineer-in-Charge.. (Sample of wall paper shall be got approved from Engineer-in-Charge).	30.00	Sqm	INR	2500.00	75000.00	INR Seventy Five Thousand Only
1.11	Providing and fixing health faucets of make Jaquar Code: ALD-CHR-573/Hindware Code: F160112 as directed by Engineer in Charge	20.00	Nos	INR	1150.00	23000.00	INR Twenty Three Thousand Only
1.12	Providing & fixing in position 3mm Aluminium composite panel wall cladding with the help of SS Screws and silicon including fixing over 6mm plywood with the help of flat head screws at all heights including all necessary fittings complete as directed by Engineer in charge	60.00	Sqm	INR	1200.00	72000.00	INR Seventy Two Thousand Only
1.13	Deduct for Dismantling and take away of old PPR/PVC pipes including breaking of joints and bed concrete and take away of PPR pipe and fittings etc. the material so received shall be the property of contractor after dismantling duly weighed/measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete. : upto 100mm dia	65.00	RMT	INR	10.00	650.00	INR Six Hundred & Fifty Only
1.14	Providing and laying double charged vitrified wall tiles of thickness 10mm, with water absorption less than 0.08 % and conforming to I.S. 15622, of Kajaria make Code: 6204,6207 or any approved equivalent make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement & matching pigments etc. complete. (a) Size of Tile 600x600 mm	103.77	Sqm	INR	1663.00	172569.51	INR One Lakh Seventy Two Thousand Five Hundred & Sixty Nine and Paise Fifty One Only


 28/09/2023
 उप महाप्रबंधक (अभि-सिविल)
 Dy. General Manager (Engg-Civil)
 भा.वि.प्रा, विजयवाडा हवाई अड्डा
 AAI, Vijayawada Airport-521102

1.15	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	23.63	sqm	INR	52.74	1246.25	INR One Thousand Two Hundred & Forty Six and Paise Twenty Five Only
1.16	Providing and fixing modular toilet Cubicle high pressure laminate partitions of make Merino besco/Green Lam Industries Ltd of 12mm thick compact laminate and size of cubicle As per Site (W) x 1550mm x 2003mm(H) with door size of 1750mm height X 600MM(w) with divider size 1775mm(H) and overall height of cubicle 2003mm (including bottom Gap of 150mm) Including S.S shoe box with standard S.S grade304 foot sliding latch with indicator, S.S accessories of Aluminium U Channel, Aluminium F Channel, Aluminium door stopper channel, aluminium top rail, nylon coat hook, nylon privacy thumb turn c/w occupancy indicator, Nylon door knob, nylon gravity hinges left/right, nylon adjustable foot, rubber door stopper lining,ss screws 304G & PVC wall plugs etc as per manufacture specifications and direction of Engineer-in- Charge.	24.00	Each	INR	45000.00	1080000.00	INR Ten Lakh Eighty Thousand Only
1.17	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS:15801, UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer-in-Charge. Concealed work,including cutting chases and making good the wall etc. PN - 16 Pipe, 25mm OD (SDR-7.4)	65.00	RMT	INR	350.00	22750.00	INR Twenty Two Thousand Seven Hundred & Fifty Only
1.18	Deduct for Dismantling and takeaway of toilet cubical unit made with 12mm thick compact laminated board i.e. the fittings etc complete and take away of toilet cubical unit. The material so received shall be the property of contractor after dismantling duly measured before removing from the site in the presence of Engineer-in-charge or his authorised representative all complete.	76.64	sqm	INR	50.00	3832.00	INR Three Thousand Eight Hundred & Thirty Two Only
1.19	Dismantling of Sanitary Fixtures Urinal/Wash Basin including stacking of useful materials near the site and disposal of unserviceable materials within 50 metre lead as per direction of Engineer-in-charge.	38.00	Each	INR	1000.00	38000.00	INR Thirty Eight Thousand Only
1.2	Providing and fixing bottle trap of Hindware make Code: F850015/ jaquar make of code ALD-CHR-769L300X190 as required and complete as directed by Engineer-in-charge.	22.00	Each	INR	2100.00	46200.00	INR Forty Six Thousand Two Hundred Only

Paul
28/09/2023

उप महाप्रबंधक (अभि-सिविल)
Dy.General Manager (Engg-Civil)
भा.वि.प्रा, विजयवाडा हवाई अड्डा
AAI, Vijaywada Airport-521102

1.21	Providing and fixing in wash basin counters with 6mm thick cultured Marble (Korian Marble) of approved brand, fixed over 16 mm thick water proof plywood on counter to be fixed over 304 grade SS frame(steel work will be paid separately) with all mechanical fixtures and fastener as per manufacturer's specification and guideline including fascia and back splash area as per approved drawings and site condition. The quoted rates shall include fixing of solid acrylic surface over 16 mm thick water proof plywood with suitable adhesive, moulding of edges, with all taxes etc complete as per direction of Engineer In charge.	24.60	Sqm	INR	10000.00	246000.00	INR Two Lakh Forty Six Thousand Only
1.22	Extra on above item no 21, for providing and fixing under counter wash basin of Jaquar make, code:FNS-WHT-40701 of size:595x410x200mm/ or Hindware of approved colour and design and as per site condition as directed by Engineer-Incharge in 6 mm thick acrylic solid surface. The quoted rates shall include fabricating and instalation in line with item no 21 with all necessary fixtures,silicon sealants, moulding of edges,flushing of joints etc complete as per direction of Engineer In charge.The wash basins to be fixed as per drawing and design approved Engineer In charge.	20.00	Each	INR	3700.00	74000.00	INR Seventy Four Thousand Only
1.23	Providing and fixing 8mm thick frosted toughened glass (Saint Gobain / Modiguard) of appropriate size and design complete fixed on the wall for urinal partition with suitable patch fitting at all levels as directed by Engineer-in-charge. (Sample of glass shall be got approved from Engineer-in-Charge).	10.00	Sqm	INR	2100.00	21000.00	INR Twenty One Thousand Only
1.24	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	21.00	Each	INR	500.00	10500.00	INR Ten Thousand Five Hundred Only
1.25	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge	2.00	Each	INR	500.00	1000.00	INR One Thousand Only
1.26	Providing and fixing wall hung EWC of Jaquar make code: ARS-WHT-39953BIUFMS/ Hindware make code:92538(P-23) including toilet seat of Jaquar make and concealed cistern with full frame of Jaquar make code:JCS-WHT-2400FS/ Hindware make code:518236 and flush plate of Jaquar make, code:JCP-CHR-152415/Hindware make concealed flush plate including cutting, fixing, transportation making good the surface as per the direction of Engineer in charge.	21.00	Nos	INR	24050.00	505050.00	INR Five Lakh Five Thousand & Fifty Only
1.27	Providing and fixing IWC orissa pan of Jaquar or Hindware make including cutting, fixing, transportation making good the wall surface as per the direction of Engineer in charge.	2.00	Nos	INR	3500.00	7000.00	INR Seven Thousand Only

Paul
28/09/2023

उप महाप्रबंधक (अभि-सिविल)
Dy.General Manager (Engg-Civil)
भा.वि.प्रा, विजयवाडा हवाई अड्डा
AAI, Vijayawada Airport-521103

1.28	Providing & fixing urinal basin of Jaquar make with code:URS-WHT-13263/ Hindware make of code 60010 with Urinal sensor concealed type flushig valve of Jaquar make of catlog no: SNR-STL-51083 or Hindware Code: 500964 with all necessary fitting including cutting & making good the walls and floors wherever required: as per direction of engineer in charge.	16.00	Nos	INR	17000.00	272000.00	INR Two Lakh Seventy Two Thousand Only
Total in Figures						3354693.26	INR Thirty Three Lakh Fifty Four Thousand Six Hundred & Ninety Three and Paise Twenty Six Only
Quoted Rate in Words		INR Thirty Three Lakh Fifty Four Thousand Six Hundred & Ninety Three and Paise Twenty Six Only					


 28/09/2023
 उप महाप्रबंधक (अभि-सिविल)
 Dy.General Manager (Engg-Civil)
 भा.वि.प्रा, विजयवाड़ा हवाई अड्डा
 AAI, Vijayawada Airport-521102